



PCB DELINEATION SAMPLING

Doors and Windows Replacement Project
Buildings A, B, C, D, E, F, G and H

Webster Elementary School

3602 Winter Canyon Road
Malibu, California 90265

Prepared for:

Santa Monica-Malibu Unified School District
Facilities Improvements Projects
2828 4th Street
Santa Ana, California 90405

Project No.: SMSD-16-6514
Date: Revised, February 14, 2017

Alta Environmental

3777 Long Beach Boulevard Annex Building
Long Beach CA 90807 United States of America
T (562) 495 5777 F (562) 495 5877
Toll-free (US only) 800 777-0605 altaenviron.com

EXECUTIVE SUMMARY

On November 21, 22, and 23 2016, and January 19, 25, and 26, 2017, Alta Environmental conducted PCB delineation sampling for the door and window replacement project in buildings A, B, C, E, F, G, and H at Webster Elementary School located at 3602 Winter Canyon Road, Malibu, California 90265 (Site).

The objective of this sampling was to determine if PCBs associated with PCB Bulk Product Waste may have migrated to adjacent porous surfaces beyond 1" and 3" away from the possibly impacted windows and doors casings (Components) slated to be remove and replaced.

The Reporting Limit (RL) used by the laboratory for this project was below the benchmark (1 ppm) currently being used as approved by the USEPA.

A total of 62 samples were analyzed representative of the surrounding porous surfaces. The sampling started at 1 inch (1") and extended to intervals of 3 inches (3") and 6 inches (6") away from the Components from a surface depth of 0-.5". As per the Districts request, initially, only 1" samples were analyzed, with the intent of analyzing the associated 3" and 6" samples only if the 1" samples reported levels of PCBs greater than 1ppm.

One sample collected at the 1" interval was reported to contain 1.76 parts per million (ppm) PCBs (1.45 ppm Aroclor 1242 and 0.309 ppm Aroclor 1248). The 3" sample collected from this location was subsequently analyzed and reported by the laboratory to contain 0.185 ppm PCBs (Aroclor 1248). In order to further characterized the migration of PCBs, Alta conducted more sampling (January 19, 25 and 26, 2017) representative of the groups of buildings similar to building F. All additional samples collected on January 19, 25, and 26, 2016 were reported as "Not Detected" above the RL.

During the delineation sampling, both caulking and glazing was observed around the window and door casings. The caulking and glazing was not sampled at the District request but was assumed to be PCB Bulk Product Waste. Additionally, the porous materials 0 to 3 inch (0-3") installed around the possibly impacted doors and windows casings are assumed to be PCB Remediation Waste.

Removal of PCB Bulk Product Waste and PCB Remediation Waste should be conducted using proper engineering controls including but not limited to containment, worker training, worker protection etc. PCB waste should be characterized, packaged, labeled and disposed as required by TSCA 40 CFR 761 and California hazardous waste regulation set forth in Title 22, Division 4.5 of the California Code of Regulations unless testing is performed prior to demolition and analytical results confirms that PCBs are less than 50 ppm in the window and door caulking and window glazing.

Summary of Findings:

1. All window and door caulking and window glazing are assumed to be PCB Bulk Product Waste, all buildings,
2. All porous materials installed around the window and door casings, approximately 0-1" are assumed to be PCB Remediation Waste, buildings A, G, and H. Porous materials installed beyond 1" were reported as non-detected by the laboratory during the delineation sampling completed during this project-therefore, not interpreted to require removal and disposal as PCB waste at this time.
3. All porous materials installed around the window and door casings, approximately 0-3" are assumed to be PCB Remediation Waste, buildings B, C, D, E, and F. Porous materials installed beyond 3" were reported as non-detected by the laboratory during the delineation sampling completed during this project-therefore, not interpreted to require removal and disposal as PCB waste at this time.

TABLE OF CONTENTS

1	INTRODUCTION	1
2	SCOPE OF WORK	1
3	METHODOLOGY	3
4	RESULTS	3
5	QUALITY CONTROL	5
6	CONCLUSIONS, RECOMMENDATIONS AND LIMITATIONS	5
7	ASSUMPTIONS AND LIMITATIONS	6
8	SIGNATORY	6

Appendices

Appendix A: Sample Inventories

Appendix B: Laboratory Reports

Appendix C: Sample Location Maps

Appendix D: Photographs

REPORTED: Revised, February 14, 2017

PROJECT NO.: SMSD-16-6514

CLIENT: Santa Monica-Malibu Unified School District
Facility Improvements Projects
2828 4th Street
Santa Monica, California 90405

ATTENTION: Mr. Chris Emmett

REF: PCBs Delineation Sampling
Buildings A, B, C, D, E, F, G, and H
Webster Elementary School
3602 Winter Canyon Road
Malibu, California 90265

1 INTRODUCTION

On November 21, 22, and 23, 2016, and January 19, 25, and 26, 2017, Alta Environmental conducted PCB delineation sampling for the door and window replacement project in buildings A, B, C, E, F, G, and H at Webster Elementary School located at 3602 Winter Canyon Road, Malibu, California 90265 (Site).

The sampling was completed by Fabian Ruvalcaba, and Therese Rizarri, both Cal/OSHA Hazardous Waste Operations and Emergency Response (HAZWOPER) trained technicians, and assistant field technician, Oscar Garcia.

2 SCOPE OF WORK

The Santa Monica-Malibu Unified School District (District) retained Alta Environmental (Alta) for the sampling (approved proposal dated, November 10, 2016, and January 19, 2017).

The PCBs delineation sampling was completed around doors and window casings slated for removal and replacement in buildings A, B, C, D, E, F, G, and H in areas identified in project drawings prepared by dsk architects, dated November 15, 2016.

Alta delineation sampling was completed as follows:

1. A one inch sized diameter drill bit was used in conjunction with a rotary impact hammer to collect samples from stucco, and wall plaster surfaces.
2. A polyethylene drop-sheet will be placed below the sampling area to capture any dust which may be dislodged during the sample collection.
3. Samples were placed inside an appropriate glass jar with a Teflon lined cap.
4. Samples were labelled, packaged, and documented on a Chain of Custody for shipping to the laboratory.
5. Samples were shipped to the laboratory in a chilled ice chest.
6. Sampled areas were patched using a non-PCBs sealant. The patch area is temporary, intended only to provide a barrier to the exposed sampled substrates.
7. Each sample location was documented using digital photographs.
8. Equipment and tools were decontaminated using a two-step decontamination process. First, all used drill bits, and tools were cleaned using scrub brushes and detergent with de-ionized water base solution. Second, each piece was rinsed using de-ionized water. After the two step decontamination procedures, the equipment was placed on top of clean paper towels (or equivalent material) and were set to dry individually. Each piece of equipment was inspected by Alta for evidence of residual dust and debris.

The sampling was conducted in accordance with the approved proposal, a site-specific work plan prepared for this project (Alta Work Plan, dated November 15, 2016), which was reviewed and approved by the District and "USEPA Region I Standard Operation Procedures for Sampling Porous Surfaces for Polychlorinated Biphenyl," approved for use by the District, May, 23, 2011. A predetermined number of doors and windows, and sample locations were selected as part of the approved work plan. The doors and windows and sample locations were based on similarity of each component and building construction date. At least ten percent (10%) of each similar component was randomly sampled in each building of similar construction. Below, in Table 1 is summary of the sampled components.

Table 1
Summary of Window Types and Associated Substrates

Component Type ID	Component Description	Visible Caulking Yes/No	Building	Location	Exterior Substrate	Interior Substrate
A	Full wall metal window	Yes	D	All sides	Stucco	Wood
B	New aluminium window	Yes	D	North side	Stucco	Drywall
C	4'X8" half wall metal windows (restrooms, storages, work rooms etc.)	Yes	A, B, C, D, E, F	All sides	Stucco	Drywall, plaster wood, concrete
		Yes	G, and H	All sides		
D	Full wall (floor to roof) metal window	Yes	G, H	East sides	Stucco	Plaster
E	Full wall new aluminium window	Yes	G	South side	Stucco	Plaster
F	Full wall metal window on concrete saddle wall	Yes	E, F	East	Stucco and concrete	Plaster and concrete
G	Full wall, all metal window (floor to roof)	Yes	B, C	East	Stucco	Drywall, wood
H	Doors embedded in full wall metal windows (type F)	Yes	E, F	East	Concrete	Concrete, plaster
I	Full wall metal windows	Yes	A	East	Stucco	Wood

Component Type ID	Component Description	Visible Caulking Yes/No	Building	Location	Exterior Substrate	Interior Substrate
J	Full wall metal back windows (thru covered walkways)	Yes	E, F	Backside classrooms	Concrete and stucco	Plaster and concrete
K	Single exterior door	Yes	B, C, D, E, F	Restrooms, heater rooms, work rooms, back side classrooms	Stucco all sides	Interior drywall, concrete, wood, plaster

3 METHODOLOGY

A total of 62 samples were analyzed representative of the surrounding porous surfaces. The sampling started at 1 inch (1") and extended to intervals of 3 inches (3") and 6 inches (6") away from the Components from a surface depth of 0-.5". As per the Districts request, initially, only 1" samples were analyzed, with the intent of analyzing the associated 3" and 6" samples only if the 1" samples reported levels of PCBs greater than 1ppm.

The bulk samples were placed in an appropriate glass jar with a Teflon cap. Samples were labeled and packaged in a cooler and kept cool with ice during shipment.

Samples including QA/QC field duplicate samples were analyzed by Enviro-Chem, located at 1214 East Lexington Avenue, Pomona, California, a Cal ELAP accredited laboratory (#1555)

Split QA/QC samples were analyzed by and EMSL Laboratory (EMSL), located in Cinnaminson, NJ 08077, a Cal ELAP (#1877) and RDL/NELAC nationally accredited (#03036).

4 RESULTS

Table 2.0
Summary of Sample Results

Component (from Table 1 above)	Building	Reported Construction Date	Number of Components Tested	Total Potentially Impacted Components to be renovated	Total Samples Analyzed	Results
A	D	1948	1	5	2	Not Detected
B	D	1948	1	1	2	Not Detected
C	B, C, D, E, F	1948	5	9	13	Not Detected
C	G, H	1952	1	7	2	Not Detected
C	A	1961	1	4	2	Not Detected

Component (from Table 1 above)	Building	Reported Construction Date	Number of Components Tested	Total Potentially Impacted Components to be renovated	Total Samples Analyzed	Results
D	H	1952	1	4	2	Not Detected
E	G	1952	1	1	2	Not Detected
F	E, F	1948	2	9	7	Not Detected
G	B, C	1948	3	7	7	Not Detected
H	B, C, D, E, F	1948	1	7	2	Not Detected
I	A	1961	1	4	2	Not Detected
J	B, C, D, E, F	1948	3	14	1	1.76 ppm (1.45 ppm Aroclor 1242 and 0.309 ppm Aroclor 1248, at 1" interval)
					8	Not Detected (1" interval)
					1	0.185 ppm (Aroclor 1248 at 3" interval)
					1	Not Detected (6" interval)
K	B, C, D, E, F	1948	4	26	8	Not Detected

All samples were analyzed in accordance with EPA Method 3540C/8082A for PCBs.

The Reporting Limit (RL) used by the laboratory for this project was below the benchmark (1 ppm) currently being used as approved by the USEPA. One sample collected at the 1" interval was reported to contain 1.76 parts per million (ppm) PCBs (1.45 ppm Aroclor 1242 and 0.309 ppm Aroclor 1248). The 3" sample collected from this location was subsequently analyzed and reported by the laboratory to contain 0.185 ppm PCBs (Aroclor 1248), and the 6" samples were reported as not detected at above the RL. All other samples were reported as not detected at the laboratory RL.

Refer to Appendix A in this report for a summary of samples collected and relevant sample information.

Refer to Appendix B for laboratory reports and relevant sample analysis information.

5 QUALITY CONTROL

Nine field duplicate samples were collected side by side from the 1" interval. Field duplicate samples were reported with consistent results.

Three split duplicate samples were collected from two separate locations representative of the 1" interval. The samples were homogenized, and split in to two identical samples. The split samples were then submitted and analyzed by both Enviro-Chem, and EMSL laboratories. Both laboratories reported consistent results as not-detected at above the RL.

EMSL reported "The samples were received in good condition. The QC data associated with the samples results meets the recovery and precision requirement established by NELAP." Similarly, Enviro-Chem reported, "all samples were received intact, and accompanying chain of custody."

Enviro-Chem reported results with heavy matrix interference (sample number, 161121-22 (I-1-11P), 170120-56 (25-119), and 170120-59 (28-119)). The matrix interference is likely related to paint or other surface coatings/materials, such as primers, paints which impacted the sample analysis. The laboratory reported results as non-detected for PCBs, however, at a higher reporting limit than the action level of 1 ppm. Additional sampling may be necessary to substantiate these results.

Based on review of the QC data associated with the sample analysis, the recovery and precision is within the acceptable limits of the laboratory.

6 CONCLUSIONS

The PCB delineation sampling was completed around doors and window casings scheduled for removal and replacement in buildings A, B, C, D, E, F, G, and H in areas identified in project drawings prepared by dsk architects, dated November 15, 2016.

The objective of this sampling was to determine if PCBs may have migrated to adjacent porous surfaces beyond 1", and 3" away from the possibly impacted windows and doors casings (Components) slated to be remove and replaced.

During the delineation sampling, both caulking and glazing was observed around the window and door casings. The caulking and glazing was not sampled at the District request but was assumed to be PCB Bulk Product Waste. Additionally, the porous materials 0 to 3 inch (0-3") installed around the possibly impacted doors and windows casings are assumed to be PCB Remediation Waste.

Summary of Findings:

1. All window and door caulking and window glazing are assumed to be PCB Bulk Product Waste, all buildings.
2. All porous materials installed around the window and door casings, approximately 0-1" are assumed to be PCB Remediation Waste, buildings A, G, and H. Porous materials installed beyond 1" were reported as non-detected by the laboratory during the delineation sampling completed during this project-therefore, not interpreted to require removal and disposal as PCB waste at this time.
3. All porous materials installed around the window and door casings, approximately 0-3" are assumed to be PCB Remediation Waste, buildings B, C, D, E, and F. Porous materials installed beyond 3" were reported as non-detected by the laboratory during the delineation sampling completed during this project-therefore, not interpreted to require removal and disposal as PCB waste at this time.

7 RECOMMENDATIONS

Removal of PCB Bulk Product Waste and PCB Remediation Waste should be conducted using proper engineering controls including but not limited to containment, worker training, worker protection etc. PCB waste should be characterized, packaged, labeled and disposed as required by TSCA 40 CFR 761 and

California hazardous waste regulation set forth in Title 22, Division 4.5 of the California Code of Regulations unless testing is performed prior to demolition and analytical results confirms that PCBs are less than 50 ppm in the window and door caulking and window glazing.

A site-specific removal work plan should be prepared, reviewed and approved by the District prior to the start of any removal action.

8 ASSUMPTIONS AND LIMITATIONS

It is understood that the data contained in this report is to be used for planning and budgeting purposes related to a scheduled door and window replacement project. Additional sampling may be required to further characterized the site, waste disposal characterization, and area clearance following the removal of the impacted doors.

This report was prepared exclusively for use by Santa Monica-Malibu Unified School District, and may not be relied upon by any other person or entity without Alta Environmental's express written permission. The information, conclusions and recommendations described in this report apply to conditions existing at certain locations when services were performed and are intended only for the specific purposes, locations, time frames and project parameters indicated. Alta Environmental cannot be responsible for the impact of any changes in environmental standards, practices or regulations after performance of services.

In performing our professional services, we have applied present engineering and scientific judgment and used a level of effort consistent with the current standard of practice for similar types of studies.

As applicable, Alta Environmental has relied in good faith upon representations and information furnished by individuals with respect to operations and existing property conditions, to the extent that they have not been contradicted by data obtained from other sources. Accordingly, Alta Environmental accepts no responsibility for any deficiencies, omissions, misrepresentations, or fraudulent acts of persons interviewed.

Alta Environmental will not accept any liability for loss, injury claim, or damage arising directly or indirectly from any use or reliance on this report. Alta Environmental makes no warranty, expressed or implied.

This report is issued with the understanding that the client, the property owner, or its representative is responsible for ensuring that the information, conclusions, and recommendations contained herein are brought to the attention of the appropriate regulatory agencies, as required.

Material quantities are in some cases listed within this document. These quantities are not intended to be used for removal bidding purposes. Nor is this document intended as a contract manual. Work methods and sequence, coordination of participants, applicable codes, engineering controls, required submittals and notifications should in all cases be addressed in a separate and independent bidding and contract document. If you have any questions, please do not hesitate to contact the undersigned at (562) 495-5777. We appreciate the opportunity to be of service to Santa Monica-Malibu Unified School District.

9 SIGNATORY

Respectfully submitted by:

Alta Environmental



Cesar Ruvalcaba
Project Manager

Reviewed by:

Alta Environmental



David Schack
Vice President, Building Sciences

Appendix A

Sample Inventories

Summary of PCBs Deliniation Sampling

CLIENT: Webster Elementary School
PROJECT NO: SMSD-16-6414
PROJECT: Windows and Doors Removal Project at Webser ES-Initial Step-out Sampling
Date: November 21 to 23, 2016

Building Name	Component ID	Sample Number	Substrate	Sample Location	Photograph	Total PCBs
A	I	I-1-20	Wood	Northwest- room 20 interior (1")	1	Not Detected
A	I	X-1-20	Stucco	Northwest- room 20 exterior (1")	2	Not Detected
A	C	I-1-20B	Wood	Southwest- room 20 interior (1")	3	Not Detected
A	C	X-1-20B	Stucco	Southwest- room 20 exterior (1")	4	Not Detected
B	G	I-1-11P	Drywall	Northwest corner- room 11 interior (1")	5	Not Detected
B	G	X-1-11S	Stucco	Northwest corner- room 11 exterior (1")	6	Not Detected
B	C	I-1-211D	Drywall	South center- room 11 restroom interior (1")	7	Not Detected
B	C	X-1-211S	Stucco	South center- room 11 exterior (1")	8	Not Detected
D	A	I-1-NW	Wood	West center- nurse's office interior (1")	9	Not Detected
D	B	I-1-RD	Drywall	West center- nurse's office exterior (1")	11	Not Detected
D	A	X-1-RS	Stucco	West center exterior (1")	12	Not Detected
D	B	X-1-NS	Stucco	West center Exterior (1")	10	Not Detected
E	F	X-1-7S	Stucco	Northeast corner- room 7 exterior (1")	14	Not Detected
E	F	X-1-7C	Concrete	Northeast corner- room 7 exterior (1")	14	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: Webster Elementary School
PROJECT NO: SMSD-16-6414
PROJECT: Windows and Doors Removal Project at Webser ES-Initial Step-out Sampling
Date: November 21 to 23, 2016

Building Name	Component ID	Sample Number	Substrate	Sample Location	Photograph	Total PCBs
E	F	I-1-7C	Concrete	Northeast corner- room 7 interior (1")	13	Not Detected
E	F	I-1-7P	Plaster	Northeast corner- room 7 interior (1")	13	Not Detected
F	J	X-1-S10	Stucco	Southeast- room 10 exterior (1")	16	1.76 (1.45 Aroclor 1242 and 0.309 Aroclor 1248)
F	J	X-3-S10	Stucco	Southeast- room 10 exterior (3")	16	0.185 (aroclor 1248)
F	J	X-1-C10	Concrete	Southeast- room 10 exterior (1")	16	Not Detected
F	J	I-1-10A	Concrete	Southeast- room 10 interior (1")	15	Not Detected
F	H	X-1-10B	Concrete	North center- room 10 exterior (1")	18	Not Detected
F	H	I-1-10B	Concrete	North center- room 10 interior (1")	17	Not Detected
G	E	I-1-CAF	Plaster	Northeast- cafeteria interior (1")	19	Not Detected
G	E	X-1-CAF	Stucco	Northeast- cafeteria exterior (1")	20	Not Detected
G	C	I-1-G2	Plaster	North center- kiln room interior (1")	21	Not Detected
G	C	X-1-G2	Stucco	North center- kiln room exterior (1")	22	Not Detected
H	D	I-1-H1	Plaster	Northwest- room H1 interior (1")	23	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: Webster Elementary School
PROJECT NO: SMSD-16-6414
PROJECT: Windows and Doors Removal Project at Webser ES-Initial Step-out Sampling
Date: November 21 to 23, 2016

Building Name	Component ID	Sample Number	Substrate	Sample Location	Photograph	Total PCBs
H	D	X-1-H1	Stucco	Northwest- room H1 exterior (1")	24	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: Webster Elementary School
PROJECT NO: SMSD-16-6414.1
PROJECT: Windows and Doors Removal Project at Webser ES-Initial Step-out Sampling
Date: November 21 to 23, 2016

QA/QC Samples

Building Name	Sample Number	Type of Window or Door	Sample Description	Sample Location	Photograph Number	Total PCBs (mg/kg)
Duplicate QA/QC Samples						
A	I-1-20B-DUP	C	Wood	Southwest- room 20 interior (1")	3	Not Detected
B	I-1-211D-DUP	C	Drywall	South center- room 11 restroom interior (1")	7	Not Detected
D	X-1-NS-DUP	B	Stucco	West center exterior (1")	10	Not Detected
F	X-1-S10-DUP	J	Stucco	Southeast- room 10 exterior (Duplicate sample of X-1-S10) (1")	16	1.74 (1.37 Aroclor 1242 and 0.371 Aroclor
Split Duplicate QA/QC Samples						
A	X-1-20B-SPLIT	I	Stucco	Southwest- room 20 exterior, analyzed by Enviro-Chem laboratory (1")	4	Not Detected
A	X-1-20B-SPLIT	I	Stucco	Southwest- room 20 exterior, analyzed by EMSL laboratory (1")	4	Not Detected
A	I-1-20-SPLIT	C	Wood	Northwest- room 20 interior, analyzed by Enviro-Chem laboratory (1")	1	Not Detected
A	I-1-20-SPLIT	C	Wood	Northwest- room 20 interior, analyzed by EMSL laboratory (1")	1	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-16-6514.1
PROJECT: Windows and Doors Removal Project at Webser ES-Additional Step-out Sampling
Date: January 25, 2016

Building Name	Sample Number	Type of Window or Door	Sample Description	Sample Location	Photograph Number	Total PCBs (mg/kg)
B	1-0125	K	Drywall	1"- Interior heater closet, southwest corner	No Photo Available	Not Detected
B	2-0125	K	Stucco	1"- Exterior heater closet, southwest corner, approx. 4' up	2	Not Detected
B	5-0125	C	Stucco	1"- Exterior room 12 closet, southwest corner, approx. 4' up	No Photo Available	Not Detected
B	8-0125	C	Drywall	1"-Interior room 12 closet, southwest corner, approx. 4' up	No Photo Available	Not Detected
B	11-0125	G	Drywall	1"- Interior room 12, northwest corner, approx. 4' up	5	Not Detected
B	14-0125	G	Stucco	1"- Exterior room 12, northwest corner, approx. 4' up	6	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-16-6514.1
PROJECT: Windows and Doors Removal Project at Webser ES-Additional Step-out Sampling
Date: January 25, 2016

Building Name	Sample Number	Type of Window or Door	Sample Description	Sample Location	Photograph Number	Total PCBs (mg/kg)
C	17-0125	J	Wood	1"- Interior room 16, southwest corner window, approx. 6' up, insufficient material	No Photo Available	Not Detected
C	18-0125	J	Stucco	1"- Exterior room 16, southwest corner window, approx. 6' up	8	Not Detected
C	21-0125	G	Wood	1"- Interior room 16, northwest corner window, approx. 6' up, insufficient material	No Photo Available	Not Detected
C	24-0125	G	Stucco	1"- Exterior room 16, northwest corner window, approx 6' up	No Photo Available	Not Detected
C	27-0125	C	Plaster	1"- Interior women's restroom, southwest center, approx. 4' up	14	Not Detected
C	30-0125	C	Stucco	1"- Exterior women's restroom, southwest center, approx. 4' up	16	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-16-6514.1
PROJECT: Windows and Doors Removal Project at Webser ES-Additional Step-out Sampling
Date: January 19 and 25, 2016

Building Name	Sample Number	Type of Window or Door	Sample Description	Sample Location	Photograph Number	Total PCBs (mg/kg)
D	25-0119	A	Wood	1"- Interior principal office, south window	No Photo Available	Not Detected
D	27-0119	K	Plaster	1"- Interior teachers work room, north wall, northwest corner door, insufficient material	No Photo Available	Not Detected
D	28-0119	K	Wood	1"-Interior teachers work room, north wall, northwest corner door, insufficient material	No Photo Available	Not Detected
D	29-0119	K	Stucco	1"- Exterior teachers work room, north wall, northwest corner door	No Photo Available	Not Detected
D	33-0125	A	Wood	1"- Exterior principal office, south center window	No Photo Available	Not Detected

Summary of PCBs Step-Out Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-16-6514.1
PROJECT: Windows and Doors Removal Project at Webser ES-Additional Step-out Sampling
Date: January 19, 2016

Building Name	Sample Number	Type of Window or Door	Sample Description	Sample Location	Photograph Number	Total PCBs (mg/kg)
E	1-0119	K	Concrete	1"-Interior room 7, south end, southwest door	18	Not Detected
E	4-0119	K	Concrete	1"- Exterior room 7, south end southwest door	19	Not Detected
E	7-0119	J	Concrete	1"- Interior library, south end, west corner window	20	Not Detected
E	10-0119	J	Plaster	1"-Interior library, south end, west corner window	21	Not Detected
E	13-0119	J	Plaster	1"- Exterior library, south end, west corner window	No Photo Available	Not Detected
E	16-0119	J	Stucco	1"- Exterior library, south end, west corner	No Photo Available	Not Detected
E	18-0119	H	Plaster	1"- Interior work area room, north end, north center door	24	Not Detected
E	22-0119	H	Stucco	1"- Exterior work area room, north end, north center door	No Photo Available	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-16-6514.1
PROJECT: Windows and Doors Removal Project at Webser ES-Additional Step-out Sampling
Date: January 26, 2016

Building Name	Sample Number	Type of Window or Door	Sample Description	Sample Location	Photograph Number	Total PCBs (mg/kg)
F	1-0126	J	Stucco	6"- Exterior room 10, southeast corner, approx. 4' up	No Photo Available	Not Detected
F	2-0126	F	Concrete	1"- Interior room 10 window, approx 8' west of northeast corner note: no plaster sample taken, window incased in metal	No Photo Available	Not Detected
F	5-0126	F	Concrete	1"- Exterior room 10 window, approx. 8' west of northeast corner	No Photo Available	Not Detected
F	8-0126	F	Stucco	1"- Exterior room 10 window, approx. 8' west of northeast corner	No Photo Available	Not Detected
F	11-0126	C	Plaster	1"- Interior boy's restroom, southwest corner	No Photo Available	Not Detected
F	14-0126	C	Concrete	1"- Interior boy's restroom, approx. 4' east	No Photo Available	Not Detected
F	17-0126	C	Concrete	1"- Exterior boy's restroom, approx. 4' east	No Photo Available	Not Detected
F	20-0126	C	Stucco	1"- Exterior boy's restroom, approx. 4' east	No Photo Available	Not Detected
F	24-0126	K	Stucco	1"-Exterior janitors closet, west center door, approx. 4' up	No Photo Available	Not Detected
F	27-0126	K	Plaster	1"- Interior janitor's closet, west center door, approx. 4' up	No Photo Available	Not Detected
F	31-0126	C	Concrete	1"- Exterior girl's restroom window, approx 3' up	No Photo Available	Not Detected
F	34-0126	C	Stucco	1"- Exterior girl's restroom window, approx 3' up, insufficient material, gutter in the way	No Photo Available	Not Detected
F	35-0126	C	Concrete	1"- Interior girl's restroom window, southwest corner, approx. 4' east	No Photo Available	Not Detected
F	38-0126	C	Plaster	1"- Interior girl's restroom window, southwest corner, west wall	No Photo Available	Not Detected

Summary of PCBs Deliniation Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-16-6514.1
PROJECT: Windows and Doors Removal Project at Webser ES-Additional Step-out Sampling
Date: January 19, 25, and 26 2017

QA/QC Samples

Building Name	Sample Number	Type of Window or Door	Sample Description	Sample Location	Photograph Number	Total PCBs (mg/kg)
Duplicate QA/QC Samples						
E	19-0119	H	Plaster	Duplicate of sample 18-0119 (1")	Photo Not Available	Not Detected
C	22-0125	G	Wood	Duplicate of sample 21-0125 (1")	Photo Not Available	Not Detected
D	34-0125	A	Wood	Duplicate of sample 34-0125 (1")	Photo Not Available	Not Detected
F	21-0126	C	Stucco	Duplicate of sample 20-2126 (1")	Photo Not Available	Not Detected
F	39-0126	J	Plaster	Duplicate of sample 38-0126 (1")	Photo Not Available	Not Detected
Split Duplicate QA/QC Samples						
F	28a-0126	H	Plaster	Split duplicate of 28b-0126 (Enviro-Chem Lab) (1")	Photo Not Available	Not Detected
F	28b-0126	H	Plaster	Split duplicate of 28a-0126 (EMSL Lab) (1")	Photo Not Available	Not Detected

Appendix B

Laboratory Reports

Enviro - Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766 Tel (909) 590-5905 Fax (909) 590-5907

Date: December 5, 2016

Mr. Cesar Ruvalcaba
Alta Environmental
3777 Long Beach Blvd, Annex Building
Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com

Project: **SMSD-16-6514**
Lab I.D.: **161121-10 through -43**

Dear Mr. Ruvalcaba:


The **analytical results** for the solid samples, received by our laboratory on November 21, 2016, are attached. The samples were received intact, and accompanying chain of custody.

Enviro-Chem appreciates the opportunity to provide you and your company this and other services. Please do not hesitate to call us if you have any questions.

Sincerely,



Curtis Desilets
Vice President/Program Manager



Andy Wang
Laboratory Manager

LABORATORY REPORT

CUSTOMER: **Alta Environmental**
3777 Long Beach Blvd, Annex Building, Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com

PROJECT: **SMSD-16-6514**

DATE RECEIVED: 11/21/16
DATE SAMPLED: 11/18/16 DATE EXTRACTED: 11/29/16
MATRIX: SOLID DATE ANALYZED: 11/30/16
REPORT TO: MR. CESAR RUVALCABA DATE REPORTED: 12/05/16

PCBs ANALYSIS

METHOD: EPA 3540C/8082

UNIT: mg/Kg = MILLIGRAM PER KILOGRAM = PPM

SAMPLE I.D.	LAB I.D.	PCB-1016	PCB-1221	PCB-1232	PCB-1242	PCB-1248	PCB-1254	PCB-1260	TOTAL PCBs*	DF
X-1-7S	161121-10	ND	ND	ND	ND	ND	ND	ND	ND	4^
X-1-7C	161121-12	ND	ND	ND	ND	ND	ND	ND	ND	8^
I-1-7C	161121-15	ND	ND	ND	ND	ND	ND	ND	ND	8^
I-1-7P	161121-18	ND	ND	ND	ND	ND	ND	ND	ND	4^
I-1-11P	161121-22	ND	ND	ND	ND	ND	ND	ND	ND	160^
X-1-11S	161121-24	ND	ND	ND	ND	ND	ND	ND	ND	4^
I-1-211D	161121-27	ND	ND	ND	ND	ND	ND	ND	ND	80^
X-1-211S	161121-28	ND	ND	ND	ND	ND	ND	ND	ND	2^
I-1-NW	161121-31	ND	ND	ND	ND	ND	ND	ND	ND	20^
I-1-211D-										
DUP	161121-33	ND	ND	ND	ND	ND	ND	ND	ND	20^
I-1-RD	161121-34	ND	ND	ND	ND	ND	ND	ND	ND	10^
X-1-RS	161121-37	ND	ND	ND	ND	ND	ND	ND	ND	10^
X-1-NS	161121-40	ND	ND	ND	ND	ND	ND	ND	ND	10^
X-1-NS-										
DUP	161121-43	ND	ND	ND	ND	ND	ND	ND	ND	10^
Method Blank		ND	ND	ND	ND	ND	ND	ND	ND	1

PQL 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01

COMMENTS

DF = Dilution Factor

PQL = Practical Quantitation Limit


Actual Detection Limit = DF X PQL

ND = Non-Detected Or Below the Actual Detection Limit

^ = Actual Detection Limit Raised Due To limited Sample Quantity

* = Sum of the PCB 1016, 1221, 1232, 1242, 1248, 1254 and 1260

*** = The concentration exceeds the TTLC Limit of 50, and the sample is defined as hazardous waste as per CCR-TITLE 22 (if marked)

Data Reviewed and Approved by: 

CAL-DHS ELAP CERTIFICATE No.: 1555

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**

Date Analyzed: 11/29-30/2016

Unit: mg/Kg(PPM)

Matrix Spike (MS)/Matrix Spike Duplicate (MSD)

Spiked Sample Lab I.D.: **161130-LCS1/2**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.113	113%	0.109	109%	4%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.103	103%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	161121-10	161121-12	161121-15	161121-18	161121-22	161121-24
Tetra-chloro-meta-xylene	50-150	110%	121%	124%	128%	134%	130%	144%
Decachlorobipneyl	50-150	96%	85%	80%	82%	77%	71%	128%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	161121-27	161121-28	161121-31	161121-33	161121-34	161121-37	161121-40	161121-43
Tetra-chloro-meta-xylene	140%	121%	135%	130%	126%	131%	131%	127%
Decachlorobipneyl	85%	75%	77%	100%	94%	78%	79%	77%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.						
Tetra-chloro-meta-xylene						
Decachlorobipneyl						

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: 

Final Reviewer: 

Enviro-Chem, Inc. Laboratories
 1214 E. Lexington Avenue,
 Pomona, CA 91766
 Tel: (909) 590-5905 Fax: (909) 590-5907
CA-DHS ELAP CERTIFICATE #1555

Turnaround Time
☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☒ 1 Week (Standard)
 Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required												COMMENTS	Misc./PO#			
		DATE	TIME																					
X-1-7s	161121-0	11/18/16	1700		1	ice	X																	
X-3-7s	-11		1706		1		X																	archive
X-1-7c	-12		1712		1		X																	
X-3-7c	-13		1720		1		X																	archive
X-6-7c	-14		1723		1		X																	archive
I-1-7c	-15		1734		1		X																	
I-3-7c	-16		1746		1		X																	archive
I-6-7c	-17		1753		1		X																	archive
I-1-7p	-18		1800		1		X																	
I-3-7p	-19		1803		1		X																	archive
I-6-7p	-20		1806		1		X																	archive
I-3-11p	-21		1841		1		X																	archive
I-1-11p	-22		1847		1		X																	
I-6-11p	-23		1853		1		X																	archive
X-1-11s	-24		1857		1		X																	

Company Name: Alta Environmental

Address: 3777 Long Beach Blvd, Annex Bldg

City/State/Zip: Long Beach, CA 90807

Project Contact: Cesar Ruvalcaba

Tel: 562-498-5777

Fax/Email: cesar.ruvalcaba@altaenviren.com

Sampler's Signature: [Signature]

Project Name/ID: 5MSD-16-6514

Relinquished by: <u>[Signature]</u>	Received by: <u>Thore Rizarri</u>	Date & Time: <u>11/18/16 2100</u>
Relinquished by: <u>Thore Rizarri</u>	Received by: <u>[Signature]</u>	Date & Time: <u>11/21/16 11020</u>
Relinquished by: <u>[Signature]</u>	Received by: <u>[Signature]</u>	Date & Time: <u>11/21/16 11311</u>

Instructions for Sample Storage After Analysis:

☐ Dispose of ☐ Return to Client ☐ Store (30 Days)

☐ Other:

CHAIN OF CUSTODY RECORD

Date: 11/21/16

WHITE WITH SAMPLE • YELLOW TO CLIENT

Enviro-Chem, Inc. Laboratories
 1214 E. Lexington Avenue,
 Pomona, CA 91766
 Tel: (909) 590-5905 Fax: (909) 590-5907
CA-DHS ELAP CERTIFICATE #1555

Turnaround Time
☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☒ 1 Week (Standard)
 Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
		DATE	TIME															
X-3-11s	161121-25	11/10/16	1900		1		ice	X									archive	
X-6-11s	-26		1903		1			X									archive	
I-1-211D	-27		1926		1			X										
X-1-211s	-28		1935		1			X										
X-3-211s	-29		1940		1			X									archive	
X-6-211s	-30		1942		1			X									archive	
I-1-NW	-31		2007		1			X										
I-3-NW	-32		2009		1			X									archive	
I-1-211D-DUP	-33		1926		1			X										
I-1-RD	-34		2014		1			X										
I-3-RD	-35		2017		1			X									archive	
I-6-RD	-36		2019		1			X									archive	
X-1-Rs	-37		2023		1			X										
X-3-Rs	-38		2026		1			X									archive	
X-6-Rs	-39		2029		1			X									archive	

Company Name: Alta Environmental

Address: 3777 Long Beach Blvd, Annex Bldg

City/State/Zip: Long Beach, CA 90807

Project Contact: Cesar Ruvalcaba

Tel: 562-493-5777

Fax/Email:

Sampler's Signature: F. Ruvalcaba / T. Rizami

Project Name/ID: SM5D-16-6S14

Relinquished by: [Signature]

Received by: Theresa Rizami

Date & Time: 11/10/16 2100

Relinquished by: Theresa Rizami

Received by: [Signature]

Date & Time: 11/10/16 1020

Relinquished by: [Signature]

Received by: [Signature]

Date & Time: 11/24/16 1427

Instructions for Sample Storage After Analysis:

☐ Dispose of ☐ Return to Client ☐ Store (30 Days)

☐ Other:

CHAIN OF CUSTODY RECORD

Date: 11/21/16

WHITE WITH SAMPLE • YELLOW TO CLIENT

CA-DHS ELAP CERTIFICATE #1555

Other: _____

Company Name: Alta Environmental		Project Contact: Cesar Rualcaba		Sampler's Signature: F. Rualcaba / J. Riazami <i>[Signature]</i>	
Address: 3777 Long Beach Blvd, Annex Bldg		Tel: 562-495-5777		Project Name/ID: SMOD-16-6514	
City/State/Zip: Long Beach CA 90807		Fax/Email:			
Relinquished by: <i>[Signature]</i>	Received by: Therese Riazami <i>[Signature]</i>	Date & Time: 11/16/20	Instructions for Sample Storage After Analysis: <input type="checkbox"/> Dispose of <input type="checkbox"/> Return to Client <input type="checkbox"/> Store (30 Days) <input type="checkbox"/> Other:		
Relinquished by: Therese Riazami <i>[Signature]</i>	Received by: <i>[Signature]</i> (LINTI DESUETI)	Date & Time: 11/16/20			
Relinquished by: <i>[Signature]</i> (Cristina Morales)	Received by: <i>[Signature]</i>	Date & Time: 11/16/20			

CHAIN OF CUSTODY RECORD

Date: December 1, 2016

Mr. Cesar Ruvalcaba
Alta Environmental
3777 Long Beach Blvd, Annex Building
Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com

Project: **Webster E.S.**
Lab I.D.: **161122-83 through -134**

Dear Mr. Ruvalcaba:

The **analytical results** for the solid samples, received by our laboratory on November 22, 2016, are attached. The samples were received intact, and accompanying chain of custody.

Enviro-Chem appreciates the opportunity to provide you and your company this and other services. Please do not hesitate to call us if you have any questions.

Sincerely,



Curtis Desilets
Vice President/Program Manager



Andy Wang
Laboratory Manager

LABORATORY REPORT

CUSTOMER: **Alta Environmental**
3777 Long Beach Blvd, Annex Building, Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviro.com

PROJECT: **Webster E.S.**

DATE RECEIVED: 11/22/16
DATE SAMPLED: 11/21/16 DATE EXTRACTED: 11/30/16
MATRIX: SOLID DATE ANALYZED: 11/30&12/01/16
REPORT TO: MR. CESAR RUVALCABA DATE REPORTED: 12/01/16

PCBs ANALYSIS

METHOD: EPA 3540C/8082; PAGE 1 OF 2

UNIT: mg/Kg = MILLIGRAM PER KILOGRAM = PPM

SAMPLE I.D.	LAB I.D.	PCB-1016	PCB-1221	PCB-1232	PCB-1242	PCB-1248	PCB-1254	PCB-1260	TOTAL PCBs*	DF
<u>I-1-Caf</u>	161122-83	ND	ND	ND	ND	ND	ND	ND	ND	2^
<u>X-1-Caf</u>	161122-86	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>I-1-G2</u>	161122-89	ND	ND	ND	ND	ND	ND	ND	ND	4^
<u>X-1-G2</u>	161122-92	ND	ND	ND	ND	ND	ND	ND	ND	40^
<u>I-1-H1</u>	161122-95	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>X-1-H1</u>	161122-98	ND	ND	ND	ND	ND	ND	ND	ND	2^
<u>X-1-S10</u>	161122-101	ND	ND	ND	1.45	0.309	ND	ND	1.76	10
<u>X-1-S10</u>										
<u>Dup</u>	161122-102	ND	ND	ND	1.37	0.371	ND	ND	1.74	10
<u>X-1-C10</u>	161122-104	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>I-1-10A</u>	161122-107	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>X-1-10B</u>	161122-110	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>I-1-10B</u>	161122-113	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>I-1-20</u>	161122-116	ND	ND	ND	ND	ND	ND	ND	ND	4^
<u>X-1-20</u>	161122-119	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>I-1-20B</u>	161122-122	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>I-1-20</u>										
<u>Dup</u>	161122-123	ND	ND	ND	ND	ND	ND	ND	ND	20^
<u>X-1-20B</u>	161122-126	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>I-1-20B</u>										
<u>Split</u>	161122-129	ND	ND	ND	ND	ND	ND	ND	ND	2^
<u>I-1-20</u>										
<u>Split</u>	161122-131	ND	ND	ND	ND	ND	ND	ND	ND	10^
<u>Rinse Set</u>	161122-133	ND	ND	ND	ND	ND	ND	ND	ND	1
<u>Method Blank</u>		ND	ND	ND	ND	ND	ND	ND	ND	1

PQL 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01

COMMENTS

DF = Dilution Factor

PQL = Practical Quantitation Limit


Actual Detection Limit = DF X PQL

ND = Non-Detected Or Below the Actual Detection Limit

^ = Actual detection limit raised due to limited sample quantity

* = Sum of the PCB 1016, 1221, 1232, 1242, 1248, 1254 and 1260

*** = The concentration exceeds the TTLC Limit of 50, and the sample is defined as hazardous waste as per CCR-TITLE 22 (if marked)

Data Reviewed and Approved by: 

CAL-DHS ELAP CERTIFICATE No.: 1555

LABORATORY REPORT

CUSTOMER: Alta Environmental
3777 Long Beach Blvd, Annex Building, Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com
PROJECT: Webster E.S.

DATE SAMPLED: 11/21/16 DATE RECEIVED: 11/22/16
MATRIX: SOLID DATE EXTRACTED: 11/30/16
REPORT TO: MR. CESAR RUVALCABA DATE ANALYZED: 12/01/16
DATE REPORTED: 12/01/16

PCBs ANALYSIS

METHOD: EPA 3540C/8082; PAGE 2 OF 2

UNIT: mg/Kg = MILLIGRAM PER KILOGRAM = PPM

SAMPLE I.D.	LAB I.D.	PCB- 1016	PCB- 1221	PCB- 1232	PCB- 1242	PCB- 1248	PCB- 1254	PCB- 1260	TOTAL PCBs*	DF
Seal Blank	161122-134	ND	ND	ND	ND	ND	ND	ND	ND	1
Method Blank		ND	ND	ND	ND	ND	ND	ND	ND	1
PQL		0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	

COMMENTS

DF = Dilution Factor


PQL = Practical Quantitation Limit

Actual Detection Limit = DF X PQL

ND = Non-Detected Or Below the Actual Detection Limit

* = Sum of the PCB 1016, 1221, 1232, 1242, 1248, 1254 and 1260

*** = The concentration exceeds the TTLC Limit of 50, and the sample is defined as hazardous waste as per CCR-TITLE 22 (if marked)

Data Reviewed and Approved by: 

CAL-DHS ELAP CERTIFICATE No.: 1555

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**Date Analyzed: 11/30-12/1/2016Unit: mg/Kg(PPM)**Matrix Spike (MS)/Matrix Spike Duplicate (MSD)****Spiked Sample Lab I.D.:** **161130-LCS1/2**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.104	104%	0.115	115%	10%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.112	112%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	161122-83	161122-86	161122-89	161122-92	161122-95	161122-98
Tetra-chloro-meta-xylene	50-150	145%	129%	116%	115%	138%	125%	121%
Decachlorobipneyl	50-150	119%	89%	78%	97%	80%	90%	84%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	161122-101	161122-102	161122-104	161122-107	161122-110	161122-113	161122-116	161122-119
Tetra-chloro-meta-xylene	133%	145%	125%	133%	132%	142%	131%	123%
Decachlorobipneyl	74%	94%	86%	110%	89%	87%	67%	80%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	161122-122	161122-123	161122-126	161122-129	161122-131	161122-133
Tetra-chloro-meta-xylene	122%	116%	144%	134%	102%	142%
Decachlorobipneyl	80%	57%	78%	76%	81%	90%

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By:

Final Reviewer:

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**

Date Analyzed: 12/1/2016

Unit: mg/Kg(PPM)

Matrix Spike (MS)/Matrix Spike Duplicate (MSD)

Spiked Sample Lab I.D.: **161201-LCS1/2**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.104	104%	0.111	111%	7%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.103	103%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	161122-134					
Tetra-chloro-meta-xylene	50-150	120%	124%					
Decachlorobipneyl	50-150	115%	91%					

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.								
Tetra-chloro-meta-xylene								
Decachlorobipneyl								

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.						
Tetra-chloro-meta-xylene						
Decachlorobipneyl						

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: 

Final Reviewer: 

Date: December 5, 2016

Mr. Cesar Ruvalcaba
Alta Environmental
3777 Long Beach Blvd, Annex Building
Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com

Project: **Webster E.S.**
Lab I.D.: **161122-83 through -134**

Dear Mr. Ruvalcaba:

The **additional PCB results** for the solid samples, received by our laboratory on November 22, 2016, are attached. The samples were received chilled, intact, accompanying chain of custody and also stored per the EPA protocols.

Enviro-Chem appreciates the opportunity to provide you and your company this and other services. Please do not hesitate to call us if you have any questions.

Sincerely,


Curtis Desilets
Vice President/Program Manager


Andy Wang
Laboratory Manager

LABORATORY REPORT

CUSTOMER: Alta Environmental
3777 Long Beach Blvd, Annex Building, Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com
PROJECT: Webster E.S.

DATE SAMPLED: 11/21/16 DATE RECEIVED: 11/22/16
MATRIX: SOLID DATE EXTRACTED: 12/05/16
REPORT TO: MR. CESAR RUVALCABA DATE ANALYZED: 12/05/16
DATE REPORTED: 12/05/16

PCBs ANALYSIS

METHOD: EPA 3540C/8082

UNIT: mg/Kg = MILLIGRAM PER KILOGRAM = PPM

SAMPLE I.D.	LAB I.D.	PCB- 1016	PCB- 1221	PCB- 1232	PCB- 1242	PCB- 1248	PCB- 1254	PCB- 1260	TOTAL PCBs* DF
X-3-S10	161122-103	ND	ND	ND	ND	0.185	ND	ND	0.185 4
Method Blank		ND	ND	ND	ND	ND	ND	ND	ND 1
PQL		0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01

COMMENTS

DF = Dilution Factor

PQL = Practical Quantitation Limit

Actual Detection Limit = DF X PQL

ND = Non-Detected Or Below the Actual Detection Limit

* = Sum of the PCB 1016, 1221, 1232, 1242, 1248, 1254 and 1260

*** = The concentration exceeds the TTLC Limit of 50, and the sample is defined as hazardous waste as per CCR-TITLE 22 (if marked)

Data Reviewed and Approved by: [Signature]
CAL-DHS ELAP CERTIFICATE No.: 1555

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**

Date Analyzed: 12/5/2016

Unit: mg/Kg(PPM)

Matrix Spike (MS)/Matrix Spike Duplicate (MSD)

Spiked Sample Lab I.D.: **161205-LCS1/2**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.101	101%	0.100	100%	2%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.107	107%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	161122-103					
Tetra-chloro-meta-xylene	50-150	121%	124%					
Decachlorobipneyl	50-150	77%	77%					

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.								
Tetra-chloro-meta-xylene								
Decachlorobipneyl								

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.						
Tetra-chloro-meta-xylene						
Decachlorobipneyl						

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: 

Final Reviewer: 

Enviro-Chem, Inc. Laboratories1214 E. Lexington Avenue,
Pomona, CA 91766

Tel: (909) 590-5905 Fax: (909) 590-5907

CA-DHS ELAP CERTIFICATE #1555

Turnaround Time

0 Same Day

0 24 Hours

0 48 Hours

0 72 Hours

☒ 1 Week (Standard)

Other:

SAMPLE ID	LAB ID	SAMPLING DATE TIME		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
I-1-Caf	1611-83	11-21-16	1610	40/12	1	107/16	X											
I-3-Caf	-84	11-21-16	1615		1	107/16											Archive	
I-6-Caf	-85	11-21-16	1622		1	107/16											Archive	
X-1-Caf	-86	11-21-16	1630		1		X											
X-3-Caf	-87	11-21-16	1633		1												Archive	
X-6-Caf	-88	11-21-16	1636		1												Archive	
I-1-G2	-89	11-21-16	1700		1		X											
I-3-G2	-90	11-21-16	1701		1												Archive	
I-6-G2	-91	11-21-16	1702		1												Archive	
X-1-G2	-92	11-21-16	1709		1		X											
X-3-G2	-93	11-21-16	1713		1												Archive	
X-6-G2	-94	11-21-16	1715		1												Archive	
I-1-H1	-95	11-21-16	1800		1		X											
I-3-H1	-96	11-21-16	1803		1												Archive	
I-6-H1	-97	11-21-16	1806		1												Archive	

Company Name: <u>Alta Environmental</u>		Project Contact: <u>Cesar Rivalcob</u>		Sampler's Signature: <u>[Signature]</u>	
Address:		Tel:		Project Name/ID:	
City/State/Zip:		Fax/Email: <u>Cesar.Rivalcob@altaenv.com</u>		Webster E.S.	
Relinquished by: <u>[Signature]</u>		Received by: <u>[Signature]</u>		Date & Time: <u>11/23/16 1045</u>	
Relinquished by: <u>[Signature]</u>		Received by: <u>[Signature]</u>		Date & Time: <u>11/24/16 1150</u>	
Relinquished by:		Received by:		Date & Time:	

Instructions for Sample Storage After Analysis:	
<input type="checkbox"/> Dispose of	<input type="checkbox"/> Return to Client
<input type="checkbox"/> Other:	<input checked="" type="checkbox"/> Store (30 Days)

CHAIN OF CUSTODY RECORDDate: 11-21-16

WHITE WITH SAMPLE • YELLOW TO CLIENT

Page 1 of 1

Enviro-Chem, Inc. Laboratories1214 E. Lexington Avenue,
Pomona, CA 91766

Tel: (909) 590-5905 Fax: (909) 590-5907

CA-DHS ELAP CERTIFICATE #1555

Turnaround Time

0 Same Day

0 24 Hours

0 48 Hours

0 72 Hours

0 7 Week (Standard)

Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required												COMMENTS
		DATE	TIME																	
X-1-H1	16112-98	11.21.16	1811		1		Ice	X												
X-3-H1	-99	11.21.16	1815		1													Archive		
X-6-H1	-100	11.21.16	1817		1													Archive		
X-1-S10	-101	11.21.16	1842		1			X												
X-1-S10 D-p	-102	11.21.16	1850		1			X												
X-3-S10	-103	11.21.16	1851		1			X										Archive		
X-1-C10	-104	11.21.16	1856		1			X												
X-3-C10	-105	11.21.16	1900		1													Archive		
X-6-C10	-106	11.21.16	1903		1													Archive		
I-1-10A	-107	11.21.16	1911		1			X												
I-3-10A	-108	11.21.16	1913		1													Archive		
I-6-10A	-109	11.21.16	1921		1													Archive		
X-1-10B	-110	11.21.16	1935		1			X												
X-3-10B	-111	11.21.16	1938		1													Archive		
X-6-10B	-112	11.21.16	1945		1													Archive		

Company Name: Alta Environmental		Project Contact: Cesar Ruvalcaba		Sampler's Signature: <i>[Signature]</i>	
Address:		Tel:		Project Name/ID:	
City/State/Zip:		Fax/Email: Cesar.Ruvalcaba@altaenv.com		Webster E.S.	
Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Date & Time: 11/23/16/84P	Instructions for Sample Storage After Analysis:		
Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Date & Time: 11/24/16/1500	O Dispose of O Return to Client <input checked="" type="checkbox"/> Store (30 Days)		
Relinquished by:	Received by:	Date & Time:	O Other:		

CHAIN OF CUSTODY RECORD

Date: 11-21-16

WHITE WITH SAMPLE • YELLOW TO CLIENT

Page 2 of 34

Enviro-Chem, Inc. Laboratories1214 E. Lexington Avenue,
Pomona, CA 91766

Tel: (909) 590-5905 Fax: (909) 590-5907






CA-DHS ELAP CERTIFICATE #1555

Turnaround Time

☐ Same Day☐ 24 Hours☐ 48 Hours☐ 72 Hours☒ 1 Week (Standard)

Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
		DATE	TIME															
I-1-10B	1412-113	11-21-16	1948		1		ICE	X										
I-3-10B	-114	11-21-16	1950		1												Archive	
I-6-10B	-115	11-21-16	1952		1												Archive	
I-1-20	-116	11-21-16	2038		1			X										
I-3-20	-117	11-21-16	2040		1												Archive	
I-6-20	-118	11-21-16	2042		1												Archive	
X-1-20	-119	11-21-16	2044		1			X										
X-3-20	-120	11-21-16	2046		1												Archive	
X-6-20	-121	11-21-16	2048		1												Archive	
I-1-20B	-122	11-21-16	2052		1			X										
I-1-20Dup	-123	11-21-16	2054		1			X										
I-3-20B	-124	11-21-16	2058		1												Archive	
I-6-20B	-125	11-21-16	2100		1												Archive	
X-1-20B	-126	11-21-16	2103		1			X										
X-3-20B	-127	11-21-16	2106		1												Archive	

Company Name: Alta Environmental		Project Contact: Cesar Ruelas -		Sampler's Signature: 	
Address:		Tel:		Project Name/ID: Webster E.S. -	
City/State/Zip:		Fax/Email: Cesar.Ruelas@altaenviro.com			
Relinquished by: 	Received by: 	Date & Time: 11/21/16 941		Instructions for Sample Storage After Analysis:	
Relinquished by: 	Received by: 	Date & Time: 11/22/16/1500		<input type="radio"/> Dispose of <input type="radio"/> Return to Client <input checked="" type="radio"/> Store (30 Days)	
Relinquished by:	Received by:	Date & Time:		<input type="radio"/> Other:	

CHAIN OF CUSTODY RECORD

Date: 11-21-16

WHITE WITH SAMPLE - YELLOW TO CLIENT

Page 3 of 4



EMSL Analytical, Inc.

200 Route 130 North, Cinnaminson, NJ 08077

Phone: (856) 303-2500 Fax: (856) 858-4571 Email: EnvChemistry2@emsl.com

Attn:

**CESAR RUVALCABA
Alta Environmental
3777 Long Beach Blvd
Annex Building
Long Beach, CA 90807**

Phone: (562) 495-5777

Fax:

12/1/2016

The following analytical report covers the analysis performed on samples submitted to EMSL Analytical, Inc. on 11/23/2016. The results are tabulated on the attached data pages for the following client designated project:

Window and doors replacement project at Webster ES

The reference number for these samples is EMSL Order #011608011. Please use this reference when calling about these samples. If you have any questions, please do not hesitate to contact me at (856) 303-2500.

Approved By:

Phillip Worby, Chemistry Laboratory Manager



The test results contained within this report meet the requirements of NELAP and/or the specific certification program that is applicable, unless otherwise noted.

NELAP Certifications: NJ 03036, NY 10872, PA 68-00367, CA ELAP 187

The samples associated with this report were received in good condition unless otherwise noted. This report relates only to those items tested as received by the laboratory. The QC data associated with the sample results meet the recovery and precision requirements established by the NELAP, unless specifically indicated. All results for soil samples are reported on a dry weight basis, unless otherwise noted. This report may not be reproduced except in full and without written approval by EMSL Analytical, Inc.

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (856) 303-2500 / (856) 858-4571

<http://www.EMSL.com>EnvChemistry2@emsl.com

EMSL Order: 011608011
CustomerID: ALTA34
CustomerPO: SMSD-16-6415
ProjectID:

Attn: **CESAR RUVALCABA**
Alta Environmental
3777 Long Beach Blvd
Annex Building
Long Beach, CA 90807

Phone: (562) 495-5777
Fax:
Received: 11/23/16 9:45 AM

Project: **Window and doors replacement project at Webster ES**

Analytical Results

Client Sample Description X-1-20B split

Collected: 11/21/2016 **Lab ID:** 0001

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1221	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1232	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1242	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1248	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1254	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1260	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1262	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1268	ND	0.49	mg/Kg	11/30/2016	AB	12/1/2016	EH

Client Sample Description X-1-20 split

Collected: 11/21/2016 **Lab ID:** 0002

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1221	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1232	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1242	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1248	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1254	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1260	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1262	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH
3540C/8082A	Aroclor-1268	ND	0.98	mg/Kg	11/30/2016	AB	12/1/2016	EH

Definitions:

ND - indicates that the analyte was not detected at the reporting limit

RL - Reporting Limit (Analytical)

EMSL Analytical Inc.

SOIL / SOLID SURROGATE RECOVERY

Lab Name:		EMSL Analytical				
* : Values outside of QC limits D: Surrogate diluted out						
Compound Name:		TCX	TCX2	DCB	DCB2	Total Out
CAS #:		877-09-8	877-09-8	2051-24-3	2051-24-3	
QC Limits:		(30-137)	(30-137)	(30-138)	(30-138)	
011608011-2 MS	12/01/16 13:09	76 D	84 D	93 D	95 D	0
011608040-9 4X	12/01/16 13:22	68 D	72 D	72 D	70 D	0
011608011-2 MSD	12/01/16 13:36	72 D	79 D	88 D	89 D	0
011608040-11 3X	12/01/16 13:52	92 D	92 D	91 D	85 D	0
LCS 1 OP 3530-40	12/01/16 10:22	75	83	90	91	0
011608065-1 5X	12/01/16 10:50	82 D	88 D	89 D	93 D	0
011608009-1 4X	12/01/16 11:18	76 D	84 D	90 D	90 D	0
011608009-2 4X	12/01/16 11:45	65 D	72 D	82 D	83 D	0
011608040-2 4X	12/01/16 11:54	97 D	98 D	87 D	89 D	0
011608011-1 10X	12/01/16 12:13	66 D	73 D	87 D	86 D	0
011608040-3 2X	12/01/16 12:23	79 D	77 D	74 D	75 D	0
011608011-2 4X	12/01/16 12:41	70 D	78 D	90 D	91 D	0
011608040-4 4X	12/01/16 12:53	82 D	86 D	81 D	90 D	0
011608040-12 CU	12/01/16 14:22	101	91	103	86	0
MB 1 OP 3530-40	12/01/16 09:55	74	83	90	94	0
TCX=Tetrachloro-m-xylene DCB=Decachlorobiphenyl						

EMSL Analytical Inc.

PCB ORGANICS ANALYSIS DATA SHEET

		Customer Sample#:	MB 1 OP 3530-40 CU	
Lab Name:	EMSL Analytical			
EMSL Sample ID:			Project:	
Lab File ID:	X53064.D		Sample Matrix:	
Instrument ID:	ECD-X		Sampling Date:	
Analyst:	EH		Date Extracted:	
GC Column:	CLPest I (0.25 mm)		Analysis Date	
GC Column 2:	CLPest II (0.25 mm)		Sample wt/vol:	
% Moisture:	0		Dilution Factor:	
PH:	0		Concentrated Extract Vol:	
GPC Cleanup(Y/N):	N		Injection Volume:	
Extraction Type:	3540C		Sulfur Cleanup:	
Method:	SW846 8081b/8082a			
CAS NO	COMPOUND	Report Limit (mg/Kg)	CONC. (mg/Kg)	Q
12674-11-2	Aroclor 1016	0.050		U
11104-28-2	Aroclor 1221	0.050		U
11141-16-5	Aroclor 1232	0.050		U
53469-21-9	Aroclor 1242	0.050		U
12672-29-6	Aroclor 1248	0.050		U
11097-69-1	Aroclor 1254	0.050		U
11096-82-5	Aroclor 1260	0.050		U
37324-23-5	Aroclor 1262	0.050		U
11100-14-4	Aroclor 1268	0.050		U
Qualifier Definitions U = Undetected B = Compound detected in method blank E = Estimated value J = Estimated Concentration. Detected below Practical Quantitation Level D = Dilution40%				

EMSL Analytical Inc.

SOIL / SOLID LCS/QCS/ LFB RECOVERY

	Lab Name:	EMSL Analytical		Original	LCS 1 OP		
				File ID:	X53064.D/X53065.D		
	* : Values outside of						
	COMPOUND	CAS NO	LOW LIMIT	HIGH LIMIT	SPIKE ADDED mg/Kg	LCS CONC. mg/Kg	LCS REC%
1	Aroclor 1016	12674-11-2	58	123	1.500	1.370	91
2	Aroclor 1260	11096-82-5	63	131	1.500	1.454	97
Total Out							0 of 2

EMSL Analytical Inc.

SOIL / SOLID MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

[illegible]



EMSL ANALYTICAL, INC.
LABORATORY / PRODUCTS / TRAINING

Environmental Chemistry Chain of Custody EMSL Order Number (Lab Use Only):

011608011

EMSL ANALYTICAL, INC.
200 ROUTE 130 NORTH
CHERRINGTON, NJ 08077
PHONE: (800) 220-3675
FAX: (856) 786-5974

Report To Contact Name: Cesar Ruvalcaba				Bill To Company: Same			
Company Name: Alta Environmental				Attention To:			
Street: 3777 Long Beach Boulevard, Annex Building				Street:			
City: Long Beach		State/Province:		City:		State/Province:	
Phone: 562-495-5777		Fax:		Phone:		Fax:	
Project Name: Window and doors replacement project at Webster ES				Email Results To: Cesar Ruvalcaba@altaviron.com			
Number of Samples in Shipment: 2				Date of Shipment: 11/22/16		Purchase Order: SMSD-16-0415	
Standard Turnaround Time: <input type="checkbox"/> 2 Weeks				The following TAT's are subject to lab approval: <input checked="" type="checkbox"/> 1 Week <input type="checkbox"/> 4 Days <input type="checkbox"/> 3 Days <input type="checkbox"/> 2 Days <input type="checkbox"/> 1 Day			
Failure to complete will hinder processing of samples				List Test(s) Needed			
Client Sample ID	Comp	Grab	Date/Time	Matrix W=Water S=Soil A=Air SL=Sludge O=Other	Preservative 1=HCL 2=HNO3 3=H2SO4 4=ICE 5=Other	EPA method 8082 (PCBs)	Comments
X-1-20B split	X		11/22/16 2114	O	4	X	
X-1-20 split	X		11/21/16 2120	O	4	X	
Released By (Signature) <i>FR</i>				Date & Time 11/22/16 9am		Received By <i>4c</i>	
Fabian Ruvalcaba						Date & Time 11/23/16 0945	
Please indicate reporting requirements: <input type="checkbox"/> Results Only <input checked="" type="checkbox"/> Results and QC <input type="checkbox"/> Reduced Deliverables <input type="checkbox"/> Disk Deliverable <input type="checkbox"/> Other _____							
Instructions or Comments:							

Enviro-Chem, Inc. Laboratories
1214 E. Lexington Avenue,
Pomona, CA 91766
Tel: (909) 590-5905 Fax: (909) 590-5907

Enviro-Chem, Inc. Laboratories
1214 E. Lexington Avenue,
Pomona, CA 91766
Tel: (909) 590-5905 Fax: (909) 590-5907

Tel: (909) 590-5905 Fax: (909) 590-5907

CA-DHS ELAP CERTIFICATE #1555

[illegible]

Company Name: Alt Environmental

Address:

City/State/Zip:

Relinquished by:

Relinquished by:

Relinquished by:

Project Contact: Cesar Ruvelcab-

Tel:

Fax/Email:

Received by:

Received by:

Received by:

Sampler's Signature

Project Name/ID:

Webster E.S.

Instructions for Sample Storage After Analysis:

☐ Dispose of ☐ Return to Client ☒ ~~Store (30 Days)~~

0 Other:

CHAIN OF CUSTODY RECORD

WHITE WITH SAMPLE • YELLOW TO CLIENT

Enviro - Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766 Tel (909) 590-5905 Fax (909) 590-5907

Date: January 27, 2017

Mr. Cesar Ruvalcaba
Alta Environmental
3777 Long Beach Blvd, Annex Building
Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com


Project: **Webster ES Additional Step-Out**
Lab I.D.: **170120-33 through -62**

Dear Mr. Ruvalcaba:


The **analytical results** for the solid samples, received by our laboratory on January 20, 2017, are attached. The samples were received intact, and accompanying chain of custody.

Enviro-Chem appreciates the opportunity to provide you and your company this and other services. Please do not hesitate to call us if you have any questions.

Sincerely,



Curtis Desilets
Vice President/Program Manager



Andy Wang
Laboratory Manager

LABORATORY REPORT

CUSTOMER: **Alta Environmental**
3777 Long Beach Blvd, Annex Building, Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com
PROJECT: **Webster ES Additional Step-Out**

DATE SAMPLED: 01/19/17 DATE RECEIVED: 01/20/17
MATRIX: SOLID DATE EXTRACTED: 01/25-26/17
REPORT TO: MR. CESAR RUVALCABA DATE ANALYZED: 01/26/17
DATE REPORTED: 01/27/17

PCBs ANALYSIS

METHOD: EPA 3540C/8082

UNIT: mg/Kg = MILLIGRAM PER KILOGRAM = PPM

SAMPLE I.D.	LAB I.D.	PCB- 1016	PCB- 1221	PCB- 1232	PCB- 1242	PCB- 1248	PCB- 1254	PCB- 1260	TOTAL PCBs*	DF
1-0119	170120-33	ND	ND	ND	ND	ND	ND	ND	ND	40^
4-0119	170120-36	ND	ND	ND	ND	ND	ND	ND	ND	40^
7-0119	170120-39	ND	ND	ND	ND	ND	ND	ND	ND	40^
10-0119	170120-42	ND	ND	ND	ND	ND	ND	ND	ND	20^
13-0119	170120-45	ND	ND	ND	ND	ND	ND	ND	ND	40^
16-0119	170120-48	ND	ND	ND	ND	ND	ND	ND	ND	40^
18-0119	170120-50	ND	ND	ND	ND	ND	ND	ND	ND	20^
22-0119	170120-53	ND	ND	ND	ND	ND	ND	ND	ND	20^
25-0119	170120-56	ND	ND	ND	ND	ND	ND	ND	ND	100^
27-0119	170120-58	ND	ND	ND	ND	ND	ND	ND	ND	50^
28-0119	170120-59	ND	ND	ND	ND	ND	ND	ND	ND	100^
29-0119	170120-60	ND	ND	ND	ND	ND	ND	ND	ND	20^
Method Blank		ND	ND	ND	ND	ND	ND	ND	ND	1

PQL 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01

COMMENTS

DF = Dilution Factor

PQL = Practical Quantitation Limit

Actual Detection Limit = DF X PQL

ND = Non-Detected Or Below the Actual Detection Limit

* = Sum of the PCB 1016, 1221, 1232, 1242, 1248, 1254 and 1260

^ = Actual detection limit raised due to matrix interference

*** = The concentration exceeds the TTLC Limit of 50, and the sample is defined as hazardous waste as per CCB-TITLE 22 (if marked)

Data Reviewed and Approved by: 
CAL-DHS ELAP CERTIFICATE No.: 1555

Enviro-Chem, Inc. Laboratories
 1214 E. Lexington Avenue,
 Pomona, CA 91766
 Tel: (909) 590-5905 Fax: (909) 590-5907
CA-DHS ELAP CERTIFICATE #1555

Turnaround Time
☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☐ 1 Week (Standard)
 Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
		DATE	TIME															
1-0119	170120-33	01/19/17	1745	Bulk	1		ice	X										
2-0119	- 34		1757		402			X										archive
3-0119	- 35		1802					X										archive
4-0119	- 36		1808					X										
5-0119	- 37		1813					X										archive
6-0119	- 38		1820					X										archive
7-0119	- 39		1850					X										
8-0119	- 40		1858					X										archive
9-0119	- 41		1905					X										archive
10-0119	- 42		1910					X										
11-0119	- 43		1914					X										archive
12-0119	- 44		1917					X										archive
13-0119	- 45		1923					X										
14-0119	- 46		1930					X										archive
15-0119	- 47		1935					X										archive

Company Name: Alta Environmental

Address: 3777 Long Beach Blvd, Annex Bldg

City/State/Zip: Long Beach, CA, 90808

Relinquished by: F. Ruvakaba 1-19-17 (2230)

Relinquished by: Alta Pujari 1/20/17

Relinquished by:

Project Contact: Cesar Ruvakaba

Tel: 562-498-8777

Fax:

Received by: T. Rizami 2230

Received by:

Received by:

Sampler's Signature: [Signature]

Project Name/ID: webster ES
Additional step-out

Date & Time: 1-19-17

Date & Time: 1-20-17/0750

Date & Time: 1/20/17/1230

Instructions for Sample Storage After Analysis:

☐ Dispose of ☐ Return to Client ☐ Store (30 Days)

☐ Other:

CHAIN OF CUSTODY RECORD

Date: _____

WHITE WITH SAMPLE • YELLOW TO CLIENT

Enviro-Chem, Inc. Laboratories
 1214 E. Lexington Avenue,
 Pomona, CA 91766
 Tel: (909) 590-5905 Fax: (909) 590-5907
CA-DHS ELAP CERTIFICATE #1555

Turnaround Time
☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☐ 1 Week (Standard)
 Other:

SAMPLE ID	LAB ID	SAMPLING DATE	SAMPLING TIME	MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
16-0119	170/20-48	01/19/17	1940	Bulk	1		ICE	X										
17-0119	-49		1949			402		X									archive	
18-0119	-50		1988					X										
20-0119	-51		1984					X									archive	
21-0119	-52		2002					X									archive	
22-0119	-53		2010					X										
23-0119	-54		2013					X									archive	
24-0119	-55		2018					X									archive	
25-0119	-56		2051					X										
26-0119	-57		2058					X									archive	
27-0119	-58		2108					X										
28-0119	-59		2111					X										
29-0119	-60		2115					X										
30-0119	-61		2118					X									archive	
31-0119	-62		2123					X									archive	

Company Name: **Alta Environmental**


Address: **3777 Long Beach Blvd, Annex Bldg**

City/State/Zip: **Long Beach, CA, 90807**

Project Contact: **Cesar Ruvalcaba**

Tel: **562-498-5777**

Fax:

Sampler's Signature: 

Project Name/ID: **webster ES, additional step-out**

Relinquished by: **F. Ruvalcaba** 1-19-17 (2230)

Relinquished by: **Alta Environmental** 1/20/17

Relinquished by:

Received by: **T. Riazam** 2230

Received by: **Alta Environmental**

Received by: **WJP**

Date & Time: **1-19-17**

Date & Time: **1-20-17 0950**

Date & Time: **1/20/17 11230**

Instructions for Sample Storage After Analysis:

☐ Dispose of ☐ Return to Client ☐ Store (30 Days)

☐ Other:

CHAIN OF CUSTODY RECORD


Date: _____

WHITE WITH SAMPLE • YELLOW TO CLIENT

Software Version : 6.3.2.0646
 Sample Name : 170120-33 5/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/5
 Sample Amount : 1.000000
 Cycle : 10

Date : 1/27/2017 8:59:27 AM
 Data Acquisition Time : 1/26/2017 2:40:44 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1701\170124\B115.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\170124.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
14	1-Bromo-2-Nitrobenzene	3.18	3717329.18	633791.51	
16	Tetra chloro-meta-xylene	4.03	1794868.86	556612.34	115.469
	PCB (1016+1260)	7.27	2305773.82	460391.40	0.194
60	Decachlorobiphenyl	11.84	3390126.78	663834.15	120.998
			11208098.65	2314629.40	236.661

Software Version : 6.3.2.0646
 Sample Name : 170120-36 5/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/6
 Sample Amount : 1.000000
 Cycle : 11

Date : 1/27/2017 9:00:45 AM
 Data Acquisition Time : 1/26/2017 3:01:07 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1701\170124\B116.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\170124.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
13	1-Bromo-2-Nitrobenzene	3.19	3237963.15	614160.97	-----
18	Tetra chloro-meta-xylene	4.03	1693889.62	566731.22	125.106
	PCB (1016+1260)	7.26	2166221.40	458981.59	0.209
64	Decachlorobiphenyl	11.83	2004473.07	605691.06	82.134
			9102547.23	2245564.84	207.449

Software Version : 6.3.2.0646
 Sample Name : 170120-39 5/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/7
 Sample Amount : 1.000000
 Cycle : 12

Date : 1/27/2017 9:01:52 AM
 Data Acquisition Time : 1/26/2017 3:21:31 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1701\170124\B117.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\B117.rst




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
12	1-Bromo-2-Nitrobenzene	3.18	3559956.41	600192.17	
14	Tetra chloro-meta-xylene	4.04	1686009.53	565389.02	113.261
	PCB (1016+1260)	7.27	3086014.10	518917.96	0.271
57	Decachlorobiphenyl	11.84	2506142.21	557330.13	93.402
			10838122.25	2241829.28	206.933

Software Version : 6.3.2.0646
 Sample Name : 170120-42 10/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/8
 Sample Amount : 1.000000
 Cycle : 13

Date : 1/27/2017 9:02:53 AM
 Data Acquisition Time : 1/26/2017 3:41:55 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017E\1701E\170124\B118.rst
 Sequence File : D:\GC DATA\GC-E\02017E\1701E\170124\B118.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
15	1-Bromo-2-Nitrobenzene	3.18	3498234.38	596174.30	
18	Tetra chloro-meta-xylene	4.03	1639086.61	560868.67	112.051
	PCB (1016+1260)	7.26	2999524.71	486247.48	0.268
63	Decachlorobiphenyl	11.83	2738526.35	580354.81	103.863
			10875372.04	2223645.26	216.183

Software Version : 6.3.2.0646
 Sample Name : 170120-45 5/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/9
 Sample Amount : 1.000000
 Cycle : 14

Date : 1/27/2017 9:03:59 AM
 Data Acquisition Time : 1/26/2017 4:02:16 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1701\170124\B119.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\170124.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
13	1-Bromo-2-Nitrobenzene	3.18	3057387.22	616990.97	
17	Tetra chloro-meta-xylene	4.03	1656375.33	562422.52	129.561
	PCB (1016+1260)	7.26	2776780.38	579492.18	0.284
56	Decachlorobiphenyl	11.83	2768660.57	569638.81	120.147
			10259203.50	2328544.48	249.991

Software Version : 6.3.2.0646
 Sample Name : 170120-48 5/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/10
 Sample Amount : 1.000000
 Cycle : 15

Date : 1/27/2017 9:05:02 AM
 Data Acquisition Time : 1/26/2017 4:22:38 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017E\1701E\170124\B120.rst
 Sequence File : D:\GC DATA\GC-E\02017E\1701E\170124\B120.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
13	1-Bromo-2-Nitrobenzene	3.17	3759942.04	589069.77	-----
16	Tetra chloro-meta-xylene	4.03	1690193.95	553138.35	107.503
	PCB (1016+1260)	7.26	3920254.32	784887.67	0.326
59	Decachlorobiphenyl	11.83	3260273.32	620980.45	115.045
			12630663.63	2548076.24	222.873

Software Version : 6.3.2.0646
 Sample Name : 170120-50 10/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/11
 Sample Amount : 1.000000
 Cycle : 16

Date : 1/27/2017 9:06:07 AM
 Data Acquisition Time : 1/26/2017 4:43:03 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017E1701E170124\B121.rst
 Sequence File : D:\GC DATA\GC-E\02017E1701E170124\B121.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
14	1-Bromo-2-Nitrobenzene	3.19	3830400.49	590066.68	-----
17	Tetra chloro-meta-xylene	4.04	1848630.86	554442.62	115.417
	PCB (1016+1260)	7.27	6569750.92	814700.02	0.536
63	Decachlorobiphenyl	11.83	3222756.39	653515.08	111.629
			15471538.66	2612724.40	227.582

Software Version : 6.3.2.0646
 Sample Name : 170120-53 10/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/12
 Sample Amount : 1.000000
 Cycle : 17

Date : 1/27/2017 9:07:19 AM
 Data Acquisition Time : 1/26/2017 5:03:28 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1701\170124\B122.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\B122.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
11	1-Bromo-2-Nitrobenzene	3.17	3250419.69	585351.20	-----
15	Tetra chloro-meta-xytene	4.03	1859354.25	560277.97	136.800
	PCB (1016+1260)	7.26	3075492.07	542029.66	0.296
64	Decachlorobiphenyl	11.83	3105346.63	654884.33	126.755
		11.290612.63	2342543.17		263.851

Software Version : 6.3.2.0646
 Sample Name : 170120-56 2/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/13
 Sample Amount : 1.000000
 Cycle : 18

Date : 1/27/2017 9:08:34 AM
 Data Acquisition Time : 1/26/2017 5:23:53 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017E1701E170124\B123.rst
 Sequence File : D:\GC DATA\GC-E\02017E1701E170124\B123.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
15	1-Bromo-2-Nitrobenzene	3.19	3797594.12	618182.30	
17	Tetra chloro-meta-xylene	4.04	1805253.74	555511.20	113.683
	PCB (1016+1260)	7.27	2955027.69	519768.49	0.243
67	Decachlorobiphenyl	11.83	3140534.35	649552.98	109.721
			11698409.90	2343014.97	223.647

Software Version : 6.3.2.0646
 Sample Name : 170120-58 4/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/14
 Sample Amount : 1.000000
 Cycle : 19

Date : 1/27/2017 9:09:37 AM
 Data Acquisition Time : 1/26/2017 5:44:18 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1701\170124\B124.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\170124.seq




PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
14	1-Bromo-2-Nitrobenzene	3.18	3829638.73	603061.02	-----
17	Tetra chloro-meta-xylene	4.03	1805308.03	553883.26	112.735
	PCB (1016+1260)	7.26	3976632.58	726787.14	0.325
64	Decachlorobiphenyl	11.83	3016656.70	642512.50	104.511
			12628236.03	2526243.93	217.570

Software Version : 6.3.2.0646
 Sample Name : 170120-59 2/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/15
 Sample Amount : 1.000000
 Cycle : 21

Date : 1/27/2017 9:11:16 AM
 Data Acquisition Time : 1/26/2017 6:25:06 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000


Result File : D:\GC DATA\GC-E\02017\1701\170124\B126.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\B170124.seq



Software Version : 6.3.2.0646
 Sample Name : 170120-60 10/20 Alta
 Instrument Name : GC-E
 Rack/Vial : 0/16
 Sample Amount : 1.000000
 Cycle : 22

Date : 1/27/2017 9:12:13 AM
 Data Acquisition Time : 1/26/2017 6:45:31 PM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1701\170124\B127.rst
 Sequence File : D:\GC DATA\GC-E\02017\1701\170124\170124.seq



PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
15	1-Bromo-2-Nitrobenzene	3.17	3932718.20	587100.97	
19	Tetra chloro-meta-xylene	4.03	1864204.28	550123.88	113.361
	PCB (1016+1260)	7.26	3045622.66	560748.83	0.242
66	Decachlorobiphenyl	11.82	2626898.35	648659.33	88.623
			11469443.49	2346633.01	202.226

Enviro – Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766 Tel (909) 590-5905 Fax (909) 590-5907

Date: January 27, 2017

Mr. Cesar Ruvalcaba
Alta Environmental
3777 Long Beach Blvd, Annex Building
Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com


Project: **Webster ES Additional Step-Out**
Lab I.D.: **170120-33 through -62**

Dear Mr. Ruvalcaba:

The **analytical results** for the solid samples, received by our laboratory on January 20, 2017, are attached. The samples were received intact, and accompanying chain of custody.

Enviro-Chem appreciates the opportunity to provide you and your company this and other services. Please do not hesitate to call us if you have any questions.

Sincerely,



Curtis Desilets
Vice President/Program Manager



Andy Wang
Laboratory Manager

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**

Date Analyzed: 1/26-27/2017

Unit: mg/Kg(PPM)

Matrix Spike (MS)/Matrix Spike Duplicate (MSD)

Spiked Sample Lab I.D.: **170126-LCS1/2**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.092	92%	0.090	90%	2%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.119	119%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	170124-61	170124-62	170124-58	170124-60		
Tetra-chloro-meta-xylene	50-150	118%	86%	132%	111%	97%		
Decachlorobipneyl	50-150	76%	70%	83%	79%	82%		

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.								
Tetra-chloro-meta-xylene								
Decachlorobipneyl								

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.						
Tetra-chloro-meta-xylene						
Decachlorobipneyl						

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: 

Final Reviewer: 

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**

Date Analyzed: 1/26-27/2017

Unit: mg/Kg(PPM)

Matrix Spike (MS)/Matrix Spike Duplicate (MSD)

Spiked Sample Lab I.D.: 170126-LCS1/2

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.092	92%	0.090	90%	2%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.119	119%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	170120-33	170120-36	170120-39	170120-42	170120-45	170120-48
Tetra-chloro-meta-xylene	50-150	118%	115%	125%	113%	112%	130%	108%
Decachlorobipneyl	50-150	76%	121%	82%	93%	104%	120%	115%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	170120-50	170120-53	170120-56	170120-58	170120-59	170120-60	170125-2	170125-3
Tetra-chloro-meta-xylene	115%	137%	114%	113%	112%	113%	121%	121%
Decachlorobipneyl	112%	127%	110%	105%	104%	89%	68%	77%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.						
Tetra-chloro-meta-xylene						
Decachlorobipneyl						

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: 

Final Reviewer: _____

Date: February 3, 2017

Mr. Cesar Ruvalcaba
Alta Environmental
3777 Long Beach Blvd, Annex Building
Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com


Project: **Webster ES, Additional Step-Out**
Lab I.D.: **170127-130 through -162**


Dear Mr. Ruvalcaba:

The **analytical results** for the solid samples, received by our laboratory on January 27, 2017, are attached. The samples were received intact, and accompanying chain of custody.

Enviro-Chem appreciates the opportunity to provide you and your company this and other services. Please do not hesitate to call us if you have any questions.

Sincerely,


Curtis Desilets
Vice President/Program Manager


Andy Wang
Laboratory Manager

LABORATORY REPORT

CUSTOMER: **Alta Environmental**
3777 Long Beach Blvd, Annex Building, Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com

PROJECT:

DATE SAMPLED: 01/25/17 DATE RECEIVED: 01/27/17
MATRIX: SOLID DATE EXTRACTED: 01/31-02/01/17
REPORT TO: MR. CESAR RUVALCABA DATE ANALYZED: 02/01&02/17
DATE REPORTED: 02/03/17

PCBs ANALYSIS

METHOD: EPA 3540C/8082; PAGE 1 OF 2

UNIT: mg/Kg = MILLIGRAM PER KILOGRAM = PPM

SAMPLE I.D.	LAB I.D.	PCB- 1016	PCB- 1221	PCB- 1232	PCB- 1242	PCB- 1248	PCB- 1254	PCB- 1260	TOTAL PCBs*	DF
01-0125	170127-130	ND	ND	ND	ND	ND	ND	ND	ND	10^
02-0125	170127-131	ND	ND	ND	ND	ND	ND	ND	ND	1
05-0125	170127-134	ND	ND	ND	ND	ND	ND	ND	ND	1
08-0125	170127-137	ND	ND	ND	ND	ND	ND	ND	ND	10^
Method Blank		ND	ND	ND	ND	ND	ND	ND	ND	1

PQL 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01

COMMENTS

DF = Dilution Factor

PQL = Practical Quantitation Limit

Actual Detection Limit = DF X PQL

ND = Non-Detected Or Below the Actual Detection Limit

* = Sum of the PCB 1016, 1221, 1232, 1242, 1248, 1254 and 1260

^ = Actual detection limit raised due to matrix interference

*** = The concentration exceeds the TTLC Limit of 50, and the sample is defined as hazardous waste as per CCR-TITLE 22 (if marked)

Data Reviewed and Approved by: _____

CAL-DHS ELAP CERTIFICATE No.: 1555

LABORATORY REPORT

CUSTOMER: **Alta Environmental**

3777 Long Beach Blvd, Annex Building, Long Beach, CA 90807

Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com

PROJECT:

DATE SAMPLED: 01/25/17

MATRIX: SOLID

REPORT TO: MR. CESAR RUVALCABA

DATE RECEIVED: 01/27/17

DATE EXTRACTED: 01/31-02/01/17

DATE ANALYZED: 02/01&02/17

DATE REPORTED: 02/03/17

PCBs ANALYSIS

METHOD: EPA 3540C/8082; PAGE 2 OF 2

UNIT: mg/Kg = MILLIGRAM PER KILOGRAM = PPM

SAMPLE I.D.	LAB I.D.	PCB- 1016	PCB- 1221	PCB- 1232	PCB- 1242	PCB- 1248	PCB- 1254	PCB- 1260	TOTAL PCBs*	DF
<u>11-0125</u>	<u>170127-140</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>14-0125</u>	<u>170127-143</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>17-0125</u>	<u>170127-146</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>18-0125</u>	<u>170127-147</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>21-0125</u>	<u>170127-150</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>24-0125</u>	<u>170127-152</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>27-0125</u>	<u>170127-155</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>30-0125</u>	<u>170127-158</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>33-0125</u>	<u>170127-161</u>	ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>
<u>Method Blank</u>		ND	ND	ND	ND	ND	ND	ND	ND	<u>1</u>

PQL 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01 0.01

COMMENTS

DF = Dilution Factor

PQL = Practical Quantitation Limit

Actual Detection Limit = DF X PQL

ND = Non-Detected Or Below the Actual Detection Limit

* = Sum of the PCB 1016, 1221, 1232, 1242, 1248, 1254 and 1260

*** = The concentration exceeds the TTLC Limit of 50, and the sample is defined as hazardous waste as per CCR-TITLE 22 (if marked)

Data Reviewed and Approved by: _____


CAL-DHS ELAP CERTIFICATE No.: 1555

Software Version : 6.3.2.0646
 Sample Name : 170127-130 2/100 RE
 Instrument Name : GC-E
 Rack/Vial : 0/6
 Sample Amount : 1.000000
 Cycle : 6

Date : 2/2/2017 1:42:16 PM
 Data Acquisition Time : 2/2/2017 10:41:43 AM
 Channel : B
 Operator : manager
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\01702\0170201\B072.rst
 Sequence File : D:\GC DATA\GC-E\02017\01702\0170201\0170201.seq

(01-0125) (MATRIX INTERFERANCE)



PCB Results


Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
14	1-Bromo-2-Nitrobenzene	3.18	1845416.52	411951.16	
16	Tetra chloro-meta-xylene	4.03	806164.97	288012.70	104.471
	PCB (1016+1260)	7.26	3684350.58	397491.43	0.624
60	Decachlorobiphenyl	11.83	944340.01	207797.62	67.893
			7280272.08	1305252.91	172.988

Software Version : 6.3.2.0646
 Sample Name : 170127-137 2/100 RE
 Instrument Name : GC-E
 Rack/Vial : 0/9
 Sample Amount : 1.000000
 Cycle : 2

Date : 2/2/2017 1:44:38 PM
 Data Acquisition Time : 2/2/2017 11:49:43 AM
 Channel : B
 Operator : GC
 Dilution Factor : 1.000000

Result File : D:\GC DATA\GC-E\02017\1702\170201\B075.rst
 Sequence File : D:\GC DATA\GC-E\02017\1702\170201\170201.seq

OR-0125 - MATRIX
INTERPRETATION



PCB Results

Peak #	Component Name	Time [min]	Area [uV*sec]	Height [uV]	Adjusted Amount
13	1-Bromo-2-Nitrobenzene	3.18	1657171.86	410937.45	
16	Tetra chloro-meta-xylene	4.03	772404.27	283999.71	111.466
	PCB (1016+1260)	7.27	752241.17	107504.65	0.142
65	Decachlorobiphenyl	11.83	929539.62	208760.16	74.421
			4111356.92	1011201.98	186.028

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**

Date Analyzed: 2/1-2/2017

Unit: mg/Kg(PPM)

Matrix Spike (MS)/Matrix Spike Duplicate (MSD)

Spiked Sample Lab I.D.: **170127-36~38 MS/MSD**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.092	92%	0.100	100%	8%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.099	99%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	170127-36~38	170127-91	170127-92	170127-95	170127-98	170127-101
Tetra-chloro-meta-xylene	50-150	117%	117%	110%	121%	121%	112%	127%
Decachlorobipneyl	50-150	69%	72%	67%	76%	94%	70%	76%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	170127-104	170127-107	170127-110	170127-113	170127-116	170127-117	170127-120	170127-123
Tetra-chloro-meta-xylene	134%	134%	125%	134%	105%	116%	103%	116%
Decachlorobipneyl	84%	85%	75%	76%	68%	100%	68%	72%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	170127-124	170127-127	170127-130	170127-131	170127-134	170127-137
Tetra-chloro-meta-xylene	115%	123%	104%	109%	127%	111%
Decachlorobipneyl	74%	76%	68%	70%	78%	74%

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: 

Final Reviewer: 

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**Date Analyzed: 2/1-2/2017Unit: mg/Kg(PPM)**Matrix Spike (MS)/Matrix Spike Duplicate (MSD)****Spiked Sample Lab I.D.:** **170201-LCS1/2**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.102	102%	0.113	113%	10%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.097	97%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	170127-140	170127-143	170127-146	170127-147	170127-150	170127-152
Tetra-chloro-meta-xylene	50-150	122%	109%	126%	136%	117%	145%	130%
Decachlorobipneyl	50-150	70%	72%	78%	98%	55%	110%	65%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	170127-155	170127-158	170127-161	170130-22	170130-23	170130-24	170130-25	170130-28
Tetra-chloro-meta-xylene	104%	93%	104%	104%	122%	125%	113%	135%
Decachlorobipneyl	69%	58%	79%	55%	85%	66%	75%	84%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	170130-31	170130-34	170130-35	170130-38	170130-41	
Tetra-chloro-meta-xylene	110%	107%	114%	141%	104%	
Decachlorobipneyl	73%	88%	72%	87%	71%	

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: 

Final Reviewer: _____

Enviro-Chem, Inc. Laboratories
 1214 E. Lexington Avenue,
 Pomona, CA 91766
 Tel: (909) 590-5905 Fax: (909) 590-5907
CA-DHS ELAP CERTIFICATE #1555

Turnaround Time
☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☐ 1 Week (Standard)
 Other:

SAMPLE ID	LAB ID	SAMPLING DATE	SAMPLING TIME	MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required				COMMENTS
1-0125	170127-130	01/25/17	1621	Bulk			Ice	X				
2-0125	-131		1624					X				
3-0125	-132		1627					X				archive
4-0125	-133		1630					X				archive
5-0125	-134		1636					X				
6-0125	-135		1639					X				archive
7-0125	-136		1642					X				archive
8-0125	-137		1646					X				
9-0125	-138		1650					X				archive
10-0125	-139		1652					X				archive
11-0125	-140		1700					X				
12-0125	-141		1702					X				archive
13-0125	-142		1705					X				archive
14-0125	-143		1709					X				
15-0125	-144		1712					X				archive

Company Name: Alta Environmental
 Address: 3777 Long Beach Blvd., Annex Bldg.
 City/State/Zip: Long Beach, California 90807

Project Contact: Cesar Ruvalcaba
 Tel: 562-495-5777
 Fax:

Sampler's Signature: *[Signature]*
 Project Name/ID: Webster ES, Additional Step-out

Relinquished by: <i>[Signature]</i> 1-25-17 2230	Received by: <i>[Signature]</i> 1-25-17 2230	Date & Time	Instructions for Sample Storage After Analysis: <input type="radio"/> Dispose of <input type="radio"/> Return to Client <input checked="" type="radio"/> Store (30 Days) <input type="radio"/> Other:
Relinquished by: <i>[Signature]</i> 1-26-17	Received by: <i>[Signature]</i> 1-26-17	Date & Time	
Relinquished by: <i>[Signature]</i> 01/27/17 1050	Received by: <i>[Signature]</i> 1/27/17	Date & Time	

Date: 1/27/16

CHAIN OF CUSTODY RECORD

Enviro-Chem, Inc. Laboratories
 1214 E. Lexington Avenue,
 Pomona, CA 91766
 Tel: (909) 590-5905 Fax: (909) 590-5907
CA-DHS ELAP CERTIFICATE #1555


Turnaround Time
☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☐ 1 Week (Standard)
 Other:

Misc./PO#
 SMSD-16-6424.1

SAMPLE ID	LAB ID	SAMPLING DATE	TIME	MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required					COMMENTS
16-0128	170129-145	01/25/17	1716	Bulk			Ice	X					archive
17-0128	-146		1743					X					
18-0128	-147		1745					X					
19-0128	-148		1747					X					archive
20-0128	-149		1750					X					archive
21-0128	-150		1800					X					
23-0128	-151		1804					X					archive
24-0128	-152		1808					X					
25-0128	-153		1810					X					archive
26-0128	-154		1813					X					archive
27-0128	-155		1820					X					
28-0128	-156		1825					X					archive
29-0128	-157		1828					X					archive
30-0128	-158		1832					X					
31-0128	-159		1835					X					archive

Company Name: Alta Environmental

Project Contact: Cesar Ruvalcaba

Sampler's Signature: 

Address: 3777 Long Beach Blvd., Annex Bldg.

Tel: 562-495-5777

Project Name/ID: Webster ES, Additional Step-out

City/State/Zip: Long Beach, California 90807

Fax:

Relinquished by:  1-25-17 2:30

Received by:  1-25-17 2:30

Date & Time

Instructions for Sample Storage After Analysis:

Relinquished by:  1-26-17

Received by:  1-26-17

Date & Time

☐ Dispose of ☐ Return to Client ☒ Store (30 Days)

Relinquished by:  1/27/17 10:50

Received by:  1/27/17

Date & Time

☐ Other:

CHAIN OF CUSTODY RECORD

Date: 1/27/17

Page 2 of 3

CA-DHS ELAP CERTIFICATE #1555

Other:

☐ Other:

Date: February 3, 2017

Mr. Cesar Ruvalcaba
Alta Environmental
3777 Long Beach Blvd, Annex Building
Long Beach, CA 90807
Tel: (562) 495-5777 Email: Cesar.Ruvalcaba@altaenviron.com

Project: **Webster Additional Step-Out Sampling**
Lab I.D.: **170127-91 through -129**

Dear Mr. Ruvalcaba:

The **analytical results** for the solid samples, received by our laboratory on January 27, 2017, are attached. The samples were received intact, and accompanying chain of custody.

Enviro-Chem appreciates the opportunity to provide you and your company this and other services. Please do not hesitate to call us if you have any questions.

Sincerely,



Curtis Desilets
Vice President/Program Manager



Andy Wang
Laboratory Manager

Enviro-Chem, Inc.

1214 E. Lexington Avenue, Pomona, CA 91766

Tel (909)590-5905 Fax (909)590-5907

EPA 8082 QA/QC Report

Matrix: **Soil/Solid/Sludge**Date Analyzed: 2/1-2/2017Unit: mg/Kg(PPM)**Matrix Spike (MS)/Matrix Spike Duplicate (MSD)****Spiked Sample Lab I.D.: 170127-36~38 MS/MSD**

Analyte	S.R.	spk conc	MS	%REC	MSD	%REC	%RPD	ACP %RPD	ACP %REC
PCB (1016+1260)	0.000	0.100	0.092	92%	0.100	100%	8%	0-20%	70-130

Lab Control Spike (LCS) Recovery:

Analyte	spk conc	LCS	% REC	ACP %REC
PCB (1016+1260)	0.100	0.099	99%	75-125

Surrogate Recovery	ACP%	ACP%	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.		MB	170127-36~38	170127-91	170127-92	170127-95	170127-98	170127-101
Tetra-chloro-meta-xylene	50-150	117%	117%	110%	121%	121%	112%	127%
Decachlorobipneyl	50-150	69%	72%	67%	76%	94%	70%	76%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	170127-104	170127-107	170127-110	170127-113	170127-116	170127-117	170127-120	170127-123
Tetra-chloro-meta-xylene	134%	134%	125%	134%	105%	116%	103%	116%
Decachlorobipneyl	84%	85%	75%	76%	68%	100%	68%	72%

Surrogate Recovery	%REC	%REC	%REC	%REC	%REC	%REC
Sample I.D.	170127-124	170127-127	170127-130	170127-131	170127-134	170127-137
Tetra-chloro-meta-xylene	115%	123%	104%	109%	127%	111%
Decachlorobipneyl	74%	76%	68%	70%	78%	74%

S.R. = Sample Result

* = Surrogate fail due to matrix interference (If Marked)

spk conc = Spike Concentration

Note: LCS, MS, MSD are in control therefore results are in control.

%REC = Percent Recovery

ACP %RPD = Acceptable Percent RPD Range

ACP %REC = Acceptable Percent Recovery Range

Analyzed and Reviewed By: Final Reviewer: 

Enviro-Chem, Inc. Laboratories

1214 E. Lexington Avenue,

Pomona, CA 91766

Tel: (909) 590-5905 Fax: (909) 590-5907

CA-DHS ELAP CERTIFICATE #1555

Turnaround Time

0 Same Day

0 24 Hours

0 48 Hours

0 72 Hours

0 1 Week (Standard)

Other:

SAMPLE ID	LAB ID	SAMPLING DATE	SAMPLING TIME	MATRIX	NO. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required		COMMENTS
1-0126	170127-P1	1/26/17	1708	Bulk			ICE	X		
2-0126	-P2		1715			40°C Jar		X		
3-0126	-P3		1720					X		archive
4-0126	-P4		1724					X		archive
5-0126	-P5		1730					X		
6-0126	-P6		1734					X		archive
7-0126	-P7		1737					X		archive
8-0126	-P8		1740					X		
9-0126	-P9		1743					X		archive
10-0126	-100		1746					X		archive
11-0126	-101		1810					X		
12-0126	-102		1813					X		archive
13-0126	-103		1822					X		archive
14-0126	-104		1825					X		
15-0126	-105		1828					X		archive

Company Name: Alta Environmental		Project Contact: Cesar Ruvalcaba		Sampler's Signature: <i>[Signature]</i> 1/25/17 2300	
Address: 3777 Long Beach Blvd Annex bldg		Tel: 562-495-5777		Project Name/ID: Webster Addition / Step out sampling	
City/State/Zip: Long Beach, CA 90807		Fax:			
Relinquished by: <i>[Signature]</i> 1-25-17 2300		Received by: <i>[Signature]</i> 2300 01/26/17		Instructions for Sample Storage After Analysis:	
Relinquished by: <i>[Signature]</i> 0800 02/1/17		Received by: <i>[Signature]</i> 1/31/17		<input type="radio"/> Dispose of <input type="radio"/> Return to Client <input type="radio"/> Store (30 Days)	
Relinquished by:		Received by: <i>[Signature]</i> 1/27/17		<input type="radio"/> Other:	

CHAIN OF CUSTODY RECORD

Date: _____

WHITE WITH SAMPLE - YELLOW TO CLIENT

Page 1 of 3

Enviro-Chem, Inc. Laboratories

1214 E. Lexington Avenue,

Pomona, CA 91766

Tel: (909) 590-5905 Fax: (909) 590-5907

CA-DHS ELAP CERTIFICATE #1555

Turnaround Time

0 Same Day

0 24 Hours

0 48 Hours

0 72 Hours

0 1 Week (Standard)

Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
		DATE	TIME															
16-0126	170127-106	1/26/17	1831	Bulk			ICC	X										archive
17-0126	-107		1843					X										
18-0126	-108		1845					X										archive
19-0126	-109		1848					X										archive
20-0126	-110		1851					X										
22-0126	-111		1853					X										archive
23-0126	-112		1857					X										archive
24-0126	-113		1902					X										
25-0126	-114		1907					X										archive
26-0126	-115		1910					X										archive
27-0126	-116		1912					X										
28-0126	-117		1915					X										
29-0126	-118		1921					X										archive
30-0126	-119		1924					X										archive
31-0126	-120		1935					X										

Company Name: <u>Alta Environmental</u>		Project Contact: <u>Cesar Ruvicaba</u>		Sampler's Signature: <u>[Signature]</u> 1/25/17 2300	
Address: <u>3777 Long Beach Blvd Annex bldg</u>		Tel: <u>562-495-5777</u>		Project Name/ID: <u>Jobster Additional Step-out Sampling</u>	
City/State/Zip: <u>Long Beach, CA 90807</u>		Fax:			
Relinquished by: <u>[Signature]</u> 1-25-17 2300	Received by: <u>[Signature]</u> 1/26/17 2300		Date & Time: <u>1/27/17</u>		Instructions for Sample Storage After Analysis: <input type="radio"/> Dispose of <input type="radio"/> Return to Client <input type="radio"/> Store (30 Days) <input type="radio"/> Other:
Relinquished by: <u>[Signature]</u> 0800 1/27/17	Received by: <u>[Signature]</u>		Date & Time: <u>1/27/17</u>		
Relinquished by:	Received by: <u>[Signature]</u>		Date & Time: <u>1/27/17</u>		

CHAIN OF CUSTODY RECORD

Date: _____

WHITE WITH SAMPLE • YELLOW TO CLIENT

Page 2 of 3

CA-DHS ELAP CERTIFICATE #1555

Other

[illegible]

CHAIN OF CUSTODY RECORD

Date: _____

WHITE WITH SAMPLE - YELLOW TO CLIENT

Enviro-Chem, Inc. Laboratories1214 E. Lexington Avenue,
Pomona, CA 91766

Tel: (909) 590-5905 Fax: (909) 590-5907

CA-DHS ELAP CERTIFICATE #1555

Turnaround Time

☐ Same Day☐ 24 Hours☐ 48 Hours☐ 72 Hours☐ 1 Week (Standard)

Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
		DATE	TIME															
1-0126	170127-P1	1/26/17	1708	Bulk			ice	x										
2-0126	-P2		1715					x										
3-0126	-P3		1720					x								archive		
4-0126	-P4		1724					x								archive		
5-0126	-P5		1730					x										
6-0126	-P6		1734					x								archive		
7-0126	-P7		1737					x								archive		
8-0126	-P8		1740					x										
9-0126	-P9		1743					x								archive		
10-0126	-100		1746					x								archive		
11-0126	-101		1810					x										
12-0126	-102		1813					x								archive		
13-0126	-103		1822					x								archive		
14-0126	-104		1825					x										
15-0126	-105		1828					x								archive		

Company Name: Alta Environmental		Project Contact: Cesar Ruvalcaba		Sampler's Signature: <i>[Signature]</i> 1/25/17 2300	
Address: 3777 Long Beach Blvd Annex bldg		Tel: 562-498-5777		Project Name/ID:	
City/State/Zip: Long Beach, CA 90807		Fax:			

Relinquished by: <i>[Signature]</i> 1-25-17 2300	Received by: <i>[Signature]</i> 2300 01/26/17	Date & Time: 1/27/17 1000	Instructions for Sample Storage After Analysis: <input type="radio"/> Dispose of <input type="radio"/> Return to Client <input type="radio"/> Store (30 Days) <input type="radio"/> Other:
Relinquished by: <i>[Signature]</i> 0800 01/27/17	Received by: <i>[Signature]</i>	Date & Time: 1/27/17 1200	
Relinquished by:	Received by:		

CHAIN OF CUSTODY RECORD

Date: _____

WHITE WITH SAMPLE • YELLOW TO CLIENT

Page 1 of 3

Enviro-Chem, Inc. Laboratories1214 E. Lexington Avenue,
Pomona, CA 91766

Tel: (909) 590-5905 Fax: (909) 590-5907

CA-DHS ELAP CERTIFICATE #1555

Turnaround Time

- ☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☐ 1 Week (Standard)
 Other:

SAMPLE ID	LAB ID	SAMPLING		MATRIX	No. OF CONTAINERS	TEMPERATURE	PRESERVATION	Analysis Required										COMMENTS
		DATE	TIME															
16-0126	170127-106	1/26/17	1831	Bulk			ice	X									archive	
17-0126	-107		1843					X										
18-0126	-108		1845					X									archive	
19-0126	-109		1848					X									archive	
20-0126	-110		1851					X										
22-0126	-111		1853					X									archive	
23-0126	-112		1857					X									archive	
24-0126	-113		1902					X										
25-0126	-114		1907					X									archive	
26-0126	-115		1910					X									archive	
27-0126	-116		1912					X										
28-0126	-117		1915					X										
29-0126	-118		1921					X									archive	
30-0126	-119		1924					X									archive	
31-0126	-120		1935					X										

Company Name: Alta Environmental

Address: 3777 Long Beach blvd Annex bldg

City/State/Zip: Long Beach, CA 90807

Project Contact: Cesar Ruvalecaba

Tel: 562-495-5777

Fax: _____

Sampler's Signature: [Signature] 1/25/17 2300

Project Name/ID: _____

Relinquished by: [Signature] 1-25-17 2300

Relinquished by: [Signature] 0800 1/27/17

Relinquished by: _____

Received by: [Signature] 2300 1/26/17

Received by: [Signature]

Received by: [Signature]

Date & Time: _____

Date & Time: 1/27/17 1050

Date & Time: 1/27/17 1200

Instructions for Sample Storage After Analysis:

☐ Dispose of ☐ Return to Client ☐ Store (30 Days)

☐ Other: _____

CHAIN OF CUSTODY RECORD

Date: _____

WHITE WITH SAMPLE • YELLOW TO CLIENT

1214 E. Lexington Avenue,
Pomona, CA 91766
Tel: (909) 590-5905 Fax: (909) 590-5907
CA-DHS ELAP CERTIFICATE #1555

☐ Same Day
☐ 24 Hours
☐ 48 Hours
☐ 72 Hours
☐ 1 Week (Standard)
 Other:

[illegible]

CHAIN OF CUSTODY RECORD



EMSL Analytical, Inc.

200 Route 130 North, Cinnaminson, NJ 08077

Phone: (856) 303-2500 Fax: (856) 858-4571 Email: EnvChemistry2@emsl.com

Attn:

**CESAR RUVALCABA
Alta Environmental
3777 Long Beach Blvd
Annex Building
Long Beach, CA 90807**

Phone: (562) 495-5777

Fax:

2/2/2017

The following analytical report covers the analysis performed on samples submitted to EMSL Analytical, Inc. on 1/30/2017. The results are tabulated on the attached data pages for the following client designated project:

Window and Doors Replacement Project at Webster ES

The reference number for these samples is EMSL Order #011700785. Please use this reference when calling about these samples. If you have any questions, please do not hesitate to contact me at (856) 303-2500.

Approved By:

Phillip Worby, Chemistry Laboratory Manager



The test results contained within this report meet the requirements of NELAP and/or the specific certification program that is applicable, unless otherwise noted.

NELAP Certifications: NJ 03036, NY 10872, PA 68-00367, CA ELAP 187

The samples associated with this report were received in good condition unless otherwise noted. This report relates only to those items tested as received by the laboratory. The QC data associated with the sample results meet the recovery and precision requirements established by the NELAP, unless specifically indicated. All results for soil samples are reported on a dry weight basis, unless otherwise noted. This report may not be reproduced except in full and without written approval by EMSL Analytical, Inc.

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (856) 303-2500 / (856) 858-4571

<http://www.EMSL.com>EnvChemistry2@emsl.com

EMSL Order: 011700785

CustomerID: ALTA34

CustomerPO: SMSD-16-6514

ProjectID:

Attn: **CESAR RUVALCABA**
Alta Environmental
3777 Long Beach Blvd
Annex Building
Long Beach, CA 90807

Phone: (562) 495-5777

Fax:

Received: 01/30/17 8:45 AM

Project: Window and Doors Replacement Project at Webster ES

Analytical Results**Client Sample Description** 19-0119**Collected:** 1/19/2017**Lab ID:** 0001

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1221	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1232	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1242	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1248	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1254	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1260	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1262	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1268	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH

Client Sample Description 22-0125**Collected:** 1/25/2017**Lab ID:** 0002

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1221	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1232	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1242	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1248	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1254	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1260	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1262	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1268	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH

Client Sample Description 34-0125**Collected:** 1/28/2017**Lab ID:** 0003

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1221	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1232	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1242	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1248	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1254	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1260	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1262	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1268	ND	0.98	mg/Kg	1/31/2017	SD	2/1/2017	EH

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (856) 303-2500 / (856) 858-4571

<http://www.EMSL.com>EnvChemistry2@emsl.com

EMSL Order: 011700785

CustomerID: ALTA34

CustomerPO: SMSD-16-6514

ProjectID:

Attn: **CESAR RUVALCABA**
Alta Environmental
3777 Long Beach Blvd
Annex Building
Long Beach, CA 90807

Phone: (562) 495-5777

Fax:

Received: 01/30/17 8:45 AM

Project: Window and Doors Replacement Project at Webster ES

Analytical Results**Client Sample Description** 21-0126**Collected:** 1/26/2017**Lab ID:** 0004

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1221	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1232	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1242	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1248	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1254	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1260	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1262	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1268	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH

Client Sample Description 28b-0126**Collected:** 1/26/2017**Lab ID:** 0005

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1221	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1232	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1242	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1248	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1254	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1260	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1262	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1268	ND	0.93	mg/Kg	1/31/2017	SD	2/1/2017	EH

Client Sample Description 38-0126**Collected:** 1/26/2017**Lab ID:** 0006

Method	Parameter	Result	RL	Units	Prep Date	Analyst	Analysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1221	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1232	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1242	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1248	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1254	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1260	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1262	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH
3540C/8082A	Aroclor-1268	ND	0.96	mg/Kg	1/31/2017	SD	2/1/2017	EH



EMSL Analytical, Inc.

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (856) 303-2500 / (856) 858-4571

<http://www.EMSL.com>

EnvChemistry2@emsl.com

EMSL Order:	011700785
CustomerID:	ALTA34
CustomerPO:	SMDS-16-6514
ProjectID:	

Definitions:

ND - indicates that the analyte was not detected at the reporting limit

RL - Reporting Limit (Analytical)



EMSL ANALYTICAL, INC.
LABORATORY PRODUCTS TRAINING

Environmental Chemistry Chain of Custody

EMSL Order Number (Lab Use Only):

011700785

EMSL ANALYTICAL, INC.
200 ROUTE 130 NORTH
CINNAMINSON, NJ 08077
PHONE: (800) 220-3675
FAX: (856) 786-5974

Report To Contact Name: Cesar Ruvalcaba		Bill To Company: Same	
Company Name: Alta Environmental		Attention To:	
Street: 3777 Long Beach Boulevard, Annex Building		Street:	
City: Long Beach	State/Province:	City:	State/Province:
Phone : 562-495-5777	Fax :	City:	State/Province:
Project Name: Window and doors replacement project at Webster ES		U.S. State where Samples Collected: CA	
Number of Samples in Shipment: 7	Date of Shipment: 01/19-01/26/16	Purchase Order: SMSD-16-6514	
Standard Turnaround Time: <input type="checkbox"/> 2 Weeks		The following TAT's are subject to lab approval: <input checked="" type="checkbox"/> 1 Week <input type="checkbox"/> 4 Days <input type="checkbox"/> 2 Days <input type="checkbox"/> 1 Day	
Failure to complete will hinder processing of samples			
Client Sample ID	Comp	Grab	Date/Time
19-0119	X		01/19/17 19:00
22-0125	X		01/25/17 18:00
34-0125	X		01/25/17 19:05
21-0126	X		01/26/17 18:51
28b-0126	X		01/26/17 19:15
38-0126	X		01/26/17 20:00
Released By (Signature)		Date & Time	
[Signature]		01/27/17 09:45	
Received By		Date & Time	
[Signature]		01/30/17 08:45	
Please indicate reporting requirements: <input type="checkbox"/> Results Only <input checked="" type="checkbox"/> Results and QC <input type="checkbox"/> Reduced Deliverables <input type="checkbox"/> Disk Deliverable <input type="checkbox"/> Other _____			
Instructions or Comments:			
sample 7 agreed's sample, emailed client about IL requirement for agreed's PCB analysis May/30 & to confirm turn around time.			

Page 1 of 2 pages

Environmental Chemistry Chain of Custody

011700795

EMSL ANALYTICAL, INC.
200 ROUTE 130 NORTH
CINNAMINSON, NJ 08077
PHONE: (800) 220-3675
FAX: (856) 786-5974









2

[illegible]

Appendix C

Sample Location Maps

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.

KEYNOTE LEGEND		DEMOLITION GENERAL NOTES	LEGEND			
B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.	1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED. 2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK. 3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS. 4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION. 5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING. 6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.		EXISTING PARTITION/WALL TO REMAIN		EXISTING DOOR TO REMAIN
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.			REMOVE EXISTING ITEMS/PARTITION/WALL		EXISTING DOOR TO BE REMOVED
G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.			REMOVE EXISTING FINISH FLOOR		EXISTING WINDOW TO BE REMOVED
G.03	REMOVE EXISTING WINDOW					
G.05	EXISTING WINDOW TO REMAIN.					
G.07	WOODEN TRIM TO REMAIN.					
H.01	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.			EXISTING CARPET		
H.02	EXISTING CASEWORK TO REMAIN. PROTECT IN PLACE. DOES NOT REQUIRE PAINT.			EXISTING TILE		
P.03	EXISTING WALKWAY COVER TO REMAIN.					




CONSULTANT

PROJECT NAME
WEBSTER
ELEMENTARY
MODERNIZATION


FACILITY INFO
WEBSTER ELEMENTARY
3602 WINTER CANYON ROAD, MALIBU, CA 90265

AGENCY STAMP



OSHPD PROJECT NO: XXXX

KEY PLAN



PROJECT ISSUE DATE: YYYY/MM/DD

[illegible]

SHEET TITLE DSK JOB NO: 16010

DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG A

A2.00A

DRAFTER: JH PM: JC REVIEWER: AK

Task architects Copyright ©
Plotted on 9/19/2016 10:12:34 AM C:\Users\Jonathan\Documents\16010 WEBSTER ES MODERNIZATION Jonathan.rvt

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.


KEYNOTE LEGEND		DEMOLITION GENERAL NOTES
B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.	1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.	2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.	3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.
F.02	REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.	4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.
G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.	5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.
G.03	REMOVE EXISTING WINDOW	6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.
H.01	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.	
H.02	EXISTING CASEWORK TO REMAIN. PROTECT IN PLACE. DOES NOT REQUIRE PAINT	
P.03	EXISTING WALKWAY COVER TO REMAIN.	



CONSULTANT


PROJECT NAME
WEBSTER
ELEMENTARY
MODERNIZATION

FACILITY INFO
WEBSTER ELEMENTARY
3602 WINTER CANYON ROAD, MALIBU, CA 90265
AGENCY STAMP



OSHPD PROJECT NO: XXXX

KEY PLAN



PROJECT ISSUE DATE: YYYY/MM/DD

[illegible]

SHEET TITLE DSK JOB NO: 1601






DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG B





SHEET NUMBER

A2.00B

DRAFTER: Author PM: JC REVIEWER: A

Task architects Copyright ©
Plotted on 9/19/2016 10:12:35 AM C:\Users\Jonathan\Documents\16010 WEBSTER ES MODERNIZATION Jonathan.rvt

KEYNOTE LEGEND		DEMOLITION GENERAL NOTES		LEGEND	
B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.	1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.		EXISTING PARTITION WALL TO REMAIN	
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.	2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.		REMOVE EXISTING ITEMS/PARTITION WALL	
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.	3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.		REMOVE EXISTING FINISH FLOOR	
F.02	REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.	4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.			
G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.	5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.		EXISTING CARPET	
G.03	REMOVE EXISTING WINDOW	6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.			
H.01	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.			EXISTING TILE	
M.03	REMOVE DRINKING FOUNTAIN AND METAL RAIL. PATCH WALL FINISH AS NEEDED AND PREPARE FOR NEW.				
P.03	EXISTING WALKWAY COVER TO REMAIN.				




CONSULTANT


PROJECT NAME
**WEBSTER
ELEMENTARY
MODERNIZATION**

FACILITY INFO
**WEBSTER ELEMENTARY
3602 WINTER CANYON ROAD, MALIBU, CA 90265**

AGENCY STAMP



OSHPD PROJECT NO: XXXX

[illegible]

SHEET TITLE

DSK JOB NO: 16010

DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG C

SHEET NUMBER

A2.00C

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.

KEYNOTE LEGEND

- B.01 REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH. CARPET TO REMAIN.
- B.05 REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.
- F.01 REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.
- G.02 REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.
- G.03 REMOVE EXISTING WINDOW
- G.07 WOODEN TRIM TO REMAIN.
- H.01 EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.
- H.02 EXISTING CASEWORK TO REMAIN. PROTECT IN PLACE. DOES NOT REQUIRE PAINT.

DEMOLITION GENERAL NOTES

1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.
2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.
3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.
4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.
5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.
6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.

LEGEND

- EXISTING PARTITION/WALL TO REMAIN
- REMOVE EXISTING ITEMS/PARTITION/WALL
- REMOVE EXISTING FINISH FLOOR
- EXISTING CARPET
- EXISTING TILE




CONSULTANT

PROJECT NAME
WEBSTER
ELEMENTARY
MODERNIZATION


FACILITY INFO
WEBSTER ELEMENTARY
3802 WINTER CANYON ROAD, MALIBU, CA 90265

AGENCY STAMP



OSHPD PROJECT NO: XXXX

KEY PLAN



PROJECT ISSUE DATE: YYYY/MM/DD

DATE NO. REVISIONS
2016/09/22 50% CD SUBMITTAL

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

DATE NO. REVISIONS

SHEET TITLE

DEMOLITION PLAN, BLDG
ELEVATIONS, SECTIONS &
DETAILS - BLDG E

SHEET NUMBER






A2.00E

DRAFTER: JH

PM: JC

REVIEWER: AK

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.

KEYNOTE LEGEND		DEMOLITION GENERAL NOTES	LEGEND	
B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.	1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.		EXISTING PARTITION/WALL TO REMAIN
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.	2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.		REMOVE EXISTING ITEMS/PARTITION/WALL
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.	3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.		REMOVE EXISTING FINISH FLOOR
F.02	REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.	4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.		EXISTING CARPET
G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.	5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.		EXISTING TILE
H.01	EXISTING CASEWORK TO REMAIN, PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.	6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.		
M.03	REMOVE DRINKING FOUNTAIN AND METAL RAIL. PATCH WALL FINISH AS NEEDED AND PREPARE FOR NEW.			
P.03	EXISTING WALKWAY COVER TO REMAIN.			



CONSULTANT

PROJECT NAME
WEBSTER
ELEMENTARY
MODERNIZATION

FACILITY INFO
WEBSTER ELEMENTARY
3602 WINTER CANYON ROAD, MALIBU, CA 90265

AGENCY STAMP

FILE NUMBER: XX-X

IDENTIFICATION STAMP

DIVISION OF THE STATE ARCHITECT


XX-XXXXXX

ACS _____ FLS _____ SSS _____

Date: _____

OSHPD PROJECT NO: XXXX

KEY PLAN

[illegible]


SHEET TITLE _____ DSK JOB NO: 16010

DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG F


A2.00F

DRAFTER: RD PM: JC REVIEWER: AK


6 DEMOLITION WALL SECTION - BUILDING F - SOUTH
3/4" = 1'-0"



4 DEMO EXTERIOR ELEVATION - BUILDING F - WEST
1/8" = 1'-0"




3 DEMO EXTERIOR ELEVATION - BUILDING F - SOUTH
1/8" = 1'-0"



2 DEMO EXTERIOR ELEVATION - BUILDING F - NORTH
1/8" = 1'-0"

ND=None Detected

INITIAL SAMPLING








1 DEMO FLOOR PLAN - BUILDING F
1/8" = 1'-0"

5 DEMOLITION WALL SECTION - BUILDING F - NORTH
3/4" = 1'-0"


dsK architects Copyright ©
Plotted on 9/19/2016 10:12:40 AM C:\Users\Jonathan\Documents\16010 WEBSTER ES MODERNIZATION_Jonathan.rvt

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.


KEYNOTE LEGEND				DEMOLITION GENERAL NOTES		LEGEND	
B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.	G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.	1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED. 2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK. 3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS. 4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION. 5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING. 6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.		EXISTING PARTITION/WALL TO REMAIN	
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.					REMOVE EXISTING ITEMS/PARTITION/WALL	
B.04	REMOVE TILE DOWN TO CONCRETE AND ABATE.	G.03	REMOVE EXISTING WINDOW			REMOVE EXISTING FINISH FLOOR	
B.06	WOOD FLOORING TO REMAIN. PREPARE SURFACE FOR REFINISHING.	P.03	EXISTING WALKWAY COVER TO REMAIN.				
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.					EXISTING CARPET	
F.04	PREPARE PREVIOUSLY PAINTED CLOSET DOOR TO RECEIVE NEW PAINT INSIDE AND OUT. SEE ELEVATIONS AND SPECS.						
F.05	EXISTING DOOR TO REMAIN. PROTECT IN PLACE.						
G.01	EXISTING WINDOW SYSTEM TO REMAIN.					EXISTING TILE	




MURAL WILL BE DAMAGED BY DOOR AND WINDOW REPLACEMENT. REMOVE?



3 DEMO EXTERIOR ELEVATION - BUILDING G - EAST
1/8" = 1'-0"




2 DEMO EXTERIOR ELEVATION - BUILDING G - WEST
1/8" = 1'-0"




ND=None Detected


INITIAL SAMPLING




7 DEMO PARTIAL EXTERIOR ELEVATION - BUILDING G - WEST ENTRY
1/8" = 1'-0"




6 DEMO PARTIAL EXTERIOR ELEVATION - BUILDING G - SPEECH RM WINDOW
1/8" = 1'-0"




5 DEMO EXTERIOR ELEVATION - BUILDING G - NORTH
1/8" = 1'-0"



4 DEMO EXTERIOR ELEVATION - BUILDING G - SOUTH
1/8" = 1'-0"




1 DEMO FLOOR PLAN - BUILDING 0
1/8" = 1'-0"



CONSULTANT


PROJECT NAME
WEBSTER
ELEMENTARY
MODERNIZATION

FACILITY INFO
WEBSTER ELEMENTARY
3602 WINTER CANYON ROAD, MALIBU, CA 90265
AGENCY STAMP



OSHPD PROJECT NO: XXXX

KEY PLAN



PROJECT ISSUE DATE: YYYY/MM/DD

DATE	NO.	REVISIONS
2016/09/22		50% CD SUBMITTAL

[illegible]

SHEET TITLE DSK JOB NO: 16010






DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG G

SHEET NUMBER

A2.00G

DRAFTER: Author PM: JC REVIEWER: AK

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.


KEYNOTE LEGEND		DEMOLITION GENERAL NOTES	LEGEND	
B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.	1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.		EXISTING PARTITION/WALL TO REMAIN
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.	2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.		REMOVE EXISTING ITEMS/PARTITION/WALL
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.	3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.		REMOVE EXISTING FINISH FLOOR
G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.	4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.		EXISTING CARPET
G.03	REMOVE EXISTING WINDOW.	5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.		EXISTING TILE
H.01	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.	6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.		
M.03	REMOVE DRINKING FOUNTAIN AND METAL RAIL. PATCH WALL FINISH AS NEEDED AND PREPARE FOR NEW.			
P.03	EXISTING WALKWAY COVER TO REMAIN.			



CONSULTANT


PROJECT NAME
WEBSTER
ELEMENTARY
MODERNIZATION

FACILITY INFO
WEBSTER ELEMENTARY
3602 WINTER CANYON ROAD, MALIBU, CA 90265
AGENCY STAMP



OSHPD PROJECT NO: XXXX

KEY PLAN



PROJECT ISSUE DATE: YYYY/MM/DD

[illegible]


SHEET TITLE DSK JOB NO: 1601

DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG H


SHEET NUMBER

A2.00H


DRAFTER: JH PM: JC REVIEWER: AL




8 DEMOLITION HEAD WINDOW DETAIL
3" = 1'-0"




4 DEMOLITION SILL WINDOW DETAIL
3" = 1'-0"




6 DEMOLITION WALL SECTION - BUILDING H - NORTH
3/4" = 1'-0"




5 DEMO PARTIAL EXTERIOR ELEVATION - BUILDING H - WEST
1/8" = 1'-0"



3 DEMO EXTERIOR ELEVATION - BUILDING H - NORTH
1/8" = 1'-0"




2 DEMO EXTERIOR ELEVATION - BUILDING H - SOUTH
1/8" = 1'-0"



1 DEMO FLOOR PLAN - BUILDING H
1/8" = 1'-0"










— BOTH OF THESE DOORS HAVE A SIDE VISION PANEL
REPLACING WITH SOLID IN NEW WORK UNLESS
THERE ARE OBJECTIONS.



SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.

B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.
F.02	REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.
G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE, NEW FIXTURES DEMOLITION DETAILS. PREPARE FOR NEW WORK.
G.03	REMOVE EXISTING WINDOW
H.01	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPEC.
H.02	EXISTING CASEWORK TO REMAIN. PROTECT IN PLACE. DOES NOT REQUIRE PAINT.
P.03	EXISTING WALKWAY COVER TO REMAIN.

1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.
2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.
3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.
4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.
5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.
6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.

	EXISTING PARTITION/WALL TO REMAIN		EXISTING DOOR TO REMAIN
	REMOVE EXISTING ITEMS/PARTITION/WALL		EXISTING DOOR TO BE REMOVED
	REMOVE EXISTING FINISH FLOOR		EXISTING WINDOW TO BE REMOVED
	EXISTING CARPET		
	EXISTING TILE		








ADDITIONAL SAMPLING

ND=None Detected

B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.
F.02	REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.
G.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.
G.03	REMOVE EXISTING WINDOW
H.01	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.
M.03	REMOVE DRINKING FOUNTAIN AND METAL RAIL. PATCH WALL FINISH AS NEEDED AND PREPARE FOR NEW.
P.03	EXISTING WALKWAY COVER TO REMAIN.

1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.
2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.
3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.
4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THE MOST AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.
5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.
6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.


	EXISTING PARTITION/WALL TO REMAIN
	REMOVE EXISTING ITEMS/PARTITION/WALL
	REMOVE EXISTING FINISH FLOOR
	EXISTING CARPET
	EXISTING TILE




PROJECT NAME
**WEBSTER
ELEMENTARY
MODERNIZATION**

FACILITY INFO
**WEBSTER ELEMENTARY
3602 WINTER CANYON ROAD, MALIBU, CA 902**

AGENCY STAMP



KEY PLAN



DATE	NO.	REVISIONS
2016/09/22		50% CD SUBMITTAL

DATE	NO.	REVISIONS
2016/09/22		50% CD SUBMITTAL

17-0125-ND

24-0125-ND
25-0125-ND
26-0125-ND

21-0125-ND
23-0125-ND

18-0125-ND
19-0125-ND
20-0125-ND

27-0125-ND
28-0125-ND
29-0125-ND

30-0125-ND
31-0125-ND
32-0125-ND

SHEET TITLE DSK JOB NO: 1601

DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG C

A2.00C

DRAFTER: Author PM: IC REVIEWER: A

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.

KEYNOTE LEGEND				DEMOLITION GENERAL NOTES		LEGEND	
B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.	H.02	EXISTING CASEWORK TO REMAIN. PROTECT IN PLACE. DOES NOT REQUIRE PAINT.				EXISTING PARTITION/WALL TO REMAIN
B.03	TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.	P.03	EXISTING WALKWAY COVER TO REMAIN.				REMOVE EXISTING ITEMS/PARTITION/WALL
B.04	REMOVE TILE DOWN TO CONCRETE AND ABATE.						REMOVE EXISTING FINISH FLOOR
F.01	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.						EXISTING CARPET
F.04	PREPARE PREVIOUSLY PAINTED CLOSET DOOR TO RECEIVE NEW PAINT INSIDE AND OUT. SEE ELEVATIONS AND SPECS.						EXISTING TILE
G.03	REMOVE EXISTING WINDOW						
G.04	REMOVE EXISTING WINDOW AND PREPARE TO INFILL ROUGH OPENING.						
G.06	REMOVE EXISTING EXTERIOR SUNSHADE SYSTEM.						
H.01	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.						

SANTA MONICA MALIBU UNIFIED SCHOOL DISTRICT
2828 4th Street, Santa Monica, CA 90405
310.399.5865

1539 Sawtelle Blvd., Suite 200, San Francisco, CA 94103
310.254.2283
928 Natoma Street, Suite 200, San Francisco, CA 94103
415.839.6416 / Fax 415.839.7584

CONSULTANT

PROJECT NAME
WEBSTER
ELEMENTARY
MODERNIZATION

FACILITY INFO
WEBSTER ELEMENTARY
3802 WINTER CANYON ROAD, MALIBU, CA 90265

AGENCY STAMP

FILE NUMBER: XX-X
IDENTIFICATION STAMP
DIVISION OF THE STATE ARCHITECT
XX-XXXXXX
ACS: _____ FLS: _____ SSS: _____
Date: _____

OSHPD PROJECT NO: XXXX


KEY PLAN

PROJECT ISSUE DATE: YYYY/MM/DD
DATE NO. REVISIONS
2016/09/22 50% CD SUBMITTAL

SHEET TITLE
DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG D


SHEET NUMBER
A2.00D

DRAFTER: Author PM: JC REVIEWER: AK



ND=None Detected

ADDITIONAL SAMPLING



ds architects Copyright ©
Plotted on 9/19/2016 10:12:37 AM C:\Users\Jonathan\Documents\16010 WEBSTER ES MODERNIZATION_Jonathan.rvt

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.

KEYNOTE LEGEND

B.01	REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH. CARPET TO REMAIN.
B.05	REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.
F.01	REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.
F.02	REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.
G.02	REMOVE EXISTING WINDOW WOODEN TRIM TO REMAIN.
G.03	EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.
G.07	EXISTING CASEWORK TO REMAIN. PROTECT IN PLACE. DOES NOT REQUIRE PAINT.
H.01	
H.02	

DEMOLITION GENERAL NOTES

1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.
2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.
3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.
4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.
5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.
6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.

LEGEND

	EXISTING PARTITION/WALL TO REMAIN
	REMOVE EXISTING ITEMS/PARTITION/WALL
	REMOVE EXISTING FINISH FLOOR
	EXISTING CARPET
	EXISTING TILE

SMUSD
SANTA MONICA MALIBU UNIFIED SCHOOL DISTRICT
2828 4th Street, Santa Monica, CA 90405
310.399.5865

dsd architects
1539 Sawtelle Blvd, Suite 14, Los Angeles, CA 90025
310.254.2263
928 Natomas Street, Suite 200, San Francisco, CA 94103
415.839.6416 / Fax 415.839.7584

CONSULTANT

PROJECT NAME
WEBSTER ELEMENTARY MODERNIZATION


FACILITY INFO
WEBSTER ELEMENTARY
3802 WINTER CANYON ROAD, MALIBU, CA 90265

AGENCY STAMP

FILE NUMBER: XX-XX
IDENTIFICATION STAMP
DIVISION OF THE STATE ARCHITECT
XX-XXXXXX
ACS: _____ FLS: _____ SSS: _____
Date: _____

OSHPD PROJECT NO: XXXX

KEY PLAN



PROJECT ISSUE DATE: YYYY/MM/DD

DATE	NO.	REVISIONS
2016/09/22	50%	CD SUBMITTAL

ND=None Detected

18-0119-ND

20-0119-ND

21-0119-ND

22-0119-ND

23-0119-ND

24-0119-ND

1-0119-ND

2-0119-ND

3-0119-ND

4-0119-ND

5-0119-ND

6-0119-ND

7-0119-ND

8-0119-ND

9-0119-ND

10-0119-ND

11-0119-ND

12-0119-ND

13-0119-ND

14-0119-ND

15-0119-ND

16-0119-ND

17-0119-ND

18-0119-ND

19-0119-ND

20-0119-ND

21-0119-ND

22-0119-ND

23-0119-ND

24-0119-ND

25-0119-ND

26-0119-ND

27-0119-ND

28-0119-ND

29-0119-ND

30-0119-ND

31-0119-ND

32-0119-ND

33-0119-ND

34-0119-ND

35-0119-ND

36-0119-ND

37-0119-ND

38-0119-ND

39-0119-ND

40-0119-ND

41-0119-ND

42-0119-ND

43-0119-ND

44-0119-ND

45-0119-ND

46-0119-ND

47-0119-ND

48-0119-ND

49-0119-ND

50-0119-ND

51-0119-ND

52-0119-ND

53-0119-ND

54-0119-ND

55-0119-ND

56-0119-ND

57-0119-ND

58-0119-ND

59-0119-ND

60-0119-ND

61-0119-ND

62-0119-ND

63-0119-ND

64-0119-ND

65-0119-ND

66-0119-ND

67-0119-ND

68-0119-ND

69-0119-ND

70-0119-ND

71-0119-ND

72-0119-ND

73-0119-ND

74-0119-ND

75-0119-ND

76-0119-ND

77-0119-ND

78-0119-ND

79-0119-ND

80-0119-ND

81-0119-ND

82-0119-ND

83-0119-ND

84-0119-ND

85-0119-ND

86-0119-ND

87-0119-ND

88-0119-ND

89-0119-ND

90-0119-ND

91-0119-ND

92-0119-ND

93-0119-ND

94-0119-ND

95-0119-ND

96-0119-ND

97-0119-ND

98-0119-ND

99-0119-ND

100-0119-ND

101-0119-ND

102-0119-ND

103-0119-ND

104-0119-ND

105-0119-ND

106-0119-ND

107-0119-ND

108-0119-ND

109-0119-ND

110-0119-ND

111-0119-ND

112-0119-ND

113-0119-ND

114-0119-ND

115-0119-ND

116-0119-ND

117-0119-ND

118-0119-ND

119-0119-ND

120-0119-ND

121-0119-ND

122-0119-ND

123-0119-ND

124-0119-ND

125-0119-ND

126-0119-ND

127-0119-ND

128-0119-ND

129-0119-ND

130-0119-ND

131-0119-ND

132-0119-ND

133-0119-ND

134-0119-ND

135-0119-ND

136-0119-ND

137-0119-ND

138-0119-ND

139-0119-ND

140-0119-ND

141-0119-ND

142-0119-ND

143-0119-ND

144-0119-ND

145-0119-ND

146-0119-ND

147-0119-ND

148-0119-ND

149-0119-ND

150-0119-ND

151-0119-ND

152-0119-ND

153-0119-ND

154-0119-ND

155-0119-ND

156-0119-ND

157-0119-ND

158-0119-ND

159-0119-ND

160-0119-ND

161-0119-ND

162-0119-ND

163-0119-ND

164-0119-ND

165-0119-ND

166-0119-ND

167-0119-ND

168-0119-ND

169-0119-ND

170-0119-ND

171-0119-ND

172-0119-ND

173-0119-ND

174-0119-ND

175-0119-ND

176-0119-ND

177-0119-ND

178-0119-ND

179-0119-ND

180-0119-ND

181-0119-ND

182-0119-ND

183-0119-ND

184-0119-ND

185-0119-ND

186-0119-ND

187-0119-ND

188-0119-ND

189-0119-ND

190-0119-ND

191-0119-ND

192-0119-ND

193-0119-ND

194-0119-ND

195-0119-ND

196-0119-ND

197-0119-ND

198-0119-ND

199-0119-ND

200-0119-ND

201-0119-ND

202-0119-ND

203-0119-ND

204-0119-ND

205-0119-ND

206-0119-ND

207-0119-ND

208-0119-ND

209-0119-ND

210-0119-ND

211-0119-ND

212-0119-ND

213-0119-ND

214-0119-ND

215-0119-ND

216-0119-ND

217-0119-ND

218-0119-ND

219-0119-ND

220-0119-ND

221-0119-ND

222-0119-ND

223-0119-ND

224-0119-ND

225-0119-ND

226-0119-ND

227-0119-ND

228-0119-ND

229-0119-ND

230-0119-ND

231-0119-ND

232-0119-ND

233-0119-ND

234-0119-ND

235-0119-ND

236-0119-ND

237-0119-ND

238-01

SHEETS PROVIDED "AS-IS" TO THE DISTRICT FOR PLANNING PURPOSES. SET IS PRE-50% CD, AND A WORK IN PROGRESS. NOT FOR CONSTRUCTION.

KEYNOTE LEGEND

- B.01 REMOVE EXISTING FLOORING MATERIAL. PREPARE SURFACE TO RECEIVE NEW FINISH.
- B.03 TILE FLOOR TO REMAIN, EXCEPT AS REQUIRED TO INSTALL NEW FIXTURES.
- F.01 REMOVE EXISTING DOOR AND FRAME IN THEIR ENTIRETY.
- F.02 REMOVE EXISTING DOOR AND HARDWARE, LEAVING DOOR FRAME IN PLACE.
- G.02 REMOVE EXISTING WINDOW SYSTEM, LEAVING STRUCTURE. SEE REFERENCED DEMOLITION DETAILS. PREPARE FOR NEW WORK.
- H.01 EXISTING CASEWORK TO REMAIN. PREPARE PREVIOUSLY PAINTED SURFACES TO RECEIVE NEW PAINT. SEE SPECS.
- M.03 REMOVE DRINKING FOUNTAIN AND METAL RAIL. PATCH WALL FINISH AS NEEDED AND PREPARE FOR NEW.
- P.03 EXISTING WALKWAY COVER TO REMAIN.

DEMOLITION GENERAL NOTES

1. ALL KEYNOTES ARE TYPICAL UNLESS OTHERWISE NOTED.
2. CONTRACTOR IS RESPONSIBLE TO PATCH AND REPAIR ALL WALLS, CEILINGS, AND FLOORING DAMAGED DURING DEMOLITION IN SCOPE OF WORK.
3. REMOVE WITHIN AREA OF WORK: EXISTING WINDOW FRAME, WOOD TRIM, AND GROUT. SEE DEMOLITION WINDOW DETAILS.
4. CONTRACTOR IS RESPONSIBLE TO REMOVE, REINSTALL, AND REWIRE ALL ELECTRICAL CONDUITS, OUTLETS, AND THERMOSTATS AS NEEDED TO PERFORM WINDOW DEMOLITION & NEW WINDOW INSTALLATION.
5. AT ALL EXISTING WINDOW ROUGH OPENINGS, REMOVE ROTTEN WOOD NAILERS AND REINSTALL NEW PRESSURE TREATED WOOD NAILER TO MATCH EXISTING.
6. SECTIONS PROVIDED TO AID WITH DEMOLITION ONLY. VERIFY EXACT CONDITIONS IN FIELD AND NOTIFY ARCHITECT OF UNFORESEEN CONDITIONS.

LEGEND

- EXISTING PARTITION/WALL TO REMAIN
- REMOVE EXISTING ITEMS/PARTITION/WALL
- REMOVE EXISTING FINISH FLOOR
- EXISTING CARPET
- EXISTING TILE

SMUSD
SANTA MONICA-MALIBU UNIFIED SCHOOL DISTRICT
2828 4th Street, Santa Monica, CA 90405
310.399.5865

EXISTING DOOR TO REMAIN

EXISTING WINDOW TO BE REMOVED

EXISTING CASEWORK TO BE REMOVED

EXISTING WALKWAY COVER TO BE REMOVED

dsd architects
1539 Sawtelle Blvd., Suite 14, Los Angeles, CA 90025
310.254.2283
928 Natoma Street, Suite 200, San Francisco, CA 94103
415.839.6416 / Fax 415.839.7584

CONSULTANT

PROJECT NAME
**WEBSTER
ELEMENTARY
MODERNIZATION**

FACILITY INFO
WEBSTER ELEMENTARY
3802 WINTER CANYON ROAD, MALIBU, CA 90265

AGENCY STAMP


FILE NUMBER: XX-X

IDENTIFICATION STAMP
DIVISION OF THE STATE ARCHITECT
XX-XXXXXX

ACS: _____ FLS: _____ SSS: _____
Date: _____


OSHPD PROJECT NO: XXXX

KEY PLAN




PROJECT ISSUE DATE: YYYY/MM/DD


DATE	NO.	REVISIONS
2016/09/22	50%	CD SUBMITTAL



6 DEMOLITION WALL SECTION - BUILDING F - SOUTH
3/4" = 1'-0"




4 DEMO EXTERIOR ELEVATION - BUILDING F - WEST
1/8" = 1'-0"



3 DEMO EXTERIOR ELEVATION - BUILDING F - SOUTH
1/8" = 1'-0"

ADDITIONAL SAMPLING



31-0126-ND
32-0126-ND
33-0126-ND
34-0126-ND

27-0126-ND
29-0126-ND
30-0126-ND

11-0126-ND
12-0126-ND
13-0126-ND

17-0126-ND
18-0126-ND
19-0126-ND
20-0126-ND
22-0126-ND
23-0126-ND

24-0126-ND
25-0126-ND
26-0126-ND

38-0126-ND
40-0126-ND
41-0126-ND

35-0126-ND
36-0126-ND
37-0126-ND

2 DEMO EXTERIOR ELEVATION - BUILDING F - NORTH
1/8" = 1'-0"

DEMOLITION WALL SECTION - BUILDING F - NORTH
1/4" = 1'-0"

1 DEMO FLOOR PLAN - BUILDING F
1/8" = 1'-0"


14-0126-ND
15-0126-ND
16-0126-ND

ND=None Detected

5-0126-ND
6-0126-ND
7-0126-ND
8-0126-ND
9-0126-ND
10-0126-ND

2-0126-ND
3-0126-ND
4-0126-ND

1-0126-ND



SHEET TITLE DSK JOB NO: 16010

**DEMOLITION PLAN,
EXTERIOR ELEVATIONS,
SECTIONS & DETAILS -
BLDG F**

SHEET NUMBER

A2.00F

DRAFTER: RD PM: JC REVIEWER: AK

Appendix D

Photographs

Sampling Photos, Webster ES

Sample # I-1-20

Sample # I-1-20-SPLIT

Photo #1



Sample # X-1-20

Photo #2




Sampling Photos, Webster ES

Sample # I-1-20B

Sample # I-1-20B-DUP

Photo #3



Sample # X-1-20B

Sample # X-1-20B-SPLIT

Photo #4



Sampling Photos, Webster ES

Sample # I-1-11P

Photo #5



Sample # X-1-11S

Photo #6



Sampling Photos, Webster ES

Sample # I-1-211D

Sample # I-1-211D-DUP

Photo #7



Sample # X-1-211S

Photo #8

No Photo Available

Sampling Photos, Webster ES

Sample # I-1-NW
Photo #9



Sample # X-1-NS


Sample # X-1-NS-DUP

Photo #10



Sampling Photos, Webster ES

Sample # I-1-RD
Photo #11



Sample # X-1-RS
Photo #12



Sampling Photos, Webster ES

Sample # I-1-7C

Sample # I-1-7P

Photo #13



Sample # X-1-7C

Sample # X-1-7S


Photo #14



Sampling Photos, Webster ES

**Sample # I-1-10A
#15**

Photo



Sample # X-1-C10

Sample # X-1-S10, X-3-S10


Sample # X-1-S10-DUP

Photo #16




Sampling Photos, Webster ES

Sample # I-1-10B
Photo #17



Sample # X-1-10B
Photo #18



Sampling Photos, Webster ES

Sample # I-1-CAF
Photo #19



Sample # X-1-CAF
Photo #20



Sampling Photos, Webster ES

Sample # I-1-G2
Photo #21




Sample # X-1-G2
Photo #22



Sampling Photos, Webster ES

Sample # I-1-H1
Photo #23



Sample # X-1-H1
Photo #24



Webster ES, Building B

01-0125

Photo #1

No Photo Available

02-0125

03-0125

04-0125

Photo #2



Webster ES, Building B

05-0125

06-0125

07-0125

Photo #3

No Photo Available

08-0125

09-0125

10-0125

Photo #4

No Photo Available


Webster ES, Building B

11-0125

12-0125

13-0125

Photo #5



14-0125

15-0125

16-0125

Photo #6



Webster ES, Building C

17-0125

Photo #7

No Photo Available

18-0125

19-0125

20-0125

Photo #8



Webster ES, Building C

21-0125

23-0125

Photo #9

No Photo Available

24-0125

25-0125

26-0125

Photo #10

No Photo Available

Webster ES, Building C

27-0125

28-0125

29-0125

Photo #11

30-0125

31-0125

32-0125

Photo #12

No Photo Available

No Photo Available

Webster ES, Building D

25-0119


26-0119

Photo #13



27-0119

Photo #14



Webster ES, Building D

28-0119

Photo #15




29-0119

30-0119

31-0119

Photo #16



Webster ES, Building D

33-0125

35-0125

Photo #17

No Photo Available


Webster ES, Building E

01-0119

02-0119

03-0119

Photo #18




04-0119

05-0119

06-0119

Photo #19




Webster ES, Building E

07-0119

08-0119

09-0119

Photo #20



10-0119

11-0119

12-0119

Photo #21



Webster ES, Building E

13-0119

14-0119

15-0119

Photo #22

16-0119

17-0119

Photo #23

No Photo Available

No Photo Available

Webster ES, Building E

18-0119

19-0119

20-0119

21-0119

Photo #24




22-0119

23-0119

24-0119

Photo #25



Webster ES, Building F

01-0126

Photo #26

02-0126

03-0126

04-0126

Photo #27

No Photo Available

No Photo Available

Webster ES, Building F

05-0126

06-0126

07-0126

Photo #28

08-0126

09-0126

10-0126

Photo #29

No Photo Available

No Photo Available

Webster ES, Building F

11-0126

12-0126

13-0126

Photo #30

14-0126

15-0126

16-0126

Photo #31

No Photo Available

No Photo Available

Webster ES, Building F

17-0126

18-0126

19-0126

Photo #32

20-0126

22-0126

23-0126

Photo #33

No Photo Available

No Photo Available

Webster ES, Building F

24-0126

25-0126

26-0126

Photo #34

27-0126

29-0126

30-0126

Photo #35

No Photo Available

No Photo Available

Webster ES, Building F

31-0126

32-0126

33-0126

Photo #36

34-0126

Photo #37

No Photo Available

No Photo Available

Webster ES, Building F

35-0126

36-0126

37-0126

Photo #38

38-0126

40-0126

41-0126

Photo #39

No Photo Available

No Photo Available