## PCB REMOVAL/REMEDIATION PROJECT RECORD Malibu High School – Buildings H and J

May 6, 2021

Prepared For:

Santa Monica Malibu Unified School District Carey Upton 2828 4<sup>th</sup> Street Santa Monica, California 90405

N | V | 5

NV5 – Alta Environmental 3777 Long Beach Blvd. Annex Building Long Beach, CA 90807 Phone: 800.777.0605

444720-0009592.01

## N V 5

## **EXECUTIVE SUMMARY**

At the request of the Santa Monica-Malibu Unified School District (District), Alta Environmental DBA NV5 (NV5) conducted monitoring services during the removal of polychlorinated biphenyl (PCB) impacted building materials (caulking) from Building H Rooms 605A, 606A, and 608 and Building J Rooms 700H, 704A, 704, and 705 within Malibu High School, located at 30215 Morning Drive, Malibu, California 90265. The removal activities were conducted in accordance with the USEPA-approved *Notification of New PCB-impacted Building Materials at Malibu High School* dated August 19, 2020.

During this project, all identified PCB Bulk Product Waste (door and window caulking) was removed by the District's removal contractor, Miller Environmental (Miller). Following the removal of identified PCB containing materials, NV5 conducted initial post-removal surface wipe sampling prior to removal of the work area containment. The results of the initial wipe samples were reported below the USEPA Region IX health-based benchmark.

Following receipt of acceptable initial wipe sample results, the work area containments were removed. Final confirmation surface wipe and air samples were collected following restoration of the work areas and prior to re-occupancy. The results of this sampling met the USEPA re-occupancy criteria.

## NV5

### **TABLE OF CONTENTS**

1.0	PROJE	ECT BACKGROUND 1
2.0	NV5 P	ROJECT SCOPE OF SERVICES 1
3.0	CONTI	RACTOR PERFORMED REMOVAL ACTIVITIES 1
3.1 3.2 3.3	REG ENG Buile	ULATED WORK AREA
3	.3.1	Door and Window Caulking
3.4	Buil	ding J2
3	.4.1	Door Caulking2
3.5	POS	T REMEDIATION CONTAINMENT INSPECTION AND CLEARANCE WIPE SAMPLING 3
3. 3.	.5.1 .5.2	Building H
3.6	CON	FIRMATION AIR AND WIPE SAMPLING PRIOR TO RE-OCCUPANCY
3 3	.6.1 .6.2	Wipe Sampling
4.0	WORK	(ER PROTECTION
5.0	WORK	(ER DECONTAMINATION
6.0	EQUIP	MENT DECONTAMINATION
7.0	QUALI	TY CONTROL
8.0	WAST	E MANAGEMENT AND DISPOSAL
9.0	PROJE	ECT SUMMARY
10.0	DISCL	AIMER
11 0	SIGNA	ATORY 6

#### **APPENDICES**

Appendix A: PCB Removal Locations Appendix B: Post Removal and Clearance Sampling Results Appendix C: Laboratory Reports

# N V 5

## **1.0 PROJECT BACKGROUND**

Previous investigations have identified polychlorinated biphenyl (PCB) impacted building materials within select areas of Building H and Building J at Malibu Middle and High School, located at 30215 Morning Drive, Malibu, California (Site). This report details monitoring services performed at the request of the Santa Monica-Malibu Unified School District (District), by Alta Environmental DBA NV5 (NV5) during the removal of door and window caulking materials containing polychlorinated biphenyls (PCBs) from Building H Rooms 605A, 606A, and 608 and from Building J Vestibules 700H and 704A and Rooms 704 and 705. The removal work was performed by the District's removal contractor, Miller Environmental (Miller or Contractor).

Appendix A provides figures detailing the locations of removed building materials.

### 2.0 NV5 PROJECT SCOPE OF SERVICES

NV5 provided the following services during the removal/remediation:

- Contractor observation to document project activities, including the Contractor's adherence to the requirements of NV5's *PCB Removal and Remediation Procedures* dated May 1, 2020 (herein identified as the "Work Plan");
- Final visual inspection confirming that applicable PCB materials and associated dust and debris was removed;
- Initial post-removal wipe sampling; and
- Final pre-occupancy surface wipe sampling and air sampling.

### **3.0 CONTRACTOR PERFORMED REMOVAL ACTIVITIES**

An overview of removal and abatement activities performed by Miller, is provided in the following sections. All PCB removal activities and waste segregation, storage, and disposal were conducted in accordance with the Work Plan.

#### 3.1 REGULATED WORK AREA

Regulated work areas were established at each of the PCB removal locations in Building H and Building J prior to the beginning of remediation activities. Physical barriers and warning signs were installed at the work area perimeters to limit access to authorized persons conducting or monitoring the remediation work. The PCB removal areas were further isolated by installing additional containment systems consisting of critical and perimeter barriers constructed with fire retardant polyethylene sheeting.

#### 3.2 ENGINEERING CONTROLS

The PCB removal area containment systems were constructed to minimize the potential for airborne dust to migrate outside the regulated work areas. Negative air pressures were established within

## N V 5

each containment using high-efficiency particulate air (HEPA) filtering fan units to maintain a minimum air pressure differential of -0.02 inches/water column. The containment area pressure differential was continuously monitored during PCB removal activities using a data-logging manometer. Additional engineering controls include the use of HEPA filter-equipped vacuums within the containment systems to collect dust generated during the remediation activities.

#### 3.3 BUILDING H

Previous investigations of Building H have identified concentrations of PCBs greater than 50 ppm in wall joint caulking associated with interior doorways and windows at Rooms 605A, 606A and 608. In addition, PCB impacts greater than 1 ppm have also been identified in the porous substrates adjoining these building components to a lateral distance of 16 inches.

#### 3.3.1 Door and Window Caulking

Miller removed the door assembly leading to Room 606A (Staff Restroom), the door and window assemblies associated with Room 605A (Cafeteria Office), the door assembly leading to Room 608 (Storage), and all adjoining porous substrate to a minimum distance of 16 inches from the door and window assemblies utilizing hand tools. Following removal activities, Miller and NV5 field personnel performed a final visual inspection of the containment areas. Once the areas were found to be acceptably free of PCB-impacted materials, dust and other debris, confirmation sampling was conducted. Following review of the laboratory results, the work area containment was removed to facilitate build-back using new building materials. Additional details of the post-remediation confirmation sampling are discussed in Section 3.5.

#### 3.4 BUILDING J

Previous investigations of Building J have identified concentrations of PCBs greater than 50 ppm in wall joint caulking associated with exterior doorways at Vestibules 700A and 704A and with interior doorways at Rooms 704 and 705. It should be noted, however, that samples collected from porous wall materials adjoining these doorways did not exhibit PCB concentrations above 1 ppm and therefore did not require remediation.

#### 3.4.1 Door Caulking

Miller removed each door assembly and all visible caulking material from the adjoining porous substrate in a staged process, with the interior doorways completed first (Rooms 704, 705) and the exterior doorways completed thereafter (Rooms 704A, 700H). All doorway assembly components, including associated PCB-impacted caulking, were fully removed, packaged, and properly disposed as Bulk Product Waste.

Following removal activities, Miller and NV5 field personnel performed a final visual inspection of the containment areas. Once the areas were found to be acceptably free of PCB-impacted materials, dust and other debris, NV5 collected clearance wipe samples. Upon notification of acceptable laboratory results, the work area containments were removed to facilitate build-back. Additional



details of the post-remediation confirmation sampling and build-back activities are discussed in Section 3.5.

## 3.5 POST REMEDIATION CONTAINMENT INSPECTION AND CLEARANCE WIPE SAMPLING

Following the removal of identified PCB containing materials, NV5 and Miller staff conducted a visual inspection of all containment areas. After the containment areas were deemed acceptable, post-removal surface wipe sampling was conducted prior to removal of the work area containments.

The wipe samples were collected on a hexane-wetted gauze pad using the Standard Wipe Test method described in 40 CFR 761.123. Following collection, the post-remediation wipe samples (including blanks) were submitted to American Environmental Testing Laboratory, a California-accredited environmental testing laboratory, for analysis. All surface wipe samples were prepared for analysis by the laboratory using EPA Method 3540 (Soxhlet extraction) and analyzed for PCBs using EPA Method 8082.

Appendix B presents a tabulated overview of the sample results and Appendix C presents copies of the laboratory reports.

#### 3.5.1 Building H

On July 21, 2020, six surface wipe samples and one blank wipe sample were collected from the floor of the containment systems for Rooms 605A, 606, 606A and 608.

Upon notification by the laboratory that the wipe samples contained PCB concentrations below the EPA Region IX health-based benchmark of 1.0 microgram ( $\mu$ g) per 100 square centimeters (cm<sup>2</sup>), the Contractor was authorized to remove the containment systems and begin build-back of removed components using new building materials (doorways, windows, wall coverings, etc).

#### 3.5.2 Building J

On July 31, 2020, five (5) surface wipe samples and one blank sample were collected from the Room 704 and 705 interior doorway containment area floors. Upon notification by the laboratory that the wipe sample PCB concentrations were reported below  $1\mu g/100 \text{cm}^2$ , the Contractor was authorized to remove the containment systems and install new door assemblies.

On August 14, 2020, a total of four (4) surface wipe samples and one blank sample were collected from the exterior doorway containments for vestibules 700H and 704A. Following laboratory notification that the wipe sample PCB concentrations were reported below  $1\mu g/100 cm^2$ , the Contractor was authorized to remove the containment systems and install new door assemblies.

#### 3.6 CONFIRMATION AIR AND WIPE SAMPLING PRIOR TO RE-OCCUPANCY

Following the completion of build-back activities and prior to re-occupancy, NV5 collected surface wipe and air confirmation samples from the PCB removal work areas within Building H. In accordance with the Plan, re-occupancy confirmation air and wipe sampling was not required for



Building J due to all interior PCB removal locations being removed from service and isolated from future use.

#### 3.6.1 Wipe Sampling

On September 11, 2020, a total of eight surface wipe samples and one blank sample were collected from the floor of the work areas for Rooms 605A, 606, 606A and 608. Each confirmation wipe sample was collected on laboratory supplied gauze pads or similar sampling media in general accordance with the Standard Wipe Test described in 40 CFR 761.123.

As presented in Appendix B, all re-occupancy confirmation samples were reported below the EPA Region IX heath-based benchmark of  $1.0\mu g/100 cm^2$ 

#### 3.6.2 Air Sampling

On September 11, 2020, three primary air samples were collected from the Room 605A, 606, 606A and 608 work areas. In addition, one ambient air sample was collected outside of the building to assess background concentrations of PCBs in air.

Each confirmation air sample was collected utilizing a calibrated pump to draw air through laboratory- supplied polyurethane foam cartridges at a flow rate of approximately 5 liters per minute, for approximately 24 hours. The air samples were collected at breathing zone height and without the use of pre-filters.

As presented in Appendix B, all re-occupancy confirmation samples were reported below the EPA evaluation criteria for the air samples. For reference, the following table presents USEPA's criteria for evaluating exposure levels in indoor air at school sites for children within the following age ranges:

<u>Age in Years</u> <u>Range</u>	<u>1 to &lt;2</u>	<u>2 to &lt;3</u>	<u>3 to &lt;6</u>	<u>6 to &lt;12</u>	<u>12 to &lt;15</u>	<u>15 to &lt;19</u>	<u>19 +</u>
PCBs ng/m <sup>3</sup>	100	100	200	300	500	600	500

## 4.0 WORKER PROTECTION

Personal protective equipment utilized by workers engaged in the PCB remediation activities included NIOSH-approved half-face air-purifying respirators with HEPA (P100) cartridges, disposable non-porous protective overalls, and eye, hand, foot and hearing protection devices.

## 5.0 WORKER DECONTAMINATION

A three-stage worker decontamination unit, integral to each work area containment, was placed at the entrance to the regulated work area and included a "dirty" room, shower room and a clean room. The decontamination facility was equipped with soap and towels.

## N V 5

## 6.0 EQUIPMENT DECONTAMINATION

Equipment used for PCB removal/remediation was wet-wiped and vacuumed with HEPA-equipped vacuums and visually inspected prior to removal from the work areas. In addition, the HEPA filters from all equipment, vacuums and negative air blowers were removed inside each containment, and the interior of the unit (filter compartment) was wet-wiped prior to removal from the containment systems. Following decontamination, all equipment, including tools, vacuums, and air filtration devices were visually inspected prior to removal from the work areas.

## 7.0 QUALITY CONTROL

Sample collection and analytical methodology used to complete this project were completed according to the Work Plan. All samples collected during this project were analyzed by a certified and accredited laboratory. NV5 reviewed all laboratory data for quality and usability in accordance with appropriate USEPA protocols. Based on a review of the laboratory QC data associated with the sample analysis, the recovery and precision are within the acceptable limits of the laboratory.

## 8.0 WASTE MANAGEMENT AND DISPOSAL

Waste generated as a result of the project activities was properly packaged, labeled and disposed of as PCB Bulk Product Waste, in accordance with the Work Plan and with 40 CFR 761.62. The PCB Bulk Product Waste was transported by BDC Special Waste Services, a California certified waste transporter. The waste was disposed at US Ecology, located at Hwy 95, 11 miles south of Beatty, Nevada.

## 9.0 PROJECT SUMMARY

PCB-related work completed during this project was done so in accordance with the Work Plan. Visual inspections confirmed that materials designated for removal were removed and that no visible dust or debris resulting from the removal activities remained in the work area.

Following the removal/remediation work, confirmation surface wipe and air samples were collected. Laboratory results of the surface wipe samples, and the air samples were reported below the level of clearance established for this project.

## **10.0 DISCLAIMER**

This report was prepared exclusively for use by the Santa Monica-Malibu Unified School District and may not be relied upon by any other person or entity without NV5 express written permission. The information, conclusions and recommendations described in this report apply to conditions existing at certain locations when services were performed and are intended only for the specific purposes, locations, time frames and project parameters indicated. NV5 cannot be responsible for the impact of any changes in environmental standards, practices or regulations after performance of services.

## NV5

In performing our professional services, we have applied engineering and scientific judgment and used a level of effort consistent with the current standard of practice for similar types of studies.

As applicable, NV5 has relied in good faith upon representations and information furnished by individuals with respect to operations and existing property conditions, to the extent that they have not been contradicted by data obtained from other sources. Accordingly, NV5 accepts no responsibility for any deficiencies, omissions, misrepresentations, or fraudulent acts of persons interviewed.

NV5 will not accept any liability for loss, injury claim, or damage arising directly or indirectly from any use or reliance on this report. NV5 makes no warranty, expressed or implied.

This report is issued with the understanding that the client, the property owner, or its representative is responsible for ensuring that the information, conclusions, and recommendations contained herein are brought to the attention of the appropriate regulatory agencies, as required.

Material quantities are in some cases listed within this document. These quantities are not intended to be used for removal bidding purposes, nor is this document intended as a contract manual. Work methods and sequence, coordination of participants, applicable codes, engineering controls, required submittals, and notifications should in all cases be addressed in a separate and independent bidding and contract document.

If you have any questions, please do not hesitate to contact the undersigned at (562) 495-5777. We appreciate the opportunity to be of service to the Santa Monica-Malibu Unified School District.

### **11.0 SIGNATORY**

Submitted for and on behalf of NV5. Prepared by: NV5

Jonathan Barker

Project Manager

Reviewed by: NV5

DURESO

David R. Schack Vice President, Building Sciences

# NV5

## APPENDIX A

**PCB Removal Locations** 

NV5.COM



**PCB** Removal Areas

Malibu High School

30215 Morning View Drive Malibu, California







# NV5

## **APPENDIX B**

Post-Removal and Clearance Sampling Results

## CLIENT:SMMUSDPROJECT NO:SMSD-20-9592PROJECT:MMHS Demolition Monitoring

Buildin g	Floor Plan ID	Sample Location	Component Description	Sampling Date	Sample ID	Total PCBs (µg/100cm <sup>2</sup> )
Н	608	Storage Room North	Containment Floor	7/21/2020	H0721-1	ND
Н	608	Storage Room South	Containment Floor	7/21/2020	H0721-2	ND
Н	606A	Staff Restroom North	Containment Floor	7/21/2020	H0721-3	ND
Н	606A	Staff Restroom South	Containment Floor	7/21/2020	H0721-4	ND
Н	605A	Kitchen Office North	Containment Floor	7/21/2020	H0721-5	ND
Н	605A	Kitchen Office South	Containment Floor	7/21/2020	H0721-6	ND
Field Bla	ink			7/21/2020	H0721-7	ND
J	705	East	Containment Floor	7/31/2020	J073120-1	ND
J	Vestibule 704/705	West	Containment Floor	7/31/2020	J073120-2	ND
J	704	South	Containment Floor	7/31/2020	J073120-3	ND
J	Vestibule 704/705	North	Containment Floor	7/31/2020	J073120-4	ND
Field Bla	ınk			7/31/2020	J073120-5	ND
J	Vestibule 704/704	Interior South center	Containment Floor	8/14/2020	J814-1	ND
J	Vestibule 704/705	Exterior north center	Containment Floor	8/14/2020	J814-2	ND
J	700H	Interior west center	Containment Floor	8/14/2020	J814-3	ND
J	700H	Exterior west center	Containment Floor	8/14/2020	J814-4	ND
Field Bla	ink			8/14/2020	J814-5	ND

Notes:

 $\mu$ g/100cm<sup>2</sup> = microgram per 100 square centimeters

PCB = polychlorinated biphenyl

J = A"J-flag" designation indicates that the reported concentration was detected above the method detection limit, but below the laboratory's practical quantitative limit

## CLIENT:SMMUSDPROJECT NO:SMSD-20-9592PROJECT:MMHS Demolition Monitoring

Building	Floor Plan ID	Sample Location	Component Description	Sampling Date	Sample ID	Total PCBs (μg/100cm <sup>2</sup> )
Н	606	Locker room southwest corner	Floor	9/11/2020	H-CL0	0.0709
Н	606	Locker room southwest corner	Floor	9/11/2020	H-CL1	0.0772
н	606A	Staff Restroom southeast corner	Floor	9/11/2020	H-CL2	0.0256J
Н	605A	Office north center	Floor	9/11/2020	H-CL3	ND
Н	Vestibule	Outside of 605A	Floor	9/11/2020	H-CL4	0.0651
Н	608	Storage east center	Floor	9/11/2020	H-CL5	0.0143
н	605B	Serving room southeast	Floor	9/11/2020	H-CL6	ND
H	605B	Serving room	Floor	9/11/2020	H-CL7	0.0416J
Field Blank				9/12/2020	H-CL9	ND

Notes:

 $\mu$ g/100cm<sup>2</sup> = microgram per 100 square centimeters

PCB = polychlorinated biphenyl

J = A"J-flag" designation indicates that the reported concentration was detected above the method detection limit, but below the laboratory's practical quantitative limit

CLIENT:SMMUSDPROJECTSMSD-20-9592PROJECT:MMHS Demolition Monitoring

Building	Room Placard ID	Room Description	Sampling Date <sup>[a]</sup>	Sample ID	Total PCBs (ng/m <sup>3</sup> )
Н	Outsic	de Ambient Sample	9/10/2020	H-CL-9	ND
Н	605B	Serving Room	9/10/2020	H-CL-10	ND
Н	605A	Kitchen Office	9/10/2020	H-CL-11	ND
Н	606A	Staff Restroom	9/10/2020	H-CL-12	12.6J

Notes:

[a] Air samples were collected over a 24-hour period with the lights on, windows and door closed, and ventilation off. Start date give

Abbreviations:

ng/m<sup>3</sup> = nanograms per cubic meter

ND = compound was analyzed for but not detected above the laboratory reporting limit

NA = Not Applicable

J = A"J-flag" designation indicates that the reported concentration was detected above the method detection limit, but below the laboratory's practical quantitative limit

# NV5

## APPENDIX C

Laboratory Reports



### American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181 Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

#### Ordered By

NV5 3777 Long Beach Blvd. Long Beach, CA 90807-

Telephone: (562)495-5777 Attention: Jonathan Barkman

Number of Pages	4
Date Received	07/21/2020
Date Reported	07/22/2020

Job Number	Order Date	Client
105485	07/21/2020	NV5

Project ID:	SMSD-20-9592
Project Name:	: Malibu High School
Site:	Malibu High School
	30215 Morning View Dr.
	Malibu, CA 90265

Enclosed please find results of analyses of 7 solid samples which were analyzed as specified on the attached chain of custody. If there are any questions, please do not hesitate to call.

Checked By:

-

Approved By:

Joe Sevrean Laboratory Director

<b>JF CUSTODY RECORD</b>	-120169	Page 1 of 1	TEST INSTRUCTIONS & COMMENTS				c															2. RELINQUISHED BY: 3.	Signature (1) Let 14 Uction	Ver Printer And OF EARCY	Time: 12. 12. The Image States	2. RECEIVED BY 3.	Signature	Printed Name:	Time: Date:/~1/20 Time:1640
	1.5000	C $S $ $L $ $C $ $D$	<b>YSIS REQUESTED</b>																			RELINQUISHED BY:	DUCENTANA VILLOAM	Printed Name: Villan	Date: [7]3/3 0	RECEIVED BY:	Signature:	Printed Name:	Date:
126-2178		AETLJOB No	ANAL	ž	esos	112 112	ertra Soxtra BJG	××	X X	×	×	× ×	X X	× X								+	3	ONES	1300	Ann 1.		くこう人気	De: 5:00
	b.com	Ś	6404	E PC	5		R PRES.	ar ICE						-1								RELINQUISHED BY	ignature: V	Pinted Namé:	7-12 1/20	ECEIVED AN:	111 A Royelio	inpred reames (	
<b>IG LABOR</b> LAP # 1541 LAC	840 www.aetla	MANAGER N BAYLM	10-920-01	# 20-9	, CA		CONTAINE NUMBER/SI	( 7.0.7 )						-1								T S	S			NURED R	S		Count Manager
L TESTIN RNIA 91504 E	X (818) 845-8	JUNGTAN	C ANONE 3		Mallinu		E MATRIX	STANK (	e MIPE	WIPE	3 WIPE	5 MIPE	6 MIRE	2 WIPE								A	JCTIONS	£		ERABLE REC			JK - Project/Ac
NMENTA SANK, CALIFO	845-8200 FA		C	ung beuc	IEW Dr.		TIM	133	1331	1340	661	191	124	(35)								ONTAINERS	ECIAL INSTRU	NV5.CO	WUI: GI	DATA DELIVI	HARD COPY E-COPY	GEOTRACKER (C	Laboratory, Pil
ENVIRO	88-AETL (818)	mental	A Direct 1	A CONTRACT	N pmm		DAT	e/eto 10:	20	20	10	Sa	70	- 10								MBER OF C	MATION / SPE	KMANG	CK (g NN				rv. CANARY - I
<b>MERICAN</b> 34 NORTH NA	TEL (888) 2	A Envino	Contra and	VICI VIDIO	DAIS MUN		LAB ID	105485	105485.	58 250	105485	105485	105485.	+ 10548C								TOTAL NU	LING INFOR	WW Bar	NOVOC.	OUND TIME			ITE - Laborato
28 A	6 LABORES R LABS COMPANY	MH- SVI	177 I D NA	ULECT NAME Y	E NAME	1100	SAMPLE ID	1-12101	6-121-9	E-10F0+	H-18404	S-IEFOI	A-ICLA	VEFUF									III .	1. Jonath	David	TURN AR	NORMAL 🔀 S/		RIBUTION: W
DIAJWA * TES	A KYZE	<u>ġ</u> ∠	5 2	<b>PRC</b>	ADD			- <b>-</b> -	4 es	4					5	2	E	2	12 I:	a ab	_			3					ISTI

CPM ENVIRONS

ampler/Uriginator ת



2834 N. NAOMI ST. BURBANK, CALIFORNIA 91504 ELAP# 1541 & 2402 LACSD# 10181 TEL (888) 288-AETL (818) 845-8200 FAX (818) 845-8840 www.aetlab.com

### **COOLER RECEIPT FORM**

Client Name: N1/5								
Project Name:	<u> </u>							
AETL Job Number: 105485		·····						
Date Received: 7/21/2020 Rece	eived b	V: Sovale	0					
Carrier: AETL Courier Client		$\overrightarrow{SO} \square \overrightarrow{Fec}$						
Others:								
Samples were received in: Cooler ( )	□ Othe	r (Specify):						
Inside temperature of shipping container No 1	3.40	No 2: , No	o 3:					
<b>Type of sample containers:</b> UOA, Glass bo	ttles, L	Wide mouth jars	s, $\Box$ HDPE bottles,					
University Specify:								
now are samples preserved: $\Box$ None, $\Box$ Ice, $\Box$ Blue Ice, $\Box$ Dry Ice								
$\Box$ None, $\Box$ HNO <sub>3</sub> , $\Box$ NaOH, $\Box$ ZnOAc, $\Box$ HCl, $\Box$ Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> ,								
	TOE							
Utner (Specify):	NIP S	NT.						
1 Are the COCs Correct?	res	<b>INO</b> , explain below	Name, if client was notified.					
2. Are the Sample labels legible?	Ň							
3. Do samples match the COC?	~							
4. Are the required analyses clear?								
5. Is there enough samples for required analysis?	V							
6. Are samples sealed with evidence tape?	NA							
7. Are sample containers in good condition?								
8. Are samples preserved?	<							
9. Are samples preserved properly for the	$\searrow$							
intended analysis?								
10. Are the VOAs tree of headspace?	NA							
11. Are the jars free of headspace?								

PLEASE NOTE ALL SAMPLES WILL BE DISPOSED OF 30 DAYS AFTER RECEIVING DATE. IF AETL IS INFORMED OTHERWISE, THERE WILL BE A STORAGE CHARGE PER SAMPLE PER MONTH FOR ANY SAMPLE HELD BEYOND 30 DAYS.

Explain all "No" answers for above questions:



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181 Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

#### Page: 1 A

#### Ordered By

#### NV5 3777 Long Beach Blvd. Long Beach, CA 90807-

Telephone: (562)495-5777 Attention: Jonathan Barkman

Project ID: SMS	D-20-9592
Date Received	07/21/2020
Date Reported	07/22/2020

Job Number	Order Date	Client
105485	07/21/2020	NV5

#### CERTIFICATE OF ANALYSIS CASE NARRATIVE

AETL received 7 samples with the following specification on 07/21/2020.

Lab ID	Sample ID	Sample Date	Matrix	Quantity Of	Containers
105485.01	H0721-1	07/21/2020	Solid	1	
105485.02	H0721-2	07/21/2020	Solid	1	
105485.03	H0721-3	07/21/2020	Solid	1	
105485.04	H0721-4	07/21/2020	Solid	1	
105485.05	H0721-5	07/21/2020	Solid	1	
105485.06	H0721-6	07/21/2020	Solid	1	
105485.07	H0721-7	07/21/2020	Solid	1	
Meth	od ^ Submethod	Req Da	ate Priority	TAT Units	
(8082		07/22/2	020 2	Rush ug/Kg	

The samples were analyzed as specified on the enclosed chain of custody. No analytical non-conformances were encountered.

Unless otherwise noted, all results of soil and solid samples are based on wet weight.

Checked By:

Approved By:

Joe Sevrean Laboratory Director

## ENVIRONAL STREET

## American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181 Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

## ANALYTICAL RESULTS

#### Ordered By

3777 Long Beach Blvd. Long Beach, CA 90807-

NV5

DICE
Malibu High School
30215 Morning View Dr.
Malibu, CA 90265

_		4			
Telephone: (562)4	95-5777				
Attn: Jonatha	n Barkman				
Page:	2				
Project ID:	SMSD-20-9592		AETL Job Number	Submitted	Client
Project Name:	Malibu Hiqh School		105485	07/21/2020	NV5

#### Method: (8082), Polychlorinated Biphenyls (PCBs) by GC

QC Batch No: 072120ZB1

Our Lab I.D.			Method Blank	105485.01	105485.02	105485.03	105485.04
Client Sample I.D.				H0721-1	H0721-2	H0721-3	H0721-4
Date Sampled				07/21/2020	07/21/2020	07/21/2020	07/21/2020
Date Prepared			07/21/2020	07/21/2020	07/21/2020	07/21/2020	07/21/2020
Preparation Method			3540C	3540C	3540C	3540C	3540C
Date Analyzed			07/22/2020	07/22/2020	07/22/2020	07/22/2020	07/22/2020
Matrix			Solid	Solid	Solid	Solid	Solid
Units			ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg
Dilution Factor			1	1	1	1	1
Analytes	MDL	PQL	Results	Results	Results	Results	Results
Aroclor-1016 (PCB-1016)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1221 (PCB-1221)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1232 (PCB-1232)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1242 (PCB-1242)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1248 (PCB-1248)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1254 (PCB-1254)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1260 (PCB-1260)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1262 (PCB-1262)	20.0	50.0	ND	ND	ND	ND	ND
Aroclor-1268 (PCB-1268)	20.0	50.0	ND	ND	ND	ND	ND
Our Lab I.D.			Method Blank	105485.01	105485.02	105485.03	105485.04
Surrogates	%Rec.Limit		% Rec.	% Rec.	% Rec.	% Rec.	% Rec.
Decachlorobiphenyl	30-150		58.8	48.6	50.4	48.8	51.0
Tetrachloro-m-xylene	30-150		43.4	48.0	58.4	54.0	60.0

## ENVIRONAL STREET

## American Environmental Testing Laboratory Inc.

 2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181

 Tel:
 (888) 288-AETL • (818) 845-8200 • Fax:
 (818) 845-8840 • www.aetlab.com

## ANALYTICAL RESULTS

#### Ordered By

3777 Long Beach Blvd. Long Beach, CA 90807-Telephone: (562)495-5777

NV5

	100
ľ	Malibu High School
3	30215 Morning View Dr.
N	Malibu CA 90265

Attn:	Jonathan Barkman					
Page:	3					
Project ID:	SMSD-20-9592	AETL	Job	Number	Submitted	Client
Project Nan	ne: Malibu High School		1054	485	07/21/2020	NV5

#### Method: (8082), Polychlorinated Biphenyls (PCBs) by GC

QC Batch No: 072120ZB1

Our Lab I.D.			105485.05	105485.06	105485.07	
Client Sample I.D.			H0721-5	H0721-6	H0721-7	
Date Sampled			07/21/2020	07/21/2020	07/21/2020	
Date Prepared			07/21/2020	07/21/2020	07/21/2020	
Preparation Method			3540C	3540C	3540C	
Date Analyzed			07/22/2020	07/22/2020	07/22/2020	
Matrix			Solid	Solid	Solid	
Units			ug/Kg	ug/Kg	ug/Kg	
Dilution Factor			1	1	1	
Analytes	MDL	PQL	Results	Results	Results	
Aroclor-1016 (PCB-1016)	20.0	50.0	ND	ND	ND	
Aroclor-1221 (PCB-1221)	20.0	50.0	ND	ND	ND	
Aroclor-1232 (PCB-1232)	20.0	50.0	ND	ND	ND	
Aroclor-1242 (PCB-1242)	20.0	50.0	ND	ND	ND	
Aroclor-1248 (PCB-1248)	20.0	50.0	ND	ND	ND	
Aroclor-1254 (PCB-1254)	20.0	50.0	ND	ND	ND	
Aroclor-1260 (PCB-1260)	20.0	50.0	ND	ND	ND	
Aroclor-1262 (PCB-1262)	20.0	50.0	ND	ND	ND	
Aroclor-1268 (PCB-1268)	20.0	50.0	ND	ND	ND	
Our Lab I.D.			105485.05	105485.06	105485.07	
Surrogates	%Rec.Limit		% Rec.	% Rec.	% Rec.	
Decachlorobiphenyl	30-150		80.0	76.0	58.8	
Tetrachloro-m-xylene	30-150		52.0	66.0	60.0	



## American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181 Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

#### QUALITY CONTROL RESULTS

#### Ordered By

3777 Long Beach Blvd. Long Beach, CA 90807-Telephone: (562)495-5777

Jonathan Barkman

4

NV5

Attn: Page:

Site
Malibu High School
30215 Morning View Dr.
Malibu, CA 90265

Project ID:	SMSD-20-9592	AETL Job Number	Submitted	Client
Project Name:	Malibu High School	105485	07/21/2020	NV5

#### Method: (8082), Polychlorinated Biphenyls (PCBs) by GC

#### QC Batch No: 072120ZB1; LCS: Blank; LCS Prepared: 07/21/2020; LCS Analyzed: 07/22/2020; Units: ug/Kg

	LCS	LCS	LCS	LCS DUP	LCS DUP	LCS DUP	LCS RPD	LCS/LCSD	LCS RPD	
Analytes	Concen	Recov	% REC	Concen	Recov	% REC	% REC	% Limit	% Limit	
Aroclor-1016 (PCB-1016)	500	484	96.8	500	487	97.4	<1	50-150	<40	
Aroclor-1260 (PCB-1260)	500	510	102	500	493	98.6	3.4	50-150	<40	
Surrogates										
Decachlorobiphenyl	50.0	29.0	58.0	50.0	27.8	55.6	4.2	30-150	<20	
Tetrachloro-m-xylene	50.0	30.5	61.0	50.0	27.7	55.4	9.6	30-150	<20	



2834 NORTH NAOMI ST. BURBANK, CALIFORNIA 91504 DHS # 1541 LACSD# 10181 TEL (888) 288-AETL (818) 845-8200 FAX (818) 845-8840 www.aetlab.com

## Data Qualifiers and Descriptors

### Data Qualifier:

#:	Recovery is not within acceptable control limits.
*:	In the QC section, sample results have been taken directly from the ICP reading. No preparation factor has been applied.
B:	Analyte was present in the Method Blank.
D:	Result is from a diluted analysis.
E:	Result is beyond calibration limits and is estimated.
H:	Analysis was performed over the allowed holding time due to circumstances which were beyond laboratory control.
J:	Analyte was detected . However, the analyte concentration is an estimated value, which is between the Method Detection Limit (MDL) and the Practical Quantitation Limit (PQL).
M:	Matrix spike recovery is outside control limits due to matrix interference. Laboratory Control Sample recovery was acceptable.
MCL:	Maximum Contaminant Level
NS:	No Standard Available
S6:	Surrogate recovery is outside control limits due to matrix interference.
S8:	The analysis of the sample required a dilution such that the surrogate concentration was diluted below the method acceptance criteria.
X:	Results represent LCS and LCSD data.

#### **Definition:**

%Limi:	Percent acceptable limits.
%REC:	Percent recovery.
Con.L:	Acceptable Control Limits
Conce:	Added concentration to the sample.
LCS:	Laboratory Control Sample
MDL:	Method Detection Limit is a statistically derived number which is specific for each instrument, each method, and each compound. It indicates a distinctively detectable quantity with 99% probability.



2834 NORTH NAOMI ST. BURBANK, CALIFORNIA 91504 DHS # 1541 LACSD# 10181 TEL (888) 288-AETL (818) 845-8200 FAX (818) 845-8840 www.aetlab.com

## Data Qualifiers and Descriptors

- MS: Matrix Spike
- MS DU: Matrix Spike Duplicate
- ND: Analyte was not detected in the sample at or above MDL.
- PQL: Practical Quantitation Limit or ML (Minimum Level as per RWQCB) is the minimum concentration that can be quantified with more than 99% confidence. Taking into account all aspects of the entire analytical instrumentation and practice.
- Recov: Recovered concentration in the sample.
- RPD: Relative Percent Difference



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

September 14, 2020

AETL Job No: BBI0120 Received Date: 09/11/2020 Project Number: SMSD-20-9592

NV5 3777 Long Beach Boulevard, Annex Building Long Beach, CA 90807

Telephone: (562) 495-5777

Attention: Jonathan Barkman

Project Name: Malibu High School

Site: Malibu High School, Bldg. H

Enclosed please find the results of analyses for samples which were analyzed as specified on the attached chain of custody. If you have any questions concerning this report, please do not hesitate to call.

Checked By:

aviet orosyan

Harriet Torosyan Project Manager

Approved By:

Corey Jones Project Manager

## Table of Contents

Clier Worl	nt Project Name: < Order Number:	Malibu High School (SMSD-20-9592) BBI0120	
1	Cover Letter		1
2	Sample Condition o	n Receipt	3
3	Chain of Custody		4
4	Cooler Receipt Forr	n	5
5	Case Narrative		6
6	Samples Received		7
7	Positive Hits Summ	ary	10
8	Analytical Results		12
9	Quality Control Res	ults	24
10	Qualifiers and Defin	itions	28



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

#### **Sample Condition on Receipt**

Cooler ID: Default Cooler		Temperature: 4.0 °C	
Are the COCs Correct	Y		
Labels Legible	Y	Containers In Good Condition	Y
COC/Labels Agree	Y	Samples Preserved Properly	Y
Sufficient Sample Volume	Y	Sufficient Holding Time for all Tests	Υ
Sample Labels intact	Y	Received on Ice	Y

IN OF CUSTODY RECORD	11/9/4	120 Page L of L	ESTED TEST INSTRUCTIONS & COMMENTS												7,021.3 2,403	7.042,75 1240	7,057,054,47	6,98.5.55 L. Koz				4ED BY: 2. RELINQUISHED BY: 3.	Signature:	Printed Name: Jim LIN	Time: Date: 9/11/23 Time: 1045	3Y: 2. RECEIVED BY 3. LABORATORY: 3.	Signature:	Printed Name:	Time: Date: 9/11/20 Time: 10 45	
CHA		AETL JOB No. (31310	S. WALYSIS REQU	101- 18	01 08 <	5872 - A. U	/ / / X	7 X	XXX	XX	× X	X	X	XX	X	X, X	X.) X	X				1. RELINQUISI	Signature:	Printed Name:	Time: Date:	1. RECEIVED I	Signature:	L C Printed Name:	Time: 0945 Date:	ler/Originator
ORATORY 1 LACSD# 10181 aetlab.com		ואמיש	195-5777	26-0292	2656-02	AINER PRES.	Dem <sup>2</sup>								21.34	42,75L	57.056	8.5 JT L				RELINQUISHED BY SAMPLER:	Signature	Pripted Name: Barl	Date:   N / ZOZO	RECEIVED BY:	Signature: A Z	Printed Name: X. M L	- Date: 9/11/20	inager, YELLOW - Samp
<b>TESTING LAB</b> IIA 91504 ELAP # 1541 (818) 845-8840 www.		PROJECT MANAGER	PHONE 570 2-4 EMAIL ON A than	PROJECT#	- QSWS *od	MATRIX CONT	Ind Join		7	0	2				7 PUF 7.0:	0 1 7,0	T ZO	J - 6 95	H ,			12	CTIONS			RABLE REQUIRED		-OBAL ID)	SPECIFY)	K - Project/Account Ma
RONMENTAL BURBANK, CALIFORN (818) 845-8200 FAX (			Pearl Blad	IL CA	Treel	DATE TIME	9/11/02/01	10/20 1445	1 / 1/43	14.57	14.57	11057	1655	1652	1/10/20 162	1 1/651	501	1 Wer	163			<b>OF CONTAINERS:</b>	I / SPECIAL INSTRUC			DATA DELIVE	HARD COPY			IARY - Laboratory, PIN
IERICAN ENVI 4 NORTH NAOMI ST. F TEL (888) 288-AETL		- GAIN-	han tt the	he y Bra	Jibu Hill S	LABID	9401000	013/0/20-02 9	20-02101596	3510120-04	BAIN 20,007	BP/0120.06	3R10120.01	BR10120.05	8810120-09 0	3810120.10	11.021912A	BR10120-12				TOTAL NUMBER	LING INFORMATION			OUND TIME	ME DAY NEXT DAY	DAYS T 4 DAYS	RUSH L RUSH	IITE - Laboratory. CAN
283.	A KYZER LABS COMPANY	COMPANY ALT	COMPANY ADDRESS	PROJECT NAME	SITE NAME ME AND ADDRESS	SAMPLE ID	H-CLO	1-1-7-H	" ユークト サ	E-70-H	トーフ-+1	"H-CL.S	1 H - CLO	" 17 - Ch 7	° H-CL9	10 H-CL10	"H-CLII	CHJ-H	13	14	15		BIL						D HSUSH L Q	USTRIBUTION: WH



2834 N. NAOMI ST. BURBANK, CALIFORNIA 91504 ELAP# 1541 & 2402 LACSD# 10181 TEL (888) 288-AETL (818) 845-8200 FAX (818) 845-8840 www.aetlab.com

#### **COOLER RECEIPT FORM**

Client Name: N1/5				
Project Name:				
AETL Job Number: 1/1/20		0		
Date Received: 9/1/2020 Recei	ved b	y: 1 Sargi's	Pireh	
Carrier:  AETL Courier  Client	G	SL D Fed	Ex $\Box$ UPS	
Others:				
Samples were received in: 🗷 Cooler ( / )	] Other	(Specify):		
Inside temperature of shipping container No 1:	4 <sup>,c</sup> ,	No 2: , No	3:	
<b>Type of sample containers:</b> $\Box$ VOA, $\Box$ Glass bot	tles, 🗆	Wide mouth jars	, $\Box$ HDPE bottles, $\Box$ Metal	
sleeves,  Others (Specify):				
How are samples preserved: 🗆 None, 🗔 Ice,	Blue	e Ice, 🗆 Dry Ice		
⊠ None, □ HNO <sub>3</sub>	, 🗆 Na	OH, $\Box$ ZnOAc,	$\Box$ HCl, $\Box$ Na <sub>2</sub> S <sub>2</sub> O <sub>3,</sub>	
□ MeOH				
□ Other (Specify):				
	Yes	NO, explain below	Name, if client was notified.	
1. Are the COCs Correct?				
2. Are the Sample labels legible?	V			
3. Do samples match the COC?	V			
4. Are the required analyses clear?	~			
5. Is there enough samples for required analysis?				
6. Are samples sealed with evidence tape?	MA			
7. Are sample containers in good condition?				
8. Are samples preserved?	>_			
9. Are samples preserved properly for the	$\left  \right\rangle$			
intended analysis?				
10. Are the VOAs free of headspace?	NA			
11. Are the jars free of headspace?				

PLEASE NOTE ALL SAMPLES WILL BE DISPOSED OF 30 DAYS AFTER RECEIVING DATE. IF AETL IS INFORMED OTHERWISE, THERE WILL BE A STORAGE CHARGE PER SAMPLE PER MONTH FOR ANY SAMPLE HELD BEYOND 30 DAYS.

Explain all "No" answers for above questions:



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

ETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
roject Number:	SMSD-20-9592		
roject Manager:	Jonathan Barkman		
roject Name:	Malibu High School	Reported:	09/14/2020 17:38
r r r	TL Job Number: oject Number: oject Manager: oject Name:	TL Job Number:       BBI0120         oject Number:       SMSD-20-9592         oject Manager:       Jonathan Barkman         oject Name:       Malibu High School	TL Job Number:BBI0120Site:oject Number:SMSD-20-9592oject Manager:Jonathan Barkmanoject Name:Malibu High SchoolReported:

#### **Case Narrative**

The following "Sample Received" Section summarizes the samples received and associated analyses requested as specified on the enclosed chain of custody.

No analytical non-conformances were encountered.

Qualifiers are noted in the report.



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

#### **Samples Received**

#### AETL received the following samples on 09/11/2020 with the following specifications

Project Name: Site:	Malibu High School, Bldg. H		
Client ID H-CL 0			Sample Date 09/10/2020 14:46
Lab ID		Matrix	Quantity of Containers
BBI0120-01		Wipe	1
Analysis		Units	ТАТ
EPA 8082		ug/100cm2	1
Client ID			Sample Date 09/10/2020 14:45
lah ID		Matrix	Quantity of Containers
BBI0120-02		Wipe	1
Analysis		Units	ТАТ
EPA 8082		ug/100cm2	1
Client ID H-CL 2			Sample Date 09/10/2020 14:47
Lab ID		Matrix	Quantity of Containers
BBI0120-03		Wipe	1
Analysis		Units	ТАТ
EPA 8082		ug/100cm2	1
Client ID H-CL 3			Sample Date 09/10/2020 14:50
Lab ID		Matrix	Quantity of Containers
BBI0120-04		Wipe	1
Analysis		Units	ТАТ
EPA 8082		ug/100cm2	1



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

#### Samples Received

(Continued)

#### AETL received the following samples on 09/11/2020 with the following specifications

IL leceived the	Tonowing samples on 09/11/2020 with the following spec	incations
Project Name: Site:	Malibu High School, Bldg. H	
Client ID H-CL 4		Sample Date 09/10/2020 14:51
Lab ID	Matrix	Quantity of Containers
BBI0120-05	Wipe	1
Analysis	Units	ТАТ
EPA 8082	ug/100cm2	1
Client ID H-CL 5		Sample Date 09/10/2020 16:57
Lab ID	Matrix	Quantity of Containers
BBI0120-06	Wipe	1
Analysis	Units	ТАТ
EPA 8082	ug/100cm2	1
Client ID H-CL 6		Sample Date 09/10/2020 16:55
Lab ID	Matrix	Quantity of Containers
BBI0120-07	Wipe	1
Analysis	Units	ТАТ
EPA 8082	ug/100cm2	1
Client ID H-CL 7		Sample Date 09/10/2020 16:56
Lab ID	Matrix	Quantity of Containers
BBI0120-08	Wipe	1
Analysis	Units	ТАТ
EPA 8082	ug/100cm2	1



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

#### Samples Received

(Continued)

#### AETL received the following samples on 09/11/2020 with the following specifications

Project Name:	Malibu High School, Bldg. H
Site:	

Client ID H-CL9 Lab ID BBI0120-09	Matrix Air	Sample Date 09/10/2020 16:27 Quantity of Containers 1
	Units	ТАТ
EPATO-10A	ng/m <sup>3</sup>	1
Client ID		Sample Date
H-CL10		09/10/2020 16:50
Lab ID	Matrix	Quantity of Containers
BBI0120-10	Air	1
Analysis	Units	ТАТ
EPA TO-10A	ng/m³	1
Client ID H-CL11		Sample Date 09/10/2020 16:45
Lab ID	Matrix	Quantity of Containers
BBI0120-11	Air	1
Analysis	Units	ТАТ
EPA TO-10A	ng/m³	1
Client ID H-CL12		Sample Date 09/10/2020 16:37
Lab ID	Matrix	Quantity of Containers
BBI0120-12	Air	1
Analysis	Units	ТАТ
EPA TO-10A	ng/m³	1

Total Number of Samples received:

12



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

#### **Positive Hits Summary**

Lab ID	Client ID				Received
BBI0120-01	H-CL 0				09/11/2020 10:45
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA 8082	Aroclor-1254 (PCB-1254)	0.0709		ug/100cm2	09/14/2020 10:50
Lab ID	Client ID				Received
BBI0120-02	H-CL 1				09/11/2020 10:45
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA 8082	Aroclor-1254 (PCB-1254)	0.0772		ug/100cm2	09/14/2020 11:11
Lab ID	Client ID				Received
BBI0120-03	H-CL 2				09/11/2020 10:45
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA 8082	Aroclor-1254 (PCB-1254)	0.0256	J	ug/100cm2	09/14/2020 11:30
Lab ID	Client ID				Received
BBI0120-05	H-CL 4				09/11/2020 10:45
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA 8082	Aroclor-1254 (PCB-1254)	0.0651		ug/100cm2	09/14/2020 12:10
Lab ID	Client ID				Received
BBI0120-06	H-CL 5				09/11/2020 10:45
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA 8082	Aroclor-1254 (PCB-1254)	0.143		ug/100cm2	09/14/2020 14:35
Lab ID	Client ID				Received
BBI0120-08	H-CL 7				09/11/2020 10:45
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA 8082	Aroclor-1254 (PCB-1254)	0.0416	J	ug/100cm2	09/14/2020 15:14
Lab ID	Client ID				Received
BBI0120-12	H-CL12				09/11/2020 10:45
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA TO-10A	Aroclor-1254 (PCB-1254)	12.6	J	ng/m³	09/14/2020 17:32

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document. No duplication of this report is allowed, except in its entirety without written approval of the laboratory.


2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

#### Positive Hits Summary (Continued)



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	)1 (Wipe)						Sa	mpled:	09/10	0/20 14	:46	
Analyte	Result Q	ualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Ana Date	lyzed e/Time	Batch	Analyst Initials	Prep. Method
PCBs												
Method:	EPA 8082											
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	0.0709		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	0 09/14/	20 10:50	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	123%				30-150		09/11/20 12:00	) 09/14,	20 10:50	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	64.8%				30-150		09/11/20 12:00	) 09/14,	20 10:50	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	)2 (Wipe)						Sar	npled:	09/10	0/20 14	:45	
Analyte	Result (	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Ana Date	lyzed e/Time	Batch	Analyst Initials	Prep. Method
PCBs												
Method:	EPA 8082											
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	0.0772		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	80.1%				30-150		09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	69.7%				30-150		09/11/20 12:00	09/14/	20 11:11	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	)3 (Wipe)						Samp	oled: 09/10	0/20 14	1:47	
Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs											
Method:	EPA 8082										
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	0.0256	J	1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria					
Surrogate: Decachlorobiphenyl	66.4%				30-150		09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	64.4%				30-150		09/11/20 12:00	09/14/20 11:30	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	94 (Wipe)						Sam	pled:	09/10	<b>)/20 1</b> 4	l:50	
Analyte	Result Qual	ifier [	Dilution	MDL	RL	Units	Prepared Date/Time	Ana Date	lyzed e/Time	Batch	Analyst Initials	Prep. Method
PCBs												
Method:	EPA 8082											
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 11:50	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	92.5%				30-150		09/11/20 12:00	09/14,	20 11:50	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	74.2%				30-150		09/11/20 12:00	09/14,	20 11:50	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	)5 (Wipe)						San	pled:	09/10	0/20 14	:51	
Analyte	Result (	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Ana Date	lyzed /Time	Batch	Analyst Initials	Prep. Method
PCBs												
Method:	EPA 8082											
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	0.0651		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/2	20 12:10	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	72.5%				30-150		09/11/20 12:00	09/14/.	20 12:10	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	68.8%				30-150		09/11/20 12:00	09/14/.	20 12:10	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	06 (Wipe)							Samp	oled: 09/1	0/20 16	5:57	
Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepar Date/Ti	ed ime	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs												
Method:	EPA 8082											
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	0.143		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	83.5%				30-150		09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	93.8%				30-150		09/11/20	12:00	09/14/20 14:35	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	7 (Wipe)						Sar	npled:	09/10	0/20 16	:55	
Analyte	Result Qual	ifier l	Dilution	MDL	RL	Units	Prepared Date/Time	Ana Date	lyzed e/Time	Batch	Analyst Initials	Prep. Method
PCBs												
Method:	EPA 8082											
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:00	09/14/	20 14:54	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	72.7%				30-150		09/11/20 12:00	09/14,	20 14:54	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	78.1%				30-150		09/11/20 12:00	09/14,	20 14:54	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	)8 (Wipe)						Sa	mpled:	09/10	0/20 16	5:56	
Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Ana Date	lyzed /Time	Batch	Analyst Initials	Prep. Method
PCBs												
Method:	EPA 8082											
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1254 (PCB-1254)	0.0416	J	1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm2	09/11/20 12:0	0 09/14/	20 15:14	B0I0238	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	97.9%				30-150		09/11/20 12:0	0 <i>09/14/</i>	20 15:14	B0I0238	ATS	3540C
Surrogate: Tetrachloro-m-xylene	88.0%				30-150		09/11/20 12:0	0 <i>09/14/</i>	20 15:14	B0I0238	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-0	9 (Air)					Samp	oled: 09/10	)/20 16	5:27	
Analyte	Result Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
Semivolatile Organic Co	ompounds									
Method:	EPA TO-10A									
Aroclor-1016 (PCB-1016)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1221 (PCB-1221)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1232 (PCB-1232)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1242 (PCB-1242)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1248 (PCB-1248)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1254 (PCB-1254)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1260 (PCB-1260)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1262 (PCB-1262)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Aroclor-1268 (PCB-1268)	ND	1	7.12	14.2	ng/m³	09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
	Recovery			Acceptance	e Criteria					
Surrogate: Decachlorobiphenyl	%			30-150		09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C
Surrogate: Tetrachloro-m-xylene	%			30-150		09/11/20 13:00	09/14/20 16:32	B0I0239	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-1	.0 (Air)					Samp	led: 09/10	0/20 16	5:50	
Analyte	Result Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
Semivolatile Organic C	ompounds									
Method:	EPA TO-10A									
Aroclor-1016 (PCB-1016)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1221 (PCB-1221)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1232 (PCB-1232)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1242 (PCB-1242)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1248 (PCB-1248)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1254 (PCB-1254)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1260 (PCB-1260)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1262 (PCB-1262)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Aroclor-1268 (PCB-1268)	ND	1	7.10	14.2	ng/m³	09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
	Recovery			Acceptance	e Criteria					
Surrogate: Decachlorobiphenyl	%			30-150		09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C
Surrogate: Tetrachloro-m-xylene	%			30-150		09/11/20 13:00	09/14/20 16:52	B0I0239	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-1	.1 (Air)					Samp	oled: 09/10	)/20 16	5:45	
Analyte	Result Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
Semivolatile Organic C	ompounds									
Method:	EPA TO-10A									
Aroclor-1016 (PCB-1016)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1221 (PCB-1221)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1232 (PCB-1232)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1242 (PCB-1242)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1248 (PCB-1248)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1254 (PCB-1254)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1260 (PCB-1260)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1262 (PCB-1262)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Aroclor-1268 (PCB-1268)	ND	1	7.09	14.2	ng/m³	09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
	Recovery			Acceptance	e Criteria					
Surrogate: Decachlorobiphenyl	%			30-150		09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C
Surrogate: Tetrachloro-m-xylene	%			30-150		09/11/20 13:00	09/14/20 17:12	B0I0239	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Analytical Results**

Lab ID: BBI0120-1	.2 (Air)						Samp	oled: 09/10	)/20 16	5:37	
Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
Semivolatile Organic C	ompounds										
Method:	EPA TO-10/	A									
Aroclor-1016 (PCB-1016)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1254 (PCB-1254)	12.6	J	1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	7.16	14.3	ng/m³	09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
	Recovery				Acceptance	e Criteria					
Surrogate: Decachlorobiphenyl	%				30-150		09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C
Surrogate: Tetrachloro-m-xylene	%				30-150		09/11/20 13:00	09/14/20 17:32	B0I0239	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Quality Control Results**

#### Semivolatile Organic Compounds (EPA TO-10A)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0I0239 - 3540C					Prepared:	09/11/2	020 13:00				
Method Blank (B0I0239-BLK1)					Analyzed:	09/14/2	020 16:13				
Aroclor-1016 (PCB-1016)	ND	6.94	13.9	ng/m³							
Aroclor-1221 (PCB-1221)	ND	6.94	13.9	ng/m³							
Aroclor-1232 (PCB-1232)	ND	6.94	13.9	ng/m³							
Aroclor-1242 (PCB-1242)	ND	6.94	13.9	ng/m³							
Aroclor-1248 (PCB-1248)	ND	6.94	13.9	ng/m³							
Aroclor-1254 (PCB-1254)	ND	6.94	13.9	ng/m³							
Aroclor-1260 (PCB-1260)	ND	6.94	13.9	ng/m³							
Aroclor-1262 (PCB-1262)	ND	6.94	13.9	ng/m³							
Aroclor-1268 (PCB-1268)	ND	6.94	13.9	ng/m³							
Surrogate: Decachlorobiphenyl	6.62			ng/m³	0.00			30-150			
Surrogate: Tetrachloro-m-xylene	4.97			ng/m³	0.00			30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Quality Control Results**

#### Semivolatile Organic Compounds (EPA TO-10A)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0I0239 - 3540C (Co	ontinued)				Prepared:	09/11/2	020 13:00				
LCS (B0I0239-BS1)	-				Analyzed:	09/14/2	020 15:34				
Aroclor-1016 (PCB-1016)	171	6.94	13.9	ng/m³	0.00			40-140			
Aroclor-1260 (PCB-1260)	113	6.94	13.9	ng/m³	0.00			40-140			
Surrogate: Decachlorobiphenyl	9.92			ng/m³	0.00			30-150			
Surrogate: Tetrachloro-m-xylene	5.10			ng/m³	0.00			30-150			
LCSD (B0I0239-BSD1)					Analyzed:	09/14/2	020 15:53				
Aroclor-1016 (PCB-1016)	128	6.94	13.9	ng/m³	0.00			40-140	28.8	40	
Aroclor-1260 (PCB-1260)	120	6.94	13.9	ng/m³	0.00			40-140	6.66	40	
Surrogate: Decachlorobiphenyl	6.31			ng/m³	0.00			30-150			
Surrogate: Tetrachloro-m-xylene	8.22			ng/m³	0.00			30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Quality Control Results**

#### PCBs (EPA 8082)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0I0238 - 3540C					Prepared:	09/11/2	020 12:00				
Method Blank (B0I0238-BLK1)					Analyzed:	09/14/2	020 10:31				
Aroclor-1016 (PCB-1016)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1221 (PCB-1221)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1232 (PCB-1232)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1242 (PCB-1242)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1248 (PCB-1248)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1254 (PCB-1254)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1260 (PCB-1260)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1262 (PCB-1262)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1268 (PCB-1268)	ND	0.0200	0.0500	ug/100cm2							
Surrogate: Decachlorobiphenyl	0.0424			ug/100cm2	0.0500		84.8	30-150			
Surrogate: Tetrachloro-m-xylene	0.0265			ug/100cm2	0.0500		53.0	30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38
Long Beach, CA 90807	Project Manager: Project Name:	Jonathan Barkman Malibu High School	Reported:	09/14/2020 17:38

## **Quality Control Results**

#### PCBs (EPA 8082)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0I0238 - 3540C (Cor	tinued)				Prepared:	09/11/2	020 12:00				
LCS (B0I0238-BS1)					Analyzed:	09/14/2	020 09:52				
Aroclor-1016 (PCB-1016)	0.715	0.0200	0.0500	ug/100cm2	1.00		71.5	50-150			
Aroclor-1260 (PCB-1260)	0.945	0.0200	0.0500	ug/100cm2	1.00		94.5	50-150			
Surrogate: Decachlorobiphenyl	0.0454			ug/100cm2	0.0500		90.9	30-150			
Surrogate: Tetrachloro-m-xylene	0.0330			ug/100cm2	0.0500		66.1	30-150			
LCSD (B0I0238-BSD1)					Analyzed:	09/14/2	020 10:11				
Aroclor-1016 (PCB-1016)	0.752	0.0200	0.0500	ug/100cm2	1.00		75.2	50-150	5.04	40	
Aroclor-1260 (PCB-1260)	0.973	0.0200	0.0500	ug/100cm2	1.00		97.3	50-150	2.97	40	
Surrogate: Decachlorobiphenyl	0.0402			ug/100cm2	0.0500		80.4	30-150			
Surrogate: Tetrachloro-m-xylene	0.0471			ug/100cm2	0.0500		94.1	30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBI0120	Site:	Malibu High School, Bldg. H
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		
	Project Name:	Malibu High School	Reported:	09/14/2020 17:38

## **Qualifiers and Definitions**

Item	Qualifiers
J	Analyte was detected. However, the analyte concentration is an estimated value, which is between the Method Detection Limit (MDL) and the Reporting Limit (RL).
Item	Definitions
% wt	Percent Weight
%REC	Percent Recovery
°C	Degrees Celsius
AETL	American Environmental Testing Laboratory, LLC
С	Carbon
CARB	California Air Resources Board
COC	Chain of Custody
DRO	Diesel Range Organics
Dup	Duplicate
ELAP	Environmental Laboratory Accreditation Program
EPA	Environmental Protection Agency
GRO	Gasoline Range Organics
HC	Hydrocarbon
LACSD	Los Angeles County Sanitation Districts
LCS	Laboratory Control Sample - A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes.
LCSD	Laboratory Control Sample Duplicate - A replicate of Laboratory Control Sample.
LOQ	Limit of Quantitation
MDL	Method Detection Limit - The minimum measured concentration of a substance that can be reported with 99% confidence. MDL is statistically derived number which is specific for each instrument, each method and each compound.
mg/kg	Miligrams per Kilogram
mg/L	Miligrams per Liter
MRO	Motor oil Range Organics
MS	Matrix Spike - A sample prepared, taken through all sample preparation and analytical steps of the procedure and analyzed as an independent test results.
MSD	Matrix Spike Duplicate - A replicate of Matrix Spike Sample.
Ν	No
ND	Analyte is not detected below Method Detection Limit.
ng/m3	Nanograms per cubic meter
NIOSH	National Institute for Occupational Safety and Health
nL/L	Nanoliters per Liter
NTU	Nephelometric Turbidity Units
Ohm-cm	Ohms per centimeter
OSHA	Occupational Safety and Health Administration

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document. No duplication of this report is allowed, except in its entirety without written approval of the laboratory.



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

_					
NV5 377	5 7 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number:	BBI0120 SMSD-20-9592	Site:	Malibu High School, Bldg. H
Lon	g Beach, CA 90807	Project Manager:	Jonathan Barkman		
		Project Name:	Malibu High School	Reported:	09/14/2020 17:38
РСВ	Polychlorinated Biphenyl				
RL RPD	Reporting Limit - The lowest concentration reported with a specified degree of confi Relative Percent Difference	on at which an analyte ca dence, accuracy and pre	an be detected in a sample and cision. For usage at AETL, RL is	its concentration equivalant to LC	n can be DQ.
SIM	Selective Ion Monitoring				
SPLF	Synthetic Precipitation Leaching Procedu	re			
STLC	C Soluble Threshold Limit Concentration				
TCLF	D Toxicity Characteristic Leaching Procedur	re			
TPH	Total Petroleum Hydrocarbons				
TTLC	C Total Threshold Limit Concentrations				
ug/kg	Micrograms per Kilogram				
ug/L	Micrograms per Liter				
ug/m	3 Micrograms per cubic meter				
NET	Waste Extraction Test				
Y	Yes				
ZHE	Zero Headspace Extraction				



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

August 04, 2020

AETL Job No: BBG0308 Project Number: SMSD-20-9592 Received Date: 07/31/2020

Jonathan Barkman NV5 3777 Long Beach Boulevard, Annex Building Long Beach, CA 90807

Project Name: Malibu High School Site: Malibu High School 30215 Morning View Dr. Malibu, CA

Enclosed please find the results of analyses for samples which were analyzed as specified on the attached chain of custody. If you have any questions concerning this report, please do not hesitate to call.

Checked By:

arriet orosyan

Harriet Torosyan Project Manager

Approved By:

Corey Jones Project Manager

# Table of Contents

Clie Wor	nt Project Name: k Order Number:	Malibu High School (SMSD-20-9592) BBG0308	
1	Cover Letter		1
2	Sample Condition o	n Receipt	3
3	Chain of Custody		4
4	Cooler Receipt Forr	n	5
5	Samples Received		6
6	Positive Hits Summ	ary	9
7	Analytical Results		10
8	Quality Control Res	ults	22
9	Qualifiers and Defin	itions	26



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School	
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.	
Long Beach, CA 90807	Project Manager: Project Name:	Jonathan Barkman Malibu High School	Reported:	08/04/2020 15:01	

## **Sample Condition on Receipt**

Cooler ID: Default Cooler		Temperature: 2.0 °C	
Are the COCs Correct	Y		
Labels Legible	Y	Containers In Good Condition	Υ
COC/Labels Agree	Y	Samples Preserved Properly	Υ
Sufficient Sample Volume	Y	Sufficient Holding Time for all Tests	Υ
Sample Labels intact	Y	Received on Ice	Υ

CHAIN OF CUSTODY RECORI	119741	AETLJOB No. 13 13 CO 308 Page 1 of 1	ANALYSIS REQUESTED	TIEST INSTRUCTIONS & COMMENT		72t	191 191 191	HQ3				XX											2 BY 1. RELINQUISHED BY: 2. RELINQUISHED BY: 3.	- W Suprumer Ullanuer Signature auf	WDY FLORES Rined Name: Villanvera Principanily	-20 <sup>TTIME</sup> 1530 073120 TIME: 1530 9246 [1U TIME: 1718	A RECEIVED BY: 2. RECEIVED BY 3.	Signature M Signature	CANNED PACILLAS PRIME NOVE PINE	Time: Jar 131 RU Time: 1530 Date: 171/70 Time: 1218
TORY # 10181 om				NUS.LON				PRES.	1 CE							_		-	4	11E			NQUISHED PLER:	iture: h	d Name	-12-t	EIVED BY:	ture:	d Name:	
<b>G LABORA</b> AP # 1541 LACSD 40 www.aetlab.cc		MANAGER	2846.106.0	vid. Schark@1	-30-9693			CONTAINER NUMBER/SIZE	1										-1				RELI	Signa	Printe	Date:		Signa	Printe	
<b>ESTIN</b> 191504 El 18) 845-88		PROJECT N	PHONE 3	FMAIL Da	SMS0	PO #		MATRIX	AIR	AIC	WIPE	_							-1	BLDNK			2	IONS			BLE REC		SAL ID)	Droiod/Ac
ALIFORNIA 00 FAX (81			2	DryBeaci				TIME	1450	1161	1501	1505	1520	1530	0211	1435	[HdD	1445	1400				NERS:	NSTRUCT			DELIVERA	ОРҮ	CKER (GLOE DI FASF SPF	
VIRONMEN 5T. BURBANK, C. 17L (818) 845-82		el .		Max Blda		a View Dr	Av.	DATE	02/02/1	0210811	9210515	0210E11	21 0E12	02/08/1	7/3//20				1	1/30/20			R OF CONTAI	ON / SPECIAL I	. \		DATA			ANADV L Shoret
ERICAN EN NORTH NAOMI S TEL (888) 288-AE		vironments		ich Blud An	1 Scheol	215 Menine	(b) the	LAB ID	8360308101	5560398.02	8360328, 23	70.3020342	50.8020 248	1336-0328.06	203020928	10:3020-92121	13136-2308.49	50 508.10	BBG0398-11	336-0306-12			TOTAL NUMBE	ING INFORMATIC	( I a ch		UND TIME	IE DAY IN NEXT DA		TE - Laboratory
2834	A KYZER LABS COMPANY	NV5 - A Ita En.	COMPANY ADDRESS	3777 LONG Rea	MOLLIOU HIGH	SITE NAME 30	ADDRESS Malo	SAMPLE ID	173020-I	T-32020-2	1-0702LZ/VL	2-0202LZM	NZ73020-3	H-02022N	1- ocietor	1073120-2	1073120-3	1073120-4	2-0216L0L	" I 73020-3	14	2		BILL		C. Low	TURN AROL Pag			

HIBUILON: WHITE - Laboratory, CANARY - Laboratory, PINK - Project/Account Manager, YELLOW - Sampler/Originator



2834 N. NAOMI ST. BURBANK, CALIFORNIA 91504 ELAP# 1541 & 2402 LACSD# 10181 TEL (888) 288-AETL (818) 845-8200 FAX (818) 845-8840 www.aetlab.com

## **COOLER RECEIPT FORM**

Client Name: N1/5								
Project Name:								
AETL Job Number: BBG0308								
Date Received: 7/3//20 Rece	ived b	V: Davais	Pirch					
Carrier: AETL Courier Client	$\Box G$	SO 🗆 Fed	Ex $\Box$ UPS					
Others:								
Samples were received in: 🛛 Cooler ( ) 🛛	] Other	(Specify):						
Inside temperature of shipping container No 1:	2.00	No 2: , No	0.3:					
<b>Type of sample containers:</b> □ VOA, □ Glass bo	ttles, 🗹	Wide mouth jars	s, $\Box$ HDPE bottles,					
□ Metal sleeves, □ Others (Specify):		-						
How are samples preserved:  None,  Ice,  Blue Ice,  Dry Ice								
$\square$ None, $\square$ HNO <sub>3</sub> , $\square$ NaOH, $\square$ ZnOAc, $\square$ HCl, $\square$ Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> .								
□ MeOH								
□ Other (Specify):								
	Yes	NO, explain below	Name, if client was notified.					
1. Are the COCs Correct?								
2. Are the Sample labels legible?	2							
3. Do samples match the COC?	>							
4. Are the required analyses clear?	>							
5. Is there enough samples for required analysis?	2							
6. Are samples sealed with evidence tape?	NA							
7. Are sample containers in good condition?								
8. Are samples preserved?								
9. Are samples preserved properly for the								
intended analysis?	V							
10. Are the VOAs free of headspace?	NIX							
11. Are the jars free of headspace?								

PLEASE NOTE ALL SAMPLES WILL BE DISPOSED OF 30 DAYS AFTER RECEIVING DATE. IF AETL IS INFORMED OTHERWISE, THERE WILL BE A STORAGE CHARGE PER SAMPLE PER MONTH FOR ANY SAMPLE HELD BEYOND 30 DAYS.

Explain all "No" answers for above questions:



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

#### **Samples Received**

#### AETL received the following samples on 07/31/2020 with the following specifications

Project Name: Site:	Malibu High School 30215 Morning View Dr. Malibu, CA			
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-01	173020-1	07/30/20 14:50	Air	1
Analysis			Units	ТАТ
EPA TO-10A			ng/m³	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-02	173020-2	07/30/20 15:11	Air	1
Analysis			Units	ТАТ
EPA TO-10A			ng/m³	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-03	WZ73020-1	07/30/20 15:01	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-04	WZ73020-2	07/30/20 15:05	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-05	WZ73020-3	07/30/20 15:20	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-06	WZ73020-4	07/30/20 15:30	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## Samples Received

(Continued)

#### AETL received the following samples on 07/31/2020 with the following specifications

Project Name: Site:	Malibu High School 30215 Morning View Dr. Malibu, CA			
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-07	J073120-1	07/31/20 14:30	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-08	J073120-2	07/31/20 14:35	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-09	J073120-3	07/31/20 14:40	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-10	J073120-4	07/31/20 14:45	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-11	J073120-5	07/31/20 14:50	Wipe	1
Analysis			Units	ТАТ
EPA 8082			ug/100cm2	5
Lab ID	Client ID	Sample Date	Matrix	Quantity of Containers
BBG0308-12	173020-3	07/30/20 14:50	Air	1
Analysis			Units	TAT
EPA TO-10A			ng/m³	5



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

**Total Number of Samples received:** 



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr.	
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA	
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01	

## **Positive Hits Summary**

Lab ID	Client ID				
BBG0308-01	173020-1	Rec			
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA TO-10A	Aroclor-1254 (PCB-1254)	30.9		ng/m³	08/03/2020 09:37
Lab ID	Client ID				
BBG0308-04	WZ73020-2	Rec	eived: 07/31/2		
Method	Analyte	Result	Qualifier	Unit	Analyzed
EPA 8082	Aroclor-1254 (PCB-1254)	0.0366	J	ug/100cm2	08/03/2020 11:21



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Analytical Results**

## Client ID: 173020-1

Lab ID: BBG0308-01 (Air)

Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
Semivolatile Organic Co	ompounds										
Method:	EPA TO-10A	1									
Aroclor-1016 (PCB-1016)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1254 (PCB-1254)	30.9		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
	Recovery				Acceptanc	e Criteria					
Surrogate: Decachlorobiphenyl	66.3%				30-150		07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C
Surrogate: Tetrachloro-m-xylene	43.3%				30-150		07/31/20 18:00	08/03/20 09:37	B0H0008	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Analytical Results**

## Client ID: 173020-2

Lab ID: BBG0308-02 (Air)

Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
Semivolatile Organic Co	ompounds										
Method:	EPA TO-10A	L .									
Aroclor-1016 (PCB-1016)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0500	0.100	ng/m³	07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
	Recovery				Acceptanc	e Criteria					
Surrogate: Decachlorobiphenyl	31.2%				30-150		07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C
Surrogate: Tetrachloro-m-xylene	37.4%				30-150		07/31/20 18:00	08/03/20 09:52	B0H0008	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number: Project Manager:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Analytical Results**

#### Client ID: WZ73020-1

Lab ID: BBG0308-03 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs											
Method:	EPA 8082										
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500 ug	g/100cm 2	07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
	Recovery				Acceptance	Criteria					
Surrogate: Decachlorobiphenyl	60.4%				30-150		07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	52.2%				30-150		07/31/20 18:00	08/03/20 11:06	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number: Project Manager:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Analytical Results**

#### Client ID: WZ73020-2

Lab ID: BBG0308-04 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs										
Method:	EPA 8082									
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	0.0366	J	1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
	Recovery				Acceptance Criteria					
Surrogate: Decachlorobiphenyl	33.6%				30-150	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	47.1%				30-150	07/31/20 18:00	08/03/20 11:21	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number: Project Manager:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Analytical Results**

#### Client ID: WZ73020-3

Lab ID: BBG0308-05 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs										
Method:	EPA 8082									
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
	Recovery				Acceptance Criteria					
Surrogate: Decachlorobiphenyl	75.8%				30-150	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	50.7%				30-150	07/31/20 18:00	08/03/20 12:39	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number: Project Manager:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Analytical Results**

#### Client ID: WZ73020-4

Lab ID: BBG0308-06 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs											
Method:	EPA 8082										
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
	Recovery				Acceptanc	e Criteria					
Surrogate: Decachlorobiphenyl	42.0%				30-150		07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	52.2%				30-150		07/31/20 18:00	08/03/20 12:54	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr.	
Long Beach, CA 90807	Project Manager:	1anager: Jonathan Barkman		Malibu, CA	
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01	

## **Analytical Results**

#### Client ID: J073120-1

Lab ID: BBG0308-07 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time Batch		Analyst Initials	Prep. Method
PCBs											
Method:	EPA 8082										
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500 u	ug/100cm 2	07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Recovery Acceptance Criteria											
Surrogate: Decachlorobiphenyl	43.3%				30-150		07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	66.9%				30-150		07/31/20 18:00	08/03/20 13:08	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Analytical Results**

#### Client ID: J073120-2

Lab ID:	BBG0308-08	(Wipe)
		( mpc

Analyte	Result	Qualifier	Dilution	MDL	RL Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs										
Method:	EPA 8082									
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
	Recovery				Acceptance Criteria					
Surrogate: Decachlorobiphenyl	31.0%				30-150	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	43.7%				30-150	07/31/20 18:00	08/03/20 13:23	B0H0010	AT	3540C


2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number: Project Manager:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Analytical Results**

#### Client ID: J073120-3

Lab ID: BBG0308-09 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs											
Method:	EPA 8082										
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500	ug/100cm 2	07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
	Recovery				Acceptan	ce Criteria					
Surrogate: Decachlorobiphenyl	59.4%				30-150		07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	38.2%				30-150		07/31/20 18:00	08/03/20 13:38	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number: Project Manager:	BBG0308 SMSD-20-9592 Jonathan Barkman	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Analytical Results**

#### Client ID: J073120-4

Lab ID: BBG0308-10 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL Units	Prepared Date/Time	Analyzed Date/Time	Batch	Analyst Initials	Prep. Method
PCBs										
Method:	EPA 8082									
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500 ug/100cm 2	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
	Recovery				Acceptance Criteria					
Surrogate: Decachlorobiphenyl	39.9%				30-150	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	45.5%				30-150	07/31/20 18:00	08/03/20 13:53	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Beach Boulevard, Annex Building	AETL Job Number: Project Number:	BBG0308 SMSD-20-9592	Site:	Malibu High School 30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Analytical Results**

#### Client ID: J073120-5

Lab ID: BBG0308-11 (Wipe)

Analyte	Result	Qualifier	Dilution	MDL	RL Units	Prepared Date/Tim	Analyzed e Date/Time	Batch	Analyst Initials	Prep. Method
PCBs										
Method:	EPA 8082									
Aroclor-1016 (PCB-1016)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0200	0.0500 ug/100 2	cm 07/31/20 18	3:00 08/03/20 14:08	B0H0010	AT	3540C
	Recovery				Acceptance Criter	ia				
Surrogate: Decachlorobiphenyl	40.7%				30-150	07/31/20 18	3:00 <i>08/03/20 14:08</i>	B0H0010	AT	3540C
Surrogate: Tetrachloro-m-xylene	44.2%				30-150	07/31/20 18	3:00 <i>08/03/20 14:08</i>	B0H0010	AT	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Analytical Results**

#### Client ID: 173020-3

Lab ID: BBG0308-12 (Air)

Analyte	Result Q	Qualifier	Dilution	MDL	RL	Units	Prepared Date/Time	Ana e Date	lyzed e/Time	Batch	Analyst Initials	Prep. Method
Semivolatile Organic C	ompounds											
Method:	EPA TO-10A											
Aroclor-1016 (PCB-1016)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1221 (PCB-1221)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1232 (PCB-1232)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1242 (PCB-1242)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1248 (PCB-1248)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1254 (PCB-1254)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1260 (PCB-1260)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1262 (PCB-1262)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
Aroclor-1268 (PCB-1268)	ND		1	0.0500	0.100	ng/m³	07/31/20 18	3:00 08/03/	20 10:07	B0H0008	ATS	3540C
	Recovery				Acceptanc	e Criteria						
Surrogate: Decachlorobiphenyl	46.2%				30-150		07/31/20 18	3:00 <i>08/03/</i>	20 10:07	B0H0008	ATS	3540C
Surrogate: Tetrachloro-m-xylene	35.9%				30-150		07/31/20 18	3:00 <i>08/03/</i>	20 10:07	B0H0008	ATS	3540C



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Quality Control Results**

### Semivolatile Organic Compounds (EPA TO-10A)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0H0008 - 3540C					Prepared:	07/31/2	020 18:00				
Method Blank (B0H0008-BLK1)					Analyzed:	08/03/2	020 09:22				
Aroclor-1016 (PCB-1016)	ND	0.0500	0.100	ng/m³							
Aroclor-1221 (PCB-1221)	ND	0.0500	0.100	ng/m³							
Aroclor-1232 (PCB-1232)	ND	0.0500	0.100	ng/m³							
Aroclor-1242 (PCB-1242)	ND	0.0500	0.100	ng/m³							
Aroclor-1248 (PCB-1248)	ND	0.0500	0.100	ng/m³							
Aroclor-1254 (PCB-1254)	ND	0.0500	0.100	ng/m³							
Aroclor-1260 (PCB-1260)	ND	0.0500	0.100	ng/m³							
Aroclor-1262 (PCB-1262)	ND	0.0500	0.100	ng/m³							
Aroclor-1268 (PCB-1268)	ND	0.0500	0.100	ng/m³							
Surrogate: Decachlorobiphenyl	0.0354			ng/m³	0.0500000		70.7	30-150			
Surrogate: Tetrachloro-m-xylene	0.0323			ng/m³	0.0500000		64.6	30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Quality Control Results**

### Semivolatile Organic Compounds (EPA TO-10A)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0H0008 - 3540C (Cont	inued)				Prepared:	07/31/	2020 18:00				
LCS (B0H0008-BS1)					Analyzed:	08/03/	2020 08:52				
Aroclor-1016 (PCB-1016)	0.554	0.0500	0.100	ng/m³	1.00000		55.4	40-140			
Aroclor-1260 (PCB-1260)	0.614	0.0500	0.100	ng/m³	1.00000		61.4	40-140			
Surrogate: Decachlorobiphenyl	0.0309			ng/m³	0.0500000		61.8	30-150			
Surrogate: Tetrachloro-m-xylene	0.0304			ng/m³	0.0500000		60.9	30-150			
LCSD (B0H0008-BSD1)					Analyzed:	08/03/	2020 09:07				
Aroclor-1016 (PCB-1016)	0.492	0.0500	0.100	ng/m³	1.00000		49.2	40-140	11.9	40	
Aroclor-1260 (PCB-1260)	0.595	0.0500	0.100	ng/m³	1.00000		59.5	40-140	3.26	40	
Surrogate: Decachlorobiphenyl	0.0349			ng/m³	0.0500000		69.8	30-150			
Surrogate: Tetrachloro-m-xylene	0.0290			ng/m³	0.0500000		58.1	30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

## **Quality Control Results**

### PCBs (EPA 8082)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0H0010 - 3540C					Prepared:	07/31/2	020 18:00				
Method Blank (B0H0010-BLK1)					Analyzed:	08/03/2	020 10:51				
Aroclor-1016 (PCB-1016)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1221 (PCB-1221)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1232 (PCB-1232)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1242 (PCB-1242)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1248 (PCB-1248)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1254 (PCB-1254)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1260 (PCB-1260)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1262 (PCB-1262)	ND	0.0200	0.0500	ug/100cm2							
Aroclor-1268 (PCB-1268)	ND	0.0200	0.0500	ug/100cm2							
Surrogate: Decachlorobiphenyl	0.0533			ug/100cm2	0.0500000		107	30-150			
Surrogate: Tetrachloro-m-xylene	0.0438			ug/100cm2	0.0500000		87.6	30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Quality Control Results**

### PCBs (EPA 8082)

Analyte	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
Batch: B0H0010 - 3540C (Cont	inued)				Prepared:	07/31/2	2020 18:00				
LCS (B0H0010-BS1)					Analyzed:	08/03/2	2020 10:21				
Aroclor-1016 (PCB-1016)	0.509	0.0200	0.0500	ug/100cm2	1.00000		50.9	50-150			
Aroclor-1260 (PCB-1260)	0.688	0.0200	0.0500	ug/100cm2	1.00000		68.8	50-150			
Surrogate: Decachlorobiphenyl	0.0366			ug/100cm2	0.0500000		73.2	30-150			
Surrogate: Tetrachloro-m-xylene	0.0346			ug/100cm2	0.0500000		69.2	30-150			
LCSD (B0H0010-BSD1)					Analyzed:	08/03/2	2020 10:36				
Aroclor-1016 (PCB-1016)	0.629	0.0200	0.0500	ug/100cm2	1.00000		62.9	50-150	21.1	40	
Aroclor-1260 (PCB-1260)	0.570	0.0200	0.0500	ug/100cm2	1.00000		57.0	50-150	18.6	40	
Surrogate: Decachlorobiphenyl	0.0389			ug/100cm2	0.0500000		77.7	30-150			
Surrogate: Tetrachloro-m-xylene	0.0319			ug/100cm2	0.0500000		63.7	30-150			



2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5	AETL Job Number:	BBG0308	Site:	Malibu High School
3777 Long Beach Boulevard, Annex Building	Project Number:	SMSD-20-9592		30215 Morning View Dr.
Long Beach, CA 90807	Project Manager:	Jonathan Barkman		Malibu, CA
	Project Name:	Malibu High School	Reported:	08/04/2020 15:01

### **Qualifiers and Definitions**

Item	Qualifiers
J	Analyte was detected. However, the analyte concentration is an estimated value, which is between the Method Detection Limit (MDL) and the Reporting Limit (RL).
Item	Definitions
%REC	Percent Recovery
°C	Degrees Celsius
AETL	American Environmental Testing Laboratory, LLC
CARB	California Air Resources Board
COC	Chain of Custody
Dup	Duplicate
ELAP	Environmental Laboratory Accreditation Program
EPA	Environmental Protection Agency
HC	Hydrocarbon
LACSD	Los Angeles County Sanitation Districts
LCS	Laboratory Control Sample - A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes.
LCSD	Laboratory Control Sample Duplicate - A replicate of Laboratory Control Sample.
LOQ	Limit of Quantitation
MDL	Method Detection Limit - The minimum measured concentration of a substance that can be reported with 99% confidence. MDL is statistically derived number which is specific for each instrument, each method and each compound.
mg/kg	Miligrams per Kilogram
mg/L	Miligrams per Liter
MS	Matrix Spike - A sample prepared, taken through all sample preparation and analytical steps of the procedure and analyzed as an independent test results.
MSD	Matrix Spike Duplicate - A replicate of Matrix Spike Sample.
N	
ND	Analyte is not detected below Method Detection Limit.
ng/m3	Nanograms per cubic meter
NIOSH	National Institute for Occupational Safety and Health
nL/L	Nanoliters per Liter
NIU	Nephelometric Turbidity Units
OSHA	Occupational Safety and Health Administration
RL	Reporting Limit - The lowest concentration at which an analyte can be detected in a sample and its concentration can be reported with a specified degree of confidence, accuracy and precision. For usage at AETL, RL is equivalant to LOQ.
RPD	Relative Percent Difference
SIM	Selective Ion Monitoring
TPH	Total Petroleum Hydrocarbons
ug/kg	Micrograms per Kilogram



Yes

# AMERICAN ENVIRONMENTAL TESTING LABORATORY

2834 North Naomi Street Burbank, CA 91504 • ELAP# 1541 & 2402 • LACSD# 10181 TEL (888) 288-AETL • (818) 845-8200 • www.aetlab.com

NV5 3777 Long Bea Long Beach, C	ach Boulevard, Annex Building CA 90807	AETL Job Number: Project Number: Project Manager:	BBG0308 SMSD-20-9592 Jonathan Barkman	Site:	Malibu High School 30215 Morning View Dr. Malibu, CA
		Project Name:	Malibu High School	Reported:	08/04/2020 15:01
ug/L	Micrograms per Liter				
ug/m3	Micrograms per cubic meter				

Ŷ

