

SANTA MONICA-MALIBU UNIFIED SCHOOL DISTRICT 1717 4TH STREET SANTA MONICA, CA 90401

> prepared by: NAC 837 N Spring St, 3rd Floor Los Angeles, CA 90012 (323) 475-8075

> > AUGUST 11, 2023 Final



NAC

INTRODUCTION 1. 3.3 SCHEME 2 1.1 TABLE OF CONTENTS 3.3.1 INTRODUCTION 1.2 3.3.2 **EXECUTIVE SUMMARY NARRATIVES** 3.3.3 1.3 TEAM DIRECTORY **DRAWINGS** 3.3.4 **CODE JUSTIFICATION** 2. **EXISTING SITE & BUILDING ASSESSMENT** 3.3.5 PLUMBING FIXTURE COUNTS 2.1 ARCHITECTURAL 2.2 HISTORICAL **OPINION OF PROBABLE COST** 4. 2.3 CIVIL 2.4 LANDSCAPE **APPENDIX** 5. 2.5 STRUCTURAL 5.1 HISTORICAL 2.6 MECHANICAL 5.2 **STRUCTURAL ENVIRONMENTAL REPORT:** 5.3 2.7 PLUMBING ASBESTOS AND LEAD 2.8 ELECTRICAL 5.4 DSA COORDINATION 2.9 FIRE ALARM & FIRE PROTECTION 2.10 TECHNOLOGY 2.11 ACOUSTICS 2.12 EVENTS AND ATHLETICS 2.13 THEATRE 2.14 MARKET SUPPLY & DEMAND DIAGNOSTIC **PROPOSED WORK** 3. **PARAMETERS** 3.1 3.1.1 **PROGRAM** 3.1.2 ATHLETIC COURT LAYOUTS 3.1.3 **PARKING**

3.2 SCHEME 1

3.1.4

- 3.2.1 INTRODUCTION
- 3.2.2 NARRATIVES
- 3.2.3 DRAWINGS
- 3.2.4 CODE JUSTIFICATION
- 3.2.5 PLUMBING FIXTURE COUNTS

CITY OF SANTA MONICA REGULATIONS



1.2 EXECUTIVE SUMMARY

The Santa Monica-Malibu Unified School District (District) is in the process of implementing a multi-phased Campus Plan at Santa Monica High School. They have been presented with the opportunity to evaluate if the Santa Monica Civic Auditorium (Auditorium), a City-owned landmark closed to the public since 2013, can be re-purposed to meet the needs identified in the Campus Plan and be reactivated for public events. The District is interested in bringing the Auditorium up to current standards to meet the Field Act with approval from the Division of the State Architect (DSA) and the California Department of Education. NAC has been retained to lead a team of consultants to conduct a feasibility study and document the findings that will aid the District in deciding whether or not to pursue the acquisition of the building to be used as an athletics and multi-use assembly space for the school and the community.

This report will demonstrate that the project is feasible. The team has documented the myriad conditions that require remediation. Some conditions require extensive work to create compliant and reliable rehabilitations, while others require fairly standard means and methods to address deferred maintenance issues. The work is indeed complicated by the rigors of compliance with the Division of the State Architect as a building for school use. However, the team has defined a means of compliance that is logical and efficient. Ultimately, the process is still discretionary and will require negotiation of scope and design strategy to ensure timely approvals.

The District has endeavored to balance the potential for the renovation of the existing historic building with the needs of Santa Monica High School and its athletic uses, and their secondary performance uses. The blend of programming envisioned has led to a solution that renovates the existing building and adds a new ancillary structure to support additional athletic programming.



1 Julius Shulman / Job 2673: Welton Becket and Associates, Santa Monica Civic Auditorium via Getty Images

The team has detailed an approach that celebrates the architectural history of the building, paying particular attention to key elements in the historical designation including the character defining elements: Brise Soleil, Pylons, and Hydraulic Tilting Floor.

An approach has been developed to address each. Multiple options for addressing various deficits were explored. While several solutions were viable, the solutions recommended here considered the original design condition, compliance of the project overall with the Secretary of the Interior's Standards for Rehabilitation, compliance with DSA standards, ability to support the new uses, and cost.

The pylons at the front of the building can be preserved but will require a fiber wrap for strength and lateral stability. The Brise Soleil can be preserved but will require bracing to tie it back to the building structure. Additional shear walls and lateral reinforcement is required, and the team has endeavored to locate such structure with minimal alteration to the exterior presentation of the building. The tilting floor can be preserved with its mechanics retained in place but will be designed to function in its flat position to address the primary athletic facility use and accessibility issues and compliance with the Americans with Disabilities Act. While not a complete list, this represents some of the most significant issues that will be found within this report.

The report defines estimated costs for this work. It will be the work of the District to assess the value of the building in the context of an already impacted High School campus. To support this evaluation, the report will detail a great deal of research on the existing building and its renovation potential from the historical significance of the Auditorium, an evaluation of the existing conditions and an exploration of the opportunities for the adaptive reuse.



Santa Monica-Malibu Unified School District

Carey Upton Chief Operations Officer cupton@smmusd.org

Steve Massetti Bond Program Manager smassetti@smmusd.org

Barbara Chiavelli Sr. Design Manager bchiavelli@smmusd.org

Alan Braatvedt Director of Projects alan.b@smmusd.org

Santa Monica-Malibu Unified School District Consultant

Brenda Levin & Associates Architects Historical Consultant blevin@levinarch.com

NAC

Architectural

Michael Pinto Design Principal

Mpinto@nacarchitecture.com

Leticia Ochoa Principal in Charge

Lochoa@nacarchitecture.com

Esmeralda Ward

Associate Principal, Project Architect

Eward@nacarchitecture.com

Louise Griffin Planner

Lgriffin@nacarchitecture.com

Hooman Kia Designer

Hkia@nacarchitecture.com

P2S

Mechanical, Electrical, Plumbing, Fire Protection, Technology

Travis Taylor Project Manager

Travis.taylor@p2sinc.com

Macen Cabral Mechanical Engineer

Macen.cabral@p2sinc.com

Daniel Ihlenfeldt

Electrical / Fire Alarm / Lighting Engineer

Daniel.ihlenfeldt@p2sinc.com

Andres Jimenez Fire Protection

Andres.jimenez@p2sinc.com

Eric Gomez Plumbing Engineer Eric.gomez@p2sinc.com

Massoud Safaee Technology

Massoud.safaee@p2sinc.com

POPULOUS

Sports Performance

Geoff Cheong Senior Principal

geoff.cheong@populous.com

Cumming Group

Cost Estimator

Merilyn Olave Associate Director

Molave@cumming-group.com

Priya Vishnupantulu Senior Cost Manager

Pvishnupantulu@cumming-group.com

Historic Resources Group

Historical

Christine Lazzaretto Managing Principal

Christine@historicresourcesgroup.com

John LoCascio Principal Architect

John@historicresourcesgroup.com

Adam Rajper

Historic Preservation Specialist Adam@historicresourcesgroup.com

KPFF

Civil, Structural

Civil Engineer Ishwar Dhungana Principal

Ishwar.dhungana@kpff.com

Samuel Vanhersecke

Civil Engineer

Samuel.vanhersecke@kpff.com

Structural Engineer Aldrin J. Orue Principal,

Aldrin.orue@kpff.com

OLIN

Landscape

Jessica Henson

Partner, Landscape Architect Jhenson@theolinstudio.com

Derek Lazo

Landscape Designer Dlazo@theolinstudio.com

Newson Brown Acoustics

Acoustics

Michael Brown Principal Acoustician

Michael@newsonacoustics.com

CSL

Sports / Entertainment Advisors

Tyler Othen Project Manager Tothen@cslintl.com

Salas O'Brien

Theatre


Jeff Miller

Senior Consultant

Jeff.miller@salasobrien.com

Vance Breshears Senior Vice President

Vance.breshears@salasobrien.com





2.1 ARCHITECTURE NARRATIVE

Introduction

The Santa Monica Civic Auditorium in the City of Santa Monica marked the culmination of the Civic Center buildout in 1958 and is considered a significant work of Mid-century Modern institutional architecture. Designed by Welton Becket and Associates, the Auditorium was designated as a City of Santa Monica Landmark in 2002. In recent years the City has continued maintenance of the building despite not been used publicly since 2013. The Civic Auditorium was closed due to seismic and accessibility concerns. The City is entertaining proposals to infuse new life into the iconic structure. The Santa Monica - Malibu Unified School District sees this as an opportunity to utilize the Auditorium as an educational and community asset.

The Civic Auditorium was designed as a multi-use event space. It has supported many different types of events, e.g., concerts, theatre performances, gala awards shows (including the Oscars), and conventions. It also supported sporting events, e.g., boxing, wrestling, and tennis. The feasibility study evaluates the existing Auditorium in the context of an adaptive reuse that can house athletics programs for Santa Monica High School and provide a multi-use assembly space for the school and community at-large. The campus is already largely built out. Space for new buildings is limited and the campus and surrounding Civic Center area density makes construction staging logistically complex.

Future planning for Santa Monica High School includes replacement space for athletics. Specifically, additional indoor gymnasium space is needed. Programs including Basketball, Volleyball, Wrestling, and Training / Fitness facilities are identified with associated locker and other support spaces. As originally designed, the Auditorium anticipated sporting events. The interior floor was sized to accommodate Basketball and Tennis, for example. Reclaiming that history is part of the potential of reuse.

2. Criteria

In short, this report will demonstrate that it is possible to renovate the Auditorium for reuse in an educational environment. We have studied diverse criteria in determining the feasibility of the proposed reuse. The categories below define criteria by which we propose the project be evaluated:

- A. Structural Feasibility
- B. Programmatic Feasibility
- C. Compatible Feasibility (Historical and School goals)
- D. Cost

3. District Goals

In order to evaluate the feasibility of the project envisioned, it is important to understand the goals of the District. There are a variety of goals that can be identified here representing several different parties. The building has history and is valued by the broader community. The Civic Center area is important to the City and its evolution. The land on which this building sits has a history and is meaningful and should be understood in today's context. The District is primarily responsible for providing a comprehensive, relevant education to its students.

The District acknowledges the diverse aspirations for the building and site. If the District ultimately decides to pursue the reuse of the Auditorium, the team must respond to a particular set of goals that are relevant to their mission. Foremost, it needs to be a responsible use of

available funds. School funds, particularly school construction funds are limited, and must be allocated responsibly in the context of other demands across the District. This report will not evaluate comparative demands on funds but will provide estimates of anticipated costs to support that assessment.

There is a goal to support the needed athletics programs outlined in the existing planning as well as support the designed use of the existing Auditorium for a variety of performances and events. Therefore, the goal to support athletics and performance has led to concept proposals that envision potentially separable uses, meaning that many athletics uses could happen both consecutively and simultaneously with performance uses.

It is clear that the District aims to provide excellent facilities for its educational programs. Additionally, there is a goal to identify any necessary compromises that must be anticipated with this project. Those compromises are highlighted in the report with the recommendations.

Finally, the District wishes to identify a scope of work necessary to reuse the building that is complete and thorough. While this is still a broad and high level review of feasibility, the NAC team has been asked to anticipate a project that is complete and lasting. While there are building systems, for example, that may have limited additional life expectancy, we have erred on the side of replacement. The goal is to provide a picture of a comprehensive cost of reuse with new, modern systems.

A. Architectural Assessment

During site visits the team was able to visually evaluate the condition of the building and focus on their specific disciplines, findings are found in each respective section of the report.

For the architectural assessment, it was observed that the Auditorium main space including the west and east wings are part of the original construction that needed to be evaluated against the historical characteristics identified by the Landmarks Commission. The additions along the south façade, however, were built as temporary storage areas afterwards and do not contribute to the character of the building. The ticket sales along the north façade is not original. It was expanded beyond the original façade limits and does not need to remain.

The exterior glazing in the Auditorium is boarded up to prevent access and vandalism. Based on what could be seen, it is implied that the exterior is intact and true to the original design. The City currently uses the building for event staging and storage primarily in the main space between the stage and fixed seating.

The pylons and Brise Soleil on the North are primary defining characteristics of the building and special considerations will be given to do further testing and try to retain the original design with minimal alterations.

A Code analysis to today's standards was done to identify the deficiencies in the existing building in regards to accessibility and fire, life, safety (FLS) within the architectural scope.

4. Code Analysis

Built in 1958, the Santa Monica Civic Auditorium is a cast in place concrete building. Additions/renovations over the years have added storage and functional adjustments but have not altered the type or materiality of the building significantly. The original building drawings do not contain a code analysis or justification.

The team conducted a preliminary code analysis on the existing building to establish a baseline condition. The following uses the CBC 2022 to justify the existing building in today's standards, using information derived from the original as built drawings.

- A. Size: 69,820 gross sf (approx.)
 - i. 1st Floor 49,790 sf
 - ii. 2nd Floor 3,745 sf
 - iii. 3rd Floor (Concourse) 15,260 sf
 - iv. 4th Floor (Control Rooms) 1,025 sf
 - v. (Basement is 7,455 sf but does not contribute towards gross sf of building for area calculation purposes 506.1.3)
- B. Height: 80' to top of fly tower
- C. Stories: 3, plus mezzanine and technical levels
- D. Occupancies
 - i. A 1 per 303.2 (stage, auditorium, support spaces, community room in east wing)
 - ii. B (offices in west wing)
 - iii. S (assorted storage spaces)
- E. Material/Construction: cast in place concrete frame/shear
- F. Assuming a fully compliant automatic sprinkler system and fire alarm system would be installed in any renovation of the building, the building could be justified as a Type II A building following 506.2.2 Mixed Occupancy Buildings with non separated occupancies analysis per 508.3.2 using A 1 as the most stringent occupancy.
- G. Building Height (504 and Table 504.3)
 - i. Allowed: 85'
 - ii. Actual: 80'
- H. Building Stories (504 and Table 504.4)
 - i. Allowed: 4 stories (without area increase)
 - ii. Actual: 3 stories
- I. Building Area (506 and Table 506.2)
 - i. Allowed Area per floor: (with frontage of 0.25)

$$A_a = [A_t + (NS \times I_f)]$$

 $A_a = [46,500 + (15,500 \times 0.25)]$

 $A_a = 50,375$ sf per floor

ii. Actual Area (on largest floor): 49,790 sf


5. Existing conditions

The architectural evaluation of the building includes accessibility, life safety, configuration of spaces to support gym program and a visual assessment of the general condition of the exterior, the building finishes, and the building elements.

A. Exterior of main Auditorium building

The building's reinforced concrete structure is also its exterior finish face. The exposed concrete walls of the main Auditorium are scored and painted while the exposed walls of the fly space have a smooth painted finish. The prominent north elevation is made up of concrete screen panels with a storefront system behind them. The concrete screen panels begin approximately 10' o" above the finish floor, exposing the storefront system along the entrance to the building. The storefront system is made up of a mix of clear and textured glass.

The main Auditorium roofing system is a built up roof and gravel over 1" rigid insulation over 2" poured gypsum on 1" form board and appears to be the original. On the east and west elevations, there is a portion of the roof with standing seam roofing over 1" ridge insulation over 3" gypsum roof tile and appear to be the original.



Detail section from 1956 Welton Becket & Associates Drawings

The roofing system over the stage/fly space is built up roof & gravel over 1" rigid insulation over the concrete roof slab.

The canopy, located behind the six pylons, is currently clad in metal panels with large square recessed light fixtures. These metal panels and light fixtures are not consistent with the original drawings. The original design shows a plaster canopy soffit with round recessed light fixtures. The canopy's roofing system is composite roofing over $\frac{1}{2}$ " rigid insulation and 1 $\frac{1}{2}$ " steel decking.

The iconic 69' o" high pylons are located in front of the canopy. Refer to the structural narrative for suggested seismic upgrades.

In the original drawings and in historic photos by Julius Shulman, there was a reflecting pool and railing. The pool and railing are no longer on site and the pool has been filled in with concrete.





Julius Shulman / Job 2673: Welton Becket and Associates, Santa Monica Civic Auditorium via Getty Images

Along the south elevation of the building are aluminum louvers letting air flow to the exterior mechanical equipment areas. Behind a portion of the louvers are aluminum framed windows.



Photo showing south elevation showing aluminum louvers

There is a large ramp leading up to a loading dock area inside the building with a sliding door. There are two exterior structures along the south elevation of the building. These structures are not shown in the original drawings and appear to have been added at a later.

The loading dock is located along the west elevation. The as built drawings show a loading dock, a concrete stair, two large sliding doors and a single door. Three pairs of double doors have been added between the sliding doors and three sets of metal stairs with railings.



Photo showing loading dock along west elevation

B. Exterior of East Wing (Committee) building wing

The exterior façade of the East Wing is exposed concrete scored at a similar spacing to the main Auditorium building wing. There is full height storefront on the east and north facades. The glazing is boarded up but visible from the inside of the building.

The south elevation appears to be changed from the original design. The as built drawings show a Redwood post and header beam with full height Redwood louvers, a loading door, an entrance door, and concrete steps leading up to the loading dock. The existing condition has a ramp running north/south and an enclosed structure at the loading dock. The door is located along the east side of the enclosure. The enclosure appears to have been built on top of the concrete loading dock and is lower than the height of the Committee building wing.

There are screens on the roof of the building shielding mechanical equipment. The screens are located along the south elevation and a portion of the east elevation. They do not appear to be in the original drawings.

C. Exterior of West Wing (Administration) building wing

Exterior façade of the West Wing is concrete. Above the windows is plaster and below the windows is exposed concrete. In the as built drawings, the west elevation has aluminum louvers in front of the windows. It appears many of the louvers have been removed and air condition window units placed in portions of the windows. The lower portion of the windows are boarded up. A similar condition exists on the south elevation. Louvers remain over a portion of one window while they are missing over the second window which also has a window-mounted unit in it.



Photo showing West Wing (Administration) building

The windows along the north elevation have been boarded up. The as built drawings show full height storefront windows while the windows on site have a low wall below them, a counter, and a fabric awning over them. These items do not appear in the original drawings.



Photo of north elevation of West Wing (Administration) building


D. Interior of main Auditorium building

The building was designed as a multi-event performance venue. The main Auditorium is made up of a raked seating area that has 958 fixed seats and a flat floor area for 1572 removable Auditorium chairs. The flat floor area also has the ability to tilt towards the stage giving the audience a better view of the stage.



Academy Awards show photographs, Margaret Herrick Library, Academy of Motion Picture Arts and Sciences

When the floor is in its flat position, the raked seating is approximately 1' 4" higher than the floor and is accessed by portable steps at each gallery aisle. The orchestra lift and the floor are at the same elevation. When the floor is in its tilted position, the raked seating is approximately 8" higher than the floor. Along the orchestra lift and stage, the tilted floor is approximately 3' o" lower.



Building section from 1956 Welton Becket & Associates Drawings

Based on the as built drawings, the Auditorium can accommodate basketball, tennis, boxing as well as performances on stage.





SMCA 50th Anniversary - City TV 2008 video

Valley Times Collection, LAPL Photo Collection


The solid metal panels and perforated metal panels match the existing drawings. There are wall sconces placed in front of the panels. The first panel north of the stage is a hardwood louvered panel on both sides of the Auditorium.

The Auditorium's suspended plaster ceiling system and light fixtures match the as-built drawings and appear to be the original. There are also mechanical grills in the plaster ceiling.

i. Auditorium Lobby and Stairs

The Auditorium Lobby is located along the north side and is accessed through two sets of double doors on either side of the ticket sales. The sets of storefront doors appear to be original, but the ticket sales area has been replaced with larger volumes on both the interior and exterior volumes. There are also two sets of double doors on both the east and west elevations.

There are two monumental stairs in the Lobby leading up to the Concourse level. Stair #1 and Stair #2 are concrete with terrazzo treads and hardwood railings. The hardwood railing and birch slats are supported by a metal guard rail frame. At the Concourse level, the guardrails and birch slats frame the opening below.





Photos of stair at Lobby and Concourse level

The as built drawings show two circular concessions in the Lobby. The concessions have been removed along with the casework, equipment, and floor sinks.

Wood panels line the Lobby's south walls leading into the Auditorium.

There are two sets of Men's and Women's restrooms off the Lobby. There are some small rooms adjacent to the restrooms. These rooms were locked during the time of the site visit.

The existing flooring in the Lobby and continuing up to the Concourse level is terrazzo. The terrazzo flooring is listed on Santa Monica's Public Art Archive. "Two Hundred Fourteen Movements and a View" was completed in 1997 by Renée Petropoulos. The as built drawings show terrazzo flooring at the two entrances off the north and in front of Stair #1 and Stair #2. The rest of the Lobby is noted to be carpet.

The ceiling appears to be the original acoustic tile on plaster as noted in the as-built drawings.



Photo of ceiling in Lobby

ii. Concourse Area


The Concourse is accessed by the Stairs # 1 and Stair #2. The exposed storefront glazing on the Concourse level is textured glass. There appears to be some textured glass panels that have been replaced with a textured glass varying slightly from the original. The ceiling appears to be the original.

The as built drawings show a concession area on this level. It has been removed.

The Projection Room is accessed by a stair off the Concourse level.

There are six double doors that provide access to the raked fixed seating.





Photos of former concession (now a niche) on Concourse level

iii. Stage, Orchestra Lift, Proscenium and Fly Space

The Auditorium has a counterweight fly system made up of ropes, cable, hardware, and electric lines used for rigging lights, draperies, and scenery during productions. It appears to be the original system.

The top of the grid iron is noted at +70' o" in the as built drawings.

The Proscenium opening is approximately 65' 6" wide x 31' 6" high.

The stage's flooring system is 2 1/2" pine flooring over asphalt impregnated sand over concrete. The orchestra lift flooring system is 2 1/2" pine flooring over rigid cane fiberboard fill. The as built drawings note the framing of the orchestra lift platform are found in the specifications and the elevator shop drawings. The specifications and elevator shop drawings do not appear to be included in the existing documentation provided by the City of Santa Monica. The orchestra lift was not tested during the site visits so it cannot be confirmed if the lift is functional.

iv. Dressing rooms and restrooms

There are several dressing rooms and performance related support spaces at the stage level/first floor and on the second floor. There is a Men's restroom with showers on the stage level/first floor and a Women's restrooms with showers on the second floor. The rooms appear to match the as built drawings. The existing plumbing fixtures, casework and built in features appear to be the original. Several of the ceiling tiles have fallen off the ceiling substrate.



Photo of dressing room

v. Basement storage, tilt floor area and support spaces

The basement has a Men's and a Women's restrooms along with performance related support space, maintenance shop and lockers. The basement houses the electrical switchgear and main transformer. Refer to the electrical narrative for additional information.

The orchestra lift is accessed by a set of large double doors. The doors were locked at the time of the site visit.



Photo of double doors in the basement at orchestra lift

vi. Stairs

There are 11 stairs in the as built drawings. In addition to the two main stairs in the Lobby, there are two sets of stairs serving the basement through the 3rd floor. These stairs are labeled Stair #4 and #5.

Stair #3 serves the 1st floor behind the stage to the 3rd floor Mechanical Equipment area. Stair #6 connects the basement and stage.

Stairs #7 & #8 appear to go below the fixed floor area in the Auditorium.




Photo of floor above & concealing Stair #7 & #8

Stair #9 connects the Concourse level to the Projection Room. Stairs #10 and #11 provide access to the cat walks.

vii. Mechanical Equipment Rooms

There is a mix of exterior and enclosed Mechanical Equipment Rooms located on the third floor.

The Project Booth Area is accessed from the Concourse level using Stair #9. The layout of spaces appears to match the original drawings.

viii. Interior of Committee Building wing

The interior of the Committee Building main room appears to have been altered since it was originally constructed. The flooring appears to be replaced at a later date. The ceiling in the documents show a 1' x 1' ceiling tile with linear 1' x 8' lighting fixtures. The existing ceiling is a 2 x 4 ACT ceiling with 2 x 4 recessed florescent fixtures. The original drawings show several folding doors and tracks crisscrossing the space. These appear to have been removed. The full height sliding door along the west side is still visible.

The Catering kitchen in the Committee building wing is still present. It is not possible to confirm if the layout and equipment is original. The as built drawings refer to a kitchen sheet, K 1 which was not part of the as built drawing set.

The passage and restrooms appear to be the same.

ix. Interior of Administration Building wing

The interior of the Administration Building wing appears to have been reconstructed. The flooring finish has been removed and the concrete slab exposed. The interior layout is significantly different. There are various new wood stud walls in various stages of completion. There is a lobby area that does not match the existing as-built drawings. There are partial glass walls with wooden mullions.

The 1' x 1' acoustic ceiling tiles appear to be the original, but the light fixtures have been replaced with fluorescent fixtures.

E. Conclusion and Recommendations

i. Exterior of main Auditorium building

The exposed concrete walls and the storefront system are both character defining features of the building. The team recommends cleaning and painting the existing exposed concrete to return it to the original design. It is recommended to keep the storefront but replace the clear and textured glass with laminated and tempered glass. The clear glass would be made up of two layers of 1/8" thick tempered glass laminated with a low e interlayer. The textured glass would be 1/4" thick tempered with a texture pattern resembling the original textured pattern as much as possible.



Photo of textured glazing. Replacement of one panel is apparent in photo.

The team recommends replacing the entire roof at the Auditorium. The structural roof assembly recommendation is in the structural narrative. On top of the new structural

roof would be a polyvinyl chloride (PVC) single-ply membrane over coverboard over insulation. The shape of the replacement roof is to match the original and new standing seam metal panels would replace the existing ones. A similar PVC single-ply membrane roofing system is recommended at the Fly Space roof.

The team recommends removing the existing metal panels and recessed square light fixtures on the canopy and returning the canopy soffit to cement plaster with recessed round fixtures to match the original design. Given the age of the existing roofing system, the recommendation is to replace it with a single ply PVC membrane similar to the main Auditorium domed roofing system.

The aluminum louvers and aluminum windows along the south elevation are both secondary character-defining elements and the recommendation is to keep them. The team recommends replacing the existing glass with tempered and laminated glass.

Since the two exterior structures along the south elevation are not in the original drawings, the team recommends removing them.

Along the east elevation, the existing loading dock bumpers and guard rails appear to be in poor condition. If the loading dock is to remain a loading dock, the recommendation would be to replace the guard rails and wood bumpers.

At all existing doors, the recommendation is to replace with new code-compliant doors and hardware. New doors can have access control.

ii. Exterior of East Wing (Committee) building

If the decision is to keep the wing, maintain the existing storefront and replace the glass with two 1/8" thick layers of tempered δ laminated glass with a low-e interlayer. The doors would be replaced with code compliant doors and hardware. Their profile and frame finish should match the existing. The glazing in the door should be tempered δ laminated glass.



Photo of storefront in East Wing (Committee) building

Given the age of the roofing system, the team recommends replacing the building's existing roofing system. The recommendation is a single ply PVC membrane similar to the main Auditorium domed roofing system.

The recessed light fixtures in the cement plaster soffit can be replaced with new energy efficient light fixtures that resemble the original.

Existing exterior doors in the concrete should be replaced with code compliant doors and hardware. This would provide the opportunity to connect the replacement door for an access control system.

iii. Exterior of the West Wing (Administration) building

The team recommends replacing the existing roofing system given its age. The recommendation is a single ply PVC membrane similar to the main Auditorium domed roofing system.

If the decision is to keep the wing, maintain the existing storefront and replace the glass with two 1/8" thick layers of tempered & laminated glass with a low e interlayer. If future program permits, the original full height storefront windows along the north elevation can be partially or fully brought back.

iv. Interior Auditorium

Although the fixed seating appears to be in good condition a cost has been identified to provide more comfortable seating. Refer to the theatre's narrative for additional information.

The existing solid metal panels are in good condition but reflect sound in a way that is not conducive to some potential uses of the facility. The perforated metal panels provide some acoustic benefits. Refer to the Acoustic narrative for additional information.

Refer to the structural narrative for recommendations on the existing concrete on the tilted floor.

The existing counterweight rigging system appears to be original and outdated. Refer to the theatre narrative for additional information and recommendations at the grid iron, cat walks and stage.

Refer to acoustic narrative for recommendations on replacing the existing plaster ceiling in the main auditorium and the theatre narrative for recommendations above the gym floor.

v. Lobby

The existing terrazzo at the main entrances is not the original flooring. It shows signs of water damage. The recommendation is to restore the flooring. As the terrazzo is part of public art piece, the City of Santa Monica may have existing drawings as reference.

The two stairs, Stairs #1 and Stairs #2, are character defining elements in the building. The recommendation is to provide additive elements to bring them up to current code without changing their aesthetics.

The team recommends replacing the existing acoustic tile on plaster ceiling as some pieces are missing or have fallen off.

The team recommends replacing the plumbing fixtures and partitions in the Men's and Women's restrooms off the Lobby. The fixtures would be code compliant and include the required number of accessible fixtures/stalls. The team also recommends adding two Single User restrooms.

The team recommends bringing circular concessions back similar to the original drawings but with modern amenities like Point Of Sale (POS) systems and audio visual capabilities.

The team also recommends bringing back the smaller Ticket Sales with access from the exterior and interior. The exterior elevation would match the original drawings. The interior access could provide light refreshments.

vi. Dressing Rooms

The recommendation is to replace the existing fixtures with code compliant fixtures. The existing showers have curbs. An accessible shower would need to be provided with a zero threshold. The finishes and casework appear to be the original as per the as built drawings. Some areas have missing ceiling tiles or openings exposing the floor above. If the dressing rooms are to remain, the recommendation would be to build new code compliant and accessible dressing rooms.

vii. Basement

The team recommends replacing the existing plumbing fixtures and stalls in the basement restrooms. The fixtures would be code compliant and include the required number of accessible fixtures/stalls.

viii. Stairs

In general, the stairs are not code complaint per today's building codes. They lack landings, nosing strips, and handrail extensions. The stair widths may be too narrow based on the number of occupants it serves.

The recommendation is to provide new compliant handrails and nosing on existing stairs.



2.2 HISTORICAL AND ADAPTIVE REUSE NARRATIVE

The purpose of this report is to provide background information to support the development of a feasibility study for the potential adaptive reuse of the Santa Monica Civic Auditorium by the Santa Monica Malibu Unified School District (SMMUSD). The Civic Auditorium is part of the Santa Monica Civic Center and is located in the Santa Monica Civic Center Specific Plan (adopted in 2005) area at 1855 Main Street in the City of Santa Monica, California.

The Santa Monica Civic Auditorium was completed in 1958. It was designed by the master architectural firm Welton Becket and Associates in the Mid century Modern architectural style. The Santa Monica Civic Auditorium was designated as a City of Santa Monica Landmark on April 9, 2002 (Landmark No. 43). It is a significant work of Mid century Modern institutional architecture designed by a master architect who is responsible for some of the most celebrated buildings in the Los Angeles region. In addition to its architectural significance, the Civic Auditorium is an important civic monument in Santa Monica, marking the culmination of plans for the Civic Center and instantly becoming a beloved and vibrant community gathering place, hosting everything from sporting events to symphony concerts, to the Academy Awards. The Landmark designation generally identifies character-defining features on the exterior, specific interior features, as well as select elements of the surrounding landscape. The Landmark designation does not identify a period of significance; however, the character defining features included in the designation are associated with original exterior and interior design elements.

This report includes an overview of the development history of the Civic Auditorium; an identification of alterations; documentation of the character defining features, including photographs and condition notes; and general guidance for meeting relevant preservation standards and guidelines in order to accommodate a new use while maintaining those historic features that contribute to the building's significance. HRG completed a field inspection on March 8, 2023, to document the building's physical features; conducted research and consulted primary and secondary sources to prepare the development history; and reviewed historic photographs to confirm existing features and alterations over time.

- A. Contemporary newspaper articles
- B. Historic photographs
- C. Primary and secondary sources related to the history and development of the Santa Monica Civic Auditorium
- D. Original architectural plans by architectural firm Welton Becket and Associates for the Santa Monica Civic Auditorium (1956)
- E. Landmark designation report (2001, included in Appendix A of this report for reference)

2. Historic Overview and Development History

A. Santa Monica Civic Center: The Santa Monica Civic Auditorium was constructed in 1958 as part of the post World War II expansion of the Civic Center. Originally established in the 1930s, the Civic Center was built on land purchased from the Southern Pacific Railway Company. The only building in the Civic Center completed prior to the United States' entrance into World War II is the Santa Monica City Hall. Like other communities throughout the United States, Santa Monica experienced tremendous population growth after World War II due to the influx of GIs. In turn, Santa Monica's civic and educational

institutions expanded to meet the growing needs of the community. This included a renewed focus on completion of the Civic Center in the 1950s.

- i. Santa Monica City Hall, 1939 (1658 Main Street, Landmark No. 12): Santa Monica's first City Hall was a Mission Revival style building constructed in 1903 at the corner of 4th Street and Santa Monica Boulevard. In 1939, it was replaced by the current Public Works Administration (PWA) Moderne style building designed by architects Donald B. Parkinson and Joseph M. Estep. In 1958, a three story concrete and brick masonry addition (J. Harold Melstrom, architect) was made to City Hall containing space for the police department, as well as offices for the traffic engineer and recreation department.
- ii. County Court House, 1951 (1725 Main Street): As a result of postwar population growth on the west side of Los Angeles County, the Los Angeles County Court House (Frederick Barienbrock and Robert Klliegman, architects) was constructed in 1951. The Modern concrete and glass building expanded the footprint of the Civic Center towards the south.
- iii. Santa Monica Civic Auditorium, 1958 (1855 Main Street, Landmark No. 43): Santa Monica's Civic Center was expanded to Pico Boulevard with the construction of the Santa Monica Civic Auditorium in 1958, which is located south of the County Court House. Design for the Mid century Modern building began in 1956 by the master architectural firm Welton Becket and Associates. Murray Erick Associates was the structural engineer, and Vern O. Knudsen designed the acoustics. After construction was complete, the Santa Monica Civic Auditorium supplanted the nearby Ocean Park Municipal Auditorium, located at the waterfront and completed in 1921 (demolished c. 1970s), and Barnum Hall, originally known simply as "The Auditorium" and built in 1938 under the auspices of the Works Progress Administration (located on the Santa Monica High School campus) to become the City's principal municipal auditorium.
- B. Welton Becket and Associates: Welton David Becket (1902 1969; shown in Figure 1) was born on September 8, 1902 in Washington State. He studied architecture at the University of Washington from 1923 1927 and at the Ecole des Beaux Arts in 1928. After completion of his studies, Becket returned to Seattle and started an architectural firm with his former classmate Walter Wurdeman. In 1933, Wurdeman and Becket moved to Los Angeles and formed a partnership with Charles Plummer under the firm name Becket, Wurdeman and Plummer. In 1939, Charles Plummer died and Wurdeman and Becket continued the firm for another decade. Following Wurdeman's death in 1949, Becket continued the Wurdeman and Becket firm until 1950, when he bought out Wurdeman's heirs and formed a solo practice under the name "Welton Becket and Associates."

During the building boom following World War II, Wurdeman and Becket shifted their practice to focus primarily on large commercial projects. The firm was highly innovative in the fields of design, planning, and construction, introducing novel lightweight construction and modular office design methods. The firm's "total design" philosophy, in which the architects oversaw all phases of a project, from planning to construction, and all aspects of the design, including interior features, signage, and landscaping, was particularly influential.

Over the course of Becket's career, he designed many corporate and civic landmarks in Southern California and around the world, and in particular made a significant impact on the architectural landscape of postwar Los Angeles. Notable commissions include numerous sports and entertainment venues: the Pan Pacific Auditorium (1935); Capitol Records (1956) and the Cinerama Dome (1963) in Hollywood; the Music Center's Dorothy Chandler Pavilion (1964) and Mark Taper Forum (1967) in downtown Los Angeles; and the Los Angeles Sports Arena (1959). Welton Becket died at the age of 66, on January 16, 1969.

C. Santa Monica Civic Auditorium

- i. Description and Alterations: The Santa Monica Civic Auditorium is located at the south end of the Civic Center Specific Plan area, about one mile southeast of downtown Santa Monica (see Map 1). The building occupies an irregularly shaped lot at the northeast corner of Main Street and Pico Boulevard, where the former obliquely intersects with the latter.
- ii. The Santa Monica Civic Auditorium is oriented along a north south axis, parallel to the Pacific Ocean to the west. It is of reinforced concrete construction, and is composed of the following elements: a curved metal canopy attached to the primary (north) façade, supported by six slender concrete pylons; a curved first floor lobby and third floor concourse, both fronted by a glass curtain wall screened by concrete brise soleil; a three story auditorium with sloped seating, a large floor, an orchestra pit, and a stage; a raised rectangular fly tower over the stage; a one story rectangular east wing containing committee rooms; and a smaller, one story rectangular administrative west wing facing Main Street.
- iii. The Santa Monica Civic Auditorium is largely intact, despite some exterior and interior alterations over time. Two, one story additions were constructed at the rear of the building, one at the southwest corner (c. 1967 1971), and one at the southeast corner (c. 1993 1994). At an unknown date, a one story projecting box office addition was constructed on the primary façade, between the two main entrances. A reflecting pool surrounding the base of the pylons was removed by the early 1960s. Interior alterations include replacement of an original enclosed ticket sales area with a larger one in the first floor lobby; removal of two circular concession stands in the first floor lobby; removal of carpet in the first floor lobby; replacement of original terrazzo floors in the first floor lobby with new terrazzo; replacement of asphalt tile floors in the concourse with terrazzo; and extensive remodel of the west administration wing. To illustrate the site's development and the extent of changes over time, a comparison of historic and current exterior and interior photographs is provided in Appendix B and historic aerial photographs are included in Appendix C.
- iv. Welton Becket and Associates prepared architectural drawings for the Santa Monica Civic Auditorium in 1956, and construction began the following year (see Figure 2 for a rendering; and Figures 3 4 for photographs of the auditorium under construction). The total project cost was \$2.9 million. The Civic Auditorium was officially inaugurated in June 1958 (see Figures 5 10 for photographs of the exterior and interior upon completion).
- v. At the time of its completion, the Santa Monica Civic Auditorium was lauded for its design, engineering, and acoustics. In 1960, Welton Becket and Associates received a prestigious American Institute of Architects (AIA) Merit Award for the design.

Innovations in engineering include the building's two hydraulic systems, both housed in the basement, that can tilt the main floor of the auditorium, transforming it from a flat surface for conventions to a raked floor for theatrical productions (Figures 11 and 12 show the main floor in "flat" and "tilted" position); and raise or lower the orchestra pit floor to create a sunken pit or flat surface level with the main floor. At the time of its construction, the tilt floor was the third and largest of its type in the United States (See Figure 13 for a photograph of the hydraulic mechanism). Vern Oliver Knudsen (1893-1974), a University of California, Los Angeles physics professor and renowned acoustics expert, designed the building acoustics. Though Knudsen's original specifications were not found, it is likely that he oversaw the design of the metal acoustical panels flanking the auditorium and soundproof doors between the auditorium and east wing (committee rooms).

- vi. The Civic Auditorium was the primary indoor gathering space in the City, and a major cultural and social hub in Southern California until its closure in 2013. Notable entertainers, including Duke Ellington, Ella Fitzgerald, Frank Sinatra, Bob Dylan, Mick Jagger, Elton John, and David Bowie, performed there from the 1960s to 1980s. From 1961 to 1968, the Civic Auditorium hosted the Academy Awards (see Figures 14 and 15 for photographs of the 39th and 40th Academy Awards). Other events included symphonies, live theater and film screenings, various sports events, and conventions and trade shows.
- vii. At its inauguration in the summer of 1958, the Los Angeles Times described the Santa Monica Civic Auditorium: "Striking, severe architecture of newly completed Santa Monica Civic Auditorium is functional, yet handsome...the building is considered the last word in modern hall construction." Vacant since 2013, the building remains a significant example of Mid century Modern institutional architecture in the Santa Monica Civic Center, and is remembered as a major cultural center that hosted some of the nation's most celebrated events and entertainers.

3. Summary of Significance

A. City of Santa Monica Landmark Criteria: In 1976, the City of Santa Monica adopted the Landmarks and Historic District Ordinance. The ordinance includes criteria and procedures for designating City of Santa Monica Landmarks, Structures of Merit, and Historic Districts. Landmarks may include structures, natural features, or any type of improvement to a property that is found to have particular architectural or historical significance to the City. Landmarks are considered to have the highest level of individual historical or architectural significance locally. Structures of Merit are historic resources with a more limited degree of individual significance. In 1992, the City became a Certified Local Government (CLG) and has continued its involvement in the state's program under the Office of Historic Preservation.

The Landmarks Commission may approve the landmark designation of a structure, improvement, natural feature or an object if it finds that it meets one or more of the following criteria, outlined in Section 9.56.100(A):

- i. It exemplifies, symbolizes, or manifests elements of the cultural, social, economic, political or architectural history of the City.
- ii. It has aesthetic or artistic interest or value, or other noteworthy interest or value.

- It is identified with historic personages or with important events in local, state or national history.
- iv. It embodies distinguishing architectural characteristics valuable to a study of a period, style, method of construction, or the use of indigenous materials or craftsmanship, or is a unique or rare example of an architectural design, detail or historical type valuable to such a study.
- v. It is a significant or a representative example of the work or product of a notable builder, designer, or architect.
- vi. It has a unique location, a singular physical characteristic, or is an established and familiar visual feature of a neighborhood, community or the city.
- B. Santa Monica Civic Auditorium Landmark Designation: The Santa Monica Civic Auditorium was designated as a City of Santa Monica Landmark on April 9, 2002, under Criteria 1 6 (Landmark No. 43). The Landmark designation report is included in Appendix A of this report for reference. In summary, the Civic Auditorium was identified as significant for its association with the development of the Santa Monica Civic Center; as an excellent example of Mid century Modern architecture by master architectural firm Welton Becket and Associates; and as an important local venue where notable entertainers performed and important events occurred, including the Academy Awards. The Landmark designation report does not identify a period of significance; however, the character defining features outlined in the designation all correspond to original features designed by Welton Becket and Associates or other members of the engineering and acoustical teams, that were present when construction was completed in 1958.

The following character defining features are identified in the Landmark designation for the Santa Monica Civic Auditorium: the overall exteriors of the building, the pygmy palm trees at the northwest corner of the site, and specific interior features (summarized below):

- i. Overall height and configuration of first floor lobby and third floor concourse
- ii. First floor lobby features: two staircases, columns, auditorium entry doors, and wood paneling along south wall
- iii. Overall configuration of auditorium
- iv. Tilt floor in auditorium and associated hydraulic mechanism in basement.
- v. Metal acoustical panels with affixed light fixtures
- vi. Two soundproof doors between auditorium and east wing (committee rooms)
- 4. Character Defining Features Analysis
 - Every historic building is unique, with its own identity and its own distinctive character. Character defining features are those visual aspects and physical features or elements, constructed during the period of significance, that give the building its historic character and contribute to its historic integrity. Character defining features should be considered in the planning and design of a project and preserved to the maximum extent possible. Character-defining features can identify the building as an example of a specific building type, usually related to the building's function; they can exemplify the use of specific materials or methods of construction or embody an historical period or architectural style; and they can convey the sense of time and place in buildings associated with significant events or people.

A building's character defining features can include but are not limited to its setting and site; shape and massing; roof and related features, such as chimneys or skylights; projections such as balconies or porches; recesses or voids, such as galleries or arcades; windows and doors and their openings, pattern, and proportions; materials, with their distinguishing textures, finishes, colors and craftsmanship; and interior features, materials, finishes, spaces, and spatial relationships. In general, retaining character defining features retains the integrity of a historic property and maintains its eligibility as a historic resource. Removal or alteration of one feature does not necessarily change the eligibility of a historic resource: significant impacts result from major change, or many incremental changes over time.

Character defining features associated with the Santa Monica Civic Auditorium as identified in the Landmark designation are identified in Table 1. The Landmark designation does not identify a period of significance; however, all the identified character defining features are associated with the building's original (1958) exterior and interior design. Because the Landmark designation does not identify specific exterior features as character defining (it simply identifies the "overall exteriors of the building" as part of the designation), this report identifies those exterior features that contribute to the building's significance in order to inform the feasibility study. Character defining features are identified as either "primary" or "secondary," based on the degree to which they contribute to the building's significance, as well as their overall condition.

As noted above, the building has been vacant since 2013. Exterior openings are presently boarded, and the building may not have been appropriately "mothballed," per guidance from the National Park Service, to prevent deterioration. Therefore, the extent of deterioration of exterior and interior features will require in depth analysis from the appropriate specialists on the project team for the feasibility study and could potentially add cost to the restoration. Any references in Table 1 to the building's current conditions are based on preliminary visual observations, and do not constitute a comprehensive conditions assessment.

5. Guidance for the Treatment of Historic Properties

A. Secretary of the Interior's Standards for the Treatment of Historic Properties: The Secretary of the Interior's Standards for the Treatment of Historic Properties (the "Standards") provide guidance for reviewing proposed projects that may affect historic resources. The Standards and associated guidelines address four distinct historic "treatments," including: (1) preservation; (2) rehabilitation; (3) restoration; and (4) reconstruction. The specific Standards and guidelines associated with each of these possible treatments are provided on the National Park Service's website regarding the treatment of historic resources. The Standards for Rehabilitation (36 CFR 67) address the most prevalent treatment. "Rehabilitation" is defined as "the process of returning a property to a state of utility, through repair or alteration, which makes possible an efficient contemporary use while preserving those portions and features of the property which are significant to its historic, architectural, and cultural values." As stated in the definition, the treatment "rehabilitation" assumes that at least some repair or alteration of the historic building will be needed in order to provide for an efficient contemporary use; however, these repairs and alterations must not damage or destroy materials, features or finishes that are important in defining the building's historic character.

The intent of the Standards is to assist the long term preservation of a property's significance through the preservation, rehabilitation, and maintenance of historic materials and features. The Standards pertain to historic buildings of all materials, construction types, sizes, and occupancy and encompass the exterior and interior of the buildings. The Standards also encompass related landscape features and the building's site and environment, as well as attached, adjacent, or related new construction. Standards 9 and 10 apply specifically to new additions, exterior alterations, and related new construction including new construction in historic districts.

B. The Guidelines for Rehabilitating Historic Buildings: The Guidelines for Rehabilitating Historic Buildings were initially developed in 1977 to help property owners, developers, and Federal Managers apply the Secretary of the Interior's Standards for Rehabilitation during the project planning stage by providing general design and technical recommendations. The Guidelines pertain to historic buildings of all sizes, materials, occupancy, and construction types; and apply to interior and exterior work as well as new exterior additions.

The Standards are intended as general guidance for work on any historic building; the Guidelines for Rehabilitating Historic Buildings expand the discussion to the treatment of historic districts and provide more specific direction regarding infill construction. The key recommendations related to new construction in relation to an existing historic resource include:

- i. Limiting the size and scale of new construction in relationship to the historic building.
- ii. Designing new additions in a manner that makes clear what is historic and what is new.
- iii. Design of the new work may be contemporary or may reference design motifs from adjacent historic buildings.
- iv. In either case, the new construction should always be clearly differentiated from the historic buildings and be compatible in terms of mass, materials, relationship of solids to voids, and color.
- v. In addition, the Guidelines provide appropriate approaches to designing additions to historic buildings:
- vi. A modern addition should be readily distinguishable from the older work; however, the new work should be harmonious with the old in scale, proportion, materials, and color.
- vii. The new addition should be designed in a manner that provides some differentiation in material, color, and detailing so that the new work does not appear to be part of the historic building. The character of the historic resource should be identifiable after the addition is constructed.
- viii. In either case, the new construction should always be clearly differentiated from the historic buildings and be compatible in terms of mass, materials, relationship of solids to voids, and color.
- C. Preservation Briefs: In addition to the Standards and Guidelines, the National Park Service provides Preservation Briefs that recommend methods and approaches for preserving, rehabilitating, and restoring historic buildings and districts in a manner consistent with their historic character, and help owners recognize and resolve common problems prior to work. Preservation Brief 14, New Exterior Additions to Historic Buildings: Preservation Concerns, provides guidance on new additions to historic buildings and new construction in

historic districts. The basic design guidance recommended by Preservation Brief 14 is summarized as follows:

i. There is no formula or prescription for designing a new addition [or new construction] that meets the Standards. A new addition to a historic building [or new construction in a historic district] that meets the Standards can be any architectural style – traditional, contemporary or a simplified version of the historic building. However, there must be a balance between differentiation and compatibility in order to maintain the historic character and the identity of the building being enlarged [and the district in which new construction occurs]. New additions [and new construction] that too closely resemble the historic building[s] or are in extreme contrast to it fall short of this balance. Inherent in all of the guidance is the concept that an addition needs to be subordinate to the historic building.

6. Preliminary Recommendations

The Santa Monica Civic Auditorium was designed in the Mid century Modern architectural style by noted architectural firm Welton Becket and Associates. It was completed in 1958 as the culmination of the Santa Monica Civic Center. The Santa Monica Civic Auditorium was designated as a City of Santa Monica Landmark in 2002 (Landmark No. 43). It retains the character defining features identified in the Landmark designation and continues to convey its architectural and cultural significance.

The Civic Auditorium closed in 2013 and has been vacant for nearly a decade, posing a significant threat to a historical resource. The SMMUSD proposes to maintain the Santa Monica Civic Auditorium as an important local community space possessing social and cultural significance while adaptively reusing the building to accommodate new athletics related functions.

The Secretary of the Interior's Standards for Rehabilitation and Guidelines for Rehabilitating Historic Buildings anticipate that changes to spaces and features of historic buildings are often necessary to accommodate new uses and ensure the long term viability of historical resources. The appropriate approach to rehabilitating a historic building is to review proposed changes holistically; it may be acceptable to change individual features or spaces as long as the building overall continues to convey its significance. The recommendations herein are provided as part of a feasibility study for the potential adaptive reuse of the building; specific details would be reviewed as part of the design development of the project to ensure that impacts to character defining features are minimized to the extent possible, and that the building would continue to convey its historic significance.

The SMMUSD is studying two potential adaptive reuse schemes for the Santa Monica Civic Auditorium (Scheme 1 and Scheme 2), as described below. The two schemes vary in terms of the type of alterations required to accommodate the new programmatic requirements: Scheme 1 would require more interior alteration, while Scheme 2 anticipates exterior additions. However, both schemes would retain the majority of the character defining features that convey the significance of the Civic Auditorium, and the improvements contemplated under either scheme would ensure the long term viability of the historical resource.

A. Scheme 1: Scheme 1 would primarily accommodate new uses within the existing envelope of the Civic Auditorium, including adding two floors to the interior of the existing fly tower

for new sports uses. This alteration would maintain the appearance of this space from the exterior, while capturing otherwise unused interior space for the new use. In addition, a new detached building would be constructed to house athletics related functions. The new one story building would be located at the rear (southeast corner) of the property and would be clearly subordinate to the existing auditorium. Therefore, it would not result in a significant visual intrusion that would impact the ability of the Civic auditorium to convey its historic significance. While Scheme 1 would require some interior alterations to character defining features and spaces, the exterior of the historic building would remain largely intact. This solution creatively adapts interior space and maximizes new uses within the existing envelope with minimal impacts to the property's overall exterior visual character.

- B. Scheme 2: Scheme 2 would accommodate significant new programmatic requirements within new additions at the east and west wings and rear of the historic building, in addition to required alterations to the existing interior spaces. In lieu of building two new floors in the fly tower, this scheme would result in more new construction on the property, and a larger exterior addition to the historic building. However, the new construction would be limited to secondary façades; would be differentiated from the historic building in terms of materials and design; and would be compatible with and subordinate to the historic building in terms of size, scale, proportion, and massing. Finally, the proposed addition to the east wing would be "notched" at the northeast corner to align with the original front setback of that wing. Therefore, although Scheme 2 would include the construction of a significant new addition to the property, it represents an acceptable approach to accommodating the change in use.
- C. Both schemes incorporate certain interior and exterior alterations that are necessary to accommodate the Civic Auditorium's proposed new use and meet life safety and seismic upgrades required for school buildings. In order to make the necessary upgrades while maintaining the historic integrity of the Civic Auditorium, the design team should consider the general comments outlined below: Character-defining features should be retained to the extent feasible to achieve conformance with the Secretary of the Interior's Standards and protect the building's Landmark status.
- D. In general, some alteration or removal of character defining features may be acceptable to accommodate a new use, as long as the project generally complies with the intent of the Standards, and the historic building continues to convey its significance after project implementation.
- E. Where appropriate, the California Historical Building Code (CHBC) should be applied for alternative building regulations that can facilitate the building's rehabilitation and adaptive reuse to preserve its historic features and materials and provide reasonable safety and accessibility.
- F. There is more flexibility for making changes to secondary features or spaces. On the exterior, the significant architectural features reflecting Becket's design, including the pylons, brise soleil, and curtain wall are on the primary façade; other facades are more utilitarian in nature.
- G. Reuse of the interior volume of the fly tower is an acceptable alteration. The overall exterior volume of the fly tower should be retained so that there is a clear visual representation of the building's historic use as an entertainment venue.
- H. The hydraulic floor was a significant technological achievement at the time the building was completed, and it has been identified as a primary character defining feature of the

building. However, if retention of the functionality of the moveable floor is not possible to accommodate a new use, or to meet applicable safety requirements and ensure the long-term viability of the building, the mechanics can be abandoned in place, and the floor can be fixed in a permanent flat state. Ideally, the hydraulic equipment would be retained in place, if feasible.

- I. Necessary upgrades to address accessibility are acceptable. These upgrades should be designed to minimize impacts to historic features and spaces to the extent possible.
- J. New additions to the site and/or the existing building are acceptable to maximize the utility of the site overall and achieve the programmatic requirements. Any new addition to the site should be compatible with the historic building in terms of size, scale, massing, and materials. Any addition to the building itself should be designed to be minimally visible from the primary (north) façade and readily distinguishable from, but compatible with, the historic building.
- K. The existing non contributing rear additions can be removed.

Preliminary Recommendations:

Below is preliminary guidance on the treatment of specific exterior and interior features of the Santa Monica Civic Auditorium based on solutions proposed as part of the feasibility study. As noted above, all aspects of the project would be further reviewed as part of design development of the project.

Exterior:

- A. Canopy soffit: The project proposes to restore the original plaster finish and recessed can light fixtures of the canopy soffit. At an unknown date, a metal panel soffit with square light fixtures was installed. Because the soffit is already altered, restoration is not required. However, because the canopy is a highly visible feature on the primary façade, the design team is proposing to restore it to its original appearance. This is beneficial to the project overall and will enhance the historic integrity of the building as originally designed by Becket. There is sufficient documentation to reproduce these missing features and finish.
- B. Reflecting pool: Originally, there was an irregularly shaped reflecting pool below the canopy, encompassing the bases of the reinforced concrete pylons; the pool was enclosed on the south side by a metal pipe railing. The pool and railing were removed at an unknown date. Based on available historic photographs, this feature was removed by the early 1960s. As such, its restoration is not required as part of this project. However, if the design team proposes an interpretation of a water feature in this location, that would be an acceptable alteration that recalls the historic feature.
- C. Concrete pavers: The original landscape plan for the property notes cast concrete pavers of various sizes in the planter at the east side of the primary façade. It is unknown if these pavers were installed, as they are out of view in available historic photographs. At present, there are no concrete pavers in this location. As such, replication of these non extant features is optional, but not required.
- D. East wing (committee rooms) storefronts: The east wing features original aluminum frame storefronts fitted with clear glass. Consistent with the treatment of the curtain wall as discussed further on in this report (see section D in Seismic Upgrades section), the project should retain and repair the existing frame to the furthest extent possible. However, since

- the east wing is a secondary feature of the building, it would be possible to install glazing of a different design to accommodate a change in use and provide needed privacy. Any combination of clear, translucent, or opaque glass panels, tempered or otherwise, would be possible, as long as the thickness of the existing is retained. If different degrees of transparency are desired on the upper and lower portions of the storefronts, it is recommended that internal mullions, removable in the future, be installed to create separations.
- E. Louvers: The rear façade features original horizontal aluminum louvers at the third floor; these conceal original paired aluminum frame multi light hopper windows. If the louvers are found to be in serviceable condition, they should be retained and rehabilitated. To facilitate cleaning and repainting of the windows, it would be acceptable to remove and reinstall the louvers. It is preferable that the windows be retained and repaired; however, if they are found to be in poor condition, replacement is possible since they are on a secondary façade and largely concealed from view. Replacement windows should match the originals or, if a different configuration is required by the change in use, compatible new units.

Interior:

- A. Lobby and concourse floors: The lobby originally had a carpeted floor with small terrazzo sections at the stair landings. These finishes, and the original asphalt tile flooring in the concourse, were replaced in 1997 by the present terrazzo flooring which was designed by contemporary artist Renée Petropoulos and added as part of a City sponsored public art program. As such, the City of Santa Monica should be consulted regarding any potential considerations related to the retention of, or rights to, the terrazzo floors. Restoration of the original floor is not required, and if the terrazzo is in good condition, it can be retained as part of the project. If the project proposes to replace the floor, and that is permissible according to the agreement with the artist, any new floor finish would need to be compatible with the overall Mid century Modern style of the building.
- B. Lobby ceiling: The acoustic tile lobby ceiling with recessed can light fixtures appears to be original based on the original architectural drawings and available historic photographs. If future investigations determine that the ceiling is too deteriorated to repair, or contains hazardous materials that must be abated, replacement with materials that are similar in appearance to the existing is recommended.
- C. Lobby lighting: The lobby originally featured suspended pendent light fixtures; these were removed at an unknown date, with some stored onsite. If new lobby lighting is required, it is recommended that original pendant light fixtures be reinstalled and/or replicated, or that new pendant light fixtures resembling the originals be installed. If this were found to be infeasible, new compatible light fixtures of a different design would be acceptable.
- D. Lobby staircases: The lobby features two original and identical staircases (east and west), each with closed concrete stringers (painted) and concrete risers and treads (terrazzo finish); two landings; metal rails and newels (painted); and wood handrails and balusters (unpainted). Alterations to the staircases to meet current code requirements would be acceptable. The preferred approach would be to retain the existing railings and modify them as needed. For example, a new handrail could be added above the existing; or new horizontal or vertical elements could be added to close spaces that exceed code allowance.

- Any new element should be simple in appearance and compatible with the overall design of the staircases.
- E. Lobby restroom tile: The restrooms are not considered character defining spaces. Accordingly, replacement of existing fixtures, fittings, and finishes is acceptable.
- F. Auditorium tilt floor: The steel frame and concrete finish tilt floor, operated by a hydraulic mechanism in the basement, is an original character-defining feature of the auditorium. In order to accommodate the new use and meet safety requirements, it is necessary to fix the tilt floor in the "flat" position, replace the existing concrete floor and subfloor framing, and install a new finish material to accommodate the new athletic function of the building. The potential to retain the original concrete floor as a subfloor beneath the new finished floor was evaluated; however, this would result in the tilt floor being out-of plane with adjacent floors, creating a tripping hazard. The proposed solution would accommodate the new hardwood flooring system so that it is level with the adjacent floors along the perimeter, orchestra lift, and stage. The hydraulic mechanism would be retained in place, and the floor could be returned to operability in the future. Therefore, these alterations to accommodate the new use would be acceptable.
- G. Auditorium ceiling: The configuration of the auditorium ceiling is an original feature; however, it does not meet the acoustical requirements to accommodate the new use. After studying alternatives, and based on the configuration of the auditorium, the proposed treatment is to remove the existing ceiling above the tilt floor and replace the existing ceiling above the sloped seating area with a new gypsum board ceiling that meets acoustical requirements and allows for flexibility to incorporate openings to meet programmatic needs This will also maintain the overall form of the present ceiling. This is an acceptable alteration in order to meet the necessary programmatic requirements of the new use.
- H. Auditorium acoustical panels and sconces: There are metal acoustical panels with paired metal sconces on the upper portions of the east and west walls of the auditorium. However, these panels do not meet current acoustical requirements. After studying alternatives, the proposed treatment is to either install a curtain over the existing panels; or to replace the panels with new perforated metal panels that are similar to the existing in appearance but have improved acoustical qualities. The existing sconces would be retained and reinstalled. Although this proposed solution would result in the replacement of a character defining feature, it is a necessary upgrade to accommodate the new use. The auditorium overall would continue to convey its significance, and the panels would be designed to be compatible new replacements that meet the required performance specifications.
- I. Auditorium seating: Auditorium seating is not original and could therefore be replaced as needed. To improve overall acoustics, compatible new upholstered seating would be acceptable.
- J. Auditorium/east wing soundproof doors: Between the auditorium and east wing (committee rooms), there are two original and identical soundproof insulated wood sliding doors. To improve acoustics in the auditorium, it would be acceptable to cover the doors with acoustical panels (preferable option); or to retract the doors and install new doors providing improved acoustic performance (secondary option). If neither option is feasible, replacement of the existing doors with new doors that retain the overall appearance of the existing while providing improved acoustics would be acceptable.

New elevator: The Civic Auditorium does not currently have an elevator; however, an elevator is required to connect the lobby and concourse to comply with accessibility requirements. Based on preliminary studies, two potential locations for the new elevator have been identified: 1) in the northwest corner of the lobby, adjacent to the existing stair; or 2) in the center of the lobby in place of the non-original enclosed ticket booth, abutting the primary façade. Further analysis is required, as both options could potentially result in impacts due to visibility through the curtain wall, and/or visibility of the elevator override through the roof. Seismic Upgrades:

Based on information provided by the structural engineer as part of the feasibility study, seismic upgrades would be required to meet Division of the State Architect (DSA) requirements and make the building safe and viable for a new use. Seismic upgrades may include unavoidable and potentially substantial alterations to significant character defining features and spaces, including the pylons, brise soleil, curtain wall, and lobby. Although the required alterations may not fully comply with the Standards, these improvements would retain existing historic fabric, would maintain the overall exterior visual appearance of the building, and would not alter the Civic Auditorium such that it could no longer convey its historic significance. Once specifications are available for required seismic upgrades, review will be required to ensure that alterations to character defining features are minimized.

- A. Pylons: The original concrete pylons, situated on the primary façade, require reinforcement due to their tall and slender design and susceptibility to lateral movement during seismic events. After studying alternatives, the proposed treatment is to install a fiber reinforced polymer (FRP) wrap around the pylons. The new material would alter the original profile of the pylons by less than an inch. Therefore, their general appearance would remain largely unchanged as viewed from the public right of way. In addition, this approach would maintain the original historic fabric, which is preferred in lieu of wholesale replacement of the pylons or a more significant visual intervention. Review of final specifications, including the finish material and appearance, will be required to ensure that the pylons are not altered in a manner that would substantially deviate from their original design and appearance.
- B. Brise soleil: According to the preliminary structural study, it appears that the concrete brise soleil would require the addition of bracing to appropriately secure it to the primary facade. The bracing would be installed on the inside face of the brise soleil to minimize visibility from the public right of way and maintain the original outward appearance of the primary façade as designed by Welton Becket. This approach would maintain the original historic fabric while providing the necessary structural upgrades, which is the preferred treatment.
- C. Shear walls: Based on preliminary evaluation, the structural engineer is recommending the potential addition of three concrete shear walls at the outer (northwest and northeast) corners and center of the primary façade in order to achieve the required seismic upgrades and meet DSA requirements. Due to the design and construction of the building, limited options are available for the placement of the required seismic interventions, and the addition of shear walls in this location has been identified as a potential solution. However, this would result in the introduction of solid walls in three locations in the lobby and the concourse and would partially obstruct the curtain wall in those locations. Although this alteration would be visible from the exterior, particularly when the building is lit from within, it would otherwise allow the exterior of the building to remain intact and retain the

- significant character defining features of the exterior as designed by Welton Becket. While the introduction of shear walls in these locations may not fully comply with the Standards because this change would alter the physical and visual appearance of the lobby, this seismic improvement would ensure the long term viability and usability of the historic building. However, it is recommended that alternative locations in secondary spaces or in less prominent and visible areas of the building be explored to minimize impacts to character defining features and spaces.
- D. Curtain wall: The primary façade features an original aluminum frame curtain wall (frame painted) with clear glass panels on the first floor and textured glass panels on the second and third floors. Glazing of this type was used throughout the post World War II period, and no evidence was found to suggest that it was a unique or custom designed feature of the building. Selective replacement of the textured glass panels, with close but not exact replicas, has occurred over time, resulting in an erosion of original visual uniformity. The project proposes to retain and repair the existing aluminum frame to the furthest extent possible, replacing only those sections that are deteriorated beyond repair. However, to meet DSA safety requirements, the curtain wall glazing must be replaced with shatterproof glass. The new glazing would match the original in dimension, transparency, color, and texture. This would have the additional benefit of returning the curtain wall to its original uniform visual appearance. Therefore, the installation of tempered and laminated glass within the existing curtain wall framing in order to meet safety requirements would be an acceptable change provided that the historic visual character and appearance is maintained.

7. Conclusion

The SMMUSD is proposing the adaptive reuse of the Santa Monica Civic Auditorium, which was designed by the master architectural firm Welton Becket and Associates in the Mid century Modern architectural style and completed in 1958. The Civic Auditorium was designated City of Santa Monica Landmark No. 43 in 2002 and is significant both architecturally and culturally.

Two potential adaptive reuse schemes have been developed as part of the feasibility study: Scheme 1, which would primarily accommodate new uses within the existing envelope of the historic building; and Scheme 2, which would accommodate some new uses within the existing envelope and some in new exterior additions to the property. Both schemes would require interior and exterior alterations, in particular to accommodate the necessary seismic upgrades.

Historic preservation practice allows for changes to historic buildings and considers the cumulative effect of a potential project overall on the historic features and character of significant resources. There are some components of the proposed project that do not fully comply with the Standards and would result in alterations to character defining features and spaces. However, those alterations are required in order to meet DSA structural requirements; due to the design and construction of the building there are no viable alternatives to achieve the necessary improvements without some alteration. However, the approach has been selected to maintain as much historic fabric as possible and minimize the visual impact to the extent feasible.

When viewed holistically, despite the required alterations to accommodate the new use, the majority of the exterior and interior character defining features and materials of the Civic

Auditorium would be retained, and the building would continue to convey its historic significance. Both schemes would ensure the long term viability of this important and threatened historical resource which has been vacant since 2013. The project, based on available information compiled as part of the feasibility study, would not result in a significant adverse impact to historical resources pursuant to CEQA.

8. References

- A. California Office of Historic Preservation. Built Environment Resource Directory, Los Angeles County, 2020.
- B. Calisphere, University of California. Accessed April 7, 2023, https://calisphere.org.
- C. City of Santa Monica. Landmarks and Historic District Ordinance, Section 9.36.100. March 24, 1974.
- D. City of Santa Monica. "Findings and Determination of the Landmarks Commission of the City of Santa Monica in the Matter of the Designation of a Landmark," 1855 Main Street (Civic Auditorium), November 12, 2001.
- E. Los Angeles Times. "Santa Monica Unveils \$2,900,00 Auditorium." June 15, 1958.
- F. Online Archive of California (OAC). Accessed April 4, 2023, https://oac.cdlib.org.
- G. Online Archive of California. Finding aid for the A. Quincy Jones papers, 1942 1979, accessed April 7, 2023, https://oac.cdlib.org/view?style=oac4;view=dsc;docld=tfoj49n6wn;query=Methodist;dsc.position=65001.
- H. Santa Monica Public Library
- I. National Park Service. "Secretary of the Interior's Standards for the Treatment of Historic Properties." Denver Service Center Workflows. https://www.nps.gov/dscw/cr treatment-of historic properties.htm (accessed April 2022).
- J. U.S. Department of the Interior. National Register Bulletin 16: How to Complete the National Register Registration Form. Washington, D.C.: National Park Service, 1997.
- K. U.S. Department of the Interior. Preservation Brief 43: The Preparation and Use of Historic Structures Report. Washington, D.C.: National Park Service, 2005.

MAPS



Map 1: Location Map

TABLES

Table 1 – Character Defining Features Table (SEE APPENDIX)

FIGURES



Figure 1. Welton Becket with photo of Santa Monica Civic Auditorium in background, 1960 (Los Angeles Herald Examiner Photo Collection).



Figure 2. Rendering of the Santa Monica Civic Auditorium by Welton Becket, c. 1956 (Santa Monica Public Library).



Figure 3. Primary (north) façade, view facing southwest, during construction, 1957 (Santa Monica Public Library).




Figure 4. Auditorium, view facing northwest, during construction, 1957 (Santa Monica Public Library).



Figure 5. Primary façade (left) and west (Main Street, side) façade, view facing southeast, just after completion, 1958 (Santa Monica Public Library).



Figure 6. Primary façade (right) and east (side) façade, view facing southwest, just after completion, 1958 (Santa Monica Public Library).



Figure 7. Canopy and reflecting pool, view facing southeast, 1958 (Julius Shulman, photographer Getty Research Institute)



Figure 8. Canopy and reflecting pool, view facing west, 1958 (Julius Shulman, photographer Getty Research Institute)



Figure 9. First floor lobby, circular concession stand, view facing northeast, 1958 (Santa Monica Public Library).



Figure 10. Auditorium, view facing southeast, 1958 (Santa Monica Public Library).



Figure 11. Convention in auditorium (note main floor in "flat" position), 1960 (Santa Monica Public Library).



Figure 12. Theatrical event in auditorium (note main floor in "tilted" position), c. 1958 (Julius Shulman, photographer Getty Research Institute)



Figure 13. Detail of hydraulic system in basement (to operate tilt floor), 1958 (Santa Monica Public Library)



Figure 14. 39th Annual Academy Awards, 1967 (Los Angeles Herald Examiner Photo Collection)



Figure 15. 40th Annual Academy Awards, 1968 (Security Pacific National Bank Photo Collection)

APPENDICES (see PDFs sent separately)

Appendix A – Landmark Designation Report (2001)

Appendix B – Comparison of Historic and Current Photographs

Appendix C – Historic Aerial Photographs



2.3 CIVIL NARRATIVE

Introduction

The purpose of this narrative is to provide a preliminary report of the relevant existing civil conditions with a potential to affect this project. These include a summary of existing site utilities and topographic conditions.

The civil engineering services include development of criteria for erosion control measures, site demolition, utility relocations & make ready work, precise grading and drainage, stormwater mitigation, paving (in coordination with landscape architecture), site utility design including sanitary sewer, domestic water, and fire water as well as horizontal and vertical coordination for site gas, electrical, data, and hydronic systems.

Civil related work shall be done in accordance with applicable sections of national, state and local codes, laws, ordinances, rules and regulations of authorities having jurisdiction, including:

- A. State Water Resources Control Board (SWRCB).
- B. Standard Specifications for Public Works Construction (SSPWC).
- C. Americans with Disabilities Act (ADA).
- D. American Water Works Association (AWWA).
- E. American Society of Testing and Materials (ASTM).
- F. State of California Building Code, current edition.
- G. Uniform Plumbing Code, current edition.
- H. City of Santa Monica Code and Standards (for offsite improvements)

2. Existing Conditions

A. Topography and Site Conditions

The review of the site conditions and topography is based on the topographic survey dated August 2009 by MVE and the site visit on March 8, 2023. The site is completely developed around the existing Civic Auditorium building located at the center of the site with concrete walkways, concrete plazas, and planted areas. A loading dock area with asphalt pavement is located on the east side and an asphalt parking lot is located at the southeast corner of the site. The land is an irregularly shaped parcel bounded by Main Street on the south, Pico Boulevard on the east, and driveways for the surface parking lot of the sustainable water project on the west and north sides. The highest elevation of the site is the finish floor of the Civic Auditorium building between 59.0' and 59.5'. The lowest elevation of the site is located at the southeast corner of the site, near the intersection of Main Street and Pico Boulevard, at 52.0'.

No surface drains were observed during the site and no site drainage system is shown on asbuilt drawings for the site runoff. Site runoff sheet flows directly to the adjacent streets and driveways.

Cracks, stains, and ponding issues have been observed within the existing concrete pavement on multiple areas and the asphalt pavement on the south side is in poor conditions with cracks, ponding issues, and uneven surface. Because of the difference in elevation between the building finish floor and elevation on Main Street, ADA access does not seem to be met on the south side of the building. No ADA stalls have been observed within the existing parking lot. Uneven surface conditions and non standards curb ramps have been

observed on the public sidewalk along the project site. Refer to Figure 1 below for additional information.



Figure 1. Existing Site Conditions Exhibit

A. Site utilities

The review of the existing site utilities is based on the Civic Auditorium Building as built plans, as built information from the City of Santa Monica and the site visit. The building is connected to the existing 18" City sewer main on Pico Boulevard via two sewer laterals that connects to City sewer manholes at a depth of approximately 10'. Domestic water and Fire water supplies are provided from the 12" City main on Pico Boulevard. Irrigation Water supply is connected to the 12" City main on Main Street. Roof runoff is directed to a private 8" underground storm drain line located at the southwest corner of the building that connects to the street curb via a curb drain observed on Main Street. Refer to Figure 2 below for an exhibit on existing site utilities.




Figure 2. Existing Site Utilities Exhibit



2.4 LANDSCAPE NARRATIVE

The Civic Auditorium, designed by architect Welton D. Becket, is located at an incredible crossroad between the civic center of Santa Monica, the beachfront, and the neighborhoods to the south (see Figure 1 for context). Given this location, there is a significant opportunity for the Auditorium to, once again, anchor this neighborhood as part of the connective open space of the community and the school district facilities.



Figure 1. Santa Monica Civic Auditorium and context (OLIN 2023)

The team reviewed the original landscape architectural plans and planting palette as designed by renowned landscape architect Ruth P. Shellhorn. Becket and Shellhorn collaborated on numerous projects throughout Southern California, which led her to being instrumental in defining the Southern California landscape style, using many exotics to create lush oases from the car dominated landscape, punctuated by species with color and surprise. Shellhorn was also well known for her master plan of UC Riverside as well as her work with Walt Disney on the circulation for Disneyland Park in Anaheim (The Cultural Landscape Foundation, 2001 – 2023).

In addition to Shellhorn's plans, the team also reviewed historical photos, historic preservation reports and conducted an in person site visit to review the current landscape conditions. In the following sections, the current site conditions are documented with special attention to preservation, noting what has been altered, and further areas of investigation and improvements are proposed. Lastly, a brief narrative describes how the landscape architecture could respond to the proposed schemes (Schemes 1 and 2).

2. Existing Conditions

Shellhorn's landscape palette at the Civic Auditorium was dominated by exotics, especially through use of specimen trees such as palms (*Phoenix reclinata*), carob trees (*Ceratonia siliqua*), eucalyptus (*Eucalyptus viminalis*) and giant flower of paradise (*Strelitzia nicolai*). Though most of the original tree stock remains, the understory character has changed significantly from what was originally planted, which was lush, ornamental and flowering, and instead replaced with hardy, easily maintained shrubs (see Figure 2 for sample of original palette).



Figure 2. Sample of original planting palette by Ruth P. Shellhorn

In addition, the original site design has been altered in significant ways, though some original sections remain (see Figure 3 for a diagram of the changes). In addition, the original site design has been altered in significant ways, though some original sections remain (see Figure 3 for a diagram of the changes).




Figure 3. Annotated original site plan documenting changes to Shellhorn's design.

The planted area at the very corner of Main St and Pico Blvd has been converted from lawn into shrub plantings. New buildings have been added on both sides of the backstage entrance parallel to Pico Blvd. In addition, infrastructural improvements, including cooling towers and electrical transformers have been added to the back of house, replacing planted areas. A planter that helped screen the Committee Rooms has been pared back and chopped up into three small planter boxes. The parking along the eastern edge has been augmented, especially with the development of New Belmar Park. Walkways were added to the service / parking area and between the admin terrace and the front entrance promenade. Lastly, the entire grassy

area in front of the entrance's iconic pylons has been retrofitted by the SWIP project, though it has been replaced.

The organization and form of the planting areas along the Main St side and the front entrance promenade remain true to the original design, though likely they will need significant redesign due to accessibility and grading issues.

As the site was reviewed, careful attention was paid to the historical character of the landscape. The entrance sequence, where the pylons are located, was designed to set the building in a verdant, lush, low bed of planting so that the brise soleil and architectural pylons would provide a grand entrance. The team aligns with the recommendations of the Landmarks Commission to keep the palms that frame the front façade (see Figure 4 for images).





Figure 4. Historical palm species to remain.

The team found many of the trees in good condition and recommends retaining the trees in place as much as possible.

3. Planting Opportunities

Shellhorn was a master of creating special environments through her landscape designs. The planting design, as originally designed, was a choreography of scale, color and seasonality, pushing the Civic Auditorium to feel like a verdant, lush oasis. Unfortunately, many of these species no longer remain prudent as the Southern California climate continues to cycle through deeper droughts and drier conditions. Most species also do not provide any habitat or ecological benefits, though there is an opportunity to plant with these goals in mind.

The team recommends revegetating the gardens following the spirit of the original design using a modern climate understanding, planting natives and drought tolerant species while reinscribing the cadence of planting diversity and interest around the site. Proposed planting opportunities include:

- A. Retain mature trees; transplanting preferred to removal and replacement
- B. Replace lawn with native coastal meadow / native groundcovers
- C. Replace tropical, shade tolerant understory plantings with drought tolerant, shade plantings along the entrance façade that mimics the lush feel
- D. Add pollinator and habitat plant species to encourage biodiversity
- E. Comply with Coastal Conservancy species requirements

4. Landscape Elements for Restoration

Precast Concrete Block (along North Elevation):

A series of concrete blocks lined the planting area against the entrance façade. Screened by planting, this small pathway likely was utilized as a hidden maintenance route for plant upkeep. The team recommends restoring this landscape element as an ode to the holistic thoughtfulness of Shellhorn's original design.

Continuous Planter Outside Committee Room Terrace (East of Main Entrance):

A long, continuous planter outside the east Committee Room has been divided into individual planters over time and should be considered for restoration, though the team does not recommend replacing the understory planting as originally designed. This area receives high shade and is influenced by the ocean breeze including a minimal, but present amount of salt spray. Native plant species that can thrive in these conditions will replace some of the tropical plantings originally were planted here. It is also of note that the planter's restoration may not coalesce with all renovation schemes (see Landscape Responses to Schemes for more details). Reflecting Pool Partial Restoration / Conversion

The original design had the entrance pylons landing in a crisp, shallow water feature, which added to the entrance's sense of levity and airiness. This feature's complete restoration does not align with the intended programs for students; however, it should be studied whether an artistic paving such as a mosaic may mimic the feel of water while also utilizing less water and being more durable and resilient choice for a student driven program.

5. Programming Opportunities

As a potential new space for the Santa Monica and Malibu Unified School District, the site could accommodate new programming opportunities such as outdoor classrooms, food and beverage terraces, farmers' markets, or outdoor reading rooms. This offers a significant opportunity to enhance the existing and historic design to meet new project goals.

6. Regulations and Codes

Because the site would be upgraded to present day codes and regulations, access and grading would have a significant impact on the site especially on the Main St. side of the site. Site upgrades will require improving the site accessibility with walkways that are ADA accessible. This can be accomplished through ramps less than 8.3% with handrails and landings or, preferably, through sloped walkways with less than 5% slope, which would not require handrails.

The site upgrades will also be required to comply with applicable Low Impact Development (LID) standards (see Civil section for description of stormwater management and related strategies). One of these strategies is to install a cistern (see Civil section). Regarding the cistern location, it is recommended that the cistern avoid disturbing any existing trees and to place access points so that they will not be readily viewed by the public or visitors. In addition, it is recommended that the cistern, if possible, should be located underneath hardscape areas such as the revised parking lot.

Lastly, plantings would also be subject to and in compliance with Santa Monica, LA County and CA Coastal Commission regulations for drought tolerance, habitat and biodiversity. (See Figure 5 for diagram of improvement study areas).



Figure 5. Current site plan with historical elements to preserve and future study areas

7. Conclusions

In conclusion, though the site has been altered and will likely require additional alteration to improve accessibility, the team understands there is a way to preserve the spirit of the original landscape architecture design, while adapting the site to future the needs of the community in a sustainable way. Historical plantings and trees will be preserved to the extent possible while renovating the site be compliant with all current codes and climate adaptive planting standards. Once restored and renovated, the Civic Auditorium would return to its place as a hub of community, educational, and civic activity.



2.5 STRUCTURAL NARRATIVE

2. Executive Summary

A. The team completed a preliminary a structural seismic assessment of the existing Santa Monica Civic Auditorium to identify potential structural deficiencies in the building and estimate potential retrofit measures that may be required if the building is to be used as a public school building. It is worth noting that the potential retrofit measures listed in this report were provided to highlight potential structural scope scenarios for planning studies and budget purposes; alternative retrofit measures shall be investigated during the design of the project to mitigate the impact to the historic character defining features of the building. Below is a summary of our findings and potential retrofit measures that may be required.

Potential Deficiencies:

Potential Retrofit Measures:

| | Potential Deficiencies: | Potential Retrofit Measures: |
|---|------------------------------------|--|
| 1 | Seismic Vertical Resistance System | Existing shear wall strengthening with |
| | | shotcrete or FRP. Additional shear walls |
| | | are needed. |
| 2 | Discontinuous Concrete Shear Walls | New walls below discontinuous walls |
| | | and/or strengthening of beams and |
| | | columns supporting the discontinued |
| | | walls from the upper levels. |
| 3 | Main Roof Diaphragm – Gypsum with | Roof gypsum diaphragm will likely need |
| | Bulb Tee | to be removed and replaced with a new |
| | | metal deck system and/or strengthen |
| | | with horizontal lateral bracing at |
| | | underside of the roof. |
| 4 | Bottom Chord Diaphragm Truss | Reinforcing, replacement, and or adding |
| | Bracing | new horizontal bracing will likely be |
| | | required. |
| 5 | Tilt Floor | Tilt floor will need to be restrained to |
| | | adequately transfer its seismic inertia |
| | | forces into the existing shear walls or to |
| | | new buttress walls below the floor. |
| 6 | Pile Foundation System | New piles and strengthen of existing |
| | | pile caps will likely be needed at corners |
| | | and intersections of existing shear |
| | | walls. |
| 7 | Projection Room Lateral Bracing | New seismic vertical bracing from |
| | | projection room floor to bottom chord |
| | | of main roof trusses. |
| 8 | Canopy | Strengthening of Pylons and Girders |
| | | with FRP wrap will likely be required. |
| | | New or strengthening of horizontal |
| | | steel bracing at the ceiling level. |
| 9 | Brise Soleil | Load testing of existing panels will |
| | | likely be required to demonstrate |
| | | conformance or strengthening of the |
| | | |

| | | existing panels If conformance cannot |
|----|-----------------------------------|--|
| | | be demonstrated by testing, |
| | | replacement and/or re construction of |
| | | panels maybe required. |
| 10 | 1 Story Administration Building – | Seismically separate the building by |
| | West Addition | creating a seismic gap between the 1 |
| | | story addition and the main auditorium |
| | | building. Provide new shear walls and |
| | | gravity support near the new seismic |
| | | joint with new pile foundations. |
| | | Existing shear walls will likely need to |
| | | be strengthened with shotcrete or FRP. |
| | | Existing pile caps will likely need new |
| | | piles and may need to be strengthened |
| | | at ends of shear walls. |
| 11 | 1 Story Committee Building – East | Existing gypsum roof will likely need to |
| | Addition | be replaced with metal deck system |
| | | and/or reinforced with horizontal |
| | | bracing. New shear walls and/or |
| | | strengthening of existing walls will |
| | | likely need to be strengthen with |
| | | shotcrete or FRP. |
| | | |

२. General

Α.

At the request of the Santa Monica Malibu Unified School District (SMMUSD), KPFF performed a preliminary seismic assessment of the Santa Monica Civic Auditorium for the feasibility study of renovating this building to a public school use. In order to adapt this existing city owned building into a public school building, it would need to be rehabilitated to comply with the Division of State Architects (DSA) current standards and regulations for the rehabilitation of existing buildings. The purpose of our study was to provide a general understanding of the potential seismic deficiencies of the structure and identify the major structural upgrades that may be required for the rehabilitation of this building.

B. Scope

Our scope consisted of performing a preliminary seismic assessment of the existing building to identify potential seismic deficiencies and estimate the potential retrofit that may be required to convert the building to a public school building. Our investigation, evaluation, assessment, recommendations, and conclusions were based on the following tasks:

- i. Site visit on March 08, 2023, and April 04,2023.
- ii. Perform an ASCE41 17 Tier 1 Seismic Evaluation of the primary structure (ASCE 41 17 Tier 1 Screening Checklist). A nonstructural evaluation of the existing secondary components was not performed (ASCE 41 17 Nonstructural Screening Checklist).
- iii. Review of the following documents
 - a. 08/08/56 Architectural As built Drawings (Sheets 1 thru 28)
 - b. 08/08/56 Architectural As built Drawings (Sheets 1 thru 28)

- c. o8/o8/56 Structural As built Drawings (Sheets S 1 through S42)
- d. o5/o5/o5 Architectural 35% Submittal Drawings for New Ice Storage System (Sheets Ao.1 thru A 3.1)
- e. 10/16/85 Architectural Drawings Addition of Exiting Doors and Stairs (Sheets 1,2, and 3)
- f. 12/17/93 Structural Record Drawings Outside Storage Area Roof (Sheets S 1 thru S 20)
- g. o6/2012 Morley Construction Remodel & Seismic Upgrade Report
- h. 07/05/12 Preliminary Geotechnical Report Willdan Geotechnical
- i. o8/15/20 Feasibility Study for Hydraulic Floor System NYA

C. Key Assumptions

- i. We have assumed that as built drawings provided to us for this evaluation are representative of the current building conditions and the on-site material properties.
 We also assume that the structural elements are in good condition unless detected and identified otherwise during our site visit.
- ii. A geotechnical and geological hazard investigation was not performed at this time. It is recommended that a qualified geotechnical and geological engineer perform an evaluation of the site conditions in order to identify any potential geotechnical/geological risks with the rehabilitation of this building and provide recommendations to the retrofit of the foundation system where required.

D. Limitations

- i. The conclusions and conceptual seismic upgrade drawings/diagrams/sketches presented in this report were based on the limited scope noted above and the use of our engineering judgement and experience with similar projects and building types. The results and findings in this report are for the sole use of the Santa Monica Malibu School District and are not intended to be used by other parties as it may not contain the appropriate information for other uses. The extent of our site observations and field surveys was also limited to the portions of the structure that were readily accessible and visible during our site visit(s). A more detailed investigation and evaluation of the structure will be required during design to confirm the conclusions summarized in this report. It is recommended that in developing any estimate for construction based on this preliminary study that a minimum cost contingency of 20% be provided.
- ii. Our professional services have been provided in a manner consistent with the level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions and circumstances. No other warranty, expressed or implied, is made.

4. Code and Reference Standards

A. Division of State Architect (DSA)

The Division of State Architect (DSA) is the governing agency responsible for the review and approval of K 12 public schools and Community Colleges in California. The DSA adopts the California Building Code (CBC) with exclusive DSA standards and amendments. The provisions and regulations of the CBC have primarily been developed for the design and construction of new buildings. For existing buildings, the DSA also adopts selective sections of the California Existing Building Code (CEBC) which allows the use of the ASCE-41 Standard for the rehabilitation of school buildings.

If this building is to be converted into a conforming DSA building, it will need to either comply with the CBC regulations for new buildings or comply with the CEBC and ASCE 41 Standard for existing buildings. The CEBC and ASCE 41 provisions were the basis of the feasibility study presented herein as compliance with new building regulations could be extremely challenging for existing structures.

B. 2022 California Building Code (CBC)

As an alternative to complying with the minimum seismic standards of the California Existing Building Code, the building could be evaluated and made to comply with new building construction regulations per the California Building Code. In general, rehabilitating a building for compliance with new building standards is very difficult and cost prohibited. The feasibility study of this design option was beyond the scope of this study and was not investigated.

- C. 2022 California Administrative Building Code (CABC)

 Per Section 4 307 of the California Administrative Code (CABC) an existing nonconforming building rehabilitated for use as a school building shall comply with Sections 317 323 of the California Existing Building Code (CEBC).
- D. 2022 California Existing Building Code (CEBC)

The applicable DSA sections of the CEBC establish the minimum standards for earthquake evaluation and retrofit design of existing buildings to be used as public school buildings. The CEBC allows the use of ASCE 41 as the evaluation standard for demonstrating conformance with DSA regulations of existing buildings.

Per the CEBC, this building will be required to comply with the following seismic performance levels based on the ASCE 41 standard.

2022C Chapter 3 Table 317.5(DSA SS) – Risk Category III

- i. BSE 1N, S 2 Damage Control, N B Position Retention
- ii. BSE 2N, S 4 Limited Safety, N D Hazards Reduced
- E. ASCE 41 17 Seismic Evaluation Standard

ASCE 41 17 is the reference standard in the 2022 California Existing Building Code (CEBC) and can be used for the seismic evaluation and rehabilitation of existing buildings. The feasibility study in this report assumes that the building will need to be rehabilitated to comply with this standard per DSA regulations if converted to a public school building.

5. Site and Building Descriptions

A. Site

The site is completely developed around the existing Civic Auditorium building located at the center of the site with concrete walkways, concrete plazas, and landscape areas. A loading dock area with asphalt pavement is located on the west side and an asphalt parking lot is located at the southeast corner of the site. The land is an irregularly shaped parcel bounded by Main Street on the south, Pico Boulevard on the east, and driveways for the surface parking lot of the sustainable water project on the west and north sides. The highest elevation of the site is the finish floor of the Civic Auditorium building between 59.0' and 59.5'. The lowest elevation of the site is located at the southeast corner of the site, near the intersection of Main Street and Pico Boulevard, at 52.0'.

B. Building

- i. The Civic Auditorium consists of a concrete structure built circa 1956 with multiple partial levels. The building has overall plan dimensions of approximately 160 feet by 235 feet. The structure incorporates a modern style architecture designed by master architect Welton Becket that is highlighted by the parabolic pylons at the main entrance canopy to the auditorium.
- The entrance canopy structure consists of a metal deck supported by steel beams and pre cast concrete frames with integral concrete pylons. The pylons are approximately 62 feet above the exterior grade. The canopy structure is attached to the main structure with horizontal steel bracing.
- iii. The lobby area has two levels. The second level and roof over the lobby area consists of reinforced concrete joists and girders supported by concrete columns. The second level leads to the top section of the auditorium seating. The first level is a concrete slab on grade and leads to the main floor area.
- iv. The stage area is approximately 120 feet by 41 feet in plan with reinforced concrete walls on all sides and a high roof area at approximately 77 feet above the stage floor. The stage roof is constructed of reinforced concrete slab, beams, and girders supported by the concrete walls. There are two mezzanine levels around the stage area that are also comprised of concrete slabs and beams.
- v. The main floor area consists of a large seating area that is divided into two sections. One section of the floor consists of fixed cast in place concrete raker seating that slopes from the first level to the second level of the lobby area. The other section closer to the stage consists of a tilting platform area for removable seating. The tilting platform structure is comprised of steel beams and concrete filled metal deck. The roof over the main area is consists of a poured gypsum slab supported by steel beams and trusses and is approximately 54 feet above the stage area. The top chord o the trusses support the main roof and the bottom chord of the trusses support the catwalk system over the main floor of the auditorium.
- vi. The foundation of the auditorium consists of a pile system with interconnecting grade beams attached to pile caps that support the walls and columns of the building. The piles consist of steel shelled piles with concrete. The auditorium also has a one level partial below grade basement over the stage area and tilting floor area.
- vii. There are two one story additions to the main auditorium building. The addition on the west side is approximately 57 feet by 35 feet in plan and is constructed of gypsum roof slab supported by steel beams and girders at approximately 12 feet above the stage floor. The addition is connected to the west concrete wall of the auditorium. The foundation of the addition consists of concrete grade beams and piles. The east building addition is separated from the main structure by a 2 inch gap and consists of a poured gypsum roof slab supported by steel beams and tapered steel girders. The plan dimensions of the east addition is approximately 89 feet by 72 feet and its roof is approximately 16 feet above the stage floor.

6. Condition Assessment

A. General Condition

 Based on the visible structural elements during our site visit, the overall structure of the building appeared to be in good structural condition. No concerning cracks were noted on the concrete walls in or outside of the building.

- ii. Cracks on the concrete fill over metal deck at the tilting floor area was observed but appeared to have been repaired with a type of epoxy injection. It is assumed that the repair condition of the cracks have preserved the original structural capacity of the floor and are not of a structural concern; but it is worth noting that the visible area was limited by furniture and storage boxes present on the floor at the time of our visit.
- iii. The steel beams supporting the tilting floor seemed to be in structural good condition, as well as the steel trusses and roof members at the catwalk area below the main roof.

B. Site Observations

i. KPFF visited the site on March o8, 2023 and April 21, 2023, to observe the general condition of the building. Our observations were limited to the exposed structural areas that were readily accessible and visible at the time of our site visit. Below is a list of some notable structural elements observed during our site visit. For photos and other observed conditions please see Appendix A of this report.

Building Elements:

Observed Condition

| 1 | Exterior walls of the Auditorium | Appeared in good general condition. |
|---|---------------------------------------|---|
| 2 | Original one story addition at the | Addition is structurally separated by a |
| | Auditorium East Elevation | gap from the main exterior auditorium |
| | | wall |
| 3 | Original one story addition at the | The addition is attached and connected |
| | Auditorium West Elevation. | at the roof to the main exterior wall. |
| 4 | Tilt floor concrete slab at the main | Cracks were observed that appeared to |
| | floor area of the Auditorium. | have been repaired with epoxy |
| | | injection. |
| 5 | Steel girders at tilt floor below the | Appeared to have been strengthen |
| | main floor area. | with additional steel section at the |
| | | bottom flange. |
| 6 | Brise Soleil | Appeared to be in good general |
| | | condition. |

7. Seismic Evaluation

A. ASCE 41 17 Seismic Evaluation and Retrofit of Existing Buildings
An ASCE 41 17 Tier 1 Screening was performed on the as built condition of the existing
building to gain a general understanding of the structure and assist in identifying potential
impacts to the building that will likely result from its proposed renovation and
rehabilitation. The results of our Tier 1 Screening is summarized on the Tier 1 Checklist
included in this report (Appendix B).

It is worth noting here that a Tier 1 evaluation procedure is a simplistic engineering tool used by engineers to rapidly identify potential deficiencies in an existing structure based on the performance of similar buildings in past earthquakes. A Tier 1 evaluation is a rapid assessment and a good starting point for the comprehensive engineering analysis that is ultimately required to understand the total seismic vulnerabilities of an existing building. Its limitation should be recognized and shall not be construed as a complete evaluation of

the structure due to the very basic and partial analysis required to perform the Tier 1 Screening procedure.

In order to finalize the retrofit requirements and final recommendations for the seismic upgrade of the building, an ASCE 41 17 Tier 3 evaluation will be required. A Tier 3 evaluation consists of a comprehensive engineering analysis that requires detailed calculations and analytical models of the structure to more accurately predict the seismic deficiencies and retrofit measures of a building. A Tier 3 evaluation is used to confirm the findings of a Tier 1 screening, uncover other deficiencies that the building may have, and/or remove deficiencies identified by a Tier 1 evaluation. Only a Tier 1 Screening was performed for the development of this report at this time, as a Tier 3 evaluation was beyond the scope of this study.

It is worth noting that for a Tier 3 evaluation there is also an alternative non linear analysis option to the conventional linear analysis method that is more typically used. This alternative approach consists of advanced engineering analysis that requires additional engineering effort and additional peer review that may impact the design cost and schedule of a project, but at times has resulted in a reduction of retrofit measures providing value to the construction cost, construction schedule, and preservation of historic character defining features in an existing building.

B. Structural Deficiencies and Potential Retrofit Measures

The following is a list of potential structural deficiencies that were discovered during our investigation. Potential retrofit measures that will likely be required to rehabilitate the building to conform with DSA standards and regulations are also presented below.

- i. Seismic Vertical Resisting System
 - a. (Sheet S 3, S 8, S 9, S 10, S 11, and S 12) The concrete walls in the building provide the seismic lateral resistance for the structure. The walls are expected to have insufficient shear and/or flexural capacity for conformance with DSA seismic rehabilitation requirements. The existing shear walls will likely need to be strengthened by shotcrete and/or FRP methods to properly address their seismic deficiency. In addition to strengthening the existing shear walls, new shear walls may need to be added at Grid 14 and Grid 16 on the north side of the building as well at the triangular floor areas on the front side of the proscenium wall at Grid 5. A new concrete shear wall on Grid H between Grid 1 and 2 may also be required.
- ii. Discontinuous Concrete Shear Walls
 - a. (Sheet S 37) The north end of the East and West Concrete Walls of the building have an in plane vertical irregularity due to the lack of shear wall continuity at the ground floor. It may be possible to address this deficiency by infilling the wall north of Grid 17 to support the wall above and eliminate the discontinuity; however, infilling this wall may greatly impact the historic character of the lobby space and alternative retrofit measures for this deficiencies shall be investigated during design.
 - b. (Sheet S 37) The second floor walls at Grid 16 do not continue to the ground floor and create an in plane vertical discontinuity. In order to properly address the seismic impact of the discontinued walls, the existing beams below will likely need to be enlarged and strengthened to accommodate the new seismic criteria forces.

- The existing columns at the ground floor supporting these beams along Grid 16 may need to be enlarged and strengthened as well.
- c. (Sheet S 20) The main concrete walls along grid V and B are offset from their supporting walls at the ground floor. This will likely require thickening the concrete wall lines at the upper level to match the walls at the ground floor and/or thickening the walls at the ground floor by shotcrete or a pour-in place method.

iii. Main Roof Gypsum with Bulb Tee Purlins

a. (Sheet S 2 and S 12) The main roof diaphragm consists of a gypsum roof construction with bulb tee sub purlins. This system has very little capacity and reliability for seismic induced forces, and it is likely that it will either need to be replaced with a metal deck system and/or reinforced with horizontal bracing at the underside of the roof.

iv. Bottom Chord Truss Diaphragm Bracing

a. (Sheet S 11) The bottom chord truss diaphragm bracing provides seismic in plane diaphragm resistance for the spotlight gallery floor and catwalks, as well as the suspended ceiling over the auditorium gallery below. It also resists seismic out-ofplane forces from the perimeter concrete walls. The existing horizontal steel bracing between at this level will likely need to be strengthened and supplemented with additional horizontal bracing at the open bays between the bottom chord of the trusses.

v. Tilt Floor

a. (Sheet S 32) It is our understanding that due to code accessibility reasons. the tilt floor at the main floor of the auditorium will need to be locked in place at the top tilt position. It will need to be restrained from its floor seismic acceleration during an earthquake and will need to be able to adequately transfer its seismic inertia forces into the existing shear walls and/or new concrete shear walls below the floor. New walls and column supports will be installed to relieve the current hydraulic jacks and pivot mechanism from supporting the floor in order to better protect and preserve the mechanism of the tilt floor for future use if so desired. We also understand that the beams and deck/slab will need to be removed and replaced with new beams and deck/slab in order to lower the top of slab elevation and accommodate a gymnasium flooring system. It is worth noting that in order to re use the floor as a tilting floor in the future, partial removal and demolition of the new floor framing, walls, and columns that will be added to provide a fixed floor condition, will need to be removed, demolished, and partially modified in order to re install the hydraulic system and its pivot mechanism.

vi. Pile Foundation System

a. (Sheet S 3) The existing foundation system primarily consists of 14 1/2" diameter CISS (Cast in Steel Shell) Piles embedded a minimum of 40 feet into the ground with the top of the piles embedded into pile caps at the basement floor level at the south end of the building and at the ground level at the north end of the building. It is expected that some of the pile caps at the corners and intersections of the existing and new shear walls will require additional piles such as micro piles to

provide the required seismic increased capacities for the DSA rehabilitation. The pile caps will likely need to be enlarged and strengthened as well.

vii. Projection Room Lateral Bracing

a. (Sheet S 11) The projection room floor is suspended from the main roof trusses above and there appears to be a lack of seismic lateral bracing of the floor to the trusses above. Steel bracing from the floor to the bottom chord framing of the trusses will likely be required to appropriately brace the projection room floor.

viii. Canopy at the Main Entrance

- a. (Sheet S 17 and S 18) There are six concrete pylons at the Main Entrance that rise approximately 62' from grade and are attached to the concrete girders at approximately 13' above grade. The columns are expected to require strengthening to accommodate the new seismic design criteria required for this building. The strengthening will likely consist of several layers of FRP wrapped around the column surface that may result in an increase width of the pylon by ½" ¾", and may create rounded corners that may visually impact the original section of the pylon. The girders may also require similar strengthening. An option to the FRP if not desirable may consist of the demolition and reconstruction of the pylons or portions of the pylons to meet the code required concrete strength and reinforcement. Further testing of the concrete to determine the composition and performance history of the concrete is recommended. Other options shall be investigated during design to try to preserve the historic section and character defining features of the pylons if possible.
- b. The canopy is braced laterally to the building by horizontal steel bracing at the canopy ceiling level. The horizontal bracing is expected to be replaced or strengthen to meet the new seismic load demands.
- c. The canopy connections to the building and the anchorage to its foundation will likely also need to be revised and strengthened.

ix. Brise Soleil at Front Wall of Auditorium

- a. (Sheet S 2g and A28) The exterior sunscreen panels at the front wall of the auditorium consist of concrete precast panels supported by concrete spandrel beams. The precast panels and its attachment to the building's spandrel beams may be deficient for the new seismic criteria. As this may be of important historical significance, the panels, may need to be subjected to load testing for conformance if the justification by conventional engineering analysis and calculations is not possible. If conformance can not be demonstrated by testing, replacement and/or re construction of panels with adequate strength for new seismic demands may be required. Other options shall be investigated during design to try to preserve the character defining features of the brise soleil.
- x. 1 Story Administration Building at the West Auditorium Wall
 - a. (Sheet S 10) This lower one story structure is attached at a partial height of the main exterior wall of the auditorium potentially creating an unfavorable seismic vertical irregularity. In order to eliminate this potential irregularity between the two structures, a seismic joint could be implemented by separating the two structures and providing additional vertical gravity support and a seismic lateral resisting element adjacent to the joint on the office side.
- xi. 1 Story Committee Building at the East Auditorium Wall

a. (Sheet S 13) This lower one story structure appears to be separated from the main auditorium structure by a 2" gap. This structure will act independently of the main auditorium building during a seismic event and will need to evaluated and retrofitted as an independent structure. The roof diaphragm of the building consists of a gypsum roof construction with bulb tee sub purlins. This system has very little capacity and reliability for seismic induced forces, and it is likely that it will either need to be replaced with a metal deck system and/or reinforced with horizontal bracing at the underside of the roof. The 2" separation gap may not be sufficient for the required seismic design drift and may need to be enlarged. New shear walls and/or strengthening of the existing walls with shotcrete or FRP along Grid W and Z will likely be required along with an additional pile foundation system.

8. Non Structural Systems

A. DSA Requirements for Non Structural Systems

Seismic compliance of the non structural systems in the building will also be required by DSA if the building is to be rehabilitated for use as a public school building. The existing non structural systems are allowed to conform to the provisions of the California Existing Building Code (CEBC) or the California

Building Code (CBC) provisions for new buildings. The evaluation of existing non structural systems could be a challenge for engineers since older buildings and non DSA buildings many times lack the as built information necessary to properly evaluate these systems for conformance to seismic standards. If an evaluation of these systems is deemed necessary, a comprehensive field investigation and in situ testing program consisting of destructive and/or non destructive testing may be required to obtain the necessary information. Replacement of these secondary systems to new building standards is sometimes a better alternative for the cost and time needed for the investigation, analysis, evaluation, and strengthening of these existing systems. Please note that some of these non structural systems may already need to be removed or demolished to perform the primary retrofit work of the main structure. The impact to the historic significance of these elements shall be carefully considered when deciding to replace or seismically upgrade these elements.

Engineering analysis and evaluation for DSA compliance of the existing non structural systems was beyond the scope of this study; however, a general assessment and potential requirements based on our limited observations of several of the non structural items is presented below.

B. Architectural and Secondary Building Components

The architectural and secondary components in the building that are likely required to be removed, replaced, seismically retrofitted, or shown to be in conformance with new seismic standards include, but not limited, to the following:

- i. The suspended ceiling and lights/equipment at the auditorium may need to be removed and replaced with adequate attachment and bracing to the bottom chords of the roof trusses in conformance with new DSA seismic standards.
- ii. Suspended acoustical tile ceilings, plaster ceilings, and/or soffits will likely need to be removed and replaced with adequate attachment and bracing to the structure above.

- The hanging support for the large sliding and folding doors will require additional support and seismic bracing from structure above.
- iii. The front brise soleil precast panels on the north elevation of the building may not be in conformance with new DSA seismic standards. Additional investigation, testing, and/or analysis will be required to confirm the adequacy of the panels. Potential strengthening solutions if determined to be deficient will likely include additional strong backs behind the panel, additional anchorage with epoxy anchors, or scale testing of the panel construction to determine adequacy. Other options shall be investigated during design to try to preserve the character defining features of the brise soleil.
- iv. Mullions for the storefront glazing of the building will likely need to be strengthened, anchored, braced, and/or replaced with new mullions for compliance with new DSA seismic standards. Other options shall be investigated during design to try to preserve the character defining features of the storefront.
- Interior metal stud partition walls may need to be removed and replaced with new metal stud construction with proper construction details in conformance with new DSA seismic standards.
- vi. The existing stairs will likely need to be modified at the floor and/or landing to allow for seismic inter story drift of the building without imposing additional seismic loads on their structure.
- C. Mechanical, Electrical, Plumbing Systems

The mechanical, electrical, and plumbing systems in the building that may be required to be seismically anchored or seismically braced in accordance with new seismic standards include, but not limited, to the following:

- Electrical and communications equipment including panel boards, battery racks, motor control centers, switch gear, and other fixed components.
- ii. Mechanical equipment used for the operation of the building including boilers, furnaces, conveyors, and HVAC system equipment.
- iii. Plumbing systems including water tanks, water distribution pipes, and fire suppression system.

g. CONCLUSION

A. Findings

The Santa Monica Civic Auditorium Building is an existing nonconforming building under DSA regulations. It is expected that it will need to be rehabilitated to meet the seismic performance criteria per DSA standards. The rehabilitation is anticipated to consist of a comprehensive seismic upgrade of the structural elements of the building as well as the evaluation and upgrade of its non structural elements. The building retrofit is expected to include the addition of new shear walls, strengthening existing shear walls, removal and replacement of structural members, floor and roof diaphragm strengthening, new micropiles and pile cap strengthening, canopy retrofit, pre cast wall panel strengthening, and other building elements required to meet the performance criteria by DSA.

B. Next Steps

If the project is to move forward with the design and rehabilitation of the building, we recommend that an ASCE Tier 3 analysis of the proposed rehabilitated building be started prior to or during the early concept/programming phase of the project. This type of analysis is necessary to confirm the estimated deficiencies and potential mitigation measures presented in this report, identify other potential deficiencies not uncovered during this preliminary study, and/or determine which deficiencies may be eliminated by performing a more detailed Tier 3 engineering analysis. Provided the additional design cost and schedule could be accommodated in this project, the Tier 3 alternative non linear analysis approach may also be considered to assist in mitigating the retrofit impact to the building and in preserving as much as possible the historic character defining features of the building.

We also recommend an initial meeting with DSA as early as possible to introduce the project and confirm the seismic evaluation approach and criteria to be used on the project. Please note that per Section 4 307 of the California Administrative Code, Rehabilitation of an existing nonconforming building for use as a school building, a pre application and an Evaluation and Design Criteria Report (EDCR) will need to be submitted to DSA for approval prior to the submittal of a project application. It is recommended that this report be submitted during schematic or early design development phase of the project to allow time for DSA review comments on this report to be incorporated in the later phases of design prior to the final construction documents.

10. APPENDICES

APPENDIX A – Photos (under a separate cover)

APPENDIX B – ASCE 41 17 Tier 1 Screening Check List (under a separate cover)

APPENDIX C – Conceptual Retrofit Measures (under a separate cover)



2.6 MECHANICAL DESIGN NARRATIVE

This report documents the existing conditions of mechanical equipment and systems at the Santa Monica Civic Auditorium in Santa Monica, CA, and provides the team's recommendations for proposed improvements. The assessment consisted of a site visit and review of existing documents. This section provides a summary of existing mechanical systems and the remaining useful life if they were to be re incorporated into the new programming schemes, as well as recommendations for overall system improvements.

A site visit was performed by engineers of each discipline on Wednesday, March 8, 2023. During the visit, the team walked the entire building/site, documenting observations and capturing photos of current equipment and systems within and outside the building to establish existing conditions. Equipment and systems were not operational at the time of the visit.

In addition to the site visit, the following documents were reviewed as part of the assessment:

- A. As Drawings Santa Monica Civic Auditorium (August 8, 1956)
- B. Ice Storage System Drawings Civic Auditorium (April 25, 2005)

2. Existing Conditions

A. Chiller

A 185 ton Trane air cooled chiller was installed in 2005 to replace the existing condensers and cooling tower. A new plate and frame heat exchanger, and thermal energy storage system with 144 ton cooling capacity were installed as part of the same project. The chiller has not been run or maintained since the Civic center closed in 2013, with about 10 15 years of useful life remaining at that time.





B. Boilers


The original drawings indicated 4 gas fired boilers manufactured by Bryan, with a combined output of 130 tons. It appears that these boilers were replaced around 2002 2003 With non condensing Parker boilers. These boilers had an expected useful life of 10 15 years remaining when the civic center closed. and will require service prior to startup.





C. Heat Exchanger and Glycol Management

A Calmac Model S62 IS plate and frame heat exchanger with a 305 ton capacity was added in 2005 along with a glycol management system for the chiller. The heat exchanger is used to separate the 30% glycol mixture on the chiller side from the rest of the hydronic distribution system. The heat exchanger had an expected useful life of 10 15 years when the civic center closed and will require service prior to restarting the system.



D. Thermal Energy Storage System An ice thermal energy storage system with 144 ton cooling capacity was installed in 2005, along with the chiller upgrade. The system utilizes the main chilled water pumps for distribution, and can store cooling capacity to offset energy usage during peak demand. The system appears to be in good condition.





E. Air Handling Units

The air handlers found onsite are all custom, with individual supply and exhaust fans, as well as separate heating and cooling coils. They are currently set up for single zone constant volume applications with the services described below.

- i. S 1 serving the administration wing
- ii. S 2 serving the east room
- iii. S 3 serving the east portion of the auditorium
- iv. S 4 serving the auditorium dressing rooms
- v. S 5 serving the west portion of the auditorium
- vi. S 6 serving the lobby area

These air handling units are still mostly original from 1956, except for new chilled water coils and piping connections added to unit S 2 as part of the 2005 chiller upgrade. Overall, the units are in poor condition due to system age.







F. Hydronic Pumps

The chilled water pumps and were replaced as part of the 2005 chiller upgrade with single speed end suction Bell and Gossett HSC series pumps, with a total output of 1550 GPM. These pumps had 10 15 years of useful life remaining when the civic center was closed.






G. Heating Hot Water Pumps

The heating hot water pumps appear to be original single speed Chicago pumps. They are in very poor condition and are likely no longer functional due to deterioration of internal components.





H. Controls Infrastructure

The original pneumatic controls are still in place but are no longer functional. A new Trane model BMT controller for the chiller was added along with the 2005 upgrade, but the front end interface has been removed making it inaccessible.





I. Distribution

All ductwork, hydronic piping, and associated insulation appear to be from the original system installed in 1956. There is a small amount of new piping for the chiller, and the ice storage system, heat exchanger, and glycol management system included in the 2005 chiller upgrade. Ductwork, piping, and insulation from the original installation are at the end of their useful life.



2.7 ELECTRICAL AND LIGHTING DESIGN NARRATIVE

This report documents the existing conditions of electrical equipment and systems at the Santa Monica Civic Auditorium in Santa Monica, CA, and provides the team's recommendations for proposed improvements. The team's assessment consisted of a site visit and review of existing documents provided by NAC. This section provides a summary of existing electrical systems and the remaining useful life if they were to be re-incorporated into the new programming schemes, as well as recommendations for overall system improvements.

A site visit was performed by engineers of each discipline on Wednesday, March 8, 2023. During the visit, the team walked the entire building/site, documenting observations and capturing photos of current equipment and systems within and outside the building to establish existing conditions.

In addition to the site visit, the following documents were reviewed as part of the assessment:

- A. Original Drawings Santa Monica Civic Auditorium (August 8, 1956)
- B. Electrical System Upgrade Civic Auditorium (April 27, 2007)

2. Existing System

A. Lighting

Lighting in the Civic Auditorium has mostly been upgraded to fluorescent fixtures from the original 1950s installations. Lights in auxiliary rooms are predominantly troffers and surface mount fixtures, and the theater space is primarily served by high-bay pendants. There is also a theater lighting system that is outside the scope of a normal electrical investigation and should be evaluated by a theater consultant.



Figure 4.3.1 - High Bay Pendants



Figure 4.3.2 - Troffer Fixtures

The lighting control system consists of normal line-voltage on-off switches for the auxiliary spaces and relay and dimmer panels for the theater lighting. No wall switch dimmers, daylight harvesting control, or occupancy control was encountered during system review. Exit signs with "bug-eye" style lights provide exit direction and egress lighting for the space.



Figure 4.3.3 – Exit Sign with Bug-Eyes

B. Electrical Service

The civic auditorium has a transformer vault where the utility transformer is located. SCE provided a new 16kV-48oY/277V transformer supplying a 3000A bus duct as part of the 2007 electrical system upgrade. The bus duct feeds a 3000A service entrance switchboard in the main electrical room.



Figure 4.3.5 – SCE Meter

C. Power Distribution

The electrical distribution system in the Civic Auditorium is mixture of about half original equipment from the 1950s construction and half that was installed as part of the 2007 electrical systems upgrade.

The original distribution consisted of a unit transformer with high side breakers feeding two MCCs and a 48oV distribution panel ('P'). The secondary side of the transformer fed four distribution switchboards (A,B,C, and D) which distributed power throughout the Auditorium to panels located in hallways and closets.




Figure 4.3.1 – Original Single Line



Figure 4.3.2 – Example Original Panel

The 2007 electrical upgrade replaced the unit transformer with a separate 480Y/277V switchboard, a dry-type transformer, and a 120Y/208V switchboard. The MCCs, 480V Switchboard P, and 280V Switchboards A-D were all maintained and refed from the new distribution equipment. Additionally, two 208V distribution boards were added to stage right and supply panels located throughout the main floor of the auditorium. New panels were also added to switchboards A-C.






Figure 4.3.3 – Renovation Single Line

Figure 4.3.4 – New Distribution Board Nameplate

Motor Control Center 1 was also replaced sometime after the 2004 cooling tower upgrade.

Power receptacles were distributed throughout the auditorium and auxiliary spaces. Additionally, 18 sets of 12 qty -30A twistlock receptacle boxes were installed in the basement and the meeting room during the 2007 electrical upgrade.



Figure 4.3.5 – Twistlock Receptacle Block

D. Emergency System

Switchboard D is fed from an 150A ATS that is served by switchboard C and a 30 kW generator located outside the building loading dock. The switchboard feeds four emergency panels that feed lighting and fire alarm circuits throughout the building.



2.9 PLUMBING DESIGN NARRATIVE

This report documents the existing conditions of plumbing equipment and systems at the Santa Monica Civic Auditorium in Santa Monica, CA, and provides the team's recommendations for proposed improvements. The team's assessment consisted of a site visit and review of existing documents provided by NAC. Recommendations for each discipline will be found in each discipline's section.

A site visit was performed by engineers of each discipline on Wednesday, March 8, 2023. During the visit, the team walked the entire building/site, documenting observations and capturing photos of current equipment and systems within and outside the building to establish existing conditions. Equipment and systems were not operational at the time of the visit.

In addition to the site visit, the following documents were reviewed as part of the assessment:

- A. Original Drawings Santa Monica Civic Auditorium (August 8, 1956)
- B. Domestic Supply Plumbing Replacement Civic Auditorium (June 14, 1990)
- C. Sustainable Water Infrastructure Project by SM Public Works Civic Center (June 09, 2020)

2. General Overview

The plumbing needs for the existing Santa Monica Civic Auditorium building are currently met with conventional systems that include sanitary sewer, domestic water, storm drainage, and natural gas.

3. Existing Conditions (Services and Distribution)

A. Domestic Cold Water

The building is fed by a 4 inch cold water supply laterally connected to the city water main along Pico Blvd. via a 3 inch water meter. Cold water enters overhead at the basement and is distributed to plumbing fixtures, hose bibs, and water heaters.

Each plumbing fixture has individual isolation valves (fixture stops) for maintenance purposes. Shutoff valves at groups of fixtures on each floor and water hammer arrestors on cold water headers serving water closet/urinal flush valves behind access panels were not observed, and are therefore believed to be missing from the existing system.

Hose bibbs along the perimeter of the south side of the building are spaced at 75 to 100 feet apart.

B. Domestic Hot Water

Domestic hot water for the auditorium is generated using a gas fired boiler and storage tank setup located at the south side of the building on the Upper Concourse level. The hot water storage tank has a capacity of 675 gallons. Hot water is currently being generated and stored at 140 degrees F, then routed to all domestic plumbing fixtures and equipment

at 120 degrees F. The system is recirculated via a dedicated hot water return line and an inline pump back to the source equipment. Domestic hot water for the east wing (Committee building) is generated using a gas fired tank type water heater that only serves the kitchen and restrooms at this wing of the building.

Insulation on the hot water supply and return distribution piping was not observed and is therefore believed to be missing or deteriorated throughout the years.





Figure 4.4.1 - Gas-Fired Domestic Boiler

Figure 4.4.2 - Domestic Hot Water Tank

C. Sanitary Sewer and Vent System

The building's sanitary sewer piping connects to the facility sewer infrastructure and exits the property at the south to Pico Boulevard via two 6 inch sewer laterals. Sewer is routed throughout the building serving restrooms, janitor rooms, mechanical rooms, and kitchen, and exits the building at multiple locations.

There is an existing sewage ejector located in the basement that serves all fixtures on the basement level.

The kitchen at the east wing (Committee building.) does not appear to have a grease interceptor. The sanitary waste line exits the building at the south side of the building and is routed to connect to the line serving the restrooms. This line then routes to the campus sewer infrastructure.

Sanitary vent piping is routed above ceilings and terminates at various locations through the roof. Sizes range from 2 inch VTR to 4 inch VTR.

Existing upper terminal cleanouts, cleanout to grade, and change in direction cleanouts appear to be in place, as these were observed in most areas.

Trap Primer valves serving floor drains and floor sinks in the building were not observed and are believed to be missing.



Figure 4.4.3 - Sewage Ejector in Basement

D. Indirect Waste and Condensate Drainage Systems
HVAC condensate drainage piping was observed for all the major mechanical equipment.
Condensate drain is routed from fan coil units to janitor rooms and terminates into mop sinks. Condensate drain lines from larger air handling units inside the mechanical rooms route to floor sinks within the room. The walk in refrigerators within the kitchen area also include condensate drain lines that terminate into floor sinks. Auxiliary drains as part of the fire sprinkler system also discharge to floor sinks.





Figure 4.4.4 – Floor Sink for Fire Sprinkler Aux. Drain

Figure 4.4.5 - Floor Sink Outside Walk-in Freezer

E. Storm Drain System

The Auditorium and Committee building wing each have a storm drain system consisting of a piped primary system with multiple roof drain locations, and a secondary (overflow) system with scupper openings through the parapet adjacent to each roof drain location. The storm drain is routed throughout the building and down to either the basement or below floor, from where it exits the building at multiple locations.

Storm drain piping that exits at the south and east side of the building daylights through exterior walls and spills to grade. Storm drain that exits at the west side of the building spills through the face of the curb along Main Street. It is the team's understanding that

surface runoff at the surrounding areas of the facility are being partly diverted into the large storm holding tank as part of the recently (2020) installed Advanced Water Treatment Facility (AWTF) that was performed by Santa Monica Public Works Department based on review of such drawings. The system is located north of the project site.

F. Natural Gas System

The natural gas system is composed of a gas pressure regulator, lube type shutoff at the gas rise, and a gas company meter. The gas assembly is located on the south side of the building, next to the loading dock.

Gas supply into the building steps down from high pressure to low pressure and is distributed within the building to serve hydronic water heating, domestic water heating, and kitchen equipment.





Figure 4.4.6 – Gas Assembly (Facing North)

Figure 4.4.7 – Gas Assembly (Facing West)

G. Specialty Equipment

The kitchen has the following specialty equipment and fixtures for cooking operations:

- i. A commercial grade dishwasher with booster heater.
- ii. A commercial grade exhaust hood with fire suppression system.
- iii. Commercial grade gas cooking ranges.
- iv. 3 compartment sinks, hand sinks, prep sinks, etc.
- v. Steam cookers, gas fired ovens, and ranges.
- vi. Free standing freezers, walk in refrigerators, and freezers.





Figure 4.4.8 – Gas-Fired Cooking Range w/Hood

Figure 4.4.9 – 2-Compartment Sink

H. Summary (Condition and Age Review)

Domestic water pipes and fittings are believed to be galvanized, with some repairs made with copper. Both the sanitary sewer and waste piping are cast iron with no hub couplings. Gas piping is Schedule 40 black steel with threaded fittings. The capacity of all system mains is of adequate size to support future renovations with no significant increase in fixture loads.

Major equipment items such as water heaters and storage tanks appear to be reaching the end of their useful life. Existing insulation on the hot water storage tank located at the upper level may contain asbestos and shall be addressed accordingly.

The existing plumbing distribution systems appear to be in working order; however, most of the piping is original to the building construction and shall be replaced as all systems have reached, if not exceeded, their life expectancy. Piping should be also considered for replacement in areas where walls will be opened or replaced entirely should the building undergo a complete renovation.

The condition of existing plumbing fixtures varies throughout the building as there have been modifications made during the building's life. Although the fixtures that appear to be original to the building construction are in good working order, most fixtures do not meet the code required flow rates and are likely not in compliance with the lead free requirements; therefore, they should be considered for replacement.



2.9 FIRE PROTECTION AND ALARM DESIGN NARRATIVE

The Santa Monica Civic Auditorium building is currently protected by a partial coverage sprinkler system and Class II hose cabinets on the stage and seating area. The existing fire alarm system consists of audio visual notification, voice evacuation functions, and detection throughout the building, with the exception of the areas described below.

2. Existing Conditions

A. Fire Protection System

The building has two connections to the city's water network, and each one feeds a different fire sprinkler system. During the visit it was only possible to identify a backflow preventer in the newer connection that serves the meeting room. The original connection has check valves not in compliance with the current codes. Both connections have a fire department connection on Pico Boulevard.




Figure 4.5.1 - Site Plan

The building is partially sprinklered. The original connection serves the office areas, restrooms, lobby, mechanical rooms, electrical rooms, dressing rooms, the backstage

storage area and only one of the storage areas outside the building. The second connection feeds the kitchen, bathrooms, and the meeting room in the east wing.

Hose cabinets are located on each side of the stage and on the first and second levels at the back of the seating area. The fire hoses appear to be connected to the domestic water system and not to the building's fire protection system.




Figure 4.5,2 – Fire Sprinkler Coverage







Figure 4.5.4 - East Wing Fire Riser Assembly



Figure 4.5.5 – Fire Hose Cabinets

In addition to the lack of protection in the aforementioned areas, deficiencies such as corroded and painted sprinklers heads were found. Obstructions to the discharge pattern of the

sprinklers in the lobby were identified. The hoods in the kitchen have an Ansul suppression system. The condition of this system could not be verified.





Figure 4.5.6 – Obstruction Below Soffit Not Sprinklered

Figure 4.5.7 – Corroded Sprinkler Head



Figure 4.5.8 – Painted Sprinkler Head



Figure 4.5.9 – Ansul Panel in Kitchen Hoods

A. Fire alarm system

The building has an existing Radionics fire alarm control panel and a separate voice vac panel. The detection includes partial coverage of smoke detectors and total coverage of the pull station; additionally, the system monitors the valves of the fire system. Occupant notification includes speaker/strobes throughout the building and exterior fire bells.




Figure 4.5.10 – Detection Point Map



Figure 4.5.11 – Fire Alarm Sequence of Operation








Figure 4.5.13 – Audio-Visual Notification in the Main Hall



2.10 TECHNOLOGY DESIGN NARRATIVE

Existing Conditions

The existing building is fed by service providers with copper cables and fiber optic.




There are three locations where POE switches are installed for the data, voice, and WIFI systems through fiber cables from the MPOE. These switches are mounted on wall-mounted racks.







There is an existing copper punch block serving existing POTs line for the building.



The building is equipped with an intrusion system with a Keypad and motion sensors.




The performance arts AV system is outdated. There is no dedicated room for the system. There is no CCTV system.



2.11 ACOUSTIC NARRATIVE

Room Acoustics

A mid frequency reverberation time of 2.4 seconds, was measured in the main Auditorium on March 15, 2023. The measured reverberation time is plotted as a function of frequency in Figure 1 below.



It should be noted that there were lots of boxes etc. being stored within the auditorium space at the time of these measurements. See Photos 1, 2 and 3 below. Please note that the reverberation time would be higher without the presence of these boxes etc. within the space. Similarly, the reverberation time of the space when in use will be reduced with increasing occupancy (people absorb sound), likewise chairs deployed on the main level would be expected to absorb sound and reduce the reverberation time to some extent.






Photo 1 Photo 2



Photo 3

It is understood that the side wall acoustical paneling, see Photo 4 below, is a historically listed feature. According to the drawings these metal wall panels are non perforated towards the stage and perforated elsewhere. As seen in Photo 4, where the panels are perforated, the area of the perforations ('free area') is relatively low. The team estimates about 4%. Where the team could perform a visual inspection, there appeared to be an air gap immediately behind the perforations. The architectural drawings indicate that there is acoustical fill beyond this airspace.




Photo 4: Auditorium Wall Acoustical Panels

Due to the relatively low percentage area that is perforated, even if the acoustical fill is in reasonable condition (or replaced) these panels will only be effective at absorbing sound at relatively low frequency (typically in the 250Hz octave band). Sound at mid and higher frequencies is mostly reflected. Unfortunately, this acoustical performance is not really suitable given the acoustical need to significantly control reverberation at all sound frequencies.

2. Sound Isolation

It is understood that the horizontally sliding doors circled in Mark-Up 1 below are considered to be features with historical significance.



Mark-Up 1

The sound isolation performance of the auditorium side sliding door was measured on March 15, 2023. This acoustical measurement quantified the 'Noise Isolation Class (NIC)', which is a single number noise reduction rating of the assembly separating two spaces where sound level differentials are measured and compared with standard contours. The higher the NIC number, the better the acoustical performance.

The measured sound isolation for this door of NIC 23 is a very modest performance. In the team's opinion, the acoustical performance was limited by perimeter acoustical seals being ineffective. In the team's experience it can be very difficult to effectively seal old doors of this type.

3. HVAC Noise Levels

Spot HVAC noise level measurements made on the Stage and in the Auditorium on March 15, 2023. These levels ranged between NC 30 and NC 40.

Given the understanding that the HVAC control system is no longer fully operational and the likelihood that extensive modifications would be required to the existing HVAC system, the team does not consider these measurement results to be particularly meaningful.



2.12 EVENTS AND ATHLETICS NARRATIVE

The purpose of this narrative is to provide architectural design considerations and programming feasibility for the project related to sporting events and performances. The project envisions converting the Santa Monica Civic Auditorium into a multipurpose event, and high school sports competition and practice facility. This report includes a summary of physical integration, spectator experience, and operational strategies for two unique design schemes.

2. Proposed Improvements

Both proposed design schemes assume the main auditorium space is transformed to include a full competition basketball and multi sport court, flanked by spectator seating on the north and south. It is anticipated that the north seating will utilize the auditorium's existing tiered seating rows, with newly installed replacement chairs. Seating on the south can be provided using standard tiered retractable seating systems used commonly in auditoriums and gymnasiums.

The design considers locating the main sport court over the existing tilting auditorium floor area. The project plans to fix the tilting floor and anticipates placing temporary seating over the sport court when not used as a competitive gym. Generally, the existing stage area would be maintained, however the exact stage footprint and clear height differs between the two design schemes.

The existing main spectator lobby will largely maintain its function of providing circulation, ticketing functions, and amenities to spectators and guests.

3. Design and Operational Considerations

The basketball and sport court should be installed over the main auditorium floor, with attention being given to the resulting additional floor thickness. The thickness will need to be taken into consideration when designing the auditorium perimeter, floor transitions, and circulation pathways into the space. For non sporting events, a temporary protective flooring system should be applied over the sport court before chairs or furniture are placed. The protective flooring can also provide acoustic benefits depending on the type of system selected.

The multipurpose and transformational design of the project will present requirements for isolating and protecting the auditorium space. The spectator lobby and other adjacent support areas that receive natural light or that are required to be well lit environments will require blackout curtaining to prevent light spillage into the main auditorium. It is also recommended that exposed walls within the auditorium be protected with padding or durable cladding given the new primary use will be sports. A proscenium curtain should be provided for theater type shows and can be deployed during other events to provide visual and acoustic separation between the auditorium and performance stage area.

To maximize flexibility for non sporting events, it is recommended that retractable seating sections are portable, and can be removed and stored. Design consideration should be given to storage areas and their access to ensure sufficient height and width clearance are provided to store seating sections, sports goals, and other equipment. Storage rooms should be located on the same level as the auditorium or easy access to a freight elevator or the existing movable orchestra pit should be provided.

Permanent scoreboards for sporting events can be affixed to the east and west auditorium walls behind the goals or suspended from the roof structure. While a center hung scoreboard may be desirable for sports, this will present a challenge for music and performance events when that scoreboard would want to retract from view. Consideration should be given to any permanent scoreboards and their appearance during other events. Deployable curtains could be utilized to conceal these elements, among other strategies.


Modification to the auditorium ceiling is expected to integrate sports lighting and other equipment over the new sport court. Consideration should be given to placement and aesthetics, especially for equipment and fixtures that will remain in view during non sporting events.

It is recommended that film and broadcast infrastructure be provided to the auditorium's existing projection booth, plus a secondary location in the lower rows of permanent tiered seating along the north sideline of the court. The infrastructure should be designed to support an appropriate level of TV broadcast, announcer and play by play, and statistician activities.

Design and operational considerations unique to the specific schemes are outlined in their respective sections.

4. Conclusion

In conclusion, this study finds that the existing auditorium can be suitably transformed to support high school sports competitions and practices, while maintaining the ability to accommodate other music and performance events. Between the two schemes explored, the ability to host certain events differs based on the size and performance capabilities of the theater stage. Scheme 1 reduces the footprint and height clearance over the stage, thus introducing limitations for certain theater events. Scheme 2 preserves the existing footprint and height clearance, and can be expected to accommodate a wider range of event types.



2.13 THEATRE NARRATIVE

The team evaluated the existing Santa Monica Civic Auditorium and its potential for use as both a high school sports facility and as a rental venue for concerts, film shoots, and other one-off or short duration uses. The goal is to find an optimal combination of uses and functionality that allow it to generate income that can be used to help fund the ongoing operation and maintenance of the building, while still fulfilling its role as a primary sports facility for Santa Monica High School. In addition, the historical nature of the building needs to be respected.

The evaluation is based on a visit to the site, review of the available as built drawings for the building, and meetings with District staff and other members of the evaluation team.

2. Existing Conditions

When originally constructed, the building was used for a number of high profile events including the Academy Awards. As such, the general design of traffic flow for people and equipment around the stage is logical and allows for large items to move easily between the stage and exterior load in points. The stage has a proscenium that is roughly 65' wide by 32' high, with an orchestra pit. The room seats about 2,500 patrons in theatrical mode, with ~ 950 of those in terraced seating at the rear of the space and the remainder on the main floor. The main floor has an innovative tilting slab design that allows the room to be shifted between flat floor events, such as basketball games, and sloped floor seating for stage performances. The building was constructed in 1958 and some of the theatrical elements were upgraded in the 1950 and some elements. The team will look at each theatrical element of the space in turn.

3. Theatrical Power

A. The existing power infrastructure is extensive, particularly in terms of accommodation for temporary power connections that can be used by groups coming in. More than 600A of 3-phase power is available on the stage alone. Some of the existing power connections are in good shape and meet modern code requirements, but others have deteriorated and/or no longer meet code. More detail is provided in the electrical report.








4. Rigging

The stage has a full height fly tower with manual counterweight rigging. The rigging system was renovated in 1992, which means the ropes and other moving parts are likely around 30 years old. Most of the steel elements appear to be original. Due to the theatre being dark for 10 years, most of the linesets have spent a long period of time in one position. This can lead to flat spots or weak spots in ropes and head blocks, which can become a point of failure.





There is a walkable grid near the top of the fly tower, which can be used to access the head blocks as well as the overhead steel for temporary connection of portable rigging elements. The assumption is there is also the ability to load the counterweight arbors from the grid. The grid is accessed via a very long vertical ladder with a cage (about 70' tall). Current code does not allow for a ladder to ascend this far in one linear run without intermediate rest platforms at regular intervals.


The structural cavity above the suspended plaster ceiling has a system of walkable paths to allow access to permanent and temporary items suspended above the main floor. These paths have railings, but do not meet current safety codes.





There are accommodations for suspending a central speaker cluster above a boxing ring, along with a cable hoist for a microphone.

Accommodation for suspending a temporary truss element, for lighting and speakers, just forward of the proscenium appears to have been added at some point. The steel beams (painted to match the ceiling) seen in the photo below would allow chain hoists or other temporary rig points to be attached.



5. AV Systems

The existing audio system is very minimal and some parts of it appear to have been abandoned in place over time. All of the existing equipment was obsolete at the time the building went dark. There are three sets of openings in the ceiling just in front of the proscenium that were designed for attachment of speakers. There are small clusters of speakers in each of these positions, which appear to be comprised of 2 or 3 Meyer UPAs. The left and right clusters also have a small subwoofer flown above the 2 full range speakers.





There is a provision for the suspension of a center cluster above the boxing ring location, but no speaker system is currently installed in that location. There is also a cable reel for a microphone to be lowered to the boxing ring, but no microphone is installed.

Some ancillary areas, such as the lobby, are provided with ceiling speakers. It is doubtful that most of these are still functional.

All amplifiers and processing for the audio system are located in a second floor office, stage left.



There is no mixing console, or apparent infrastructure, for an audio mixing position within the seating area. This would be necessary for concert or other performance uses. There is no video equipment, or infrastructure for video systems.

6. Theatrical Lighting

There is little permanently installed theatrical lighting. A few lighting instruments were found sitting in the catwalk, and even fewer were actually installed on a batten or the catwalk rail. There are several electrics over the stage, but only a single catwalk position over the audience.

The theatrical lighting system appears to have received some upgrades in the 1990s. There is a single 96 channel dimming rack (ETC SR48 loaded with D20 dimmer modules). For a stage of this size, this is barely enough dimming to provide a minimal wash. It appears that most shows brought in their own lighting equipment and the permanent systems were just for the most basic of events or even just for worklight / houselight. An ETC Express lighting console is located in the closet next to the dimming rack, which means it was not used much since an operator would not have any means of seeing the stage or what the lighting looked like.






The original Century dimming system is also still in place. It was not possible to determine whether it is being used solely for houselight, or if it was just abandoned in place.





Neither system appears to control all of the lighting in the stage/audience areas, which means an operator has to go to the controls for at least 2 systems to turn the lights on and off.

There are two carbon arc followspots located in the followspot booth. These do not appear to be operational but would make great museum pieces.



There is only one catwalk for front light, located over the front part of the main floor. The lighting angle from this location is quite steep, and the depth of the stage and apron (with the orchestra pit lift in the up position) really require at least 2 catwalk positions to be adequately lit.



There are no box boom positions at the side walls for high side light at the apron and front of the stage. Such positions would be considered a standard feature in any modern theatrical venue.

7. Main Floor


The majority of the audience area is occupied by the tilting slab element. The floor was in the flat position during our site visit (it is currently used as a storage warehouse), but reports are that the mechanism received some repairs/upgrades in the early 2000s and that it is operational. In the flat position the floor is 6" below the lobby level, and even with the stage level. With the orchestra pit lift in the up position, this gives a contiguous flat floor over a large area.

When the floor is tilted, it meets the front of the orchestra pit at a variable height due to the curvature of the front wall of the pit/front edge of the slab. The pitch of the slope is within ADA guidelines for a ramp but exceeds guidelines for a sloped floor. The slab length, front to back, is more than twice the allowable distance for a ramp without a landing. When the floor is in the sloped position, there is no flat area at the front that could be used for ADA seating. Historical photos show folding chairs set up on the slope for audience seating.



This would be problematic under modern codes due to issues with the chairs sliding down the slope. Photos also show the orchestra pit lift in a mid-position, providing a flat floor area at the front of the seating. This would allow for ADA seating at the front of the main floor but would make the sightlines unworkable for several rows behind them.

An analysis of the sightlines for an audience seated on the floor, when sloped, shows mediocre to poor sightlines for the back half of the main floor seating.



8. Orchestra Pit


There is an orchestra pit in front of the stage that is equipped with a hydraulic lift. It functions as an extension of the stage when the lift is in the up position, or as an orchestra pit when the lift is in the down position. There is a large door from the orchestra pit into the basement storage area below the stage, allowing the orchestra pit lift to be used as a freight elevator to move items between the auditorium and the basement storage area. The pit lift appears to have a pressurization instability that causes it to depress a few inches. This was reported to be an ongoing issue.

The lift machinery and controls appear to be original. There is a basic mechanical interlock for the door to the basement storage to prevent operation of the door while the lift is in motion or in the up position. The team was unable to test the functional status of the interlock.

g. Stage Floor

The existing stage floor has what appears to be a sacrificial top comprised of painted, tempered hardboard (Masonite). This is a common stage finish and it shows a normal level of wear, including paint blemishes and a few damaged panels.

There is no area where the buildup of the floor can be seen, but the as built drawings indicate that the floor has a system of sleepers (also common for stage floors). The space between the sleepers is called out to be filled with Zonolite, proper containment will need to be considered.



The stage is at the same level as the main floor when the main floor is in the flat position. The proscenium opening is about 65' wide x 32' high when measured to the hard surfaces. This corresponds with theatrical best practice that says a proscenium width should be no more than twice its height. However, as can be seen in some of the photos above, the main valence/border is trimmed in about 8', reducing the effective proscenium height to about 24' and putting the top of the opening slightly below the upper row of the seating – which is not considered desirable.

10. Audience Seating

The terraced seating in the back of the room is outfitted with solid plastic sports seats. These have an automatic seat bottom mechanism that returns it to an upright position when the seat is unoccupied. The seats appear to have been replaced in the 1990s, which would make them around 30 years old. Some seats are outfitted with aisle lights at the ends of rows and most of these appeared to be operational. The seats are in reasonably good condition, partly due to not being used in the last decade. The plastic does not show signs of stress or excessive wear.

Historical photos indicate that the original seating was padded theatre seats, rather than sports seating.






11. Support Spaces

There is a set of technical spaces located above the rear row of the auditorium seating. These were used as followspot booths and other functions, but other than followspot it is not possible to tell what at this point as most of the equipment has been removed or relocated.



There are a significant number of dressing rooms of various sizes, as well as spaces for crew and musicians. The condition of these spaces is discussed in the architectural report.



2.14 MARKET SUPPLY AND DEMAND DIAGNOSTIC

Conventions, Sports & Leisure International (CSL) was retained by the project team to conduct a market analysis of the potential redevelopment of the Civic Auditorium in Santa Monica, California. The purpose of the analysis is to assist project stakeholders in evaluating key market and building program aspects of the redevelopment.

At the outset of the market analysis process, CSL gathered invaluable input from key Santa Monica-Malibu Unified School District decisionmakers regarding the intent of the potential redevelopment and acquisition of the Auditorium. In addition to regularly hosting practices, games, and events organized by the School District, the envisioned redeveloped Auditorium would be able to host revenue generating third party events such as concerts, corporate functions, and club sport competitions. CSL reviewed preliminary designs for the Center, prepared by NAC with a focus on evaluating the building program from a market demand perspective. The detail presented herein is intended to provide project stakeholders with the information necessary to make informed, value driven decisions regarding the Center's finalized building program and its utilization.


The study process consisted of detailed research and analysis, including a comprehensive set of market specific information derived from the following:

- A. PROJECT EXPERIENCE: Experience garnered through more than 1,000 planning and benchmarking projects involving sports, recreation, entertainment, and event facilities throughout the country.
- B. LOCAL MARKET ASSESSMENT: Virtual meetings held with key community stakeholders, and analysis of the market's existing entertainment facility inventory and consumer behavior.
- C. INTERVIEWS & OUTREACH: Telephone interviews and virtual meetings with representatives of potential user groups, including athletic organizations, meeting planners, entertainment promoters, and esports leaders that could have an interest in a redeveloped Civic Center Auditorium.

2. Existing Conditions

- a. Local Market Analysis
 - i. Existing LA Entertainment Venues

As part of any potential entertainment facility project, it is important to consider the level of competition in the market. Los Angeles is a global entertainment destination with nearly 50 performance facilities that seat at least 500 spectators. In a sprawling major metropolitan area such as greater Los Angeles, location is also of crucial importance, as traffic conditions can significantly limit drive in audiences. Exhibit 1 presents a map of performance facilities in Greater LA with at least 500 seats and less than 6,001 seats.



Identified venues range from the 6,000 seat YouTube Theater in Inglewood to the 500-capacity Eli and Edyth Broad Stage in Santa Monica. Notably, the Santa Monica / western Los Angeles region only has three identified concert facilities. Though the Barker Hangar has capacity for up to 3,000 attendees, it is not a traditional concert, sports or meeting venue. This limited supply in the immediate area is a positive indicator for a potential new concert facility with capacity for 1,500 or more attendees such as the Auditorium. However, though a moderate gap in supply may exist, it is even more important to consider the demand for such a facility. This is further evaluated later herein.

ii. Los Angeles Entertainment Industry Heat Maps

The images below reflect heat maps by zip code within the Los Angeles CBSA. The star on each map represents the location of the Santa Monica Civic Auditorium. The site is located near wealthier zip codes in Los Angeles, including families and young adults. As shown, spending on travel sports (i.e., sports tournaments and competitions) and concerts is significantly high in the region. Taken together with the previously shown concert venue supply gap, the data suggest material opportunity for a new concert/entertainment venue in the market. High travel sport spending should also support potential indoor sports programming at the redeveloped Auditorium.

Concert Attendance (%)



Concert Spending (Avg)



Online Gaming Participation (%)



Travel Sports Spending (Avg.)



Exhibit 2 Consumer Behavior Heat Maps Source: ESRI, 2023

B. Market Demand Outreach

At a sizable capacity of more than 1,500, the potential redevelopment of the Santa Monica Civic Auditorium creates potential opportunities to attract a variety of third party events to Santa Monica.

The purpose of this section is to provide an analysis of third party event market demand for a redeveloped Santa Monica Civic Auditorium. Data presented represents real input from the following four types of potential Center users:

- i. Sports: organizers of tournaments, leagues and other sports programming at the youth, amateur, and high school levels.
- ii. Meetings and Banquets: corporate and independent meeting planners involved in organizing banquets, assemblies, lectures, weddings, cultural events, and other activity.
- iii. Entertainment: promoters of touring concert and comedy acts.
- iv. Esports and Emerging Events: representatives of regional gaming and esports organizations, as well as contacts representing other emerging events such as robotics, drone racing, and hackathons.

In total, CSL conducted detailed interviews with nine organizations. These groups were contacted in order to determine their interest in a new facility and the amenities and elements that would be necessary to host their events. Specific groups contacted as part of this process and stakeholder meetings include the following:

Groups Contacted (Alphabetical)

- David Pressman Events
- Everly Rose Events
- Live Nation
- Simply Troy Events
- Sterling Social Events & Experiences
- Valentine
 Entertainment
- Varsity Spirit
- Westside Mat Monsters

3. Indoor Sports Demand

Overall, interviewed gymnastics, cheer, and wrestling groups expressed generally positive interest in using a redeveloped Civic Auditorium for their events. Each group typically requires a critical mass of flat floor space and accompanying seating to host large tournaments, meets, competitions, exhibitions and other such events.

Cheerleading and gymnastics competition organizers represent a significant potential customer base for the redeveloped Santa Monica Civic Auditorium. In fact, both promoters interviewed expressed very strong interest in utilizing the facility if it meets their needs, with one expressing interest in a long term contract to use the facility. Organizers stressed the need for easy load in/load out since cheer tournaments generally provide their own mats, which are heavy and difficult to move. Organizers also expressed the need for multiple high ceilinged spaces. In addition to a primary competitive space, it is crucial for cheer tournaments to have a warmup space with at least 20 foot ceilings, which is sorely lacking in West Los Angeles. Competitions would primarily occur during the spring and fall periods.

Wrestling tournaments are another potential demand generator for a redeveloped Auditorium. Organizers recommended the availability of a large flat floor space, to fit at least four 40'x40' wrestling mats. The organizer also expressed the need for sufficient bathroom facilities, as well as space for parents to create a "staging area" for athletes in a lobby or parking lot. Most youth wrestling tournaments take place during the summer.

All interviewees, regardless of sport, expressed frustration at the lack of facilities in West LA, which forces student athletes to drive for long periods throughout the Los Angeles area to reach their competitions. Interviewees were enthusiastic about Santa Monica's dining and hotel options for multi-day tournaments, although they expressed reservations about potential costs. Ultimately, all interviewees showed enthusiasm for the Santa Monica Civic Auditorium redevelopment project.

4. Meeting and Banquet Demand

To evaluate conference/meeting market potential, CSL conducted outreach to the Meeting Professionals International (MPI) database of meeting planners that plan meetings in the Greater Los Angeles market. Meeting planners represent large local corporations, associations, tradeshow companies, and private event planning firms. Events include educational and training events, executive events, tradeshows, team building events, company dinners/galas, annual conferences/meetings, and weddings, among others. In total, five planners were interviewed.

Corporate events represent a potentially lucrative market for the redeveloped Auditorium due to the number of companies headquartered in the Greater Los Angeles area, as well as Santa Monica's reputation as an attractive destination. Meeting planner input provided invaluable data regarding the unique needs of different event types. For networking focused events, a large flat floor space is ideal. For product launches and events featuring a keynote speaker, high quality audio, lighting, and screens are crucial. Planners stated that they often rent this equipment from a third party, but suggested that offering some of this equipment and service in house would greatly reduce their costs and increase their interest in using the Auditorium. Identified events within the corporate segment generally range from 800 to 1,500 attendees.

The Los Angeles market also has one of the most robust social event industries in the world. According to interviewed planners, very large weddings, Bar/Bat Mitzvahs, Quinceañeras, and anniversaries could be potential users of the Auditorium. Although the Santa Monica Civic Auditorium would lack the unique charm or premium quality of some other Los Angeles venues such as mansions or high-end banquet centers, organizers highlighted the location in Santa Monica, high quality AV equipment, and the availability of alcohol as positive draws. Planners also strongly suggested allowing outside catering companies and partnering with multiple furniture/equipment rental companies. Lastly, wedding planners stated that they look for facilities with two rooms, one for the ceremony and another for the reception. Identified events within the social segment generally range from 500 to 1,200 attendees.

5. Entertainment Demand

Many project stakeholders noted significant interest in hosting concerts and comedy shows at a redeveloped Civic Auditorium in Santa Monica. To investigate this possibility, CSL conducted interviews with representatives from Live Nation to collect invaluable feedback regarding Santa Monica's potential in the concert and entertainment industry.

Promoters generally agreed that the Los Angeles entertainment market is relatively saturated with theaters, clubs, and performing arts venues. However, they noted that metro's western region lacks indoor venues with capacity for 1,500 or more, and that concerts at the Civic Auditorium could have a unique opportunity to draw from a highly affluent attendee base in the Santa Monica area.

Promoters estimated that the venue could likely host one concert or comedy show per month with between 1,500 and 2,500 attendees if designed with state of the industry principles. Recommended facility elements include a flat floor surface for general admission, "intermediate rigging capabilities" to support audio and lighting for shows, high quality and conveniently accessed food & beverage options, and premium seating options. Potential likely exists to generate more than \$40,000\$ in gross food <math>& beverage sales per show.

6. Esports and Emerging Event Demand

As the supply of event facilities throughout the country advances, new event types are beginning to emerge. Though not anticipated to be a significant user of a Redeveloped Civic Auditorium in the near term (the next five years) emerging event segments that may increasingly use the facility in the future may include esports, drone racing, hackathons, and robotics competitions, among other.

During recent conversations with Riot Games, Lakers Gaming of the NBA 2K League, Epic Games, ESL, NACE Starleague, and Immortals Gaming, many suggested that there is moderate opportunity for a new in person esports venue in the Los Angeles market that could accommodate a standing room crowd of between 1,000 to 2,000 attendees. Such a venue could host one to two pro or semi pro esports events per year, as well as one to two collegiate or high school championships.

7. Key Demand Findings

Overall, market analysis findings suggest that a moderate but material level of unmet demand exists to support the redevelopment of the Civic Auditorium in Santa Monica. Based on the feedback presented by each potential user group on the previous pages, the following observations have been made.

| Event Segment | Demand (o-10) | Key Observations | | |
|--------------------------------|------------------|---|--|--|
| Youth/Amateur Sports | 7 | With limited investment relative to the other event segments, the Auditorium has opportunity to host occasional cheer, gymnastics, and wrestling competitions during the fall, summer and spring seasons. | | |
| Meetings and Banquets | 6 | The Greater Los Angeles market has a robust supply of corporate and independent meeting planners seeking unique, off site special event venues. Survey results suggest opportunity to host 8 to 12 high end banquets per year at the Auditorium, in addition to one non profit event per month. | | |
| Entertainment | 7 | Concert promoter feedback suggests unmet demand for mid sized concert space in western Los Angeles. The Auditorium will require significant investment in rigging, lights, audio, and food & beverage, but concert and comedy acts also generate the highest profit per event for venues. | | |
| Esports and Emerging Events | 4 | In person esports events that require venues the size of the Auditorium are still relatively rare, even in Los Angeles. Opportunity likely exists to host collegiate and high school esports events one to two times per year, in addition to a limited number of STEM related events such as robotics or hackathon events. | | |

8. Revenue Potential

Some interviewed planners also provided information regarding the rental and food and beverage revenue their events can generate. It is important to note that the data provided below should be used for general guidance and serves as a useful indicator regarding the revenue potential of hosting third party events at the venue. Further analysis will be needed to accurately estimate the venue's financial operations.

Youth/Amateur Sports – Interviewed groups would be willing to pay between \$3,000 and \$10,000 per day. In considering industry norms, many cheer, dance, and gymnastics groups will prefer a rate closer to \$5,000 per day, with the potential to increase this price once the Auditorium has become better established in the market. These events average approximately 2,500 total attendees (participants and spectators who would come and go throughout the day) and food and beverage revenues would average \$5.00 per person. This would result in \$12,500 in gross food \$6 beverage revenue.

Meetings and Banquets – Corporate groups interviewed indicated they would pay anywhere from \$5,000 to \$25,000 per day depending on the event. In reviewing event planner preferences in Los Angeles, and considering feedback provided by planners, groups will generally be willing to pay \$10,000 per day. Groups who would be willing to use the venue's food & beverage (approximately 25 percent) are estimated to average \$15,000 in food & beverage revenue per event.

Entertainment – In considering typical promoter venue contract structures, potential to generate rental revenue from concert acts is limited. Moderate opportunity exists for one to two local/tribute acts to rent the venue for \$5,000 to \$10,000 per show for unique one off shows. Instead, many popular acts will require anywhere from \$20,000 to \$50,000 from the venue in artist fees. However, concerts averaging approximately 1,700 attendees, which could result in \$25,500 in gross food and beverage revenue (\$15 per head). Further, the venue could retain ten percent of ticket sales, which could result in approximately \$10,000 per show. Essentially, concert booking will require a strategic approach to increase the likelihood of profitability. It may be beneficial to partner with a third party booking entity such as Live Nation or similar organization in order to host acts with the greatest likelihood of financial success. In some cases, they can work with artists to lower their fees if they identity significant opportunity for high ticket sales.


q. Proposed improvements

The following recommendations have been made based on local market analysis and feedback provided by interviewed planners, organizers, and promoters. The program elements below are intended to serve as guidelines for designing a market supportable even venue.

- A. Flat Floor Layout: Interviewed planners generally recommended converting the hydraulic flooring within Civic Auditorium to a full time flat floor surface. A flat floor setting would be used for concerts, corporate events, weddings, and sports events. No use cases were identified that would prefer an inclined floor.
- B. Flooring Surface: Planners across all segments generally prefer concrete or carpeted flooring. If the Auditorium should have a permanent hardwood floor surface, temporary carpet and/or plate tile floor should be applied for concerts, meetings, and banquets. Cheer and wrestling groups would simply apply their mats atop the hardwood surface.
- C. Improved Vantage Points: In speaking with concert promotes and local stakeholders, some of the front rows of fixed seats should be removed and/or moved to enable clearer vantage point of the stage.
- D. Premium Seating Options: Opportunities to develop loge boxes and/or select areas with VIP services throughout the fixed seating areas should be evaluated. Ideally, the Auditorium would have a premium seating capacity of between 150 to 300. Premium ticket sales are significant revenue drivers for concert venues and would enhance the Auditorium's marketability to concert, comedy, and esports events. This investment does not have to include a physical build out; venues without hard structured boxes or suites often create "VIP zones" by roping off seating areas with clear vantage points and convenient access to food & beverage for attendees paying the higher ticket price.
- E. Lobby Food & Beverage: Concert promoters and sports organizers both indicated a preference for multiple food outlets within a lobby/pre function setting that serves local and authentic cuisine, akin to a miniature food hall. As a cost effective alternative to building permanent concession stands, temporary kiosks could be provided to local restaurants and food trucks to use for select shows.
- F. Auditorium Food & Beverage: Similar to the Mission Ballroom in Denver and Fillmore in Minneapolis, easy to access bars that also serve pre prepared foods should be featured on both the left and right sides of the general admission area. Alcohol sales would be shut down for school and sports events.
- G. Catering: Meeting planners highlighted the importance of housing at least a warming kitchen for their caterers, and recommended the Auditorium have an open catering policy.
- H. In House A/V: Of all the interviewed market segments, concerts demand the greatest degree of in house production capabilities. A minority of artists playing in 2,000 capacity venues tour with their own lighting and production equipment. To make the Auditorium a turnkey solution for tour artists, promoters recommended permanent speakers, controllable stage lighting, and permanent LED boards behind and/or to the sides of the stage.

- I. Rigging: Concerts and esports events require the greatest degree of in house rigging infrastructure. To accommodate these events, the Auditorium will require a truss system that can support lighting fixtures, audio equipment, and other elements. Power distribution and control system infrastructure will be required to manage this system.
- J. Broadcast Capabilities: Meeting planners, esports organizers, and comedy promoters each indicated interest in a venue that has built-in broadcast infrastructure to record, edit, and stream their events. Consideration should be given to investing in a technological "backbone" to support temporary broadcast studio set ups within the Auditorium (i.e., AV and high speed fiber connectivity and access throughout the venue). Areas for camera positions throughout the venue should also be identified. Robotic cameras, controllable by a single user, could also be installed to reduce labor costs for the building and/or events.
- K. Internet Capabilities: A reliable and high speed internet connection is crucial for hosting esports events. Consult with internet service providers (ISPs) to ensure the Auditorium has sufficient bandwidth to handle the demands of live streaming, online gaming, and other internet intensive activities. Meeting planners and concert promoters also demand robust, affordable Wi Fi networks to cater to their attendees and staff; as such, Wi Fi coverage throughout the Auditorium should be ensured.
- L. Breakout/Team Spaces: Two to four breakout spaces with 1,000 or more square feet would enable the Auditorium to accommodate the meeting space needs of corporate meeting planners and the team meeting/storage space needs of sports organizers.
- M. Outdoor Event Space: Develop a patio or plaza space just outside the Auditorium to host indoor/outdoor corporate functions, weddings, and special events. This space could also be used for sponsorship activations associated with concerts, esports, and sports events.
- N. Potential Partnerships: Auditorium management should work with the Santa Monica CVB to market the venue to corporate and independent meeting planners looking for unique off-site event space. Music venue development is also not a "build it and they will come" proposition in Los Angeles; management will have to network with regional and national concert promoters to secure concert events on a periodic basis. Alternatively, management could secure an agreement with a third party booking entity, such as Live Nation, to maximize the ability to attract concert activity to the venue.





3.1.1 PROGRAM

Introduction

Through a series of meetings with SMMUSD representatives and Santa Monica High School staff, educational spaces needed were identified that could be located at the potential Civic Auditorium site in lieu of the main Santa Monica High School campus. By utilizing the Civic Auditorium as an athletic facility to serve the High School, space on the dense high school campus is freed up for alternate educational uses. The starting point for these discussions was the program previously developed by the District and their consultants for the Blue Gym on the high school campus.

In selecting programs/spaces from the high school that could be housed at the Civic, consideration was given to how students would travel from the main campus to the Civic as well as that travel's anticipated timing. Athletic offerings at Santa Monica High School include mandated Physical Education classes for all students as well as a large variety of competitive sports teams. The athletic programs for both portions require instruction and support spaces. The PE program relies on these spaces being quickly accessed from the academic spaces at the high school, due to limited time between class periods for students to transition. With immediate adjacency to the high school the Civic Auditorium provides an excellent opportunity to support the high school's space needs, however it is a longer walk than just traveling within the campus. Therefore, priority was given to locating spaces needed by some of the school's many competitive sports teams at the Civic over the PE programs, since the competitive sports teams practice and compete at the end of the school day.

The overarching goal was to provide a space primarily to serve these competitive athletic team programs while still preserving the ability of the historic Auditorium to host a variety of performance based shows and events for the district and community.

2. Competitive Sports Teams

When evaluating the sports teams that could most effectively use the Civic Auditorium, priority was placed on selecting sports that could utilize shared spaces. A single wood sports court can be striped to provide competitive and practice courts for multiple sports – basketball, volleyball, etc., while soccer or football is unable to utilize that facility. The six teams listed below were selected as the ideal ones to potentially be housed in the Civic. The size of each team (as of March 2023) is also listed.

- A. Girls' Basketball 60 members
- B. Boys' Basketball 60 members
- C. Girls' Volleyball 45 members
- D. Boys' Volleyball 45 members
- E. Girls' Wrestling 15 members
- F. Boys' Wrestling 60 members

3. Scheme 1

Scheme 1 utilizes the main auditorium's flat floor as a space to host competitions for basketball, volleyball and wrestling, in addition to practice courts for basketball and volleyball. Support program for these sports including locker rooms, equipment storage, coaches' offices, and officials changing rooms are located in the adjacent wings on the east and west sides of the auditorium, aligned to the same floor level as the auditorium. This proximity and

relationship are desirable, providing direct access for coaches and athletes into the main auditorium.

Program areas for wrestling including locker rooms, storage, and a practice gym exist on two new floors structured within the existing theater fly space and connected via stairs and elevators to the main auditorium level. The new stairs and elevator reduce the useable footprint of the stage right wing area.

With the reduced height over the stage, an operable rigging grid would be provided to preserve as much flexibility as possible for rigging small concerts and performances. It is not expected that larger theater or Broadway style shows will be able to perform in the transformed venue given the reductions in stage footprint and the height above the stage. Discussions with the District have confirmed that Broadway style shows are not being targeted for this facility given that those shows typically occupy a facility for multiple weeks or months, and the High School athletic teams' use of the building would not permit that time commitment.

A suite of office space for FUD (Facility Use Department) along with theatrical support spaces surround the stage on the first and second floors. The theatrical support spaces include dressing rooms, toilet/shower rooms and stagecraft areas.

4. Scheme 2

Scheme 2 utilizes the main auditorium's flat floor identically to Scheme 1's use - as a space to host competitions for basketball, volleyball and wrestling, in addition to practice courts for basketball and volleyball.

Support program for sports including locker rooms, coaches' offices, and officials changerooms are located in the new construction wings on the east and west sides of the auditorium, aligned to the same floor level as the auditorium. Similarly to Scheme 1 this proximity and relationship are desirable. Scheme 2 designates one large space to each gender for student locker rooms, in addition to a smaller gender-neutral locker room. The gendered locker areas would host separated zones of locker space for each sport with a central shared shower and toilet room.

Storage for basketball, volleyball, and other sports is in the basement below the stage. The operable orchestra pit will be used to move the equipment up and down to/from the auditorium level.

The existing stage footprint and height above the stage are preserved in this scheme, providing the ability to accommodate larger shows that could utilize a full fly system if desirable. Theatrical support spaces surround the stage on the first and second floors, including dressing spaces and stagecraft areas.

The new construction of a west wing to the building houses offices for FUD (Facility Use Department), a Community Room with adjacent kitchen, and support spaces. The Community Room and kitchen match what the current east wing ('Committee Building') houses and will provide the District and community with a place to host small events, awards ceremonies and gatherings.

| 9 | Program ences | Civic Auditorium Feasibility Project | | |
|------------------|---------------------|---|------------------|----|
| 3lue Gym (sf) | Approx. (E) (sf) | Scheme 1 (sf) | Scheme 2 (sf) | No |


| | Blu (sf, | Ap (sf) | Sct (sf, | Sct (sf, | Notes |
|--|-------------|------------|-------------|-------------|--|
| ared Program | | | • | | |
| Main Hall - Upper fixed seating | | | (e) area | (e) area | 950 +/- fixed seats (958 per original drawings) |
| portion | | | | | |
| Main Hall - Bottom floor portion | 16,200 | 11,670 | (e) area | (e) area | · · |
| - Used as competition athletic court | | | | | movable audience chairs |
| with surrounding seating in bleachers | | | | | 0 11 11 11 11 11 11 |
| and loose seats - Flat floor used for additional | | | | | Seating on entire flat floor> 1,265 movable chairs/ADA spots |
| audience seating | | | | | Chairs/ADA spots |
| FUD Offices | | | 925 | 1,000 | |
| | | | | 1,000 | |
| Community Room | | | N/A | 3,400 | |
| Commercial Kitchen | | | N/A | 890 | |
| Public Restrooms - Men | 360 | 190 | 809 | 911 | SF listed is the total of 3 rooms |
| Public Restrooms - Women | 360 | 140 | 985 | 956 | SF listed is the total of 3 rooms |
| Public Restrooms - Gender Neutral | | | 236 | 227 | SF listed is the total of 3 rooms |
| Concession | 180 | 190 | 394 | 394 | SF listed is the total of the 2 circular spaces in the |
| | | | | | lobby - |
| | | | | | Size matches original design |
| Ticket Booth | 100 | - | 290 | 290 | Size matches original design |
| Lobby | 1,000 | 570 | (e) area | (e) area | |
| Support Space | | | | | Per design |


| D | Dedicated Theatrical Program | | | | | | |
|---|------------------------------|--|--|-------|-------|--------------------------|--|
| | Stage | | | 4,588 | 4,970 | (e) stage area = 5,090sf | |
| | Theatrical Dressing | | | 2,171 | 2,171 | | |
| | (RR's, showers, changing) | | | | | | |
| | Stagecraft and Storage areas | | | 1,200 | 2,120 | | |


| Wrestling Room | 5,000 | 5,000 | 4,130 | 5,000 | 3/30/23 mtg: Accommodate in Civic Aud. Site |
|--|-------|-------|-------|-------|---|
| Athletics (Weight/Fitness) Room | 3,000 | 3,700 | 3,000 | 3,000 | 3/30/23 mtg: Accommodate in Civic Aud. Site |
| Athletic Trainers' Room | 1,000 | 350 | 400 | 400 | 3/30/23 mtg: Larger one will be at SaMoHi; this smaller one will serve the Civic. |
| Basketball Team Locker Room - Girls | 500 | 1,450 | 1,700 | 2,663 | 3/30/23 mtg: 60 athletes simultaneously |
| Volleyball Team Locker Room - Girls | 500 | - | | | 3/30/23 mtg: 45 athletes simultaneously in 3 team |
| Wrestling Team Locker Room - Girls | 150 | - | 600 | | 3/30/23 mtg: 15 athletes simultaneously |
| Basketball Team Locker Room - Boys | 600 | 2,150 | 1,700 | 2,771 | 3/30/23 mtg: 60 athletes simultaneously |
| Volleyball Team Locker Room - Boys | 500 | - | | | 3/30/23 mtg: 45 athletes simultaneously in 2 team |
| Wrestling Team Locker Room - Boys | 600 | 350 | 1,000 | | 3/30/23 mtg: 60 athletes simultaneously |
| All-gender student locker/changing space w/RR & Shower | | | 550 | 250 | Scheme 1: 250 sf on 1st floor, 300sf on 4th floor |
| Coaches Locker/Shower Room - Men | 220 | 150 | 400 | 750 | |
| Coaches Locker/Shower Room - | 220 | 170 | | | |
| Coaches Locker/Shower Room - Gender Neutral | | | | | |
| Coaches Offices | 1,000 | 810 | 600 | 1,000 | Shared by Basketball, Volleyball, Wrestling Space should contain both private & shared office space |
| Officials Changing Room | 70 | - | 140 | 140 | Lockers and changing area only, no RR |
| Visiting Team Locker Room - Boys | | | 350 | 450 | 80 lockers (40 2-tier units), shower and restrooms |
| Visiting Team Locker Room - Girls | | | 350 | 450 | 80 lockers (40 2-tier units), shower and restrooms |
| Basketball & Volleyball Storage | 600 | 410 | 600 | 663 | |
| Wrestling Storage | 500 | 270 | 500 | 500 | |
| Color Guard Storage | 100 | 50 | 139 | 139 | |
| Central Storage/Distribution | 1,000 | 1,850 | 1,003 | 1,003 | |
| Laundry Room | 80 | - | 150 | 150 | |

The spaces below from the space program for SaMoHi's Blue Gym were deemed unnecessary for the Civic Auditorium site - 3/30/23 mtg.


| Academic Center | 400 | - | - | 3/30/23 mtg: N/A for Civic Aud. Site |
|-------------------------------|-------|-------|---|--|
| Multipurpose Room | 1,600 | 430 | - | 3/30/23 mtg: N/A for Civic Aud. Site |
| Golf Team Locker Room - Boys | 150 | - | - | 3/30/23 mtg: N/A for Civic Aud. Site |
| Golf Team Locker Room - Girls | 150 | - | - | 3/30/23 mtg: N/A for Civic Aud. Site |
| Shower Room - Boys | 930 | 1,680 | N/A (Showers inside locker rooms) | 3/30/23 mtg: 165 male athletes total If showers are included in individual sport locker rooms then separate shower rooms are not needed. |
| Shower Room - Girls | 930 | 1,340 | N/A (Showers inside locker rooms) | 3/30/23 mtg: 120 female athletes total If showers are included in individual sport locker rooms then separate shower rooms are not needed. |












VOLLEYBALL COMPETITION COURT LAYOUT

Scale: 1/32" = 1'-0"





3.1.3 PARKING



3.1.4 CITY OF SANTA MONICA REGULATIONS

Α.

Part of the negotiation between the City and the District is to establish what regulations will need to be enforced for the property that will be transformed to a multi-use arena and be used by school-aged students. The Division of State Architect will have jurisdiction and determine that appropriate changes are required to meet the Field Act and ensure the safety of the occupants.

B. Local Coastal Program

The Local Coastal Program (LCP) Land Use Plan was updated in 2018 and aligns with the City's policies related to mobility, sustainability and adaptation to sea lever rise, as required by the coastal commission guidelines.

These regulations are for new or changed uses of land and water. The Civic Auditorium is located within the Coastal Zone, although it will not be new or be a change of land use, the Coastal Commission will review any changes for consistency with the Coastal Act requirements.



C. Specific Plan

The proposed improvements to the Civic Auditorium are in line with the City of Santa Monica Civic Center Specific Plan. In the Specific Plan it states that improvements and an expansion will be made to the landmark building. Priority is to be given to cultural, educational, and community oriented activities.

D. The City of Santa Monica Planning Department will enforce land use and development policies, the zoning ordinance, urban design policies, and historical preservation. It is responsible to develop City policies and plans such as the Local Coastal Program and Landmarks Ordinance.



In concept, Scheme 1 inserts more program into the existing Auditorium building. In considering the total constellation of proposed uses, this scheme proposes a coexistence of uses. It imagines the primary use of the site is for athletic uses. It imagines that a full fly tower for theatrical rigging and equipment may be exceeding its likely best use. Therefore, part of the fly tower is then leveraged for athletics uses. Specifically, this scheme envisions wrestling and wrestling related facilities in the upper portion of the tower.

The existing Auditorium is renovated for multiple uses. It is envisioned that the Auditorium could house a variety of performances from drama, to music, to other student events. Theatrical equipment using a reduced fly tower would be required. Other required renovations typical of either scheme are included elsewhere in this report.

The Committee Rooms and the Administration are two structures along the east and west sides of the main Auditorium building. These structures are used in Scheme 1 to house additional athletics programs. The Committee Rooms is proposed to house home team lockers and coaches' spaces. The Administration is proposed to house visiting team facilities and additional public restrooms. New construction is limited to area needed for a fitness / training room at the south side of the property facing Pico Boulevard.

3.2.2 NARRATIVES

This narrative describes the interior improvements proposed in Scheme 1. The recommended upgrades to the exterior can be found in the Existing Assessment section of the report (2.1).

Architectural proposed improvements to the Civic Building

A. Auditorium

- i. Tilted floor converted to Competitive Gym Floor
 - a. The District would like a hardwood sprung flooring system permanently installed on the tilted floor. The floor will be fixed in its' flat position. The mechanism that permits it to tilt will be preserved to allow future use if desired. The Basis of Design for the wood flooring is Robbins Bio Channel Classic or Air Channel Star installed over 2x4 sleepers. The hardwood sprung flooring system would also be installed at the fixed areas between the tilted floor and the existing Administration and Committee Building wings. The flooring system would have integrated recessed fixed anchors for netting posts. To protect the hardwood sprung flooring system when not used as a competitive gym, the team recommends adding a floor cover tile. The Basis of Design is Covermaster Platinum Covertile (1m x 2m carpet tiles) and a storage cart. The tiles can be installed by a single person.
 - b. Moveable basketball goals would be provided at each end.
 - Addition of retractable portable bleacher seating located near the orchestra lift.
 Basis of Design: Irwin seating telescopis bleacher: Versatract retractable seating.
 Total seating count 220.
- ii. Fixed seating
 - a. Replace existing fixed seating with new. See the theatrical narrative for further information.
- iii. Provide multiple accessible seating options.
 - a. Replace the first row of fixed seating with a balcony allowing for accessible seating and companion seating with a guard rail around the perimeter of the balcony. Refer to the floor plan for the layout.
 - b. Provide accessible seating off the Concourse level. A balcony with guard rail similar to the one at the first row would be installed at the center of the top row of seating to accommodate accessible seating and companion seating. Refer to the floor plan for the layout.
- iv. Preserve the existing solid metal and perforated metal acoustic wall panels
 - a. The metal panels are character defining features. The recommendation is to add an acoustical curtain in front of them. Refer to the Acoustical Narrative for additional information. The existing wall area below the metal panels would receive wall padding or protective cladding to protect the athletes.
- Replace existing plaster auditorium ceiling with a new acoustical gypsum ceiling over the fixed seating area. Refer to the Acoustic Narrative for additional information.
 Provide new sports lighting and general lighting.

B. Stage

- Replace the existing counterweight rigging system with a motorized rigging system including lighting.
- ii. Provide a new fire curtain system
- iii. Provide an acoustic proscenium curtain deployable during sporting events
- iv. Refinish existing pine floor on stage.
- v. Provide new orchestra pit and stage lifts.

C. Lobby

- i. Stairs #1 and #2 are character defining features in the building. Stairs to be retrofitted to include new handrails on each side and height extension to guard rail throughout. Refinish and seal all materials.
- ii. Concessions As noted in the existing assessment, the team recommends building new concessions to remember the original ones but with contemporary amenities. Wood casework with solid surface finishes, point of sale (include data), and display areas. Provide power and sewer/water connection to serve refrigeration and freezer.
- iii. Reflecting Pool The reflecting pool and railing are no longer present on site. The team recommends a mosaic tile in the former location of the reflecting pool.
- iv. Elevator A 2 stop hydraulic elevator is proposed for the northwest corner of the lobby to provide accessible travel between the 1st floor lobby and the concourse above.
- v. Lift A 2 stop wheelchair lift is proposed to provide accessible travel between the concourse level and the Control Room above. By utilizing a lift instead of an elevator for this access there is no need to penetrate the Auditorium's domed roof.
- vi. Ceiling Replace the existing ceiling with an acoustical ceiling tile. The Basis of Design: Fine fissure mineral wool ceiling ACT and LED fixtures similar in size and finish to the existing light fixtures.

D. Basement

- i. The team recommends replacing the existing double doors to the Orchestra Lift with new double doors.
- ii. Locate storage rooms in the basement level along with the space and infrastructure for a new stage lift and orchestra pit lift.
- iii. The team recommends adding a viewing area at the current entrance to the tilt floor area. The viewing area would let visitors see the hydraulic mechanism and the framing of the tilted floor. There could be an exhibition area to display photos, drawings, and concert memorabilia and other collectibles. It will require excavating some of the unexcavated areas to allow for a larger, accessible view area and glass viewing wall. Visitors could walk into the tilted floor area as part of a guided tour.

E. Wrestling facilities

- i. A wrestling practice room, storage and locker rooms, and a team huddle interior/exterior space are located on two new floors (4th and 5th) in the top portion of the former fly space of the Stage. The 5th floor houses the wrestling practice room and storage, while the 4th floor houses the wrestling locker rooms, more storage and a team huddle area. The wrestling practice room can house 6 practice areas and 2 full size wrestling areas.
- ii. Windows would be added to the south side of the Stage/Fly space walls at both the 4^{th} and 5^{th} floors. Additionally, a rooftop lounge extends the team huddle space to the outdoors.
- iii. Lockers The breakdown of locker rooms, fixtures and finishes is shown below
 - a. Female Wrestling Lockers
 - (10) 2 tier lockers (20 lockers total) and changing areas with accessible benches.
 - 2. 3 showers (1 of which is accessible)
 - 3. 2 lavatories (1 of which is accessible)
 - 4. 3 Water closets (1 of which is accessible)

- b. Male Wrestling Lockers
 - (30) 2 tier lockers (60 lockers total) and changing areas with accessible benches.
 - 2. 6 showers (1 of which is accessible)
 - 3. 3 lavatories (1 of which is accessible)
 - 4. 2 water closets (1 of which is accessible) & 1 accessible urinals
- c. Gender Neutral Wrestling Lockers
 - (3) 2 tier lockers (6 lockers total) and changing areas with accessible benches.
 - 2. 1 accessible shower
 - 3. 1 gender neutral restroom (water closet and lavatory)
- iv. To access these new floors, two new stairs and a freight elevator are added.
 - **a.** One stair and the freight elevator would be added to the east wing of the stage. This stair and elevator would go from the basement up to the 5th floor where the Wrestling practice room is located. Both the stair and elevator would be accessed from the east side only at the stage level to prevent someone from entering the stage during a practice or performance.
 - b. The second stair would be located in the area south of the stage. It would go from the ground floor up to the 5^{th} floor. The stair tower would be visible from the exterior at the 4^{th} and 5^{th} floors.
- F. FUD Offices The FUD offices would be located to the west of the stage/fly space and would have a separate entrance. A new accessible ramp and stairs would be added. The breakdown of offices include 3 enclosed offices @ 150 sf each and 6 workstations @ 75 sf each. The floor to floor would be approximately 25' o" high.
- G. Committee Building Wing The Committee Building Wing is reconfigured to house student locker rooms for basketball and volleyball, coaches lockers and offices and support space.
 - i. Storage Overhead coiling door at least 8' clear height or minimum height required to accommodate moveable basketball goals.
 - ii. Student Locker Rooms
 - a. Female Student Lockers
 - ((55) 2 tier lockers (110 lockers total) and changing areas with accessible benches.
 - 2. 6 showers (1 of which is accessible)
 - 3. 3 lavatories (1 of which is accessible)
 - 4. 4 water closets (1 of which is accessible)
 - b. Male Student Lockers
 - ((55) 2 tier lockers (110 lockers total) and changing areas with accessible benches.
 - 2. 6 showers (1 of which is accessible)
 - 3. 3 lavatories (1 of which is accessible)
 - 4. Male 2 water closets (1 of which is accessible) & 2 urinals (1 of which is accessible)
 - c. Gender Neutral Student Locker
 - (3) 2 tier lockers (6 lockers total) and changing areas with accessible benches
 - 1 accessible shower
 - 3. 1 gender neutral restroom (water closet and lavatory)

- Coaches Lockers (separated into multiple spaces as needed)
 - a. (6) 2 tier lockers (12 lockers total) and changing areas with accessible benches.
 - b. 2 accessible shower
 - c. 2 single occupancy restrooms (water closet and lav)
- iv. Coaches Offices A mix of private offices and open workstations including built in casework
- v. Team Huddle
 - a. Flat screens/digital display, trophy exhibit wall. Include wood specialty suspended ceiling.
 - b. Provide new storefront glazing in (e) concrete.
- H. Administration Building wing The Administration Building Wing is reconfigured to house public restrooms, Visiting Team Locker Rooms and an Officials' Changing Space.
 - i. Public Restrooms
 - a. Men's Restroom
 - (2) water closets (1 of which is accessible)
 - 2. (2) urinals (1 of which is accessible)
 - 3. (3) lavatories ((1 of which is accessible)
 - b. Female's Restroom
 - (4) water closets (1 of which is accessible)
 - 2. (3) lavatories ((1 of which is accessible)
 - c. Single User Restroom
 - (1) accessible water closet
 - 2. (1) accessible lavatory
 - ii. Visiting Team Locker Rooms
 - a. (40) 2 tier lockers (80 lockers total) and changing areas with accessible benches
 - b. Both genders 4 showers (1 of which is accessible)
 - c. Both genders 2 lavatories (1 of which is accessible)
 - d. Female 3 water closets (1 of which is accessible)
 - e. Male 2 water closets (1 of which is accessible) & 2 urinals (1 of which is accessible)
 - iii. Officials Changing Area
 - a. (3) 2 tier locker (6 lockers total) and changing areas with accessible benches
- 2. New Athletics Building -
 - A. 3,400 SF, 18' o" high floor to floor steel framed structure to house the weight/fitness classroom and athletic trainers room.
 - i. Exterior finish cement plaster.
 - ii. Interior to include 2 sinks and 2 drinking fountains w/ bottle fillers.
 - iii. Interior finishes as appropriate for high school fitness.
- 3. Proposed Finishes throughout project include:
 - A. Bathrooms / athletic locker rooms / theatre bathrooms
 - i. Ceramic tile floor, sloped to floor drain
 - ii. Ceramic tile wall, full height
 - iii. Phenolic partitions
 - iv. Bobrick accessories as Basis of Design

- v. All lavatories in solid surface counters w/ full wall mirrors above (wall hung lavatories in locker rooms)
- vi. Air hand dryers throughout
- B. Coaches offices
 - i. LVT floor throughout
 - ii. Painted gypsum walls, level 5 finish
 - iii. Doors will sidelights in storefront frame
- C. FUD offices
 - i. Carpet tile in private offices & LVT in share spaces
 - ii. Painted gypsum walls, level 5 finish
 - iii. Doors will sidelights in storefront frame
- D. Storage rooms
 - i. Abuse resistant gypsum walls
 - ii. Sealed concrete floors
- E. Officials Changing room
 - i. Abuse resistive gypsum walls
 - ii. LVT flooring
 - iii. 3 full height lockers
- F. Ceilings Mineral Wool ACT throughout, U.N.O.
- G. Walls Level 5 gypsum board finish with wall base throughout, U.N.O.
- H. Floors All exposed concrete floors to be refinished

2. Civil Proposed Improvements

Α.

The civil scope of work for Scheme 1 is outlined in the subsequent categories, taking into consideration the site modifications recommended.

B. Proposed Conditions

i. Grading

Walks, stairways, ramps, and other surfaces will be sloped away from buildings. Typical slope planes for drainage shall be between 1% and 2%. Other slope standards include the following:

- a. Within building areas: 1.5% 2%
- b. Plazas and terraces: 2% maximum.
- c. Entrance walks and ramps along path of travel: 5% max (8.33% with handrail)
- d. Non ADA parking stalls and drive aisles: 5% max
- e. Planted slopes: 50% maximum.
- f. Lawn areas: 15% maximum.

ii. Erosion and Sediment Control

In accordance with the National Pollutant Discharge Elimination System (NPDES) permit, the construction site shall implement Best Management Practices (BMPs) to control erosion, debris, and construction related pollutants. BMPs include, but are not limited to, gravel bags and fiber rolls for perimeter control, stabilized construction entrances as tracking control, and stockpile management in accordance with good housekeeping practices. All existing catch basins shall be protected per standard plan SE 10 to minimize sediment clogging the utility system. If the project will disturb more than one acre of land, a Storm Water Pollution Prevention Plan (SWPPP) will need to be filed with the California State Water Resources Control Board. Assuming all existing pavement area will be replaced, the total area to be disturbed for this scheme will be close to one acre and a SWPPP may be required.

iii. Storm Water Management

The understanding at the time this report was written is the State Water Resources Control Board has not issued a General Permit for the Discharge of Storm Water from Small MS4s (WQ Order No. 2003 0005 DWQ) to provide permit coverage for K 12 Schools. Therefore, post construction stormwater management will have to follow requirements from the SWPPP if the total disturbed area is more than one acre and Post-Construction Water Balance Performance Standard Spreadsheet will have to be filled out. If the total site runoff volume has been increased, post construction best management practices such as porous pavement, tree planting, swales or rain barrels will have to be installed to offset. For this scheme, it is not anticipated that the runoff volume will increase as the total impervious area for the project will remain the same (assuming the new 3,000 sq.ft building addition along Pico Boulevard will be located within the exiting asphalt pavement and existing planted area will remain) and no post construction stormwater management will have to be implemented.

However, if SMMUSD would like to follow the City of Santa Monica Storm Water Management requirements, they are more stringent as the storm water volume to be mitigated is based on the total impervious area of the project (existing and proposed). Based on the City of Santa Monica Urban Runoff Drainage Plan Worksheet, about 6,500 cubic feet of storm water will have to be mitigated for Scheme 1. Based on the preliminary geotechnical report from Willdan dated July 5, 2012, infiltration does not seem feasible. A capture and reuse system with an underground cistern and a pretreatment system will then have to be installed to store the storm water volume to be mitigated. A pump located inside the cistern will feed the irrigation system for all the project planted areas.

iv. Storm Drainage

New site storm drain system with underground piping and drain inlets will have to be installed to capture the site storm drain runoff and avoid any sheet flow to the public sidewalk. If a cistern for capture and reuse is installed, the runoff will be directed to the underground cistern for future irrigation use. Overflow will be directed to the street curb via new curb drains under public sidewalk.

It is also recommended to replace the existing 8" underground storm drainpipe picking up the building roof drains at the southwest corner of the building and flowing to the street curb on Main Street if the roof runoff from the existing Civic Auditorium does not need to be mitigated with a capture and reuse system.

The storm drain lines for the project will be Heavy Wall PVC SDR.35 ASTM D3034 pipe and fittings with Bell and Spigot gasket joints.

v. Sanitary Sewer

It is recommended to replace the existing site sewer system as it is likely reaching the end of its lifespan. New sewer connection(s) will be provided to serve the new building addition and will join the site sewer system.

Sewer report with sewer manhole monitoring data may have to be submitted to the City of Santa Monica if the project will increase the current sewer load.

The sewer lines for the project will be Heavy Wall PVC SDR.35 ASTM D3034 pipe and fittings with Bell and Spigot gasket joints.

vi. Domestic and Fire Water

It is recommended to replace the existing site domestic and fire water systems as they likely are reaching the end of their lifespans. New water connections will be provided to serve the new building addition.

Water report may have to be submitted to the City of Santa Monica if new connections to the water city mains are required for the project.

Four existing fire hydrants are located in the vicinity of the project, two are located on Main Street on the project side and two others are located at the intersection of Pico Boulevard and Third Street and at the intersection of Main Street and Pico Boulevard across the street. Additional fire hydrants may be required for the project, and this should be confirmed by the Division of State Architect and possibly the City of Santa Monica Fire Department.

vii. Public Right Of Way Improvements

The existing sidewalk along Pico Boulevard has an uneven surface and is not in good condition mainly because of private and public trees and should be repaired. The City of Santa Monica may require the existing curb ramps on Main Street to be renovated and meet the current City standards. New driveway apron(s) may have to be installed to serve the project. All work within the public right-of-way will require a separate offsite improvement permit with the City of Santa Monica.

3. Landscape Proposed Improvements

A. From a landscape preservation perspective, this scheme represents the option that least impacts the original landscape design by only adding a small new structure to the Pico Boulevard side (or back of house). The original landscape design has already been removed here (the Pico Boulevard side of the property), in part due to new infrastructure (chillers) and utilities (electrical substation) sited here.

Because this scheme is least invasive to the original landscape, restoring the original long, linear planted area outside the Committee Building wing would help return this terrace to its former intent. Additionally, materials that mimic --or pay homage--to the brise soleil façade could help stitch this terrace space to the front entrance.

In addition to restored elements, this scheme offers larger opportunity areas to enhance the site overall with new program areas, improved access, and more climate adapted planting.

4. Structural Proposed Improvements

A. Building Modifications

There are two schemes being considered for the renovation and conversion of this building to a public school building. Scheme 1 primarily consists of the addition of two floor levels to accommodate the athletic wrestling functions within the existing stage tower. A new rooftop lounge area will also be constructed and will be accessible from the new lower wrestling floor level. The existing one story buildings on the east and west of the auditorium will remain and be renovated to accommodate other school functions.

B. Impact of Proposed Alterations

Scheme 1: The new floor levels at the stage tower will consist of steel framing with metal deck concrete fill. New columns and strengthening of the concrete columns is expected to be required to support the new loads from these floors along with new pile foundations. The floors will be tied to the existing stage tower walls and will require additional shotcrete or FRP on the existing walls to accommodate the new lateral forces from these floors. The new lounge area is also expected to consist of steel framing with metal deck concrete fill. At the east and west edge of the new lounge area, new shear wall elements will be required. The north and south ends of the lounge area will be tied to the existing walls that will receive new shotcrete for extra strengthening. New stairs and elevators will be required to access the two new floors in the stage tower. A new shear wall is anticipated to be required at the east end of the stage tower next to the stair and elevator on the wrestling floor area side of the stair. New shear wall will also require a new pile foundation.

Integration of any shear walls will be studied and located to ensure that the significant historical features of the building are not affected.

The existing main floor will be locked in the flat position using bolted connections that will not affect the hydraulic mechanism allowing the tilting mechanism to be used if that is desired in the future.

Provisions will be made to allow for a portion or portions of the stage to rise above the existing stage line and the orchestra pit will be re built.

5. Mechanical Proposed Improvements

- A. Scheme 1 mechanical recommendations are outlined in this section.

 As noted previously, most of the existing equipment is past or approaching its life expectancy and will need to be replaced.
 - i. Provide new 4-pipe AHU to provide space conditioning, humidity control, and ventilation to the wrestling rooms located on the 5th floor. AHU will be connected to chiller and boiler plants, and integrate into building control system. Equipment to be located on existing 4th floor roof or additional mechanical room on the 5th floor.
 - ii. Provide new 4-pipe AHU to provide space conditioning, humidity control, and ventilation to the locker rooms and rooftop lounge located on the 4th floor. AHU will be connected to chiller and boiler plants, and integrate into building control system. Equipment to be located on existing 4th floor roof or 3rd floor mechanical room if space allows.
 - iii. Provide inline exhaust fans and new ductwork to the building exterior for wrestling locker room additions to the 4^{th} floor. Fans should be located above the ceiling of the rooftop lounge to allow for access.
 - iv. Provide roof mounted exhaust fans for additional lockers and restrooms in the admin offices on the 1st floor.
 - v. Replace air handling unit S-1 and resize based on new space usage of the current admin area. New unit will be connected to chiller and boiler plants, and integrate into building control system. Provide VRF system for new FUD offices on the 1st floor. Each office should have its own fancoil unit with individual control for occupant comfort. Condensing unit to be mounted at grade near additional stair.
 - vi. Provide DOAS system for ventilation and dehumidification of new FUD offices, installed in ceiling space above offices with new ducts to the exterior and louvered intake / exhaust.
 - vii. Replace air handling unit S-2 and resize based on new space usage of the East Room. New unit will be connected to chiller and boiler plants, and integrate into building control system.
- viii. Provide new roof mounted exhaust fans for locker rooms going in the East Room.
- ix. Replace existing air handling units S-3,S-4,S-5 serving the auditorium and dressing room spaces. New units should have similar footprint and fit in existing fan rooms.
- x. Replace existing air handling units S-6 serving the lobby and concourse area. New units should have similar footprint and fit in existing fan room.
- xi. Replace all ductwork, hydronic piping, and controls associated with existing air handling units.
- xii. Replace existing air-cooled chiller, resized to meet load requirements of additional spaces on the 4^{th} and 5^{th} floor. Heat exchanger, glycol management system, and piping

- should also be resized and replaced. Equipment to be located in existing mechanical rooms open roof on the $3^{\rm rd}$ floor.
- xiii. Replace existing chilled water pumps with variable speed models, VFDs and new controls.
- xiv. Relocate existing thermal energy storage system as needed and connect new piping and controls to new chiller system.
- xv. Replace existing heating hot water boilers with high efficiency condensing type boilers.
- xvi. Replace existing heating hot water pumps with variable speed models and VFDs and new controls.

6. Electrical Proposed Improvements

- A. Scheme 1 Electrical recommendations are outlined in this section.

 Although sufficient power has been identified, the current panels and controls need to be replaced to meet current codes and needs.
 - i. Upgrade all lighting to LED fixtures throughout the entire building.
 - ii. Add Title 24 code compliant interior controls to all the spaces. This includes dimming capabilities, occupancy controls and daylighting in the rooms with adequate fenestration.
- iii. Add Title 24 code compliant exterior controls to all the exterior fixtures. This includes photocells and an astronomical time clock, as well as dimming for parking lot lighting.
- iv. Replace all Zinsco distribution panels throughout the space. This replacement should include the feeders feeding the distribution panels as well.
- v. Replace the original 208V Zinsco distribution boards in the main electrical room.
- vi. Replace MCC1 and MCC2 with distribution boards. Add separate motor starters or VFDs as needed to control equipment. Coordinate with Mechanical and Plumbing for exact needs.
- vii. Update receptacles to GFI protected receptacles as required by code. This is required for most of the restrooms, janitors' closets, and kitchen spaces.
- viii. Upgrade the emergency generator to a 150kW unit and the ATS to a 400A rating.
- ix. Provide space for new elevator machine rooms to serve elevators, estimated space required, 40 sq. ft each. Provide disconnect and panel in the room to serve elevator loads.

7. Plumbing Proposed Improvements

- A. Scheme 1 Plumbing recommendations are outlined in this section.
 - i. Provide lead free isolation valves on laterals connected to mains.
 - ii. Provide water hammer arrestors on cold water headers connected to flush valves serving water closets and urinals. Install behind access panels.
- iii. Replace the central domestic hot water boiler and storage tank serving the auditorium as this equipment has reached its useful life.
- iv. Provide a re circulation system consisting of a pump, return piping, aquastat, and timeclock to ensure proper hot water delivery to fixtures. Where sub loops are created, balancing valves shall be provided on each lateral to balance the system.
- v. Provide insulation with appropriate thickness on the hot water supply and return distribution piping.
- vi. Provide code required anti scald tempering valves on the hot water systems.
- vii. Provide trap primer valves to serve floor drains and sinks in seldom used areas.
- viii. Replace all galvanized domestic water piping with copper.
- ix. Replace all sewer waste (gravity) piping with cast iron with no hub couplings. Piping within the kitchen may contain grease buildup due to the lack of grease waste separation.
- x. Lavatory drains, supply, and stop assemblies of ADA compliant lavatories in the restrooms were not covered with protective insulation. Protective insulators shall be provided.
- xi. The drinking fountain exhibits aging, wear, and tear, and should be upgraded to a hi-lo type with hands free bottle fillers.
- xii. Hose bibbs in public restrooms are not equipped with code compliant vacuum breakers. Replacing the fixture with a recessed type with a box and locking cover, and an integral vacuum breaker is recommended if the walls will be re tiled. Otherwise, vacuum breakers shall be provided at existing surface mounted hose bibbs to be code compliant.
- xiii. Provide a seismic valve (earthquake valve) on the natural gas assembly to comply with local codes and amendments.
- xiv. Replace all plumbing fixtures with high efficient fixtures. The performance (flow rates) of existing are no longer code compliant. Flow rates for new fixtures shall not exceed:
 - a. Water closets @ 1.28 GPF.
 - b. Urinals @ 0.125 GPF.
 - c. Lavatory faucets @ 0.35 GPM.
 - d. Sink faucets @ 1.5 GPM.

8. Fire Protection and Fire Alarm Proposed Improvements

- A. Scheme 1 Fire Alarm recommendations are outlined in this section. New equipment and systems are being proposed.
 - i. Provide a new backflow preventer assembly on the original connection to the building.
 - ii. Provide a new fire water branch connection with PIV to the athletics buildings.
- iii. Provide a new Class I standpipe system at the two new staircases connecting from the basement through the 5th level.
- iv. Provide sprinklers in stage, seating, and wooden warehouse areas with an occupancy classification of Ordinary Hazard II, and main entrance overhang with an occupancy classification of Light Hazard.
- v. Provide sprinklers throughout every new area, including the new athletics building, combustible concealed spaces, and spaces above ceilings used as a plenum.
- vi. Provide sprinklers under the obstruction in the lobby.
- vii. Replace all corroded, painted, and outdated sprinkler heads.
- viii. Connect the existing hose connections located in the stage area to the fire protection system.
- ix. Replace the existing fire alarm system to provide smoke/heat detectors throughout the new and existing buildings. Complement with total coverage of speaker strobes.

g. Technology Proposed Improvements

- A. Scheme 1 Technology recommendations are outlined in this section.
 These improvements will be aligned with functions identified in the theatre section of the report.
 - i. Dedicated signal rooms shall be provided at the north and south ends of the building to feed end user data, voice, and Wi Fi systems. These rooms shall be of a minimum of 10 feet by 10 feet in size. One room will serve as the MDF and MPOE. The other room shall be an IDF room fed with fiber and copper backbone from the MDF/MPOE.
 - ii. Floor mounted data racks shall be installed to house network equipment.
- iii. Security systems shall be replaced with current technology and SMMUSD design standards. Keypads and access control shall be provided at entry points. Motion sensors shall also be provided where there is access from the outside.
- iv. A CCTV system is recommended to provide monitoring of the premises. These cameras will be POE powered from the POE switches. A dedicated AV Control Room shall be provided to house the AV system equipment. A projector and projector screen shall be provided with speakers and wireless microphones. An assistive listening system shall be provided to comply with the ADA code. The design for the system shall be per current technology and SMMUSD standards.

10. Acoustic Proposed Improvements

A. Basis Of Acoustical Recommendations

Based upon the review of the District's desired uses of the facility, it is understood that the main volume (gym/auditorium/stage) will need to provide suitable acoustics for multiple functions including athletic/gym type usage, gatherings and performances. It is the team's understanding, that orchestral performance is not a priority usage. Also, because of the large size of the auditorium, it is not considered reasonable to attempt to design this space for non-amplified voice. This is because a speaker or actor located on the stage would be so far from the rear seats that microphones and electronic sound amplification will inevitably need to be used in this space for voice. Because the space will be designed for use with an audio system, for speech intelligibility and clarity of sound it is important to control the reverberation time within the space.

This desire for reverberation control, however, needs to be balanced against practical considerations and the significant potential cost of acoustical treatment and potential conflicting requirements of a gymnasium space (which include a need for wall padding for safety and durability of other finishes). Due to the large volume of the main auditorium, the highly durable finishes generally required for indoor sports facilities, and the activities usually taking place within the buildings, some sound reverberation and the associated build-up of noise in these types of spaces is almost inevitable. On this basis, the team would note that it is not considered practical to acoustically optimize the space either for *Movie Presentations*, or as a *Sound Stage* for production of film/TV etc.

With consideration to sound isolation of the building envelope, given that the primary usage of the renovated facility would be for sports activities and given the high cost of achieving high levels of sound isolation for the envelope of such a large volume space, (the sound isolation of the envelope is only as good as the 'weakest link' and additional cost would therefore be incurred for a heavier roof, upgrades to all exterior doors, acoustical treatment at all duct penetrations, amongst other measures) the team has NOT incorporated recommendations to achieve high levels of sound isolation for the building envelope. So in this respect, the post-renovation facility would not achieve the same acoustical quality as a state-of-the-art dedicated 'sound stage' if used for TV/Film production.

Finally, it should be noted, that the recommended NC-30 HVAC noise criterion is higher than would typically be expected for a dedicated Sound Stage.

In summary, by incorporating the acoustical recommendations below it should be possible to use the space, post-renovation, for all the District's listed uses, however, it is not considered practical/economical to achieve state-of-the art acoustical movie theater and/or sound stage standards for this facility.

B. Auditorium & stage room acoustics

i. Recommended Reverberation Time Target for Auditorium and Stage
The most basic method to quantify the acoustical characteristics of a space is by considering
'reverberation time'. In approximate terms, this is the length of time a loud sound will take to
decay to an inaudible level in the space. With reference to Figure 1 below, (which is presented
for illustrative purposes only) it can be seen that the optimum reverberation time for a space,
depends upon the specific usage. In particular, speech and electronically amplified sound

benefit from a low reverberation time and symphony orchestra benefits from a longer reverberation time (ideally 1.8 to 2.2 seconds for a symphony hall).




Figure 1. Optimum mid frequency reverberation time for various functions. Reproduced from "Music Facilities: Building, Equipping and Renovation" Harold P. Geerdes, published by Music Educators National Conference.

For spaces with a reverberation time exceeding approximately 2.5 seconds, (as is currently the case) noise from typical activities within the space starts to become unpleasant, and achieving even moderate degrees of speech intelligibility becomes difficult. While there is no industry standard, typical recommendations for mid-frequency reverberation time in indoor sports facilities range anywhere from 1.5 seconds to 2.5 seconds. The lower end of this criteria range is typically reserved for spaces where achieving reasonably high levels of speech intelligibility is important, such as teaching facilities and sports hall that have other uses including performances and gatherings, such as graduation ceremonies. On this basis, the team recommends a target maximum mid-frequency reverberation time of 1.5 seconds. A concept for achieving this is described below.

- i. Recommended Acoustical Design Concept for Main Auditorium Finishes
 - Auditorium Ceiling
 Given its large area, the ceiling plane is the most important surface for controlling reverberation.

It is proposed that the existing ceiling will to be removed over most of the auditorium area to facilitate installation and use of a new production grid. It is understood that the roof will be replaced, the team recommends that the replacement roof over the auditorium should use acoustical deck. The final acoustical deck type will be subject to structural coordination. The acoustical preference is to use an acoustical with a minimum NRC o.g acoustical rating manufactured by Epic Metals.




Photo 1: Acoustical Deck

As an alternative to acoustical deck, in the auditorium area where the suspended ceiling is to be removed, the underside of the roof structure could be treated with 1" thick Tectum, with 1" min. thickness acoustical insulation above. Please note that the Tectum can be painted without significantly degrading its acoustical performance, subject to following manufacturer's recommendations.

Tectum

Contact: Stacy Martin at Armstrong

Phone: (717) 396-4783

Email: SWMartin@armstrongceilings.com

Website: https://www.armstrongceilings.com/commercial/en-ca/articles/tectum-part-of-armstrong-


portfolio.html



Photo 2: Tectum Ceiling

In this auditorium ceiling zone without a suspended ceiling, it is strongly preferred acoustically that there should be no deep beams, especially running parallel to the front of the stage (open trusses are preferred).

Above the existing raked seating at the rear of the auditorium, it is understood that a new suspended/shaped ceiling will be installed that will be visually similar to the existing ceiling in this area. Acoustically it is recommended that this ceiling should be acoustically absorptive. Assuming that this ceiling area would not be expected to be subject to high impact, USG's Ensemble Acoustical Drywall System is recommended, specified with USG High-NRC Backer Panels to provide NRC o.8 minimum for the installed system. If high impact is anticipated, a suspended Tectum Finale system, specified for minimum NRC o.9 could be considered, however, this material would not be visually similar to the existing ceiling.



a. Acoustical Wall Panels

The existing metal acoustical wall panels in the Auditorium are not acoustically effective. It is recommended to replace all existing metal wall panels with new, more effective perforated metal acoustical panels. This should have 2" min. acoustical backing (3" preferred) and provide NRCo.g minimum acoustical performance. The metal perforation should have 18% min. free area. Careful consideration will be required in the detailing and installation in order to minimize rattling in response to acoustical excitation.

Suppliers of perforated metal wall panels include:

Acoustimetal by Acoustical Surfaces, Inc.

Contact: Ted Weidman at Acoustical Surfaces, Inc

Phone: (952) 466-8225

Website: http://www.acousticalsurfaces.com/acousti_metal/acoustimetal.htm

A less preferred alternative would be to install a heavy acoustical drape in front of all existing metal wall panels

The drape material would need to be heavy, fabric velour or similar, e.g. Rose Brand Imperial Synthetic Velour, IFR, 32 oz.

http://www.rosebrand.com/productz839/32-oz-Imperial-Synthetic-Velour-

IFR.aspx?cid=150&idx=1&tid=1&info=Velour%2bFabrics

This should be deployed at 100% fullness, i.e. 2 linear yards of fabric for every yard of track and the track should be placed a minimum of 4" away from the wall.

- b. Replace Existing Fixed Hard Seating with Fabric Faced Upholstered Seating
 This would be helpful to reduce the variation in room reverberation time between fully
 occupied and lower audience occupancy scenarios. This recommendation, however, needs
 to be weighed against durability and maintenance costs.
- c. Carpet Floor Finish

It would be acoustical helpful if the fixed seat area was carpeted. This recommendation, however, needs to be weighed against durability and maintenance goals.

It is understood that a floor covering will need to be deployed to protect the wood sports floor when loose seats are installed for performances and gatherings. A carpet floor finish (instead of rubber or other non-porous material) would provide useful additional sound absorption for these events.


d. Stage Area Acoustical Treatments

It is recommended that the underside of the structure over the entire stage area should be treated with 2" thick black coated Johns Manville Insulshield, pinned directly to the underside of the structure.





C. Existing Horizontal Sliding Doors It understood that the horizontally sliding doors circled in Mark-Up 1 below are considered to be features with historical significance.



Mark-Up 1

The doors currently provide a very poor level of sound isolation. It is considered unlikely that the acoustical performance of these doors could be substantially improved by retrofitting new seals (for old doors, usually increased acoustical performance comes at the cost of increased difficulty in operating the doors.) However, it may be worthwhile consulting a specialist contractor such as Pacific Sound Control on this matter.

Doug McDaniel cell 949/231-7066 direct 714/277-1077 office 714/892-6022 www.pacific sound control.com

In Scheme 1, these opening would be required to move sports equipment, including basketball hoops, between the storage area and the main space. It will be important to verify that the current opening height is sufficient for this. If it is, then the preferred acoustical option is to install new acoustical doors at these openings while retaining the existing doors (if required for historical preservation purposes). The new sliding door would be installed on one side of the wall (not directly in the wall depth). The architectural and structural feasibility of achieving this would need to confirmed. For

the purposes of preliminary pricing, the team recommends the following door specification. (one for each of the two opening).

STC-53 Horizontally Sliding Acoustical Door by Advanced Equipment Corp (rep'd by Specialty Door): Contact W. Scott Dickson – CEO, Scott Dickson, sdickson@aecorp.net, tel. 714-635-5350.

D. Wrestling Room in The Fly Tower

Wrestling activities will generate impacts upon the Fifth floor structure that have the potential to transfer through the structure and radiate noise (especially low frequency 'thuds') that could be audible and therefore distracting on the stage.

Mitigating this would require that the Fifth floor construction is of heavy concrete construction, with a highly resilient floor material flooring material on top. The structural support for this structure would need to be stiff in order to limit movement of the structure in response to these impacts. Acoustically, the team's recommendation would be to NOT adopt Scheme 1 if simultaneous use of the Wrestling Room and the Stage is required. If this avoidance is not possible then further very detailed study would be required, likely involving finite element modeling of the new and existing fly tower structure, would be recommended in order to better quantify this noise transfer and design appropriate mitigation. This study is beyond the scope of this initial feasibility study.

E. HVAC Noise Control for New Mechanical Systems

The new mechanical system should be designed to achieve a noise level of NC-30 or below when the Auditorium and Stage is used for Performances and gatherings. This will require a number of costimpactful measures including:

- i. Selecting relatively quiet mechanical equipment
- ii. Airborne noise control for fans using duct silencers and acoustically lined duct work.
- iii. Keeping air velocities to relatively slow speeds.
- iv. Vibration isolation of main mechanical equipment.
- v. Selecting diffusers and grills for manufacturers NC ratings of NC-20 or below.

11. Theatre Proposed Improvements

A. Summary

In order to use the building for rental events in between sports events the critical element is the speed at which the venue can be converted from one use to another. This would include opportunities such as being able to load in on the stage, or use the stage, while a sports event is taking place on the main floor. It also involves examining what elements can be automated, where power is located, and other infrastructure items. Some capabilities are major investments but can reduce the time needed to shift between events by hours or even days. With an available window of half a day to a day to make that turn between events, access and automation will be critical to making the building viable as a rental space.

It is also important to examine what features/capabilities groups coming in will expect to have. Being able to meet those requirements makes the difference between a space that groups want to come to and a facility that is difficult to rent. Discussions with staff have indicated that the likely types of desired rental uses may include:

- i. Concerts
- ii. Film/TV/Commercial Production
- iii. Corporate Events
- iv. Sports Tournaments (non district)
- v. Cheerleading Tournaments
- vi. eSports Tournaments
- vii. One night shows (comedy, magic, Food Network, etc.)
- viii. Banquets/Galas/Ted Talks
- ix. Church Groups
- x. Movie Presentations

District uses would include:

- i. Sports (Basketball, Volleyball, Wrestling)
- ii. Commencement
- iii. Prom

The facility is not intended to support symphony concerts, musical theatre or other similar events requiring superior sightlines and acoustics.

The facility will be operated primarily by union personnel, either District or contract labor, although some groups will bring their own labor. This establishes some additional requirements and expectations in terms of support spaces and amenities.

The team believes both schemes are workable but leaving the fly space intact offers the potential for the fastest turnaround from event to event due to the ability to fly a curtain package out of the way without having to remove the curtains from the tracks.

B. Theatrical Power

The existing power should be reworked. The goal would be to maintain similar accommodation for outside groups coming in, but with revised locations and voltages. In particular, the 48ov feed would be reduced or replaced and the majority of the temporary power would be converted to 208v in keeping with what modern production companies are expecting. For concert and production use, temporary power connections and distribution would need to be made available at the new production grid over the main floor as well as at the walkable grid above the stage (either the existing grid or a new grid).

C. Rigging

The existing counterweight rigging would need to be replaced. In scheme 1, a new walkable grid would be installed about 7' below the new wrestling support floor level. The bottom of the new floor would be an exposed steel beam system that production companies can attach temporary rigging to. A limited set of motorized hoists would be provided to support school uses of the building.

In order to have space for the new walkable grid, the proscenium height would be lowered to approximately 25'. This would impact the width of the proscenium if there is a desire to maintain a 2:1 ratio of width to height. The proscenium width would be reduced to 50' if that ratio were maintained.

Scheme 1 does not require a fire curtain due to the stage height being reduced to less than 50'. Smoke management will be a challenge as smoke vents cannot be installed at the ceiling of the stage. This is discussed in the mechanical narrative.

Concert acts and other groups coming in will expect, and need, to suspend items over the main floor – particularly in the area between the proscenium and the catwalk. The team recommends that the existing suspended ceiling be demolished and replaced with a walkable grid, or walkable areas, that cover the entire floor. New ceiling elements could be suspended below the grid. This allows fast access to rigging points so that events can be loaded in as quickly, and safely, as possible. Removal of the existing ceiling will also simplify things like incorporating sports court lighting, both for practices and for TV/Internet broadcast of games.



D. Curtains


The existing curtain package should be replaced, but there is a legitimate question as to how extensive the need is for stage curtains. Certainly, some events will want a main curtain, and some legs and borders to mask off points of entry and technical elements. Other events, such as concert tours, may not need these items. Since musicals are not anticipated, that reduces the need for curtains, but some other types of shows, such as magic shows and even corporate events, use them more than in the past. A basic curtain package will be required, but the extent of that package would need to be carefully considered during design. All curtains should be sewn using inherently flame retardant (IFR) fabrics rather than fabrics which have been treated with a fire retardant chemical (which require regular testing and reapplication of the treatment).

E. Audio

A basic system that supports school sports and event uses of the building would be installed. This system would also be usable for basic rental events, such as corporate meetings or presentations. Audio for ancillary spaces, such as the lobby, would also be part of the permanently installed systems.

Infrastructure should be added to support large audio systems brought in by concerts or other outside groups. This infrastructure would include power, cable pathways,


interconnections to some permanent systems (such as the lobby speakers), and structural attachment points for speaker suspension. The existing speaker locations would be retained, but the weight load capacity of those locations would need to be upgraded and new locations either immediately adjacent to or directly behind those locations would need to be added. Space within the seating area would need to be designated for the audio mixing console, and conduit and power provided to it. That might be a location similar to this:




Systems would need to be able to operate in different modes and at different levels of staffing, including a simple mode that does not require an operator at all (for sports events and lectures). As the building is expected to be flexible and to scale between different sizes/types/styles of events, the systems need to do the same.

F. Video

Since there is no video system or video infrastructure existing, everything would need to be installed new. Evaluation of options indicates that a center hung scoreboard presents both height and structural challenges. The team would propose hanging two LED screens, approximately 12' \times 21' - 4" in size, on either side of the proscenium opening. These screens would serve multiple uses, including presentations, image magnification (IMAG), and scoreboards. A separate screen at the rear corner(s) of the auditorium and/or portable screens would be used to provide video support to patrons on the stage side of a sports court.



Infrastructure consisting of pathways, cabling, and patching for cameras and connections to TV truck parking would be added. This infrastructure system would allow incoming groups to drop their equipment where needed with a minimum of cable running across the floor. Connections for computer inputs at the stage, courtside/scorer's table, audio mix booth, and lighting booth would also be added. Some possible camera platform locations may include:



A permanent system of 3 or more PTZ cameras would be used for livestreaming and could also be used for image magnification. These cameras, or one or more Point of View (PoV) cameras would be used to provide video monitoring to the lobby, backstage and other support areas.

G. Theatrical Lighting

Since this building was last upgraded, theatrical lighting has moved to LED based technology. This greatly reduces the power infrastructure (and consumption) required. Permanent theatrical lighting and controls should be installed to support school and sports events. The theatrical controls should also control the architectural lighting, as well as new

work lighting at the stage, grid and catwalk(s). Running lights (blue lights) should be installed in the stagehouse and surrounding circulation areas.

In order to provide adequate lighting angles to the stage, a second catwalk, as well as attachment points for temporary lighting trusses, should be added to the ceiling system. If a tension grid is created as part of the new production grid, it can function as a highly flexible catwalk system and new catwalks would not be needed. This would also allow the existing catwalk location to be demolished. It would be highly desirable to be able to add box boom locations forward of the proscenium, but due to the historic nature of the sidewalls this is not possible. The new production grid will allow light ladders to be suspended for this purpose when needed for a particular event.


The permanent systems, and the lighting electrical and data distribution, should mesh easily with lighting elements and systems brought in by external groups. The permanent system should include enough lighting instruments to provide a repertory plot for the entire stage and Orchestra lift area so that school uses and simpler events can use the space without needing to bring in lighting or spend significant time refocusing.


H. Main Floor

One of the major questions to be resolved was whether to use the tilt mechanism of the main floor, or whether to fix the floor in the flat position. As stated previously, the sight lines from the sloped floor are not ideal and the slope would need to be reduced in order to comply with ADA regulations. This would further degrade the sightlines for the back half of the floor seating. There are a number of accessibility challenges and other issues to solve related to the interface between the tilting slab and the adjoining areas. These are discussed in the architectural narrative.

From a seating standpoint, it may be possible to have custom chairs made with longer legs in the front so that they sit flat on the sloped floor. It is unknown whether DSA would approve this. Other methodologies, such as permanent seating on rotating mechanisms that would store below the floor, were considered and rejected as not realistic for various reasons.

The team's recommendation is to fix the main floor in the flat position and use stage lifts and temporary platforming to raise the stage. The resulting sightlines will still not be ideal but are adequate for the types of events proposed for the space. The addition of video screens and image magnification will also help to resolve some of the sightline issues.






I. Orchestra Pit

The existing pit lift needs to be replaced, as well as the safety interlocks to the various pit access points. The new lift may want to be slightly narrower than the existing lift, with the end pieces becoming permanent floor that is fixed in place. These end areas would provide an opportunity for ramping if the new sports floor is built on top of the existing slab and ends up higher than the existing stage floor.

The new lift should be able to travel above the floor level, to approximately 5'. This allows multiple stage levels to be created depending on the height the lift is raised to. The lift should also connect to the new upstage lift so that it can be part of a contiguous stage floor or be used to create a multi-level stage.

J. Stage Floor

The team proposes installing a new lift, or lifts, in the stage area. The new lift should be approximately 40' in width by 20' in depth and be able to travel to approximately 5' above the current stage floor level. It should also be able to connect with the orchestra lift to create one large platform when desired.



The new lift(s) would be used to create a raised stage, for better sightlines, as well as a freight elevator to move items between the main floor and the basement storage level. Excavation of the basement area will be required in order to accommodate the new lift, and some structural modifications of the existing stage framing may also be necessary. The new excavation for the lift would be \sim 6' in depth for the full footprint of the lift.

The floor itself may need to be replaced if the sports court is built on top of the existing slab. Rebuilding the stage floor would allow it to be raised the same amount, so that the stage, orchestra pit lift, and main floor all match in elevation. However, ramping would need to be created around the perimeter of the stage to meet up with the adjoining floor level. It may be more useful to raise the loading dock area the same amount than to try and ramp the loading path to the stage. Cutting into the stage floor to install new lift locations will require containment considerations.

K. Audience Seating


The existing seating is in good enough condition that, if the type of seating is considered appropriate, it could simply be repaired as needed and retained. It probably has another decade of service life available. However, some reorganization of the seating will be required, both to resolve code issues and to provide new amenities such as camera platforms, an audio mix position, and scorer's table. There is an open question as to whether these seats could be matched if parts or a few new seats were needed to accommodate the modifications.

The recommendation is to replace the seating with a higher quality one. The goal would be to improve maintenance requirements, through the selection of a seat with a gravity rise mechanism rather than a spring based mechanism, and to improve patron comfort. The new seat would have a padded back and bottom but would not necessarily be upholstered. It could have a surface similar to those used in club seating areas at stadiums that are easily washable/cleanable.



L. Support Spaces


There are many existing support spaces in the building, from dressing rooms to electrical rooms. Some of them would be repurposed since the new program for the facility does not require them (e.g. there will not be a need for so many dressing rooms). However, a few spaces that will be necessary do not exist due to the age of the building. One or more AV Rack Room(s) will be needed to house backend AV equipment. A control room will be needed for IMAG and Livestream production. And theatrical lighting and rigging control distribution equipment may need its own space as well. Storage for technical equipment will need to be dedicated to that purpose and not just lumped in with general storage.




SCHEME 1


SCALE: N.T.S














WRESTLING VISITOR LOCKERS & OFFICIALS CHANGING ATHLETIC STUDENT LOCKERS COACHES LOCKERS & OFFICES ATHLETIC TRAINERS TICKET & CONCESSIONS COMPETITION + PRACTICE COURT STAGE RESTROOM THEATRE DRESSING SERVICE & STORAGE FUD OFFICE COMMUNITY ROOM & KITCHEN

LEGEND









WRESTLING

VISITOR LOCKERS & OFFICIALS CHANGING ATHLETIC

STUDENT LOCKERS

COACHES LOCKERS & OFFICES

ATHLETIC TRAINERS

TICKET & CONCESSIONS

STAGE


RESTROOM


THEATRE DRESSING SERVICE & STORAGE

FUD OFFICE

COMMUNITY ROOM & KITCHEN









VISITOR LOCKERS & OFFICIALS CHANGING

COMPETITION + PRACTICE COURT

WRESTLING

ATHLETIC STUDENT LOCKERS COACHES LOCKERS & OFFICES ATHLETIC TRAINERS TICKET & CONCESSIONS


STAGE

RESTROOM

THEATRE DRESSING

SERVICE & STORAGE FUD OFFICE

COMMUNITY ROOM & KITCHEN







VISITOR LOCKERS & OFFICIALS CHANGING

COMPETITION + PRACTICE COURT

COMMUNITY ROOM & KITCHEN

WRESTLING


ATHLETIC STUDENT LOCKERS COACHES LOCKERS & OFFICES ATHLETIC TRAINERS TICKET & CONCESSIONS


STAGE

RESTROOM

THEATRE DRESSING

SERVICE & STORAGE FUD OFFICE







VISITOR LOCKERS & OFFICIALS CHANGING

COACHES LOCKERS & OFFICES ATHLETIC TRAINERS TICKET & CONCESSIONS

COMPETITION + PRACTICE COURT

COMMUNITY ROOM & KITCHEN

WRESTLING


ATHLETIC STUDENT LOCKERS


STAGE

RESTROOM

FUD OFFICE


THEATRE DRESSING













NAC

3.2.4 CODE JUSTIFICATION

- A. Scheme 1 re uses the existing building for all the program in the project with the exception of the Athletics Room and Training space. These are housed in a new building adjacent to the existing building and will be separated from the auditorium by enough distance to permit it to be justified separately from a code perspective. The following preliminary analysis is split by building. Information has been gathered from the existing documents available at this time but will warrant further research and confirmation as the project progresses.
- B. Analysis per CBC 2022 and DSA IR A 26 (5/30/2019)
- 2. Scheme 1 Existing Building Code Justification
 - A. Type II A building justified under 506.2.2 Mixed Occupancy Buildings with non-separated occupancies analysis per 508.3.2 using A 1 as the most stringent occupancy. Fully compliant automatic sprinkler system and fire alarm system.
 - B. Occupancies / Occupant Load Factors
 - i. Auditorium space two scenarios
 - a. Performance A 1 w/ occupant load of 7 net for non fixed seat areas, and actual seat quantity for fixed seats
 - b. Gymnasium A 4 w/ occupant load of 7 net for non fixed seat areas, and actual seat quantity for fixed seats and bleachers
 - ii. Stage A 1 w/occupant load factor of 15 net
 - iii. Wrestling Room A 3 w/ occupant load factor of 50 gross
 - iv. Locker Rooms E w/ occupant load factor of 50 gross
 - v. Offices B w/ occupant load factor of 150 gross
 - vi. Storage S 1 w/ occupant load factor of 300 gross
 - C. Building Height (504 and Table 504.3)
 - i. Allowed: 85'
 - ii. Actual: 80'
 - D. Building Stories (504 and Table 504.4)
 - i. Allowed: 4 stories (without area increase)
 - ii. Actual: 3 stories
 - E. Building Area (506 and Table 506.2)
 - i. Allowed Area per floor: (with frontage of 0.25)
 - a. $A_a = [A_t + (NS \times I_f)]$
 - b. $A_a = [46,500 + (15,500 \times 0.25)]$
 - c. $A_a = 50,375$ sf per floor
 - ii. Actual Area (on largest floor): 49,790 sf
- 3. Scheme 1 New Building Code Justification
 - A. Type II B building justified under 506.2.1 Single Occupancy Buildings. Fully compliant automatic sprinkler system and fire alarm system.
 - B. Occupancies / Occupant Load Factors
 - i. Athletic Rooms A 3 w/ occupant load factor of 50 gross
 - C. Building Height (504 and Table 504.3)
 - i. Allowed: 75'
 - ii. Actual: 20'

- D. Building Stories (504 and Table 504.4)
 - i. Allowed: 3 stories (without area increase)
 - ii. Actual: 1 stories
- E. Building Area (506 and Table 506.2)
 - i. Allowed Area per floor: (with no frontage)
 - a. $A_a = [A_t + (NS \times I_f)]$
 - b. $A_a = [38,000 + (9,500 \times 0)]$
 - c. $A_a = 38,000 \text{ sf per floor}$
 - ii. Actual Area (on largest floor): 3,400 sf

3.2.5 FIXTURE COUNTS

1. References

- A. CA Plumbing Code 2022 Chapter 4
 - i. Table 4 1 Occupant Load Factor
 - ii. Table 422.1 Miniumum Plumbing Facilities
- B. DSA IR A 26 K 12 Occupancy Classification and Occupant Load Factors (latest version 5/30/2019)

2. Calculations

- A. Auditorium Spectators
 - Fixtures provided meet the minimums based on the Performance Use calculationin below, and are provided throughout multiple restrooms in the north and west lobbies.
 - ii. Performance Use (A 1 per IR A 26)
 - iii. Fixed Seats per Table 4.1 use 50% of fixed seating value for occupant load factor → 958 seats total x 50% = 479 occupants
 → 240 female, 240 male
 - iv. Open Area seating per Table 4.1 use occupant load factor of 11 \rightarrow 10,289 net sf/11 = 936 occupants \rightarrow 468 female, 468 male
 - v. Total occupants → 708 female, 708 male
 - vi. Total required fixtures per Table 422.1 for A 1 (A 1 per IR A 26)

| WCs Female | 8: 301 400 + 1 WC per add'l 125 | 11 |
|-----------------------|--|----|
| WCs Male * | 3: 201 400 + 1 WC per add'l 500 | 4 |
| Urinals Male * | 4: 401 600 + 1 urinal per add'l 300 | 5 |
| Lavs Female | 6: 501 750 | 6 |
| Lavs Male | 4: 601 750 | 4 |
| Drinking Fountains | 3: 501 750 + 1 df per add'l 500 | 5 |

^{*} Increase total of male fixtures to equal female

B. Athletic Use (A 4 per IR A-26)

i. Fixed Seats – per Table 4.1 use 50% of fixed seating value for occupant load factor → 958 seats total x 50% = 479 occupants
 → 240 female, 240 male

- ii. Fixed Seats in new bleachers per Table 4.1 use 50% of fixed seating value for occupant load factor → 220 seats total x 50% = 110 occupants → 55 female, 55 male
- iii. Total occupants → 295 female, 295 male
- iv. Total required fixtures per Table 422.1 for A 4 (A 4 per IR A 26)

| WCs Female | ნ: 201 300 | 6 |
|-----------------------|------------|---|
| WCs Male * | 3: 201 400 | 3 |
| Urinals Male * | 3: 201 400 | 3 |
| Lavs Female | 4: 201 300 | 4 |
| Lavs Male | 2: 201 400 | 2 |
| Drinking Fountains | 3: 501 750 | 3 |

^{*} Increase total of male fixtures to equal female

- C. 1st Floor FUD Offices
 - i. 925 sf total
 - ii. Per Table 4.1 Use occupant load factor of 150 (Business) \rightarrow 925 / 150 = 7 occupants \rightarrow 4 female, 4 male
 - iii. Total required fixtures per Table 422.1 for B

| WCs Female * | 1: 1 15 | 1 |
|--------------------|-----------|---|
| WCs Male | 1:1 50 | 1 |
| Urinals Male | 1: 1 100 | 1 |
| Lavs Female | 1:1 50 | 1 |
| Lavs Male | 1: 1 75 | 1 |
| Drinking Fountains | 1 per 150 | 1 |

^{*} Increase total of female fixtures to equal male

- iv. Fixtures provided in the west spectactor restrooms
- D. 1st floor Athletes and Coaches
 - i. 12,727 sf total (Auditorium 9,327 sf + Athletics Room 3,000 sf + Athletic Training Room 400 sf)
 - ii. Per Table 4.1 Use occupant load factor of 50 (Exercise) \rightarrow 12,727 / 50 = 255 occupants \rightarrow 128 female, 128 male
 - iii. Total required fixtures per Table 422.1 for A 3 (A 3 per "Exercise Room" in IR A 26)

| WCs Female | 4: 101 200 | 4 |
|----------------|------------|---|
| WCs Male * | 2: 101 200 | 2 |
| Urinals Male * | 2: 101 200 | 2 |
| Lavs Female | 2: 101 200 | 2 |
| Lavs Male | 1:1 200 | 1 |
| Drinking | | 2 |
| Fountains | 2: 251 500 | |

^{*} Increase total of male fixtures to equal female

iv. Fixtures provided in athletic locker rooms (coach and student)

E. 1st Floor – Stage

- i. 4,538 sf total
- ii. Per Table 4.1 Use occupant load factor of 11 (Assembly) \rightarrow 4,538 /11 = 413 occupants \rightarrow 207 female, 207 male
- iii. Total required fixtures per Table 422.1 for A 1

| WCs Female | ნ: 201 300 | 6 |
|----------------|------------|---|
| WCs Male * | 3: 201 400 | 3 |
| Urinals Male * | 2: 201 300 | 2 |
| Lavs Female | 4: 201 300 | 4 |
| Lavs Male | 2: 201 400 | 2 |
| Drinking | | 2 |
| Fountains | 2: 251 500 | |

^{*} Increase total of male fixtures to equal female

iv. Fixtures provided in Theater dressing areas adjacent to stage

F. 5th Floor – Wrestling Room

- i. 4,185 sf
- ii. Per Table 4.1 Use occupant load factor of 50 (Exercise) \rightarrow 4,185 / 50 = 84 occupants \rightarrow 42 female, 42 male
- iii. Total required fixtures per Table 422.1 for A 3 (A 3 per "Exercise Room" in IR A 26)

| WCs Female | 2: 26 50 | 2 |
|-----------------------|----------|---|
| WCs Male | 1: 1 100 | 1 |
| Urinals Male | 1: 1 100 | 1 |
| Lavs Female | 1: 1 100 | 1 |
| Lavs Male | 1:1 200 | 1 |
| Drinking Fountains | 1:1 250 | 1 |

iv. Fixtures provided in 4th floor locker rooms



In Scheme 2, the concept is to separate performance and athletics uses as much as possible. In so doing, this scheme assumes more new construction. While Scheme 1 sought to renovate the Committee Building and the Administration Building, this scheme recognizes that renovation of the buildings is costly and complex. As the program of Scheme 2 does not readily fit, the concept is to demolish these auxiliary buildings and construct new additions on the east and west sides of the existing Auditorium.

The west addition would house a kitchen, an assembly hall, public restrooms, visiting team rooms, and space for District facilities staff. The east addition would house a wrestling room, fitness / training space, home team lockers, and coaches' spaces.

The existing Auditorium is renovated for multiple uses. It is envisioned that the Auditorium could house a variety of performances from drama to music to other student events. This scheme assumes use of the full fly tower and replaces theatrical equipment as required. Other required renovations typical of either scheme are included elsewhere in this report.

3.3.2 NARRATIVES

This narrative describes the interior improvements proposed in Scheme 2. The recommended upgrades to the exterior can be found in the Existing Assessment section of the report (2.1).

Scheme 2 keeps the original stage size, the existing proscenium height and the majority of the performance based support spaces as per the original design. A laundry has been added behind the stage along the SW corner. The existing dressing rooms and restrooms surrounding the stage would be gutted and replaced with code compliant fixtures and casework. The athletic programs along with a new community room and kitchen are accommodated in two new addition structures located similarly to the current Administration Building wing and Committee Building wing but at increased sizes.

Architectural proposed improvements to the Civic Building

A. Auditorium

- i. Tilted floor converted to Competitive Gym Floor
 - a. The District would like a hardwood sprung flooring system permanently installed on the tilted floor. The floor will be fixed in its' flat position. The mechanism that permits it to tilt will be preserved to allow future use if desired. The Basis of Design for the wood flooring is Robbins Bio Channel Classic or Air Channel Star installed over 2x4 sleepers. The hardwood sprung flooring system would also be installed at the fixed areas between the tilted floor and the existing Administration and Committee Building wings. The flooring system would have integrated recessed fixed anchors for netting posts. To protect the hardwood sprung flooring system when not used as a competitive gym, the team recommends adding a floor cover tile. The Basis of Design is Covermaster Platinum Covertile (1m x 2m carpet tiles) and a storage cart. The tiles can be installed by a single person.
 - b. Moveable basketball goals would be provided at each end.
 - c. Addition of retractable portable bleacher seating located near the orchestra lift. Basis of Design: Irwin seating Telescopis bleacher: Versatract retractable seating. Total seating count 220.
- ii. Fixed seating
 - a. Replace existing fixed seating with new. See the theatrical narratives for further information.
- iii. Provide multiple accessible seating options.
 - a. Replace the first row of fixed seating with a balcony allowing for accessible seating and companion seating with a guard rail around the perimeter of the balcony. Refer to the floor plan for the layout.
 - b. Provide accessible seating off the Concourse level. A balcony with guard rail similar to the one at the first row would be installed at the center of the top row of seating to accommodate accessible seating and companion seating. Refer to the floor plan for the layout.
- iv. Preserve the existing solid metal and perforated metal acoustic wall panels
 - a. The metal panels are character defining features. The recommendation is to add an acoustical curtain in front of them. Refer to the Acoustical Narrative for additional information. The existing wall area below the metal panels would receive wall padding or protective cladding to protect the athletes.

v. Replace existing plaster auditorium ceiling with a new acoustical gypsum ceiling over the fixed seating area. Refer to the Acoustic Narrative for additional information. Provide new sports lighting and general lighting.

B. Stage

- Replacing the existing counterweight rigging system with a motorized rigging system including lighting
- ii. Provide a new fire curtain system
- iii. Provide an acoustic proscenium curtain deployable during sporting events
- iv. Refinish existing pine floor on stage.
- v. Provide new orchestra pit and stage lifts.

C. Lobby

- i. Stairs #1 and #2 are character defining features in the building. Stairs to be retrofitted to include new handrails on each side and height extension to guard rail throughout. Refinish and seal all materials.
- ii. Concessions As noted in the existing assessment, the team recommends building new concessions to remember the original ones but with contemporary amenities. Wood casework with solid surface finishes, point of sale (include data), and display areas. Provide power and sewer/water connection to serve refrigeration and freezer.
- iii. Reflecting Pool The reflecting pool and railing are no longer present on site. The team recommends a mosaic tile in the location of the former reflecting pool.
- iv. Elevator A 2 stop hydraulic elevator is proposed for the northwest corner of the lobby to provide accessible travel between the 1st floor lobby and the concourse above.
- v. Lift A 2 stop wheelchair lift is proposed to provide accessible travel between the concourse level and the Control Room above. By utilizing a lift instead of an elevator for this access there is no need to penetrate the Auditorium's domed roof.
- vi. Ceiling Replace the existing ceiling with an acoustical ceiling tile. The Basis of Design: Fine fissure mineral wool ceiling ACT and LED fixtures similar in size and finish to the existing light fixtures.

D. Basement

- i. The team recommends replacing the existing double doors to the Orchestra Lift with new double doors.
- ii. Locate storage rooms in the basement level along with the space and infrastructure for a new stage lift and orchestra pit lift.
- iii. The team recommends adding a viewing area at the current entrance to the tilt floor area. The viewing area would let visitors see the hydraulic mechanism and the framing of the tilted floor. There could be an exhibition area to display photos, drawings, and concert memorabilia and other collectibles. It will require excavating some of the unexcavated areas to allow for a larger, accessible view area and glass viewing wall. Visitors could walk into the tilted floor area as part of a guided tour.
- iv. Locate a storage room for basketball and volleyball equipment. Equipment can be moved to this room via the new freight elevator, orchestra pit lift or stage lift.
- 2. New east addition (in the former location of the Committee Building wing)
 - A. This addition is a steel brace frame building with exterior cement plaster finish. Floor to floor at north end 18' o" high and 30' o" high at south end (see axon).

- B. Windows to be storefront with IGU glazing. Glazing would be provided along all sides of wrestling, fitness and north elevation of building.
- C. To account for the grade change, an incline inside the building is added. This allows both Wrestling and Fitness to have doors open to finish grade.
- D. The breakdown of program is listed below and can be found on the floor plans included in this report.
 - i. Wrestling practice room and storage space
 - ii. Weight/Fitness classroom (Athletics)
 - iii. Athletic Trainers Room
 - i. Coaches' Offices A mix of private offices and open workstations including built in casework
 - ii. Team Huddle
 - a. Flat screens/digital display, trophy exhibit wall. Include wood speciality suspended ceiling.
 - iv. Female Student Lockers
 - a. 6ς) 2 tier lockers (130 lockers total) and changing areas with accessible benches.
 - b. 7 showers (1 of which is accessible)
 - c. 4 lavatories (1 of which is accessible)
 - d. 5 water closets (1 of which is accessible)
 - v. Male Student Lockers
 - a. (85) 2 tier lockers (170 lockers total)) and changing areas with accessible benches.
 - b. 8 showers (1 of which is accessible)
 - c. 5 lavatories (1 of which is accessible)
 - d. 3 water closets (1 of which is accessible)
 - e. 3 urinals (1 of which is accessible)
 - vi. Female Coach Lockers, Male Coach Lockers, Gender Neutral Coach Lockers, and Gender Neutral Student Lockers
 - a. (3) 2 tier lockers (6 lockers total) and changing areas with accessible benches.
 - b. 1 accessible shower
 - c. 1 gender neutral restroom (water closet and lavatory)
- 3. New west addition (in the former location of the Adminstration Building wing)
 - A. This addition is a steel brace frame building with exterior cement plaster finish. Floor to roof height is 18' o".
 - B. There would be storefront windows along the west, south and north sides of the building containing insulated glazing units. The south side would have a loading dock, stairs and an accessible ramp to allow access to the FUD offices, offloading to the kitchen and access for the kitchen staff. A grease interceptor would be located in the existing parking lot.
 - C. Community Room 3,400 SF with a moveable partition door and linear wood ceilings. The space could be used by the school and community for receptions, events and celebrations.
 - D. Kitchen full commercial kitchen to accommodate catering needs for events held in the Community Room and the main auditorium
 - E. Similar to Scheme 1, the Officials Changing and additional public restrooms are located in the new building. The breakdown of locker rooms, fixtures and finishes are shown below.
 - F. Public Restrooms
 - i. Men's Restroom

- a. (2) water closets (1 of which is accessible)
- b. (2) urinals (1 of which is accessible)
- c. (3) lavatories ((1 of which is accessible)
- ii. Female's Restroom
 - a. (4) water closets (1 of which is accessible)
 - b. (3) lavatories ((1 of which is accessible)
- iii. Single User Restroom
 - a. (1) accessible water closet
 - b. (1) accessible lavatory
- G. Visiting Team Locker Rooms
 - i. (40) 2 tier lockers (80 lockers total) and changing areas with accessible benches
 - ii. Both genders 4 showers (1 of which is accessible)
 - iii. Both genders 2 lavatories (1 of which is accessible)
 - iv. Female 3 water closets (1 of which is accessible)
 - v. Male 2 water closets (1 of which is accessible) & 2 urinals (1 of which is accessible)
- H. Officials Changing Area
 - i. (3) 2 tier locker (6 lockers total) and changing areas with accessible benches.
- 4. Proposed Finishes throughout project include:
 - A. Bathrooms / athletic locker rooms / theatre bathrooms
 - iii. Ceramic tile floor, sloped to floor drain
 - iv. Ceramic tile wall, full height
 - v. Phenolic partitions
 - vi. Bobrick accessories as Basis of Design
 - vii. All lavatories in solid surface counters w/ full wall mirrors above (wall hung lavatories in locker rooms)
 - viii. Air hand dryers throughout
 - B. Coaches offices
 - i. Lvt floor throughout
 - ii. Painted gypsum walls, level 5 finish
 - iii. Doors will sidelights in storefront frame
 - C. FUD offices
 - i. Carpet tile in private offices & lvt in share spaces
 - ii. Painted gypsum walls, level 5 finish
 - iii. Doors will sidelights in storefront frame
 - D. Storage rooms
 - i. Abuse resistant gypsum walls
 - ii. Sealed concrete floors
 - E. Officials Changing room
 - i. Abuse resistive gypsum walls
 - ii. LVT flooring
 - iii. 3 full height lockers
 - F. Community room
 - i. Wood flooring
 - ii. Painted gypsum walls w/ acoustic treatment on 40% of walls.
 - iii. Include operable partition door

- G. Commercial kitchen
 - i. Stainless steel wall cladding
 - ii. Epoxy flooring, sloped to floor drains
 - iii. Provide commercial grade equipment including grease interceptor, fume hood and water heaters
 - iv. Three compartment sink
 - v. Mop sink
- H. Ceilings Mineral Wool ACT throughout, U.N.O.
- I. Walls Level 5 gypsum board finish with wall base throughout, U.N.O.
- J. Floors All exposed concrete floors to be refinished

2. Civil Proposed Improvements

A. Proposed Conditions

i. Grading

Walks, stairways, ramps, and other surfaces will be sloped away from buildings. Typical slope planes for drainage shall be between 1% and 2%. Other slope standards include the following:

- a. Within building areas: 1.5% 2%
- b. Plazas and terraces: 2% maximum.
- c. Entrance walks and ramps along path of travel: 5% max (8.33% with handrail)
- d. Non ADA parking stalls and drive aisles: 5% max
- e. Planted slopes: 50% maximum.
- f. Lawn areas: 15% maximum.

ii. Erosion and Sediment Control

In accordance with the National Pollutant Discharge Elimination System (NPDES) permit, the construction site shall implement Best Management Practices (BMPs) to control erosion, debris, and construction related pollutants. BMPs include, but are not limited to, gravel bags and fiber rolls for perimeter control, stabilized construction entrances as tracking control, and stockpile management in accordance with good housekeeping practices. All existing catch basins shall be protected per standard plan SE 10 to minimize sediment clogging the utility system. If the project will disturb more than one acre of land, a Storm Water Pollution Prevention Plan (SWPPP) will need to be filed with the California State Water Resources Control Board. Assuming all existing pavement area will be replaced, the total area to be disturbed for this scheme will exceed one acre and a SWPPP will be required.

ii. Storm Water Management

The understanding at the time this report was written is the State Water Resources Control Board has not issued a General Permit for the Discharge of Storm Water from Small MS4s (WQ Order No. 2003 0005 DWQ) to provide permit coverage for K 12 Schools. Therefore, post construction stormwater management will have to follow requirements from the SWPPP if the total disturbed area is more than one acre and Post-Construction Water Balance Performance Standard Spreadsheet will have to be filled out. If the total site runoff volume has been increased, post construction best management practices (BMPs) such as porous pavement, tree planting, swales or rain barrels will have to be installed to offset. For this scheme, it anticipated that the runoff volume will increase from previous conditions and post construction BMPs will have to be implemented to mitigate an estimated 700 cubic feet of storm water.

However, if SMMUSD would like to follow the City of Santa Monica Storm Water Management requirements, they are more stringent as the storm water volume to be mitigated is based on the total impervious area of the project (existing and proposed). Based on the City of Santa Monica Urban Runoff Drainage Plan Worksheet, about 7,000 cubic.feet of storm water will have to be mitigated for this scheme. Based on the preliminary geotechnical report from Willdan dated July 5, 2012, infiltration does not seem

feasible. A capture and reuse system with an underground cistern and a pretreatment system will then have to be installed to store the storm water volume to be mitigated. A pump located inside the cistern will feed the irrigation system for all the project planted areas.

iii. Storm Drainage

New site storm drain system with underground piping and drain inlets will have to be installed to capture the site storm drain runoff and avoid any sheet flow to the public sidewalk. If a cistern for capture and reuse is installed, the runoff will be directed to the underground cistern for future irrigation use. Overflow will be directed to the street curb via new curb drains under public sidewalk.

It is also recommended to replace the existing 8" underground storm drain pipe picking up the building roof drains at the southwest corner of the building and flowing to the street curb on Main Street if the roof runoff from the existing Civic Auditorium does not need to be mitigated with a capture and reuse system.

The storm drain lines for the project will be Heavy Wall PVC SDR.35 ASTM D3034 pipe and fittings with Bell and Spigot gasket joints.

iv. Sanitary Sewer

It is recommended to replace the existing site sewer system as it is likely reaching the end of its lifespan. New sewer connection(s) will be provided to serve the new building additions and will join the site sewer system. Existing sewer lines are conflicted with the proposed building additions and will have to be relocated.

Sewer report with sewer manhole monitoring data may have to be submitted to the City of Santa Monica if the project will increase the current sewer load.

The sewer lines for the project will be Heavy Wall PVC SDR.35 ASTM D3034 pipe and fittings with Bell and Spigot gasket joints.

v. Domestic and Fire Water

It is recommended to replace the existing site domestic and fire water systems as they likely are reaching the end of their lifespans. New water connections will be provided to serve the new building additions. An existing fire water line is in conflict with the proposed building additions and will have to be relocated.

Water report may have to be submitted to the City of Santa Monica if new connections to the water city mains are required for the project.

Four existing fire hydrants are located in the vicinity of the project, two are located on Main Street on the project side and two others are located at the intersection of Pico Boulevard and Third Street and at the intersection of Main Street and Pico Boulevard across the street. Additional fire hydrants may be required for the project and this should be confirmed by the Division of State Architect and possibly the City of Santa Monica Fire Department.

vi. Public Right Of Way Improvements

The existing sidewalk along Pico Boulevard has an uneven surface and is not in good condition mainly because of private and public trees and should be repaired. The City of

Santa Monica may require the existing curb ramps on Main Street to be renovated and meet the current City standards. New driveway apron(s) may have to be installed to serve the project. All work within the public right-of-way will require a separate offsite improvement permit with the City of Santa Monica

3. Landscape Proposed Improvements

A. In Scheme 2, much of the new building program is pushed outside the historical building volume and into newly constructed and adapted wings – an expanded space along the Main Street side and a larger mass of new building program on the opposite side. These two moves will have significant impacts on the existing planting areas. This scheme would require the removal of six original trees. Ideally, these would be removed and replanted onsite, though this would need to be determined by an arborist to verify the health and viability of the trees.

Another consideration is whether to restore the long, linear planter (now currently separated into three planter boxes). In this scheme, it appears that significant student traffic would occur at this end and the larger end of the planter compresses the egress to the building interior. Though it may help to screen the locker rooms, this scheme may benefit from the planters being removed to create a larger staging area and terrace for these facilities. Though pedestrian traffic and use should be studied before this determination.

4. Structural Proposed Improvements

A. Building Modifications

Scheme 2 consists of the demolition and replacement of the one story east and west structures with new building construction that will house the wrestling functions, locker rooms, community room, etc. The stage tower will remain as is and no new floors will be added to this structure.

B. Impact of Proposed Alterations

Scheme 2: The two new buildings on the east and west sides of the auditorium is expected to consist of one story steel framed buildings with concrete fill metal deck roof. The new structures will likely need to be supported by a pile foundation system. A seismic separation joint is recommended between the new buildings and the existing auditorium in order for the buildings to act and be designed as independent structures without impacting the existing auditorium structure. Depending on the final design of the buildings, the seismic lateral resisting system may likely consist of a buckling restrained braced frame system or special concentric moment frame system.

Integration of any shear walls will be studied and located to ensure that the significant historical features of the building are not affected.

The existing main floor will be locked in the flat position using bolted connections that will not affect the hydraulic mechanism allowing the tilting mechanism to be used if that is desired in the future.

Provisions will be made to allow for a portion or portions of the stage to rise above the existing stage line and the orchestra pit will be re built.

5. Mechanical Proposed Improvements

- A. Scheme 2 mechanical recommendations are outlined in this section.

 As noted previously most of the existing equipment is past or approaching its life expectancy and will need to be replaced.
 - i. Provide new 4-pipe AHU to provide space conditioning, humidity control, and ventilation to the new athletics room on the 1st floor. AHU will be connected to chiller and boiler plants, and integrate into building control system. Equipment to be located on the new roof.
 - ii. Provide new 4-pipe AHU to provide space conditioning, humidity control, and ventilation to wrestling room addition to the East Room. AHU will be connected to chiller and boiler plants, and integrate into building control system. Equipment to be located on the new roof.
 - iii. Provide new exhaust fan and make-up air unit for the kitchen addition to the current administration building. Both to be located on the roof of the administration building.
 - iv. Provide new roof mounted exhaust fans for the restrooms and lockers added to the administration building.
 - v. Replace air handling unit S-1 and resize based on new space usage of the current Administration Building. New unit will be connected to chiller and boiler plants, and integrate into building control system.
 - vi. Provide roof mounted exhaust fans for the lockers added to the East Room.
 - vii. Replace air handling unit S-2 and resize based on new space usage of the East Room. New unit will be connected to chiller and boiler plants and integrate into building control system.
- viii. Replace existing air handling units S-3,S-4,S-5 serving the auditorium and dressing room spaces. New units should have similar footprint and fit in existing fan rooms.
 - ix. Replace existing air handling units S-6 serving the lobby and concourse area. New units should have similar footprint and fit in existing fan room.
 - x. Replace all ductwork, hydronic piping, and controls associated with existing air handling units.
 - xi. Replace existing air-cooled chiller, resized to meet load requirements of additional spaces on the 4th and 5th floor. Heat exchanger, glycol management system, and piping should also be resized and replaced. Equipment to be located in existing mechanical rooms open roof on the 3rd floor.
- xii. Replace existing chilled water pumps with variable speed models with VFDs and new controls.
- xiii. Relocate existing thermal energy storage system as needed and connect new piping and controls to new chiller system.
- xiv. Replace existing heating hot water boilers with high efficiency condensing type boilers.

xv. Replace existing heating hot water pumps with variable speed models, VFDs and new controls.

6. Electrical Proposed Improvements

- A. Scheme 2 electrical recommendations are outlined in this section.
 - i. Upgrade all lighting to LED fixtures throughout the entire building.
 - ii. Add Title 24 code compliant interior controls to all the spaces. This includes dimming capabilities, occupancy controls and daylighting in the rooms with adequate fenestration.
 - iii. Add Title 24 code compliant exterior controls to all the exterior fixtures. This includes photocells and an astronomical time clock, as well as dimming for parking lot lighting.
 - iv. Replace all Zinsco distribution panels throughout the space. This replacement should include the feeders feeding the distribution panels as well.
 - v. Replace the original 208V Zinsco distribution boards in the main electrical room.
 - vi. Replace MCC1 and MCC2 with distribution boards. Add separate motor starters or VFDs as needed to control equipment. Coordinate with Mechanical and Plumbing for exact needs.
 - vii. Update receptacles to GFI protected receptacles as required by code. This is required for most of the restrooms, janitors' closets and kitchen spaces.
- viii. Upgrade the emergency generator to a 150kW unit and the ATS to a 400A rating.
- ix. Provide a new 400A rated kitchen distribution board to serve new all electric commercial kitchen.
- x. Provide space for new elevator machine rooms to serve elevators, estimated space required, 40 sq. ft each. Provide disconnect and panel in the room to serve elevator loads.

7. Plumbing Proposed Improvements

- A. Scheme 2 plumbing recommendations are outlined in this section.
 - i. Provide lead free isolation valves on laterals connected to mains.
 - ii. Provide water hammer arrestors on cold water headers connected to flush valves serving water closets and urinals. Install behind access panels.
 - iii. Replace the central domestic hot water boiler and storage tank serving the auditorium as this equipment has reached its useful life.
 - iv. Replace the tank type domestic hot water heater at the east wing serving the kitchen and restrooms as this equipment has reached its useful life.
 - v. Provide a re circulation system consisting of a pump, return piping, aquastat, and timeclock to ensure proper hot water delivery to fixtures. Where sub-loops are created, balancing valves shall be provided on each lateral to balance the system.
 - vi. Provide insulation with appropriate thickness on the hot water supply and return distribution piping.
 - vii. Provide code required anti scald tempering valves on the hot water systems.
- viii. Provide trap primer valves to serve floor drains and sinks in seldom used areas.
- ix. Replace all galvanized domestic water piping with copper.
- x. Replace all sewer waste (gravity) piping with cast iron with no hub couplings. Piping within the kitchen may contain grease buildup due to the lack of grease waste separation.
- xi. Provide a new grease waste and vent piping system within the kitchen and route to grease producing fixtures.
- xii. Provide a new below grade grease interceptor to serve the kitchen and connect to the existing facility sewer infrastructure. Size according to anticipated demand, but no smaller than 750 gallons capacity. The proposed location shall be south of the auditorium and committee building within the service yard or South of the Auditorium in the parking area. Final location shall have access for serving by a commercial size truck.
- xiii. Lavatory drains, supply, and stop assemblies of ADA compliant lavatories in the restrooms were not covered with protective insulation. Protective insulators shall be provided.
- xiv. The drinking fountain exhibits aging, wear, and tear, and should be upgraded to a hillo type with hands free bottle fillers.
- xv. Hose bibbs in public restrooms are not equipped with code compliant vacuum breakers. Replacing the fixture with a recessed type with a box and locking cover, and an integral vacuum breaker is recommended if the walls will be re tiled. Otherwise, vacuum

- breakers shall be provided at existing surface mounted hose bibbs to be code compliant.
- xvi. Provide a seismic valve (earthquake valve) on the natural gas assembly to comply with local codes and amendments.
- xvii. Replace all plumbing fixtures with high efficient fixtures. The performance (flow rates) of existing are no longer code compliant. Flow rates for new fixtures shall not exceed:
 - a. Water closets @ 1.28 GPF.
 - b. Urinals @ 0.125 GPF.
 - c. Lavatory faucets @ 0.35 GPM.
 - d. Sink faucets @ 1.5 GPM.

8. Fire Protection and Fire Alarm Proposed Improvements

- A. Scheme 2 fire protection and fire alarm recommendations are outlined in this section.
 - i. Provide a new backflow preventer assembly on the original connection to the building.
 - ii. Provide sprinklers in stage, seating, and wooden warehouse areas with an occupancy classification of Ordinary Hazard II, and main entrance overhang with an occupancy classification of Light Hazard.
 - iii. Provide sprinklers throughout every new area, including combustible concealed spaces and spaces above ceilings used as a plenum.
 - iv. Provide sprinklers under the obstruction in the lobby.
 - v. Replace all corroded, painted, and outdated sprinkler heads.
 - vi. Connect the existing hose connections located in the stage area to the fire protection system.
 - vii. Replace the existing fire alarm system to provide smoke/heat detectors throughout the new and existing areas. Complement with total coverage of speaker strobes.

g. Technology Proposed Improvements

- A. Scheme 2 technology recommendations are outlined in this section.
 - i. Dedicated signal rooms shall be provided at the north and south ends of the building to feed end user data, voice, and Wi-Fi systems. These rooms shall be of a minimum of 10 feet by 10 feet in size. One room will serve as the MDF and MPOE. The other room shall be an IDF room fed with fiber and copper backbone from the MDF/MPOE.
 - ii. Floor-mounted data racks shall be installed to house network equipment.
 - iii. Security systems shall be replaced with current technology and SMMUSD design standards. Keypads and access control shall be provided at entry points. Motion sensors shall also be provided where there is access from the outside.
 - iv. A CCTV system is recommended to provide monitoring of the premises. These cameras will be POE powered from the POE switches.
 - v. A dedicated AV Control Room shall be provided to house the AV system equipment. A projector and projector screen shall be provided with speakers and wireless microphones. An assistive listening system shall be provided to comply with the ADA code. The design for the system shall be per current technology and SMMUSD standards.

10. Acoustic Proposed Improvements

A. Basis Of Acoustical Recommendations

Based upon our review of the District's desired uses of the facility, it is understood that the main volume (gym/auditorium/stage) will need to provide suitable acoustics for multiple functions including athletic/gym type usage, gatherings and performances. It is the team's understanding that orchestral performance is not a priority usage. Also, because of the large size of the auditorium, it is not considered reasonable to attempt to design this space for non-amplified voice. This is because a speaker or actor located on the stage would be so far from the rear seats that microphones and electronic sound amplification will inevitably need to be used in this space for voice. Because the space will be designed for use with an audio system, for speech intelligibility and clarity of sound it is important to control the reverberation time within the space.

This desire for reverberation control, however, needs to be balanced against practical considerations and the significant potential cost of acoustical treatment and potential conflicting requirements of a gymnasium space (which include a need for wall padding for safety and durability of other finishes). Due to the large volume of the main auditorium, the highly durable finishes generally required for indoor sports facilities, and the activities usually taking place within the buildings, some sound reverberation and the associated build-up of noise in these types of spaces is almost inevitable. On this basis, we would note that it is not considered practical to acoustically optimize the space either for *Movie Presentations*, or as a *Sound Stage* for production of film/TV etc.

With consideration to sound isolation of the building envelope, given that the primary usage of the renovated facility would be for sports activities and given the high cost of achieving high levels of sound isolation for the envelope of such a large volume space, (the sound isolation of the envelope is only as good as the 'weakest link' and additional cost would therefore be incurred for a heavier roof, upgrades to all exterior doors, acoustical treatment at all duct penetrations, amongst other measures) the team NOT incorporated recommendations to achieve high levels of sound isolation for the building envelope. So in this respect, the post-renovation facility would not achieve the same acoustical quality as a state-of-the-art dedicated 'sound stage' if used for TV/Film production.

Finally, it should be noted, that the recommended NC-30 HVAC noise criterion is higher than would typically be expected for a dedicated Sound Stage.

In summary, by incorporating the acoustical recommendations below it should be possible to use the space, post-renovation, for all the District's listed uses, however, it is not considered practical/economical to achieve state-of-the art acoustical movie theater and/or sound stage standards for this facility.

B. Auditorium & Stage Room Acoustics

i. Recommended Reverberation Time Target for Auditorium and Stage

The most basic method to quantify the acoustical characteristics of a space is by considering 'reverberation time'. In approximate terms, this is the length of time a loud sound will take to decay to an inaudible level in the space. With reference to Figure 1 below, (which is presented for illustrative purposes only) it can be seen that the optimum reverberation time for a space, depends upon the specific usage. In particular, speech and electronically amplified sound

benefit from a low reverberation time and symphony orchestra benefits from a longer reverberation time (ideally 1.8 to 2.2 seconds for a symphony hall).




Figure 1. Optimum mid frequency reverberation time for various functions. Reproduced from "Music Facilities: Building, Equipping and Renovation" Harold P. Geerdes, published by Music Educators National Conference.

For spaces with a reverberation time exceeding approximately 2.5 seconds, (as is currently the case) noise from typical activities within the space starts to become unpleasant, and achieving even moderate degrees of speech intelligibility becomes difficult. While there is no industry standard, typical recommendations for mid-frequency reverberation time in indoor sports facilities range anywhere from 1.5 seconds to 2.5 seconds. The lower end of this criteria range is typically reserved for spaces where achieving reasonably high levels of speech intelligibility is important, such as teaching facilities and sports hall that have other uses including performances and gatherings, such as graduation ceremonies. On this basis, the team recommends a target maximum mid-frequency reverberation time of 1.5 seconds. A concept for achieving this is described below.

ii. Recommended Acoustical Design Concept for Main Auditorium Finishes

a. Auditorium Ceiling

Given its large area, the ceiling plane is the most important surface for controlling reverberation.

It is proposed that the existing ceiling will to be removed over most of the auditorium area to facilitate installation and use of a new production grid. It is understood that the roof will be replaced, we recommend that the replacement roof over the auditorium should use acoustical deck. The final acoustical deck type will be subject to structural coordination. The acoustical preference is to use an acoustical with a minimum NRC o.g acoustical rating manufactured by Epic Metals.




Photo 1: Acoustical Deck

As an alternative to acoustical deck, in the auditorium area where the suspended ceiling is to be removed, the underside of the roof structure could be treated with 1" thick Tectum, with 1" min. thickness acoustical insulation above. Please note that the Tectum can be painted without significantly degrading its acoustical performance, subject to following manufacturer's recommendations.

Tectum

Contact: Stacy Martin at Armstrong Phone: (717) 396-4783

Email: SWMartin@armstrongceilings.com Website:

https://www.armstrongceilings.com/commercial/en-ca/articles/tectum-part-of-armstrong-


portfolio.html



Photo 2: Tectum Ceiling

In this auditorium ceiling zone without a suspended ceiling, it is strongly preferred acoustically that there should be no deep beams, especially running parallel to the front of the stage (open trusses are preferred).

Above the existing raked seating at the rear of the auditorium, it is understood that a new suspended/shaped ceiling will be installed that will be visually similar to the existing ceiling in this area. Acoustically it is recommended that this ceiling should be acoustically absorptive. Assuming that this ceiling area would not be expected to be subject to high impact, USG's Ensemble Acoustical Drywall System is recommended, specified with USG High-NRC Backer Panels to provide NRC o.8 minimum for the installed system. If high impact is anticipated a suspended Tectum Finale system, specified for minimum NRC o.9 could be considered, however, this material would not be visually similar to the existing ceiling.



b. Acoustical Wall Panels

The existing metal acoustical wall panels in the Auditorium are not acoustically effective. It is recommended to replace all existing metal wall panels with new, more effective perforated metal acoustical panels. This should have 2" min. acoustical backing (3" preferred) and provide NRCo.g minimum acoustical performance. The metal perforation should have 18% min. free area. Careful consideration will be required in the detailing and installation in order to minimize rattling in response to acoustical excitation.

Suppliers of perforated metal wall panels include:

Acoustimetal by Acoustical Surfaces, Inc.

Contact: Ted Weidman at Acoustical Surfaces, Inc

Phone: (952) 466-8225

Website: http://www.acousticalsurfaces.com/acousti_metal/acoustimetal.htm

A less preferred alternative would be to install a heavy acoustical drape in front of all existing metal wall panels

The drape material would need to be heavy, fabric velour or similar, e.g. Rose Brand Imperial Synthetic Velour, IFR, 32 oz.

http://www.rosebrand.com/product2839/32-oz-Imperial-Synthetic-Velour-IFR.aspx?cid=150&idx=1&tid=1&info=Velour%2bFabrics

This should be deployed at 100% fullness, i.e. 2 linear yards of fabric for every yard of track and the track should be placed a minimum of 4" away from the wall.

- c. Replace Existing Fixed Hard Seating with Fabric Faced Upholstered Seating
 This would be helpful to reduce the variation in room reverberation time between fully occupied and lower audience occupancy scenarios. This recommendation, however, needs to be weighed against durability and maintenance costs.
- d. Carpet Floor Finish

It would be acoustical helpful if the fixed seal area was carpeted. This recommendation, however, needs to be weighed against durability and maintenance goals.

It is understood that a floor covering will need to be deployed to protect the wood sports floor when loose seats are installed for performances and gatherings. A carpet floor finish (instead of rubber or other non-porous material) would provide useful additional sound absorption for these events.

e. Stage Area Acoustical Treatments


It is recommended that the underside of the structure over the entire stage area should be treated with 2" thick black coated Johns Manville Insulshield, pinned directly to the underside of the structure.





C. Existing Horizontal Sliding Doors

It understood that the horizontally sliding doors circled in Mark-Up 1 below are considered to be features with historically significance.



Mark-Up 1

Unfortunately, these doors provide a very poor level of sound isolation. It is considered unlikely that the acoustical performance of these doors could be substantially improved by retrofitting new seals (for old doors, usually increased acoustical performance comes at the cost of increased difficulty in operating the doors.) However, it may be worthwhile consulting a specialist contractor such as Pacific Sound Control on this matter.

Doug McDaniel

cell 949/231-7066

direct 714/277-1077

office 714/892-6022

www.pacificsoundcontrol.com

In Scheme 2, it appears that these doors would not be required. Under this scenario, our acoustical recommendation would be to leave the doors in place and to build new drywall partitions on each side the opening.

D. HVAC Noise Control for New Mechanical Systems

The new mechanical system should be designed to achieve a noise level of NC-30 or below when the Auditorium and Stage is used for Performances and gatherings. This will require a number of cost-impactful measures including:

- i. Selecting relatively quiet mechanical equipment
- ii. Airborne noise control for fans using duct silencers and acoustically lined duct work.
- iii. Keeping air velocities to relatively slow speeds.
- iv. Vibration isolation of main mechanical equipment.
- v. Selecting diffusers and grills for manufacturers NC ratings of NC-20 or below.

11. Theatre Proposed Improvements

A. Summary

In order to use the building for rental events in between sports events, the critical element is the speed at which the venue can be converted from one use to another. This would include opportunities such as being able to load in on the stage, or use the stage, while a sports event is taking place on the main floor. It also involves examining what elements can be automated, where power is located, and other infrastructure items. Some capabilities are major investments but can reduce the time needed to shift between events by hours or even days. With an available window of half a day to a day to make that turn between events, access and automation will be critical to making the building viable as a rental space.

It is also important to examine what features/capabilities groups coming in will expect to have. Being able to meet those requirements makes the difference between a space that groups want to come to and a facility that is difficult to rent. Discussions with staff have indicated that the likely types of desired rental uses may include:

- i. Concerts
- ii. Film/TV/Commercial Production
- iii. Corporate Events
- iv. Sports Tournaments (non district)
- v. Cheerleading Tournaments
- vi. eSports Tournaments
- vii. One night shows (comedy, magic, Food Network, etc.)
- viii. Banquets/Galas/Ted Talks
- ix. Church Groups
- x. Movie Presentations

District uses would include:

- i. Sports (Basketball, Volleyball, Wrestling)
- ii. Commencement
- iii. Prom

The facility is not intended to support symphony concerts, musical theatre or other similar events requiring superior sightlines and acoustics.

The facility will be operated primarily by union personnel, either district or contract labor, although some groups will bring their own labor. This establishes some additional requirements and expectations in terms of support spaces and amenities.

The team believes both schemes are workable but leaving the fly space intact offers the potential for the fastest turnaround from event to event due to the ability to fly a curtain package out of the way without having to remove the curtains from the tracks.


B. Theatrical Power

The existing power should be reworked. The goal would be to maintain similar accommodation for outside groups coming in, but with revised locations and voltages. In particular, the 48ov feed would be reduced or replaced and the majority of the temporary power would be converted to 208v in keeping with what modern production companies are expecting. For concert and production use, temporary power connections and distribution would need to be made available at the new production grid over the main floor as well as at the walkable grid above the stage (either the existing grid or a new grid).

C. Rigging

In scheme 2, the existing walkable grid would either be repaired or replaced and a new access ladder system installed. The existing counterweight rigging would be removed and replaced with the same limited set of motorized hoists for school uses. This scheme offers time savings for event changeover, as items can be lifted up out of the way rather than having to be completely removed. It also provides maximum space for events such as concerts, that may desire to use a larger stage area, as the proscenium height and width are not impacted. If scheme 2 is chosen, a new fire curtain would be required.

Concert acts and other groups coming in will expect, and need, to suspend items over the main floor – particularly in the area between the proscenium and the catwalk. We recommend that the existing suspended ceiling be demolished and replaced with a walkable grid, or walkable areas, that cover the entire floor. New ceiling elements could be suspended below the grid. This allows fast access to rigging points so that events can be loaded in as quickly, and safely, as possible. Removal of the existing ceiling will also simplify things like incorporating sports court lighting, both for practices and for TV/Internet broadcast of games. Depending on the design, the new grid may also replace the existing catwalk.




D. Curtains

The existing curtain package should be replaced, but there is a legitimate question as to how extensive the need is for stage curtains. Certainly, some events will want a main curtain, and some legs and borders to mask off points of entry and technical elements. Other events, such as concert tours, may not need these items. Since musicals are not anticipated, that reduces the need for curtains, but some other types of shows, such as magic shows and even corporate events, use them more than in the past. A basic curtain package will be required, but the extent of that package would need to be carefully considered during design. All curtains should be sewn using inherently flame retardant (IFR) fabrics rather than fabrics which have been treated with a fire retardant chemical (which require regular testing and reapplication of the treatment).

E. Audio

A basic system that supports school sports and event uses of the building would be installed. This system would also be usable for basic rental events, such as corporate meetings or presentations. Audio for ancillary spaces, such as the lobby, would also be part of the permanently installed systems.


Infrastructure should be added to support large audio systems brought in by concerts or other outside groups. This infrastructure would include power, cable pathways, interconnections to some permanent systems (such as the lobby speakers), and structural attachment points for speaker suspension. The existing speaker locations would be retained, but the weight load capacity of those locations would need to be upgraded and new locations either immediately adjacent to or directly behind those locations would need to be added. Space within the seating area would need to be designated for the audio mixing console, and conduit and power provided to it. That might be a location similar to this:




Systems would need to be able to operate in different modes and at different levels of staffing, including a simple mode that does not require an operator at all (for sports events and lectures). As the building is expected to be flexible and to scale between different sizes/types/styles of events, the systems need to do the same.

F. Video

Since there is no video system or video infrastructure existing, everything would need to be installed new. Evaluation of options indicates that a center hung scoreboard presents both height and structural challenges. We would propose hanging two LED screens, approximately 12' \times 21' - 4" in size, on either side of the proscenium opening. These screens would serve multiple uses, including presentations, image magnification (IMAG), and scoreboards. A separate screen at the rear corner(s) of the auditorium and/or portable screens would be used to provide video support to patrons on the stage side of a sports court.



Infrastructure consisting of pathways, cabling, and patching for cameras and connections to TV truck parking would be added. This infrastructure system would allow incoming groups to drop their equipment where needed with a minimum of cable running across the floor. Connections for computer inputs at the stage, courtside/scorer's table, audio mix booth, and lighting booth would also be added. Some possible camera platform locations may include:



A permanent system of 3 or more PTZ cameras would be used for livestreaming and could also be used for image magnification. These cameras, or one or more Point of View (PoV) cameras would be used to provide video monitoring to the lobby, backstage and other support areas.

G. Theatrical Lighting

Since this building was last upgraded, theatrical lighting has moved to LED based technology. This greatly reduces the power infrastructure (and consumption) required. Permanent theatrical lighting and controls should be installed to support school and sports events. The theatrical controls should also control the architectural lighting, as well as new work lighting at the stage, grid and catwalk(s). Running lights (blue lights) should be installed in the stagehouse and surrounding circulation areas.

In order to provide adequate lighting angles to the stage, a second catwalk, as well as attachment points for temporary lighting trusses, should be added to the ceiling system. If a tension grid is created as part of the new production grid, it can function as a highly flexible catwalk system and new catwalks would not be needed. This would also allow the existing catwalk location to be demolished. It would be highly desirable to be able to add box boom locations forward of the proscenium, but due to the historic nature of the sidewalls this is not possible. The new production grid will allow light ladders to be suspended for this purpose when needed for a particular event.


The permanent systems, and the lighting electrical and data distribution, should mesh easily with lighting elements and systems brought in by external groups. The permanent system should include enough lighting instruments to provide a repertory plot for the entire stage and Orchestra lift area so that school uses and simpler events can use the space without needing to bring in lighting or spend significant time refocusing.


H. Main Floor

One of the major questions to be resolved was whether to use the tilt mechanism of the main floor, or whether to fix the floor in the flat position. As stated previously, the sight lines from the sloped floor are not ideal and the slope would need to be reduced in order to comply with ADA regulations. This would further degrade the sightlines for the back half of the floor seating. There are a number of accessibility challenges and other issues to solve related to the interface between the tilting slab and the adjoining areas. These are discussed in the architectural report.

From a seating standpoint, it may be possible to have custom chairs made with longer legs in the front so that they sit flat on the sloped floor. It is unknown whether DSA would approve this. Other methodologies, such as permanent seating on rotating mechanisms that would store below the floor, were considered and rejected as not realistic for various reasons.

The team's recommendation is to fix the main floor in the flat position and use stage lifts and temporary platforming to raise the stage. The resulting sightlines will still not be ideal but are adequate for the types of events proposed for the space. The addition of video screens and image magnification will also help to resolve some of the sightline issues.






I. Orchestra Pit

The existing pit lift needs to be replaced, as well as the safety interlocks to the various pit access points. The new lift may want to be slightly narrower than the existing lift, with the end pieces becoming permanent floor that is fixed in place. These end areas would provide an opportunity for ramping if the new sports floor is built on top of the existing slab and ends up higher than the existing stage floor.

The new lift should be able to travel above the floor level, to approximately 5'. This allows multiple stage levels to be created depending on the height the lift is raised to. The lift should also connect to the new upstage lift so that it can be part of a contiguous stage floor or be used to create a multi level stage.

J. Stage Floor

We propose installing a new lift, or lifts, in the stage area. The new lift should be approximately 40' in width by 20' in depth and be able to travel to approximately 5' above the current stage floor level. It should also be able to connect with the orchestra lift to create one large platform when desired.



The new lift(s) would be used to create a raised stage, for better sightlines, as well as a freight elevator to move items between the main floor and the basement storage level. Excavation of the basement area will be required in order to accommodate the new lift, and some structural modifications of the existing stage framing may also be necessary. The new excavation for the lift would be \sim 6' in depth for the full footprint of the lift.

The floor itself may need to be replaced if the sports court is built on top of the existing slab. Rebuilding the stage floor would allow it to be raised the same amount, so that the stage, orchestra pit lift, and main floor all match in elevation. However, ramping would need to be created around the perimeter of the stage to meet up with the adjoining floor level. It may be more useful to raise the loading dock area the same amount than to try and ramp the loading path to the stage. Cutting into the stage floor to install new lift locations will require containment considerations.

K. Audience Seating

The existing seating is in good enough condition that, if the type of seating is considered appropriate, it could simply be repaired as needed and retained. It probably has another decade of service life available. However, some reorganization of the seating will be required, both to resolve code issues and to provide new amenities such as camera platforms, an audio mix position, and scorer's table. There is an open question as to whether these seats could be matched if parts or a few new seats were needed to accommodate the modifications.


If the seating is replaced, it should be replaced with a higher quality seat. The goal would be to improve maintenance requirements, through the selection of a seat with a gravity-rise mechanism rather than a spring based mechanism, and to improve patron comfort. The new seat would have a padded back and bottom but would not necessarily be upholstered. It could have a surface similar to those used in club seating areas at stadiums that are easily washable/cleanable.



L. Support Spaces

There are many existing support spaces in the building, from dressing rooms to electrical rooms. Some of them would be repurposed since the new program for the facility does not require them (e.g. there will not be a need for so many dressing rooms). However, a few spaces that will be necessary do not exist due to the age of the building. One or more AV Rack Room(s) will be needed to house backend AV equipment. A control room will be needed for IMAG and Livestream production. And theatrical lighting and rigging control distribution equipment may need its own space as well. Storage for technical equipment will need to be dedicated to that purpose and not just lumped in with general storage.


3.3.3 AXONOMETRIC




SCHEME 2


SCALE: N.T.S











LEGEND

VISITOR LOCKERS & OFFICIALS CHANGING ATHLETIC


> STUDENT LOCKERS COACHES LOCKERS & OFFICES ATHLETIC TRAINERS

> > TICKET & CONCESSIONS COMPETITION + PRACTICE COURT

STAGE RESTROOM

THEATRE DRESSING SERVICE & STORAGE


FUD OFFICE






















SCHEME 2 - BUILDING SECTION
Scale: 3/64" = 1'-0"



3.3.4 CODE JUSTIFICATION

- A. Scheme 2 re uses the existing building as a competition gymnasium and performance space. The athletic, wrestling and locker/support spaces are housed in a new addition at the east side of the building, while a new addition at the west side of the building houses a rentable Community Room and supporting kitchen along with visitor team and official rooms. Information has been gathered from the existing documents available at this time but will warrant further research and confirmation as the project progresses.
- B. Analysis per CBC 2022 and DSA IR A 26 (5/30/2019)

2. Scheme 2 Building Code Justification

- A. Type II A building justified under 506.2.2 Mixed Occupancy Buildings with non-separated occupancies analysis per 508.3.2 using A 1 as the most stringent occupancy. Fully compliant automatic sprinkler system and fire alarm system. Building is split into 2 fire areas, separated by a 2 hour fire wall with openings protected accordingly. (707.3.10)
 - i. West Building 49,671 sf
 - ii. East Building 21,734 sf



B. Occupancies / Occupant Load Factors

- i. Auditorium space two scenarios
 - a. Performance A 1 w/ occupant load of 7 net for non fixed seat areas, and actual seat quantity for fixed seats
 - b. Gymnasium A 4 w/ occupant load of 7 net for non fixed seat areas, and actual seat quantity for fixed seats and bleachers
- ii. Stage A 1 w/occupant load factor of 15 net
- iii. Wrestling Room A 3 w/ occupant load factor of 50 gross
- iv. Locker Rooms E w/ occupant load factor of 50 gross
- v. Offices B w/ occupant load factor of 150 gross
- vi. Storage S 1 w/ occupant load factor of 300 gross
- vii. Community Room A 2 w/occupant load factor of 15 net
- viii. Kitchen A 2 w/occupant load factor of 200 gross

- C. Building Height (504 and Table 504.3)
 - i. Allowed: 85'
 - ii. Actual: 80'
- D. Building Stories (504 and Table 504.4)
 - i. Allowed: 4 stories (without area increase)
 - ii. Actual: 3 stories
- E. Building Area West Building (506 and Table 506.2)
 - i. Allowed Area per floor: (with frontage of 0.5)
 - a. $A_a = [A_t + (NS \times I_f)]$
 - b. $A_a = [46,500 + (15,500 \times 0.5)]$
 - c. $A_a = 54,250$ sf per floor
 - ii. Actual Area (on largest floor): 49,671 sf
- F. Building Area East Building (506 and Table 506.2)
 - i. Allowed Area per floor: (no frontage)
 - a. $A_a = [A_t + (NS \times I_f)]$
 - b. $A_a = [46,500 + (15,500 \times 0)]$
 - c. $A_a = 46,500 \text{ sf per floor}$
 - ii. Actual Area (on largest floor): 21,734 sf

3.3.5 FIXTURE COUNTS

1. References

- A. CA Plumbing Code 2022 Chapter 4
 - i. Table 4 1 Occupant Load Factor
 - ii. Table 422.1 Miniumum Plumbing Facilities
- B. DSA IR A 26 K 12 Occupancy Classification and Occupant Load Factors (latest version 5/30/2019)

2. Calculations

- A. Auditorium Spectators
 - Fixtures provided meet the minimums based on the Performance Use calculationin below, and are provided throughout multiple restrooms in the north and west lobbies.
 - ii. Performance Use (A 1 per IR A 26)
 - iii. Fixed Seats per Table 4.1 use 50% of fixed seating value for occupant load factor → 958 seats total x 50% = 479 occupants
 → 240 female, 240 male
 - iv. Open Area seating per Table 4.1 use occupant load factor of 11 \rightarrow 10,289 net sf/11 = 936 occupants \rightarrow 468 female, 468 male
 - v. Total occupants → 708 female, 708 male
 - vi. Total required fixtures per Table 422.1 for A 1 (A 1 per IR A 26)

| WCs Female | 8: 301 400 + 1 WC per add'l 125 | 11 | ļii. |
|-----------------------|--|----|------|
| WCs Male * | 3: 201 400 + 1 WC per add'l 500 | 4 | v. |
| Urinals Male * | 4: 401 600 + 1 urinal per add'l 300 | 5 | ۷. |
| Lavs Female | 6: 501 750 | 6 | |
| Lavs Male | 4: 601 750 | 4 | |
| Drinking Fountains | 3: 501 750 + 1 df per add'l 500 | 5 | |

^{*} Increase total of male fixtures to equal female

- B. Athletic Use (A 4 per IR A-26)
 - i. Fixed Seats per Table 4.1 use 50% of fixed seating value for occupant load factor → 958 seats total x 50% = 479 occupants
 → 240 female, 240 male

- ii. Fixed Seats in new bleachers per Table 4.1 use 50% of fixed seating value for occupant load factor → 220 seats total x 50% = 110 occupants → 55 female, 55 male
- iii. Total occupants → 295 female, 295 male
- iv. Total required fixtures per Table 422.1 for A 4(A 4 per IR A 26)

| WCs Female | 6: 201 300 | 6 |
|-----------------------|------------|---|
| WCs Male * | 3: 201 400 | 3 |
| Urinals Male * | 3: 201 400 | 3 |
| Lavs Female | 4: 201 300 | 4 |
| Lavs Male | 2: 201 400 | 2 |
| Drinking Fountains | 3: 501 750 | 3 |

^{*} Increase total of male fixtures to equal female

- C. 1st Floor FUD Offices
 - i. 1,000 sf total
 - ii. Per Table 4.1 Use occupant load factor of 150 (Business) →
 1,000 / 150 = 7 occupants → 4 female, 4 male
 - iii. Total required fixtures per Table 422.1 for B

| WCs Female * | 1: 1 15 | 1 |
|--------------------|-----------|---|
| WCs Male | 1:1 50 | 1 |
| Urinals Male | 1: 1 100 | 1 |
| Lavs Female | 1:1 50 | 1 |
| Lavs Male | 1: 1 75 | 1 |
| Drinking Fountains | 1 per 150 | 1 |

^{*} Increase total of female fixtures to equal male

- iv. Fixtures provided in the west spectactor restrooms
- D. 1st floor Athletes and Coaches
 - i. 17,727 sf total (Auditorium 9,327 sf + Athletics Room 3,000 sf + Athletic Training Room 400 sf + Wrestling Room 5,000 sf)
 - ii. Per Table 4.1 Use occupant load factor of 50 (Exercise) \rightarrow 17,727 / 50 = 355 occupants \rightarrow 178 female, 178 male
 - iii. Total required fixtures per Table 422.1 for A 3 (A 3 per "Exercise Room" in IR A 26)

| WCs Female | 4: 101 200 | 4 |
|----------------|------------|---|
| WCs Male * | 2: 101 200 | 2 |
| Urinals Male * | 2: 101 200 | 2 |
| Lavs Female | 2: 101 200 | 2 |
| Lavs Male | 1:1 200 | 1 |
| Drinking | | 2 |
| Fountains | 2: 251 500 | _ |

^{*} Increase total of male fixtures to equal female

- iv. Fixtures provided in athletic locker rooms (coach and student)
- E. 1st Floor Stage
 - i. 5,080 sf total
 - ii. Per Table 4.1 Use occupant load factor of 11 (Assembly) \Rightarrow 5,080 / 11 = 462 occupants \Rightarrow 231 female, 231 male
 - iii. Total required fixtures per Table 422.1 for A 1

| WCs Female | б: 201 300 | 6 |
|-----------------------|------------|---|
| WCs Male * | 3: 201 400 | 3 |
| Urinals Male * | 2: 201 300 | 2 |
| Lavs Female | 4: 201 300 | 4 |
| Lavs Male | 2: 201 400 | 2 |
| Drinking Fountains | 2: 251 500 | 2 |

^{*} Increase total of male fixtures to equal female

- iv. Fixtures provided in Theater dressing areas adjacent to stage
- F. 1st Floor Community Room
 - i. 3,400 sf total
 - ii. Per Table 4.1 Use occupant load factor of 11 (Assembly) \Rightarrow 3,400 / 11 = 309 occupants \Rightarrow 155 female, 155 male
 - iii. Total required fixtures per Table 422.1 for A 1

| 10.00 E 10.00 | | |
|-----------------|------------|---|
| WCs Female * | 4: 101 200 | 4 |
| WCs Male | 2: 101 200 | 3 |
| Urinals Male | 2:101 200 | 2 |
| Lavs Female | 2: 101 200 | 2 |
| Lavs Male | 1: 1 200 | 1 |
| Drinking | | 2 |
| Fountains | 2: 251 500 | _ |

- * Increase total of female fixtures to equal male
- iv. Fixtures provided in RR's adjacent to Community Room
- G. 1st Floor Kitchen
 - i. 888 sf total

- ii. Per Table 4.1 Use occupant load factor of 50 (Kitchen) \rightarrow 888 / 50 = 18 occupants \rightarrow 9 female, 9 male
- iii. Total required fixtures per Table 422.1 for A 2

| WCs Female * | 1: 1:25 | 1 |
|--------------|----------|---|
| WCs Male | 1:1 50 | 1 |
| Urinals Male | 1: 1 200 | 1 |
| Lavs Female | 1: 1 150 | 1 |
| Lavs Male | 1: 1 150 | 1 |
| Drinking | | 1 |
| Fountains | 1: 1 150 | ' |

^{*} Increase total of female fixtures to equal male

iv. Fixtures provided in RR's adjacent to Community Room



4.0 OPINION OF PROBABLE COST

Cumming Construction Management joined the Civic Auditorium Feasibility Study team to provide Rough Order Magnitude (R.O.M.) Statement of Probable Costs for the schemes developed on potential ways that SMMUSD and Santa Monica High School could utilize the Santa Monica Civic Auditorium. Cumming's report on the following pages provides those R.O.M. costs for the two re use schemes (1 and 2) previously described in this Feasibility Report.

In addition to these two R.O.M. costs, the costs for a 'baseline' scenario titled Scheme o have been included. Scheme o includes the estimated scope for bringing the Civic Auditorium building and surrounding site up to current code standards in a general use scenario. Scheme o includes scope needed to make structural, accessibility, and fire safety improvements to the facility, as well as updating systems to typical current standards. While the R.O.M. costs for Scheme o represent a baseline project scope, additional cost is anticipated to address a particular client's specific needs.

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude Statement of Probable Cost July 13, 2023



Credits

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



The information contained within this documents is confidential and should not be distributed or copied for any reason without the consent of either Cumming Construction Management, Inc. or the intended client.

Cumming has no control over the cost of labor and materials, the general contractor's or any subcontractor's method of determining prices, or competitive bidding and market conditions.

This opinion of the probable cost of construction is made on the basis of the experience, qualifications, and best judgment of a professional consultant familiar with the construction industry. However, Cumming cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from this or subsequent cost estimates.

This document reflects fair market value construction costs obtainable in a competitive bidding market in Los Angeles, California. Cumming assumes a minimum of three (3) competitive bids from qualified general contractors, with bids from a minimum of three (3) subcontractors per trade. This statement is a determination of fair market value for the construction of the project and is not intended to be a prediction of low bid. Please note that experience indicates a fewer number of bidders may result in a higher bid amount, thus more bidders may result in a lower bid result.

The Cumming staff of professional cost consultants has prepared this estimate in accordance with generally accepted principles and practices. This staff is available to discuss its contents with any interested party.



LA | Cumming Construction Management, Inc.

Executive Summary

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Project Description

The project is a feasibility study for developing/repurposing the Santa Monica Civic Auditorium Building approximately 61,000 square feet, located at 1855 Main Street, Santa Monica. The building was designated as a city of Santa Monica Landmark in 2002. As part of its initial due diligence, the District is seeking the services of an Architectural firm the analyze the Site including whether it could be brought into compliance with California Department of Education and Field Act compliance project. If acquired, the plan would be for Santa Monica High School to use the building as a sports and entertainment venue.

| | | Scheme | 0 | | Scheme | 1 | | Scheme | 2 |
|------------------------------|-------------|---------|---------------|------------|---------|---------------|------------|---------|---------------|
| A. Construction Costs | Area | \$ / SF | Total Cost | Area | \$ / SF | Total Cost | Area | \$ / SF | Total Cost |
| Building | 61,098 SF | \$1,469 | \$89,739,102 | 73,899 SF | \$1,344 | \$99,355,140 | 91,098 SF | \$1,353 | \$123,290,405 |
| Site Development | 124,130 SF | \$71 | \$8,857,373 | 121,130 SF | \$96 | \$11,568,173 | 103,676 SF | \$103 | \$10,645,005 |
| Total Construction Costs | 61,098 SF | \$1,614 | \$98,596,474 | 73,899 SF | \$1,501 | \$110,923,313 | 91,098 SF | \$1,470 | \$133,935,410 |
| Off-site/Public Right-of-way | (Allowance) | | \$2,000,000 | | | \$2,000,000 | | | \$2,000,000 |
| Hazmat Abatement (Allowar | nce) | | \$2,894,694 | | | \$2,894,694 | | | \$2,894,694 |
| Total Construction Costs | 61,098 SF | \$1,694 | \$103,491,168 | 73,899 SF | \$1,567 | \$115,818,007 | 91,098 SF | \$1,524 | \$138,830,104 |

Cost Difference from Scheme 0 \$12,326,839 \$35,338,935

Note:

Scope is based on "220522_SMCA_Draft Report" dated May 2023 and meeting on 5/31/23 for Scheme 0 by NAC and Santa Monica-Malibu Unified School District

- 220522_SMCA_Draft Report dated May 2023
- SMCA Architectural Scope mark-ups
- Meeting on 5/31/23 for Scheme 0 by NAC
- Civic Auditorium environ (Hazmat) report by NV5 dated May 2023
- SMCA Theater Narrative & Budgets by Salas O'Brien

Market Escalation - Included to construction mid point in Jan 2027 (Based on Jan 2026 construction start at 4.5% per year)

Construction Contingency - Excluded

Soft Costs - Excluded

Hazmat Abatement - Included

Off Site Work - Cost Included as Allowance

FF&E (Any Movable furniture) - Excluded

Elemental Comparison Cost Summary

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| Element | | Scheme (| 0 | Scheme : | 1 | Scheme : | 2 |
|--|--------|--------------|----------|---------------|----------|---------------------|----------|
| | | 61,098 SF | S/SF | 73,899 SF | S/SF | 91,098 SF | \$/SF |
| A) Shell (1-5) | | \$27,967,035 | \$457.74 | \$32,532,443 | \$440.23 | \$43,597,368 | \$478.58 |
| 1 Foundations | | \$3,829,822 | \$62.68 | \$4,599,822 | \$62.24 | \$11,349,822 | \$124.59 |
| 2 Vertical Structure | | \$9,921,650 | \$162.39 | \$12,737,450 | \$172.36 | \$15,810,375 | \$173.55 |
| 3 Floor & Roof Structures | | \$8,232,856 | \$134.75 | \$7,721,892 | \$104.49 | \$8,361,452 | \$91.79 |
| 4 Exterior Cladding | | \$4,191,950 | \$68.61 | \$5,556,182 | \$75.19 | \$5,757,094 | \$63.20 |
| 5 Roofing and Waterproofing | | \$1,790,757 | \$29.31 | \$1,917,097 | \$25.94 | \$2,318,625 | \$25.45 |
| B) Interiors (6-7) | | \$4,803,711 | \$78.62 | \$3,654,274 | \$49.45 | \$4,943,631 | \$54.27 |
| 6 Interior Partitions, Doors and Glazing | | \$1,731,248 | \$28.34 | \$1,478,648 | \$20.01 | \$1,911,888 | \$20.99 |
| 7 Floor, Wall and Ceiling Finishes | | \$3,072,463 | \$50.29 | \$2,175,626 | \$29.44 | \$3,031,743 | \$33.28 |
| C) Equipment and Vertical Transportation (8-9) | | \$4,761,682 | \$77.94 | \$4,596,956 | \$62.21 | \$4,741,832 | \$52.05 |
| 8 Function Equipment and Specialties | | \$4,402,682 | \$72.06 | \$3,633,956 | \$49.17 | \$3,982,832 | \$43.72 |
| 9 Stairs and Vertical Transportation | | \$359,000 | \$5.88 | \$963,000 | \$13.03 | \$759,000 | \$8.33 |
| D) Mechanical and Electrical (10-13) | | \$15,129,083 | \$247.62 | \$16,841,048 | \$227.89 | \$18,991,553 | \$208.47 |
| 10 Plumbing Systems | | \$2,561,666 | \$41.93 | \$2,909,330 | \$39.37 | \$3,395,666 | \$37.27 |
| 11 Heating, Ventilation and Air Conditioning | | \$4,483,782 | \$73.39 | \$4,833,156 | \$65.40 | \$5,465,885 | \$60.00 |
| 12 Electrical System | | \$7,514,936 | | \$8,412,221 | \$113.83 | \$9,285,603 | |
| 13 Fire Protection Systems | | \$568,700 | \$9.31 | \$686,341 | \$9.29 | \$844,400 | \$9.27 |
| E) Building Prep & Demo (14-15) | | \$1,062,796 | \$17.39 | \$1,856,442 | \$25.12 | \$1,536,157 | \$16.86 |
| 14 Building Preparations & Protection | | \$125,000 | \$2.05 | \$170,000 | \$2.30 | \$145,000 | \$1.59 |
| 15 Building Demolition | | \$937,796 | \$15.35 | \$1,686,442 | \$22.82 | \$1,391,157 | \$15.27 |
| F) Site Work (16-18) | | \$5,302,663 | \$86.79 | \$6,925,544 | \$93.72 | \$6,372,869 | \$69.96 |
| 16 Site Preparation and Demolition | | \$1,682,715 | \$27.54 | \$1,666,215 | \$22.55 | \$1,570,218 | \$17.24 |
| 17 Site Paving, Structures & Landscaping | | \$2,642,948 | \$43.26 | \$4,132,329 | \$55.92 | \$3,675,651 | \$40.35 |
| 18 Utilities on Site | | \$977,000 | \$15.99 | \$1,127,000 | \$15.25 | \$1,127,000 | \$12.37 |
| Sub-Total Direct Construction Cost | | \$59,026,970 | \$966 | \$66,406,706 | \$899 | \$80,183,409 | \$880 |
| Design/Cost Contingency | 20.00% | \$11,805,394 | \$193.22 | \$13,281,341 | \$179.72 | \$16,036,682 | \$176.04 |
| Market Escalation | 16.54% | \$11,713,828 | | \$13,178,328 | | \$15,912,297 | |
| Total Direct Construction Cost | | \$82,546,193 | \$1,351 | \$92,866,375 | \$1,257 | \$112,132,388 | \$1,231 |
| Total Direct Construction Cost | | 702,340,133 | 71,331 | 732,800,373 | 71,237 | J112,132,388 | 71,231 |
| General Conditions | 8.50% | \$7,016,426 | | \$7,893,642 | | \$9,531,253 | |
| General Requirements | 4.00% | \$3,301,848 | | \$3,714,655 | | \$4,485,296 | |
| Subcontractor Default Insur. | 1.00% | \$825,462 | | \$928,664 | - | \$1,121,324 | |
| General Liability Insurance | 1.20% | \$1,114,374 | | \$1,253,696 | | \$1,513,787 | |
| Overhead & Profit | 4.00% | \$3,792,172 | \$62.07 | \$4,266,281 | \$57.73 | \$5,151,362 | \$56.55 |
| Sub-Total Indirect Construction Cost | | \$16,050,282 | \$263 | \$18,056,938 | \$244 | \$21,803,022 | \$239 |
| Total Construction Cost | | \$98,596,474 | \$1,614 | \$110,923,313 | \$1,501 | \$133,935,410 | \$1,470 |

Construction Cost Detail

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude July 13, 2023



Scheme 0

Direct Construction Cost Summary - Scheme 0

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| Element | | Building 61,098 SF | | Site Developm 124,130 SF | ent | Total Cost 61,098 SF | : |
|---|---|---|---|--|--|---|---|
| | | Total | \$/SF | 124,130 3F | \$/SF | Total | \$/SF |
| A) Shell (1-5) 1 Foundations 2 Vertical Structure 3 Floor & Roof Structures 4 Exterior Cladding 5 Roofing and Waterproofing | | \$27,967,035 \$3,829,822 \$9,921,650 \$8,232,856 \$4,191,950 \$1,790,757 | \$457.74 \$62.68 \$162.39 \$134.75 \$68.61 \$29.31 | | | \$27,967,035 \$3,829,822 \$9,921,650 \$8,232,856 \$4,191,950 \$1,790,757 | \$457.74 \$62.68 \$162.39 \$134.75 \$68.61 \$29.31 |
| B) Interiors (6-7)6 Interior Partitions, Doors and Glazing7 Floor, Wall and Ceiling Finishes | | \$4,803,711 \$1,731,248 \$3,072,463 | \$78.62 \$28.34 \$50.29 | | | \$4,803,711 \$1,731,248 \$3,072,463 | \$78.62 \$28.34 \$50.29 |
| C) Equipment and Vertical Transportation8 Function Equipment and Specialties9 Stairs and Vertical Transportation | (8-9) | \$4,761,682 \$4,402,682 \$359,000 | \$77.94 \$72.06 \$5.88 | | | \$4,761,682 \$4,402,682 \$359,000 | \$77.94 \$72.06 \$5.88 |
| D) Mechanical and Electrical (10-13) 10 Plumbing Systems 11 Heating, Ventilation and Air Condition 12 Electrical Lighting, Power and Commu 13 Fire Protection Systems | - | \$15,129,083 \$2,561,666 \$4,483,782 \$7,514,936 \$568,700 | \$247.62 \$41.93 \$73.39 \$123.00 \$9.31 | | | \$15,129,083 \$2,561,666 \$4,483,782 \$7,514,936 \$568,700 | \$247.62 \$41.93 \$73.39 \$123.00 \$9.31 |
| E) Building Prep & Demo (14-15)14 Building Preparations & Protection15 Building Demolition | | \$1,062,796 \$125,000 \$937,796 | \$17.39 \$2.05 \$15.35 | | | \$1,062,796 \$125,000 \$937,796 | \$17.39 \$2.05 \$15.35 |
| F) Site Work (16-18) 16 Site Preparation and Demolition 17 Site Paving, Structures & Landscaping 18 Utilities on Site | | \$0 | \$0.00 | \$5,302,663 \$1,682,715 \$2,642,948 \$977,000 | \$42.72 \$13.56 \$21.29 \$7.87 | \$5,302,663 \$1,682,715 \$2,642,948 \$977,000 | \$86.79 \$27.54 \$43.26 \$15.99 |
| Sub-Total Direct Construction Cost | | \$53,724,307 | \$879 | \$5,302,663 | \$43 | \$59,026,970 | \$966 |
| Design/Cost Contingency Market Escalation | 20.00% 16.54% | \$10,744,861 \$10,661,521 | | \$1,060,533 \$1,052,307 | \$8.54 \$8.48 | \$11,805,394 \$11,713,828 | \$193.22 \$191.72 |
| Total Direct Construction Cost | | \$75,130,690 | \$1,230 | \$7,415,502 | \$60 | \$82,546,193 | \$1,351 |
| General Conditions General Requirements Bonds General Liability Insurance Overhead & Profit | 8.50% 4.00% 1.00% 1.20% 4.00% | \$6,386,109 \$3,005,228 \$751,307 \$1,014,264 \$3,451,504 | \$49.19 \$12.30 \$16.60 | \$630,318 \$296,620 \$74,155 \$100,109 \$340,668 | \$5.08 \$2.39 \$0.60 \$0.81 \$2.74 | \$7,016,426 \$3,301,848 \$825,462 \$1,114,374 \$3,792,172 | \$114.84 \$54.04 \$13.51 \$18.24 \$62.07 |
| Sub-Total Indirect Construction Cost | | \$14,608,411 | \$239 | \$1,441,870 | \$12 | \$16,050,282 | \$263 |
| Total Construction Cost | | \$89,739,102 | \$1,469 | \$8,857,373 | \$71 | \$98,596,474 | \$1,614 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

Sub-Total: 1 Foundations

Sub-Total: 2 Vertical Structure

A) Shell (1-5)

1 Foundations

| Micro Piles - Assume no rock socket |
|---|
| Install new 14.5" dia piles, 40' deep at ends of new walls - 80 Piles |
| Install new 14.5" dia piles, 40' deep at ends of existing walls - 120 Piles |
| Pile Caps |
| New pile caps at new wall micro piles - Assume 8' x 8' x 24" |
| Existing Footing Widening - Reinforced concrete epoxy drilled into existing - 24" |
| deep x 4' wide each side |
| B disastlanda a sur |
| Miscellaneous |
| Elevator pits |
| Pit lifts - allowance for excavation and associated structural mod |

| 3,200 | VLF |
|--------|-----|
| 4,800 | VLF |
| | |
| 142 | CY |
| 35 | CY |
| | |
| | |
| 1 | EA |
| 1 | EA |
| | |
| 61,098 | SF |

| \$1,120,000 |
|-------------|
| \$2,016,000 |
| |
| \$312,889 |
| \$110,933 |
| \$20,000 |
| \$250,000 |
| |
| \$3,829,822 |
| |

2 Vertical Structure

| Shear Walls |
|--|
| New CIP concrete walls -24" thick |
| CIP concrete wall strengthening - Shotcrete Reinforced Concrete doweled into |
| existing wall, 18" thick |
| Elevator Shaft - 7' x 8'6", 25' high |
| |
| New Steel Framing |
| New diagonal bracing from projector room to Lower chord Truss Framing |
| New Steel allowance for Theater production grid, screens and speakers |
| |
| Shoring |
| Vertical Strong back shoring at Existing Concrete Screen panels |
| |

| 11,116 | SF |
|--------|----|
| | |
| 46,956 | SF |
| 2,975 | SF |
| | |
| | |
| 13 | TN |
| 15 | TN |
| | |
| | |
| 5,190 | SF |
| | |
| 61,098 | SF |
| · | |
| | |

| \$1,945,300 |
|-------------|
| |
| \$7,043,400 |
| \$291,550 |
| |
| |
| \$150,000 |
| \$180,000 |
| |
| |
| \$311,400 |
| |
| \$9,921,650 |
| |

3 Floor & Roof Structures

| Slab on grade | |
|---|--|
| Patch and repair existing SOG | |
| | |
| Suspended floors | |
| Repair / Refinish existing tilt flooring surface | |
| Tilt Floor Lock pin allowance | |
| Miscellaneous concrete levelling at balcony and walkway ramps | |

| 69,820 | SF |
|----------|----|
| | |
| | |
| 11,500 | SF |
| <u> </u> | J. |
| 11,500 | SF |
| 280 | SF |
| | |

| \$3.80 | \$265,316 |
|---------|-----------|
| | |
| | |
| \$12.00 | \$138,000 |
| \$25.00 | \$287,500 |
| \$25.00 | \$7,000 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| e | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|--------------|-------------|
| | | | | |
| New Steel Framing | | | | |
| Strengthening / bracing existing tilt floor framing | 23 | TN | \$12,000.00 | \$276,000 |
| Lower Chord Truss Framing | 64 | TN | \$12,000.00 | \$768,000 |
| Horizontal bracing at Canopy | 30 | TN | \$12,000.00 | \$360,000 |
| Allowance for all connections | 48 | TN | \$12,000.00 | \$576,480 |
| Roof | | | | |
| Upper Chord Truss Framing | 97 | TN | \$12,000.00 | \$1,164,000 |
| Roof Framing at East Wing (Committee) | 49 | TN | \$12,000.00 | \$590,400 |
| Acoustic metal deck at auditorium | 26,255 | SF | \$32.00 | \$840,160 |
| Miscellaneous | | | | |
| Seismic Separation at West Wing (Administration) | 65 | LF | \$150.00 | \$9,750 |
| New Catwalk systems Metal Catwalk and railing Allowance | 1 | LS | \$500,000.00 | \$500,000 |
| Renovation of two wings - allowance | 9,801 | SF | \$250.00 | \$2,450,250 |
| Sub-Total: 3 Floor & Roof Structures | 61,098 | SF | \$134.75 | \$8,232,856 |

4 Exterior Cladding

| Exterior finishes | | | | |
|--|--------|----|--------------|-------------|
| FRP wrap existing precast conc. Pylons and Beams | 10 | EA | \$306,250.00 | \$3,062,500 |
| Concrete block along north Façade | 813 | SF | \$42.00 | \$34,125 |
| Clean and refinish all exposed concrete | 9,247 | SF | \$10.00 | \$92,465 |
| Interior finish to exterior walls | | | | |
| Paint drywall | 545 | SF | \$36.00 | \$19,620 |
| Fascias, bands, screens and trim | | | | |
| Cement plaster soffits at canopy | 5,630 | SF | \$35.00 | \$197,050 |
| Windows, glazing and louvers | | | | |
| New storefronts - 1/4" tempered textured glazing and (2) 1/8" laminated, | | | | |
| tempered glazing with low e interlayer | 4,020 | SF | \$180.00 | \$723,600 |
| Clean and paint existing Louvers on south elevation | 1,680 | SF | \$8.00 | \$13,440 |
| Exterior doors, frames and hardware | | | | |
| Glazed entry doors | 3 | EA | \$9,300.00 | \$27,900 |
| Replace all exterior HM doors | 5 | EA | \$4,250.00 | \$21,250 |
| Sub-Total: 4 Exterior Cladding | 61,098 | SF | \$68.61 | \$4,191,950 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| le | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|-----------|------------|
| coofing and Waterproofing | | | | |
| Roofing | | | | |
| New Standing seam metal roof at main auditorium | 2,041 | SF | \$34.00 | \$69,394 |
| New TPO roofing at main auditorium - dome | 24,214 | SF | \$38.00 | \$920,132 |
| New TPO roofing at main auditorium - flat | 10,337 | SF | \$24.00 | \$248,08 |
| New TPO roofing at East Wing (Committee) | 8,200 | SF | \$24.00 | \$196,80 |
| New TPO roofing at West Wing (Administration) | 2,000 | SF | \$24.00 | \$48,00 |
| New TPO roofing at Canopy | 5,630 | SF | \$30.00 | \$168,90 |
| Caulking and sealants | 52,422 | SF | \$2.66 | \$139,44 |
| Sub-Total: 5 Roofing and Waterproofing | 61,098 | SF | \$29.31 | \$1,790,75 |

Total - A) Shell (1-5)

B) Interiors (6-7)

6 Interior Partitions, Doors and Glazing

| Partitions | |
|--|--------|
| Metal Stud Framed full height partition | 4,089 |
| | |
| Interior doors, frames and hardware | |
| HM doors allowance | 5 |
| HM doors at stairs | 5 |
| HM double door at orchestra pit | 1 |
| HM double door at Mechanical Rooms in level 3 | 1 |
| Sliding double door at auditorium entrance alongside existing historic door to | |
| remain - 16' wide, STC-53 | 1 |
| Miscellaneous Allowances - Partitions including doors | |
| Ticket Sales | 290 |
| Renovation of two wings - allowance | 9,801 |
| Sub-Total: 6 Interior Partitions, Doors and Glazing | 61,098 |

| \$28.34 | \$1,731,248 |
|-------------|-------------|
| | |
| \$150.00 | \$1,470,150 |
| \$12.00 | \$3,480 |
| | |
| | |
| \$80,000.00 | \$80,000 |
| \$4,300.00 | \$4,300 |
| \$4,300.00 | \$4,300 |
| \$3,000.00 | \$15,000 |
| \$3,000.00 | \$15,000 |
| | |
| | ,,- |
| \$34.00 | \$139,018 |
| | |

\$457.74 \$27,967,035

7 Floor, Wall and Ceiling Finishes

| Flooring | |
|----------|--|
| Orche | estra Lift floor refinish |
| Levele | ed wood platform at balconies |
| Repai | r and restore existing terrazzo in lobby |
| Ceran | nic floor tile at restrooms |
| Polish | ned concrete at Theater Dressing |
| Allow | ance for stage flooring |
| Sealed | d concrete at BOH |

| SF |
|----|
| SF |
| |

61,098

SF

EA EA EA

EΑ

SF SF

SF

| | included w/ lift |
|---------|------------------|
| \$32.00 | \$26,240 |
| \$25.00 | \$150,000 |
| \$30.00 | \$44,700 |
| \$5.00 | \$8,245 |
| \$22.00 | \$104,060 |
| \$2.50 | \$115,298 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| | Quantity | Unit | Unit Rate | Total Cost |
|--|----------|------|-----------|-------------|
| | | | | |
| Bases | | | | |
| New wall base throughout | 61,098 | SF | \$0.50 | \$30,549 |
| Ceramic tile cove base | 297 | LF | \$30.00 | \$8,910 |
| Wall Finishes | | | | |
| Wall protective Metal cladding on all exposed interior walls within auditorium | | | | |
| with acoustic backing - Allowance for acoustic metal panel and acoustic | | | | |
| perforated metal panel above 10' AFF and wall padding below | | | | |
| | 2,550 | SF | \$68.00 | \$173,400 |
| Ceramic wall tile at restrooms | 5,206 | SF | \$30.00 | \$156,188 |
| Paint Drywalls Walls | 8,178 | SF | \$1.50 | \$12,266 |
| Ceilings | | | | |
| Acoustic perforated gypboard ceiling at Auditorium | 8,335 | SF | \$22.00 | \$183,370 |
| ACT at Auditorium Lobby & Theater Dressing | 7,649 | SF | \$12.00 | \$91,788 |
| Miscellaneous Finish Allowances | | | | |
| Ticket sales booth fit out | 290 | SF | \$25.00 | \$7,250 |
| Renovation of two wings - allowance | 9,801 | SF | \$200.00 | \$1,960,200 |
| Sub-Total: 7 Floor, Wall and Ceiling Finishes | 61,098 | SF | \$50.29 | \$3,072,463 |

Total - B) Interiors (6-7) 61,098 SF \$78.62 \$4,803,711

C) Equipment and Vertical Transportation (8-9)

8 Function Equipment and Specialties

| Upholstering of existing fixed seating - Allowance | 1 | LS | \$150,000.00 | \$150,000 |
|---|--------|----|--------------|-------------|
| Upholstering of existing fixed seating - Allowance | 1 | LS | \$150,000.00 | \$150,000 |
| Blackout curtains in auditorium | 1 | LS | \$128,640.00 | \$128,640 |
| Orchestra Pit lift , 470 SF, 20' travel, multiple stops | 1 | LS | \$730,000.00 | \$730,000 |
| Stage lift , 17'4" x 43'3", 20' travel, multiple stops | 1 | LS | \$730,000.00 | \$730,000 |
| Cabinets, countertops and casework allowances | | | . , | · · · |
| Ticket Concessions | 2 | EA | \$5,000.00 | \$10,000 |
| Miscellaneous millwork allowance | 61,098 | SF | \$4.00 | \$244,392 |
| Renovation of two wings - allowance | 9,801 | SF | \$150.00 | \$1,470,150 |
| | | | | · |
| Sub-Total: 8 Function Equipment and Specialties | 61,098 | SF | \$72.06 | \$4,402,682 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|--------|-------------|------------|
| tairs and Vertical Transportation | | | | |
| Stairs | | | | |
| New Metal Pan/ conc. Treads Stair | | | | Not Requir |
| New handrails and nosing on existing stairs at basement | 1 | FLIGHT | \$5,000.00 | \$5,00 |
| New handrails and nosing on existing stairs | 14 | FLIGHT | \$6,000.00 | \$84,00 |
| Lobby Stair retrofit | 2 | EA | \$40,000.00 | \$80,00 |
| Elevators | | | | |
| Hydraulic Passenger elevator | 2 | STOPS | \$75,000.00 | \$150,00 |
| Savaria V-1504 Lift, 36" x 48" | 1 | EA | \$40,000.00 | \$40,00 |
| Sub-Total: 9 Stairs and Vertical Transportation | 61,098 | SF | \$5.88 | \$359,00 |
| al - C) Equipment and Vertical Transportation (8-9) | 61,098 | SF | \$77.94 | \$4,761,68 |

D) Mechanical and Electrical (10-13)

10 Plumbing Systems

| Г | | | | |
|---|--------|----|--------------|-----------|
| General Plumbing Equipment | | | | |
| Domestic water heater replacement (Air source heat pump allowance) | 1 | EA | \$250,000.00 | \$250,000 |
| Domestic water heater | 1 | EA | \$50,000.00 | \$50,000 |
| Kitchen water heater | 1 | EA | \$16,900.00 | \$16,900 |
| Circulating pump | 1 | EA | \$2,095.00 | \$2,095 |
| Expansion tank | 1 | EA | \$558.90 | \$559 |
| Remove and replace grease interceptor | 1 | EA | \$37,550.00 | \$37,550 |
| Sanitary Fixtures | | | | |
| Fixture replacements, high eff | 1 | EA | \$95,000.00 | \$95,000 |
| Vacuum breakers and hose bibs | 1 | LS | \$2,500.00 | \$2,500 |
| Anti-scald tempering valves | 1 | LS | \$3,500.00 | \$3,500 |
| Drinking fountains, bottle filler | 1 | LS | \$5,368.00 | \$5,368 |
| Trap primer valve | 1 | LS | \$1,500.00 | \$1,500 |
| Domestic Cold Water | | | | |
| Domestic Cold Water Piping | 61,098 | SF | \$7.74 | \$472,899 |
| Water meter allowance | 1 | EA | \$5,000.00 | \$5,000 |
| Domestic Hot Water | | | | |
| Domestic Hot Water Piping | 61,098 | SF | \$8.09 | \$494,283 |
| Water meter allowance | 1 | EA | \$5,000.00 | \$5,000 |
| Domestic Cold/Hot Water Connections | | | | |
| HW/CW connections to new fixtures | 1 | LS | \$17,379.00 | \$17,379 |
| Isolation valves on lateral lines | 1 | LS | \$5,369.00 | \$5,369 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| ode | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|-------------|-------------|
| | | | | |
| Waste Piping | | | | |
| Waste Piping, SF | 61,098 | SF | \$9.15 | \$559,047 |
| Waste Piping, kitchen waste (allowance) | 1 | LS | \$85,000.00 | \$85,000 |
| Vent Piping | | | | |
| Vent Piping, SF | 61,098 | SF | \$2.82 | \$172,296 |
| Waste/Vent Connections | | | | |
| DMV connections to new fixtures | 1 | EA | \$11,877.00 | \$11,877 |
| Condensate Drainage | | | | |
| Trap and equipment connect | 11 | EA | \$421.50 | \$4,637 |
| 3/4" pipe, cu type L, in bldg | 275 | LF | \$38.55 | \$10,601 |
| Natural Gas | | | | |
| 4" seismic shut off valve | 1 | EA | \$4,527.00 | \$4,527 |
| Miscellaneous Plumbing | | | | |
| Test / clean plumbing | 150 | HR | \$112.23 | \$16,835 |
| Start-up/check-out | 180 | HR | \$134.67 | \$24,241 |
| Commissioning assist | 80 | HR | \$118.14 | \$9,451 |
| Access panels | 10 | EA | \$211.10 | \$2,111 |
| Piping identification | 25 | EA | \$26.70 | \$668 |
| Firestopping | 25 | EA | \$55.00 | \$1,375 |
| Seismic bracing | 1 | SF | \$45,000.00 | \$45,000 |
| Basement | 7,455 | SF | \$20.00 | \$149,100 |
| Sub-Total: 10 Plumbing Systems | 61,098 | SF | \$41.93 | \$2,561,666 |

11 Heating, Ventilation and Air Conditioning

| Chilled Water Equipment | | | | |
|---|--------|----|-------------|-----------|
| Chiller, air-cooled | 1 | EA | \$52,325.00 | \$52,325 |
| Glycol management system | 1 | EA | \$16,520.00 | \$16,520 |
| Relocate existing thermal energy storage system (allowance) | 1 | LS | \$40,800.00 | \$40,800 |
| CHW pump, end suction, 5 hp, 225 gpm | 2 | EA | \$5,099.00 | \$10,198 |
| VFD to CHW pump, 5 hp | 2 | EA | \$3,583.00 | \$7,166 |
| Heat exchanger | 1 | EA | \$8,006.00 | \$8,006 |
| Heating Hot Water Equipment | | | | |
| Hot water boiler, gas fired, condensing | 2 | EA | \$32,000.00 | \$64,000 |
| HW pump, end suction, 2 hp, 50 gpm | 2 | EA | \$4,267.00 | \$8,534 |
| VFD to HW pump, 3 hp | 2 | EA | \$3,339.00 | \$6,678 |
| Chilled Water Distribution | | | | |
| Chiller connect, weld, 6" | 1 | EA | \$9,327.00 | \$9,327 |
| CHW pump connect, weld, end suct, 4" | 2 | EA | \$9,051.00 | \$18,102 |
| CHW distribution | 61,098 | SF | \$7.39 | \$451,514 |

SMMUSD Santa Monica Civic Auditorium



| e | Quantity | Unit | Unit Rate | Total Cost |
|--|----------|----------|------------------------|---------------------|
| | | | | |
| Hot Water Distribution | | | | |
| Boiler connect, cu, 2" | 2 | EA | \$5,181.00 | \$10,362 |
| HHW pump connect, cu, 2" | 2 | EA | \$1,098.00 | \$2,196 |
| HHW coil connect, cu, 3-way, 1-1/4" | 8 | EA | \$1,266.00 | \$10,128 |
| HHW distribution | 61,098 | SF | \$7.04 | \$430,130 |
| Air-Side Equipment | | | | |
| Hydronic Fancoils | | | | |
| AHUS / Fan coil, 4-pipe, horizontal | 8 | EA | \$97,110.00 | \$776,88 |
| Ductless split systems | 2 | EA | \$10,500.00 | \$21,000 |
| Fans | | | 7 - 0,000 | ¥==,000 |
| Exhaust fans | 8 | EA | \$3,182.00 | \$25,456 |
| Kitchen exhaust fan | 1 | EA | \$13,300.00 | \$13,300 |
| MAU unit | 1 | EA | \$14,850.00 | \$14,850 |
| VFD to fan, 1.5 hp | 8 | EA | \$838.40 | \$6,70 |
| Air Distribution | | | | |
| Ductwork | | | | |
| Ductwork, galv, purchased prefab'd | 70,263 | LBS | \$14.85 | \$1,043,403 |
| Grease duct | 2,500 | LBS | \$15.03 | \$1,043,40 |
| | 52,365 | SF | \$2.69 | \$140,86 |
| Duct insulation, wrap Firemaster rated insulation | 3,000 | SF SF | \$30.49 | |
| | 472 | EA | | \$91,470 |
| Manual volume damper | | LF | \$75.24 | \$35,513 |
| Flexible duct, insulated, various sizes Grilles and diffusers | 280 | LF | \$20.41 | \$5,71 |
| Return Grilles | 30 | EA | \$140.70 | ¢4.22 |
| | 10 | EA | \$140.70 | \$4,22 |
| Exhaust grilles Ceiling diffusers | 432 | EA | \$164.30 | \$1,310 \$70,978 |
| | | | | |
| Miscellaneous | 450 | | 6424.24 | 450.00 |
| Test / balance HVAC | 450 | HR | \$131.31 | \$59,090 |
| Start-up/check-out | 375 | HR | \$119.38 | \$44,76 |
| Commissioning assist | 200 | HR | \$119.38 | \$23,870 |
| MEP Coordination | 275 | HR | \$119.38 | \$32,83 |
| Seismic bracing, pipe | 1 | LS | \$50,000.00 | \$50,00 |
| Seismic bracing, duct | 1 | LS | \$50,000.00 | \$50,00 |
| Hoisting and rigging Basement | 7,455 | LS SF | \$80,000.00 \$55.00 | \$80,00 \$410,02 |
| Buschneit | 7,433 | 31 | \$33.00 | 7410,02 |
| HVAC Controls | | | 640.400.00 | A.o.:- |
| DDC controls, chiller | 1 | EA | \$19,130.00 | \$19,13 |
| DDC controls, boiler | 1 | EA | \$15,310.00 | \$15,31 |
| DDC controls, pump wth vfd | 4 | EA | \$7,654.00 | \$30,61 |
| DDC controls, fancoil, 4-pipe | 6 | EA | \$30,000.00 | \$180,00 |
| DDC controls, general exhaust fan | 9 | EA | \$1,435.00 | \$12,91 |
| DDC controls, controls workstation | 1 | EA | \$40,000.00 | \$40,000 |
| Sub-Total: 11 Heating, Ventilation and Air Conditioning | 61,098 | SF | \$73.39 | \$4,483,782 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

12 Electrical Lighting, Power and Communications

| Service and Distribution | | | | |
|--|---|------|---|-------------|
| Replace all Existing Zinsco Panels/Feeders | 1 | LS | \$122,185.00 | \$122,185 |
| Replace all Existing Zinsco Pariety/Feders Replace all Existing Zinsco Distribution Boards in main electrical room | 1 | LS | \$90,000.00 | |
| Replace Existing MCC1 and MCC2 with Distribution board/add separate starters | 1 | L3 | \$90,000.00 | \$90,000 |
| or VFDs (supplied by MC installed by EC) | 1 | LS | \$100,000.00 | \$100,000 |
| Provide 400A rated kitchen Distribution Board to serve new all electric | | | , | 1 |
| commercial kitchen including new feeder | 1 | LS | \$25,920.00 | \$25,920 |
| HVAC and Plumbing equipment connections | | | | |
| HVAC and Plumbing equipment connections | 61,098 | SF | \$7.00 | \$427,686 |
| New kitchen equipment connections | 1 | LS | \$55,000.00 | \$55,000 |
| Provide new disconnect and panel to serve elevator loads on new elevator machine rooms including new feeders | 1 | LS | \$18,500.00 | \$18,500 |
| Convenience Power | 1 | LJ | \$18,500.00 | 710,300 |
| Update with GFCI protected receptacles required for most restrooms, janitor's | | | | |
| closets and kitchen spaces | 61,098 | SF | \$1.50 | \$91,647 |
| Lighting and Lighting Controls | | | | |
| Upgrade entire existing Lighting with LED fixtures and lighting controls with Title 24 code compliant controls | 61,098 | SF | \$33.50 | \$2,046,783 |
| Upgrade existing Stage Theatrical Lighting with LED fixtures and lighting controls with Title 24 code compliant controls | 61,098 | SF | \$4.50 | \$274,941 |
| Provide Theater Aisle Lighting with J-Box & wiring | 1 | LS | \$54,000.00 | \$54,000 |
| Theater Lighting package (per Salas O'Brien quote) | 1 | LS | \$850,000.00 | \$850,000 |
| Temporary Power | | | . , | . , |
| Temporary Power | 61,098 | SF | \$1.50 | \$91,647 |
| Miscellaneous | ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | | | 1- /- |
| Start-up, Third party testing, commissioning assist, labels, firestopping, pipe | | | | |
| penetrations, seismic and misc | 61,098 | SF | \$2.00 | \$122,196 |
| General conditions / General requirements - Includes Small Tools, Office Staffing, Indirect Labor, Consumables, Equipment Rental & General Expenses | 61,098 | SF | \$6.75 | \$412,412 |
| | | | | |
| Communications Technology - provide dedicated Signal Rooms at North and South ends of the | | | | |
| building. Provide MDF/MPOE and IDF room and fiber and copper backbone | 64.000 | C.F. | Ć4 25 | ¢76 272 |
| cabling. Install floor mounted data racks Audio Visual | 61,098 | SF | \$1.25 | \$76,373 |
| Addio Visuali | | | | |
| Provide AV equipment in new AV control room. Provide projector and projector screen, speakers, wireless mic and assistive listening & wiring | 61,098 | SF | \$2.50 | \$152,745 |
| Audio Visual - conduit rough-ins | , | | | |
| | 61,098 | SF | \$1.00 | \$61,098 |
| TV Broadcasting/Radio Infrastructure | 1 | LS | \$15,000.00 | \$15,000 |
| AV Equipment for Theater (per Salas O'Brien quote) | 1 | LS | \$1,770,000.00 | \$1,770,000 |
| | | | | |

SMMUSD Santa Monica Civic Auditorium



| de | Quantity | Unit | Unit Rate | Total Cost |
|--|---|-------------|--|---|
| Security Systems | | | | |
| Replace existing Security System - provide new keypads, access control on entry | | | | |
| points and motion sensors & wiring | 61,098 | SF | \$1.75 | \$106,92 |
| CCTV Systems | | | | |
| Provide new CCTV system with IP cameras & wiring/new head end equipment | 61,098 | SF | \$2.50 | \$152,7 |
| Fire Alarm Systems | | | | |
| Replace defective Fire alarm devices such as detectors, speaker/strobes per the | | | | |
| fie alarm testing report, connection to replaced Ansul fire suppression system | 61,098 | SF | \$6.50 | \$397,1 |
| | , | | | . , |
| Sub-Total: 12 Electrical Lighting, Power and Communications | 61,098 | SF | \$123.00 | \$7,514,9 |
| Fire Protection Systems | | | | |
| Backflow preventer, red press | 1 | EA | \$7,209.00 | \$7,2 |
| Provide new sprinklers and piping (stage, seating, lobby) | 61,098 | SF | \$6.28 | \$383,6 |
| Sprinkler replacement, various areas (corroded, painted and outdated) | 61,098 | SF | \$2.91 | \$177,7 |
| | | | | |
| Sub-Total: 13 Fire Protection Systems | 61,098 | SF | \$9.31 | \$568,7 |
| otal - D) Mechanical and Electrical (10-13) | 61,098 | SF | · | \$568,7 \$15,129,08 |
| otal - D) Mechanical and Electrical (10-13) Building Prep & Demo (14-15) | | | · | |
| otal - D) Mechanical and Electrical (10-13) | | | · | \$15,129,08 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items | 61,098 | SF | \$247.62 \$125,000.00 | \$15,129,08 \$125,0 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection | 61,098 | SF LS | \$247.62 | \$15,129,08 \$125,0 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items | 61,098 | SF LS | \$247.62 \$125,000.00 | \$15,129,08 \$125,0 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection Building Demolition | 61,098 | SF LS | \$247.62 \$125,000.00 | \$15,129,08 \$125,0 \$125,0 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection Building Demolition Structural Demolition | 61,098 | LS SF | \$247.62 \$125,000.00 \$2.05 | \$15,129,08 \$125,0 \$125,0 \$7,8 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection Building Demolition Structural Demolition Demo two additions to south of building in entirety | 61,098 1 61,098 | LS SF | \$247.62 \$125,000.00 \$2.05 | \$15,129,03 \$125,0 \$125,0 \$7,8 \$4,3 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection Building Demolition Structural Demolition Demo two additions to south of building in entirety Make opening in interior concrete wall - 4'6" Demo slab for elevator shafts | 61,098 1 61,098 | LS SF | \$247.62 \$125,000.00 \$2.05 \$7,800.00 \$75.00 | \$15,129,03 \$125,0 \$125,0 \$7,8 \$4,3 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection Building Demolition Structural Demolition Demo two additions to south of building in entirety Make opening in interior concrete wall - 4'6" Demo slab for elevator shafts Building Envelope Demolition | 1 61,098 1 61,098 | LS SF | \$247.62 \$125,000.00 \$2.05 \$7,800.00 \$75.00 \$75.00 | \$15,129,08 \$125,0 \$125,0 \$14,5 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection Building Demolition Structural Demolition Demo two additions to south of building in entirety Make opening in interior concrete wall - 4'6" Demo slab for elevator shafts | 61,098 1 61,098 | LS SF SF SF | \$247.62 \$125,000.00 \$2.05 \$7,800.00 \$75.00 | \$15,129,08 \$125,0 \$125,0 \$7,8 \$4,3 \$14,5 |
| Building Prep & Demo (14-15) Building Preparations & Protection Allowance to protect existing to remain scope items Sub-Total: 14 Building Preparations & Protection Building Demolition Structural Demolition Demo two additions to south of building in entirety Make opening in interior concrete wall - 4'6" Demo slab for elevator shafts Building Envelope Demolition Remove existing Glazing at Auditorium building | 61,098 1 61,098 1 59 195 | LS SF SF SF | \$247.62 \$125,000.00 \$2.05 \$7,800.00 \$75.00 \$75.00 | |

SMMUSD Santa Monica Civic Auditorium



| | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|-------------|------------|
| Interior Demolition | | | | |
| Remove all rigging systems | 1 | LS | \$85,000.00 | \$85,00 |
| Demo for new balcony - 3 rows of chairs and accessories | 1 | LS | \$69,000.00 | \$69,00 |
| Demo ticket and small kitchen | 530 | SF | \$20.00 | \$10,60 |
| Demo existing surface finishes at Auditorium building | 61,098 | SF | \$1.50 | \$91,64 |
| MEP Demolition | | | | |
| Remove fixtures, cap lines | 1 | LS | \$11,220.00 | \$11,22 |
| Remove fixtures and associated local pipe | 1 | LS | \$4,489.00 | \$4,48 |
| Remove ductwork & registers | 61,098 | SF | \$2.81 | \$171,68 |
| Remove HVAC equipment | 1 | LS | \$22,910.00 | \$22,91 |
| Selective trade demolition - Electrical | 61,098 | SF | \$2.50 | \$152,74 |
| Sub-Total: 15 Building Demolition | 61,098 | SF | \$15.35 | \$937,79 |
| al - E) Building Prep & Demo (14-15) | 61,098 | SF | \$17.39 | \$1,062,79 |

Construction Cost Detail - Site Development Scheme 0

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023

Total - F) Site Work (16-18)



F) Site Work (16-18) 16 Site Preparation and Demolition Selective demolition and removal Hardscape demolition allowance 124,130 SF \$2.00 \$248,260 Landscape demolition allowance 124.130 \$1.00 SF \$124.130 **General Site Grading** 124,130 SF \$2.00 \$248,260 **Erosion Control** 124,130 SF \$0.50 \$62,065 \$1,000,000 \$1,000,000.00 Phase 2 Clean-up 1 LS Sub-Total: 16 Site Preparation and Demolition 124,130 SF \$13.56 \$1,682,715 17 Site Paving, Structures & Landscaping Pedestrian paving allowance - includes asphalt / concrete paving 49,652 SF \$25.00 \$1,241,300 Site furnishing and accessories LS \$150,000.00 \$150,000 1 Landscape planting and maintenance 74,478 SF \$12.00 \$893,736 \$4,000.00 \$60,000 **New Trees** EΑ 15 Irrigation 74,478 SF \$4.00 \$297,912 \$2,642,948 Sub-Total: 17 Site Paving, Structures & Landscaping 124,130 \$21.29 18 Utilities on Site Storm Drain Storm drain underground piping including drain inlets, replacement of 8" 1.000 LF \$350.00 \$350,000 existing SD pipe Storm Water management - Mitigate 6,500CF of storm water including underground cistern and pretreatment system 1 LS \$150,000.00 \$150,000 Domestic and Fire Water Replace existing domestic and fire water system including connections 300 LF \$200.00 \$60,000 New Fire hydrant \$20,000.00 \$20,000 1 EΑ Sanitary Sewer Replace existing Sewer system including connections 500 \$250.00 \$125,000 Site Electrical Upgrade emergency genset from 30kW to 150kW including 150A ATS to 400A ATS and upgrade feeders LS \$197,000.00 \$197,000 Site Lighting Upgrade existing exterior Lighting with LED fixtures and lighting controls with Title 24 code compliant controls 1 LS \$75,000.00 \$75,000 Sub-Total: 18 Utilities on Site 124,130 SF \$7.87 \$977,000

124,130

SF

\$5,302,663

\$42.72

Construction Cost Detail

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude
July 13, 2023



Scheme 1

Construction Cost Summary - Scheme 1

SMMUSD Santa Monica Civic Auditorium



| Element | | Building | | Site Developm | ent | Total Cost | |
|--|--------|--------------|----------|---------------|---------|---------------|-----------|
| | | 73,899 SF | | 121,130 SF | | 73,899 SF | |
| | | Total | \$/SF | Total | \$/SF | | |
| A) Shell (1-5) | | \$32,532,443 | \$440.23 | | | \$32,532,443 | \$440.23 |
| 1 Foundations | | \$4,599,822 | \$62.24 | | | \$4,599,822 | \$62.24 |
| 2 Vertical Structure | | \$12,737,450 | \$172.36 | | | \$12,737,450 | \$172.36 |
| 3 Floor & Roof Structures | | \$7,721,892 | \$104.49 | | | \$7,721,892 | \$104.49 |
| 4 Exterior Cladding | | \$5,556,182 | \$75.19 | | | \$5,556,182 | \$75.19 |
| 5 Roofing and Waterproofing | | \$1,917,097 | \$25.94 | | | \$1,917,097 | \$25.94 |
| B) Interiors (6-7) | | \$3,654,274 | \$49.45 | | | \$3,654,274 | \$49.45 |
| 6 Interior Partitions, Doors and Glazing | | \$1,478,648 | \$20.01 | | | \$1,478,648 | \$20.01 |
| 7 Floor, Wall and Ceiling Finishes | | \$2,175,626 | \$29.44 | | | \$2,175,626 | \$29.44 |
| C) Equipment and Vertical Transportation (8- | 9) | \$4,596,956 | \$62.21 | | | \$4,596,956 | \$62.21 |
| 8 Function Equipment and Specialties | • | \$3,633,956 | \$49.17 | | | \$3,633,956 | \$49.17 |
| 9 Stairs and Vertical Transportation | | \$963,000 | \$13.03 | | | \$963,000 | \$13.03 |
| D) Mechanical and Electrical (10-13) | | \$16,841,048 | \$227.89 | | | \$16,841,048 | \$227.89 |
| 10 Plumbing Systems | | \$2,909,330 | \$39.37 | | | \$2,909,330 | \$39.37 |
| 11 Heating, Ventilation and Air Conditioning | | \$4,833,156 | \$65.40 | | | \$4,833,156 | \$65.40 |
| 12 Electrical Lighting, Power and Communic | ations | \$8,412,221 | \$113.83 | | | \$8,412,221 | \$113.83 |
| 13 Fire Protection Systems | | \$686,341 | \$9.29 | | | \$686,341 | \$9.29 |
| E) Building Prep & Demo (14-15) | | \$1,856,442 | \$25.12 | | | \$1,856,442 | \$25.12 |
| 14 Building Preparations & Protection | | \$170,000 | \$2.30 | | | \$170,000 | \$2.30 |
| 15 Building Demolition | | \$1,686,442 | \$22.82 | | | \$1,686,442 | \$22.82 |
| F) Site Work (16-18) | | | | \$6,925,544 | \$57.17 | \$6,925,544 | \$93.72 |
| 16 Site Preparation and Demolition | | | | \$1,666,215 | \$13.76 | \$1,666,215 | \$22.55 |
| 17 Site Paving, Structures & Landscaping | | | | \$4,132,329 | \$34.11 | \$4,132,329 | \$55.92 |
| 18 Utilities on Site | | | | \$1,127,000 | \$9.30 | \$1,127,000 | \$15.25 |
| Sub-Total Direct Construction Cost | | \$59,481,162 | \$805 | \$6,925,544 | \$57 | \$66,406,706 | \$899 |
| Design/Cost Contingency | 20.00% | \$11,896,232 | \$160.98 | \$1,385,109 | \$11.43 | \$13,281,341 | \$179.72 |
| Market Escalation | 16.54% | \$11,803,962 | | \$1,374,366 | | \$13,178,328 | \$178.33 |
| | | | | | , | , ,, ,,, | , , , , , |
| Total Direct Construction Cost | | \$83,181,357 | \$1,126 | \$9,685,018 | \$80 | \$92,866,375 | \$1,257 |
| General Conditions | 8.50% | \$7,070,415 | \$95.68 | \$823,227 | \$6.80 | \$7,893,642 | \$106.82 |
| General Requirements | 4.00% | \$3,327,254 | \$45.02 | \$387,401 | \$3.20 | \$3,714,655 | \$50.27 |
| Bonds | 1.00% | \$831,814 | \$11.26 | \$96,850 | \$0.80 | \$928,664 | \$12.57 |
| General Liability Insurance | 1.20% | \$1,122,948 | \$15.20 | \$130,748 | \$1.08 | \$1,253,696 | \$16.96 |
| Overhead & Profit | 4.00% | \$3,821,352 | \$51.71 | \$444,930 | \$3.67 | \$4,266,281 | \$57.73 |
| Sub-Total Indirect Construction Cost | | \$16,173,783 | \$219 | \$1,883,155 | \$16 | \$18,056,938 | \$244 |
| | | | | | | | |
| Total Construction Cost | | \$99,355,140 | \$1,344 | \$11,568,173 | \$96 | \$110,923,313 | \$1,501 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

A) Shell (1-5)

1 Foundations

| Sub-Total: 1 Foundations | 73,899 | SF | \$62.24 | \$4,599,822 |
|---|--------|------|--------------|-------------|
| Pit lifts - allowance for excavation and associated structural mod | 1 | EA | \$250,000.00 | \$250,000 |
| Elevator pits | 2 | EA | \$20,000.00 | \$40,000 |
| Miscellaneous | | | | |
| caps - Assume 20 piles | 3,000 | SF | \$250.00 | \$750,000 |
| 14.5" dia piles, 40' deep, 6'x6' x 24" pile caps, 18" grade beams connecting pile | 2 000 | C.E. | ¢250.00 | ¢750,000 |
| Foundation at Athletics building | | | | |
| deep x 4' wide each side | 35 | CY | \$3,200.00 | \$110,933 |
| Existing Footing Widening - Reinforced concrete epoxy drilled into existing - 24" | | | | |
| New pile caps at new wall micro piles - Assume 8' x 8' x 24" | 142 | CY | \$2,200.00 | \$312,889 |
| Pile Caps | | | | |
| Install new 14.5" dia piles, 40' deep at ends of existing walls - 120 Piles | 4,800 | VLF | \$420.00 | \$2,016,000 |
| Install new 14.5" dia piles, 40' deep at ends of new walls - 80 Piles | 3,200 | VLF | \$350.00 | \$1,120,000 |
| Micro Piles - Assume no rock socket | | | | |

2 Vertical Structure

| Shear Walls | | | | |
|--|--------|----|-------------|--------------|
| New CIP concrete walls -24" thick | 11,116 | SF | \$175.00 | \$1,945,300 |
| CIP concrete wall strengthening - Shotcrete Reinforced Concrete doweled into | | _ | | |
| existing wall, 18" thick | 46,956 | SF | \$150.00 | \$7,043,400 |
| Elevator Shaft - 13'6" x 10', 80' high | 21,600 | SF | \$98.00 | \$2,116,800 |
| Elevator Shaft - 7' x 8'6", 25' high | 2,975 | SF | \$98.00 | \$291,550 |
| New CIP concrete walls -24" thick at Athletics building | 3,480 | SF | \$175.00 | \$609,000 |
| New Steel Framing | | | | |
| New diagonal bracing from projector room to Lower chord Truss Framing | 13 | TN | \$12,000.00 | \$150,000 |
| New Steel allowance for Theater production grid, screens and speakers | 15 | TN | \$12,000.00 | \$180,000 |
| Primary Structural steel for Athletics building | 8 | TN | \$12,000.00 | \$90,000 |
| Shoring | | | | |
| Vertical Strong back shoring at Existing Concrete Screen panels | 5,190 | SF | \$60.00 | \$311,400 |
| Sub-Total: 2 Vertical Structure | 73,899 | SF | \$172.36 | \$12,737,450 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



3 Floor & Roof Structures Slab on grade Patch and repair existing SOG 69,820 SF \$3.80 \$265,316 6" SOG at athletics building 3,000 SF \$12.00 \$36,000 Suspended floors Concrete at tilt floor 11,500 SF \$35.00 \$402,500 Tilt Floor Lock pin allowance 11,500 SF \$25.00 \$287,500 Concrete at new stage floor 4,265 \$28.00 \$119,420 SF Concrete at new flooring at apron ends 157 SF \$35.00 \$5,495 Miscellaneous concrete levelling at balcony and walkway ramps 280 SF \$25.00 \$7,000 Concrete infilled metal deck flooring at Wrestling \$32.00 10.800 \$345,600 **New Steel Framing** New tilt floor framing 40 TN \$12,000.00 \$483,000 New stage floor framing 15 TN \$12,000.00 \$179,130 New floor framing at apron ends 1 TN \$12,000.00 \$11,304 **Lower Chord Truss Framing** 64 \$12,000.00 TN \$768,000 Horizontal bracing at Wrestling floor 22 ΤN \$12,000.00 \$259,200 Horizontal bracing at Canopy 30 TN \$12,000.00 \$360,000 Allowance for all connections 58 TN \$12,000.00 \$700,367 Roof **Upper Chord Truss Framing** 86 TN \$12,000.00 \$1,032,000 Horizontal bracing at Wrestling Roof 22 TN \$12,000.00 \$259,200 Acoustic metal deck at auditorium 26,255 SF \$32.00 \$840,160 Roof Framing at East Wing (Committee) ΤN \$12,000.00 \$590,400 49 Roof Framing at athletics building 18 TN \$12,000.00 \$216,000 Miscellaneous Seismic Separation at West Wing (Administration) 65 LF \$150.00 \$9,750 New Catwalk systems Metal Catwalk and railing Allowance \$500,000.00 1 LS \$500,000 Walkable grid underside Wrestling floor 1 LS \$44,550.00 \$44,550 Sub-Total: 3 Floor & Roof Structures 73,899 SF \$104.49 \$7,721,892 4 Exterior Cladding Wall framing, furring and insulation Metal stud drywall interior of exterior wall 13,271 SF \$36.00 \$477,756

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| ode | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|--------------|-------------|
| Exterior finishes | | | | |
| FRP wrap existing precast conc. Pylons and Beams | 10 | EA | \$306,250.00 | \$3,062,500 |
| Concrete block along north Façade | 813 | SF | \$42.00 | \$34,125 |
| Clean and refinish all exposed concrete | 9,247 | SF | \$10.00 | \$92,465 |
| Cement Plaster at new athletics building | 3,480 | SF | \$25.00 | \$87,000 |
| Interior finish to exterior walls | | | | |
| Paint drywall | 13,271 | SF | \$36.00 | \$477,756 |
| Fascia's, bands, screens and trim | | | | |
| Cement plaster soffits at canopy | 5,630 | SF | \$35.00 | \$197,050 |
| Windows, glazing and louvers | | | | |
| Fixed Store fronts in new openings | 448 | SF | \$180.00 | \$80,640 |
| New storefronts including textured glass on north elevation | 4,020 | SF | \$180.00 | \$723,600 |
| Clean and paint existing Louvers on south elevation | 1,680 | SF | \$8.00 | \$13,440 |
| East Wing (Committee) new Storefront | 1,100 | SF | \$180.00 | \$198,000 |
| West Wing (Administration) new Storefront | 400 | SF | \$180.00 | \$72,000 |
| Exterior doors, frames and hardware | | | | |
| Glazed entry doors | 1 | EA | \$9,300.00 | \$9,300 |
| Glazed double door at Rooftop lounge | 1 | EA | \$9,300.00 | \$9,300 |
| Replace all exterior HM doors | 5 | EA | \$4,250.00 | \$21,250 |
| Sub-Total: 4 Exterior Cladding | 73,899 | SF | \$75.19 | \$5,556,182 |

5 Roofing and Waterproofing

| Waterproofing | | | | |
|---|--------|----|---------|-------------|
| Rooftop Lounge waterproofing | 760 | SF | \$11.00 | \$8,360 |
| Roofing | | | | |
| New Standing seam metal roof at main auditorium | 2,041 | SF | \$34.00 | \$69,394 |
| New TPO roofing at main auditorium - dome | 24,214 | SF | \$38.00 | \$920,132 |
| New TPO roofing at main auditorium - flat | 10,337 | SF | \$24.00 | \$248,088 |
| New TPO roofing at Canopy | 5,630 | SF | \$30.00 | \$168,900 |
| New TPO roof at Athletics building | 3,000 | SF | \$24.00 | \$72,000 |
| New TPO roof at West Wing (Administration) | 2,000 | SF | \$24.00 | \$48,000 |
| New TPO roof at East Wing (Committee) | 8,200 | SF | \$24.00 | \$196,800 |
| Terraces and Landscaping | | | | |
| Rooftop Lounge | 760 | SF | \$50.00 | \$38,000 |
| Caulking and sealants | 55,422 | SF | \$2.66 | \$147,423 |
| Sub-Total: 5 Roofing and Waterproofing | 73,899 | SF | \$25.94 | \$1,917,097 |

Total - A) Shell (1-5) 73,899 SF \$440.23 \$32,532,443

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

B) Interiors (6-7)

6 Interior Partitions, Doors and Glazing

| Partitions | | |
|--|--------|--|
| Metal Stud Framed full height partition | 11,124 | |
| Metal Stud Framed full height partition at FUD office | 3,000 | |
| Glazing | | |
| Glazed partition at FUD Offices - 25' high | 3,750 | |
| Glass viewing wall | 345 | |
| Interior doors, frames and hardware | | |
| HM doors allowance | 13 | |
| HM doors at stairs | 10 | |
| HM double door at orchestra pit | 2 | |
| HM double door at Mechanical Rooms in level 3 | 1 | |
| Sliding double door at auditorium entrance alongside existing historic door to | | |
| remain - 16' wide, STC-53 | 2 | |
| Overhead coiling door at East building, 8' high | 1 | |
| SC Doors with sidelites at FUD offices | 4 | |
| Miscellaneous Allowances - Partitions including doors | | |
| Ticket Sales | 290 | |
| East Wing (Committee) | 6,900 | |
| West Wing (Administration) | 2,000 | |
| | | |
| | | |

| Sub-Total: 6 Interior Partitions, | Doors and Glazina |
|-----------------------------------|-------------------|
| , | |

| \$34.00 | \$378,208 |
|---|--|
| \$34.00 | \$102,000 |
| | |
| | |
| \$140.00 | \$525,000 |
| \$140.00 | \$48,300 |
| | |
| | |
| \$3,000.00 | \$39,000 |
| \$3,000.00 | \$30,000 |
| \$4,300.00 | \$8,600 |
| \$4.300.00 | \$4,300 |
| , | 1 / |
| \$80,000.00 | \$160,000 |
| \$11,560.00 | \$11,560 |
| \$3,500.00 | \$14,000 |
| | |
| | |
| \$12.00 | \$3,480 |
| \$18.00 | \$124,200 |
| \$15.00 | \$30,000 |
| | |
| \$20.01 | \$1,478,648 |
| | \$34.00 \$140.00 \$140.00 \$3,000.00 \$3,000.00 \$4,300.00 \$4,300.00 \$11,560.00 \$3,500.00 \$12.00 \$18.00 |

7 Floor, Wall and Ceiling Finishes

| Flooring |
|---|
| Orchestra and Stage Lift floor finish |
| Hardwood sprung flooring system over tilted floor |
| Premium for Gym floor area with integrated recessed fixed anchors for |
| netting posts |
| Leveled wood platform at balconies |
| Repair and restore existing terrazzo in lobby |
| Ceramic floor tile at restrooms and Lockers |
| Carpet & LVT at FUD offices |
| Allowance for wrestling floor finish including mats |
| Polished concrete at Theater Dressing |
| Sealed concrete at BOH |

| 11,500 | SF |
|--------|----|
| | |
| 4,700 | SF |
| 820 | SF |
| 6,000 | SF |
| 3,340 | SF |
| 925 | SF |
| 4,185 | SF |
| 1,649 | SF |
| 32,890 | SF |
| - | |

73,899

| | included w/ lift |
|---------|------------------|
| \$38.00 | \$437,000 |
| | |
| \$18.00 | \$84,600 |
| \$32.00 | \$26,240 |
| \$25.00 | \$150,000 |
| \$30.00 | \$100,200 |
| \$9.00 | \$8,325 |
| \$15.00 | \$62,775 |
| \$5.00 | \$8,245 |
| \$2.50 | \$82,225 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023

Total - B) Interiors (6-7)



| | Quantity | Unit | Unit Rate | Total Cost |
|--|----------|------|-----------|------------|
| | | | | |
| Bases | | | | |
| New wall base throughout | 73,899 | SF | \$0.50 | \$36,95 |
| Ceramic tile cove base | 297 | LF | \$30.00 | \$8,91 |
| | | | | |
| Wall Finishes | | | | |
| Wall protective Metal cladding on all exposed interior walls within auditorium | | | | |
| with acoustic backing - Allowance for acoustic metal panel and acoustic | | | | |
| perforated metal panel above 10' AFF and wall padding below | | | | |
| | 2,550 | SF | \$68.00 | \$173,4 |
| Ceramic wall tile at restrooms and Lockers | 5,751 | SF | \$30.00 | \$172,5 |
| Paint Drywalls Walls | 28,248 | SF | \$1.50 | \$42,3 |
| Ceilings | | | | |
| Acoustic perforated gypboard ceiling at Auditorium | 13,100 | SF | \$22.00 | \$288,2 |
| ACT at Auditorium Lobby & Theater Dressing | 7,649 | SF | \$12.00 | \$91,7 |
| Miscellaneous Finish Allowances | | | | |
| Ticket sales booth fit out | 290 | SF | \$25.00 | \$7,2 |
| Athletics Building fit-out allowance | 3,400 | SF | \$32.00 | \$108,8 |
| East Wing (Committee) | , | | | |
| Laundry - Sealed concrete floor, painted walls, Exp. ceiling | 150 | SF | \$8.00 | \$1,2 |
| Team Huddle - LVT floor, Wood specialty ceiling | 250 | SF | \$55.00 | \$13,7 |
| Coach Locker - Ceramic floor and wall tile, ACT ceiling | 400 | SF | \$45.00 | \$18,0 |
| Coach Offices - LVT Flooring, painted walls, ACT ceiling | 600 | SF | \$28.00 | \$16,8 |
| Sports Storage - Sealed concrete floor, painted walls, Exp. Ceiling | 600 | SF | \$8.00 | \$4,8 |
| Student Lockers - Ceramic floor and wall tile, ACT ceiling | 3,650 | SF | \$45.00 | \$164,2 |
| Refinish existing to remain | 1,250 | SF | \$3.00 | \$3,7 |
| West Wing (Administration) | | | | |
| Visitor Lockers - Ceramic floor and wall tile, ACT ceiling | 700 | SF | \$45.00 | \$31,5 |
| Official Changing - LVT Flooring, painted walls, ACT ceiling | 140 | SF | \$28.00 | \$3,9 |
| Restrooms - Ceramic floor and wall tile, ACT ceiling | 580 | SF | \$45.00 | \$26,1 |
| Refinish existing to remain | 580 | SF | \$3.00 | \$1,7 |
| Sub-Total: 7 Floor, Wall and Ceiling Finishes | 73,899 | SF | \$29.44 | \$2,175,6 |

\$3,654,274

\$49.45

73,899

SF

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

C) Equipment and Vertical Transportation (8-9)

8 Function Equipment and Specialties

| EA \$3,500.00 | \$21,000 |
|-----------------|--------------|
| EA \$2,000.00 | \$6,000 |
| EA \$1,500.00 | \$1,500 |
| LS \$550,000.00 | \$550,000 |
| | Not Required |
| LS \$100,000.00 | \$100,000 |
| LS \$125,000.00 | \$125,000 |
| LS \$200,000.00 | \$200,000 |
| LS \$40,000.00 | \$40,000 |
| LF \$450.00 | \$81,000 |
| EA \$5,000.00 | \$10,000 |
| | |
| SF \$12.00 | \$60,000 |
| LS \$100,000.00 | \$100,000 |
| LS \$28,000.00 | \$28,000 |
| LS \$180,160.00 | \$180,160 |
| LS \$2,500.00 | \$2,500 |
| LS \$730,000.00 | \$730,000 |
| LS \$730,000.00 | \$730,000 |
| LS \$150,000.00 | \$150,000 |
| LS \$30,000.00 | \$30,000 |
| | |
| EA \$5,000.00 | \$10,000 |
| SF \$20.00 | \$60,000 |
| | |
| SF \$10.00 | \$1,500 |
| SF \$20.00 | \$5,000 |
| SF \$10.00 | \$6,000 |
| SF \$5.00 | \$3,000 |
| | |
| EA \$700.00 | \$30,100 |
| EA \$750.00 | \$2,250 |
| | |
| EA \$750.00 | \$4,500 |
| EA \$700.00 | \$40,600 |
| | |
| EA \$700.00 | \$28,000 |
| EA \$750.00 | \$2,250 |
| | \$295,596 |
| S | A \$750.00 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

9 Stairs and Vertical Transportation

| Stairs | |
|---|---|
| New Metal Pan/ conc. Treads Stair at elevator | |
| New handrails and nosing on existing stairs at basement | |
| New handrails and nosing on existing stairs | |
| Lobby Stair retrofit | |
| | |
| Elevators | |
| Hydraulic Freight elevator at stage | |
| Hydraulic Passenger elevator at lobby | - |
| Savaria V-1504 Lift, 36" x 48" | |
| | |

| 73,033 | J . |
|--------|------------|
| 73,899 | SF |
| | |
| 1 | EA |
| 2 | STOPS |
| 5 | STOPS |
| | |
| | |
| 2 | EA |
| 4 | FLIGHT |
| 1 | FLIGHT |
| 10 | FLIGHT |
| | |
| | |

| \$26,400.00 | \$264,000 |
|-------------|-----------|
| \$5,000.00 | \$5,000 |
| \$6,000.00 | \$24,000 |
| \$40,000.00 | \$80,000 |
| | |
| | |
| \$80,000.00 | \$400,000 |
| \$75,000.00 | \$150,000 |
| \$40,000.00 | \$40,000 |
| | |
| \$13.03 | \$963,000 |

Sub-Total: 9 Stairs and Vertical Transportation

73,899

SF

\$62.21

\$4,596,956

Total - C) Equipment and Vertical Transportation (8-9)

D) Mechanical and Electrical (10-13)

10 Plumbing Systems

| General Plumbing Equipment |
|---|
| Domestic water heater replacement (Air source heat pump allowance) |
| Domestic water heater |
| Circulating pump |
| Expansion tank |
| Sanitary Fixtures |
| Fixture replacements, high eff |
| Vacuum breakers and hose bibs |
| Anti-scald tempering valves |
| Drinking fountains, bottle filler |
| Trap primer valve |
| Domestic Cold Water |
| Domestic Cold Water Piping |
| Water meter allowance |
| |

| 1 | EA |
|--------|----|
| 1 | EA |
| 1 | EA |
| 1 | EA |
| | |
| | |
| 1 | LS |
| | |
| | |
| 73,899 | SF |
| 1 | EA |
| | |

| | I |
|--------------|-----------|
| | |
| 40-0000 | 40-0.00 |
| \$250,000.00 | \$250,000 |
| \$50,000.00 | \$50,000 |
| \$2,095.00 | \$2,095 |
| \$558.90 | \$559 |
| | |
| | |
| \$85,000.00 | \$85,000 |
| \$2,500.00 | \$2,500 |
| \$3,500.00 | \$3,500 |
| \$5,368.00 | \$5,368 |
| \$1,500.00 | \$1,500 |
| | |
| | |
| \$7.74 | \$571,978 |
| \$5,000.00 | \$5,000 |
| | _ |
| | - |

SMMUSD Santa Monica Civic Auditorium



| е | Quantity | Unit | Unit Rate | Total Cost |
|-------------------------------------|----------|------|-------------|------------|
| Domestic Hot Water | | | | |
| Domestic Hot Water Piping | 73,899 | SF | \$8.09 | \$597,843 |
| Water meter allowance | 1 | EA | \$5,000.00 | \$5,000 |
| | | | | |
| Domestic Cold/Hot Water Connections | | | | |
| HW/CW connections to new fixtures | 1 | LS | \$17,379.00 | \$17,37 |
| Isolation valves on lateral lines | 1 | LS | \$5,369.00 | \$5,36 |
| Water meter allowance | 1 | EA | \$5,000.00 | \$5,00 |
| Waste Piping | | | | |
| Waste Piping, SF | 73,899 | SF | \$9.15 | \$676,176 |
| Vent Piping | | | | |
| Vent Piping, SF | 73,899 | SF | \$2.82 | \$208,39 |
| Waste/Vent Connections | | | | |
| DMV connections to new fixtures | 1 | EA | \$11,877.00 | \$11,87 |
| Condensate Drainage | | | | |
| Trap and equipment connect | 11 | EA | \$421.50 | \$4,63 |
| 3/4" pipe, cu type L, in bldg | 275 | LF | \$38.55 | \$10,60 |
| Natural Gas | | | | |
| 4" seismic shut off valve | 1 | EA | \$4,527.00 | \$4,52 |
| Miscellaneous Plumbing | | | | |
| Test / clean plumbing | 120 | HR | \$112.23 | \$13,46 |
| Start-up/check-out | 140 | HR | \$134.67 | \$18,85 |
| Commissioning assist | 80 | HR | \$118.14 | \$9,45 |
| Access panels | 10 | EA | \$211.10 | \$2,11 |
| Piping identification | 25 | EA | \$26.70 | \$66 |
| Firestopping | 25 | EA | \$55.00 | \$1,37 |
| Seismic bracing | 1 | SF | \$25,000.00 | \$25,00 |
| Basement | 7,455 | SF | \$20.00 | \$149,10 |
| Athletic building | 3,000 | SF | \$55.00 | \$165,00 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



11 Heating, Ventilation and Air Conditioning Chilled Water Equipment Chiller, air-cooled \$52,325 1 EΑ \$52,325.00 Glycol management system 1 EΑ \$16,520.00 \$16,520 Relocate existing thermal energy storage system (allowance) \$40,800.00 \$40,800 1 LS CHW pump, end suction, 5 hp, 225 gpm 2 EΑ \$5,099.00 \$10,198 VFD to CHW pump, 5 hp 2 EΑ \$7,166 \$3,583.00 Heat exchanger 1 EΑ \$8,006.00 \$8,006 Heating Hot Water Equipment Hot water boiler, gas fired, condensing 2 EΑ \$32,000.00 \$64,000 HW pump, end suction, 2 hp, 50 gpm 2 EΑ \$4,267.00 \$8,534 VFD to HW pump, 3 hp 2 EΑ \$3,339.00 \$6,678 Chilled Water Distribution Chiller connect, weld, 6" 1 EΑ \$9,327.00 \$9,327 CHW pump connect, weld, end suct, 4" 2 \$9,051.00 EΑ \$18,102 CHW distribution 73,899 SF \$7.39 \$546,114 Hot Water Distribution Boiler connect, cu, 2" 2 \$5,181.00 \$10,362 EΑ HHW pump connect, cu, 2" 2 \$1,098.00 \$2,196 EΑ HHW coil connect, cu, 3-way, 1-1/4" 8 EΑ \$1,266.00 \$10,128 **HHW** distribution 73,899 SF \$7.04 \$520,249 Air-Side Equipment DOAS system 1 EΑ \$21,223.00 \$21,223 **Ductless split systems** 2 ea \$10,500.00 \$21,000 Refrigerant piping for VRF heat pump system w/ HR \$55,000.00 \$55,000 1 LS VRF fan coil ducted 5 EΑ \$2,281.00 \$11,405 VRF branch selector 1 EΑ \$5,888.00 \$5,888 **VRF** Condenser \$17,330 1 EΑ \$17,330.00 **Hydronic Fancoils** AHUS / Fan coil, 4-pipe, horizontal \$76,500.00 \$612,000 EΑ Fans Exhaust fans 7 EΑ \$3,182.00 \$22,274 VFD to fan, 1.5 hp 7 EΑ \$838.40 \$5,869

SMMUSD Santa Monica Civic Auditorium



| ie | Quantity | Unit | Unit Rate | Total Cost |
|--|-----------|------|-------------|-------------|
| Air Distribution | | | | |
| Ductwork silencer allowance | 1 | LS | \$35,000.00 | \$35,000 |
| Ductwork, galv, purchased prefab'd | 79,143 | LBS | \$14.85 | \$1,175,274 |
| Duct insulation, wrap | 51,443 | SF | \$2.69 | \$138,382 |
| Manual volume damper | 384 | EA | \$75.24 | \$28,892 |
| Flexible duct, insulated, various sizes | 280 | LF | \$20.41 | \$5,715 |
| Grilles and diffusers | | | | |
| Return Grilles | 30 | EA | \$140.70 | \$4,221 |
| Exhaust grilles | 10 | EA | \$131.00 | \$1,310 |
| Ceiling diffusers | 344 | EA | \$164.30 | \$56,519 |
| Miscellaneous | | | | |
| Test / balance HVAC | 400 | HR | \$131.31 | \$52,524 |
| Start-up/check-out | 350 | HR | \$119.38 | \$41,783 |
| Commissioning assist | 150 | HR | \$119.38 | \$17,907 |
| MEP Coordination | 250 | HR | \$119.38 | \$29,845 |
| Seismic bracing, pipe | 1 | LS | \$50,000.00 | \$50,000 |
| Seismic bracing, duct | 1 | LS | \$50,000.00 | \$50,000 |
| Hoisting and rigging | 1 | LS | \$75,000.00 | \$75,000 |
| Basement | 7,455 | SF | \$55.00 | \$410,025 |
| Athletic building | 3,000 | SF | \$60.00 | \$180,000 |
| HVAC Controls | | | | |
| DDC controls, chiller | 1 | EA | \$19,130.00 | \$19,130 |
| DDC controls, boiler | 1 | EA | \$15,310.00 | \$15,310 |
| DDC controls, pump wth vfd | 4 | EA | \$7,654.00 | \$30,616 |
| DDC controls, VRF fancoil | 5 | EA | \$4,306.00 | \$21,530 |
| DDC controls, VRF Outdoor condenser | 1 | EA | \$1,435.00 | \$1,435 |
| DDC controls, fancoil, 4-pipe | 8 | EA | \$30,000.00 | \$240,000 |
| DDC controls, general exhaust fan | 7 | EA | \$1,435.00 | \$10,045 |
| DDC controls, controls workstation | 1 | EA | \$40,000.00 | \$40,000 |
| Sub-Total: 11 Heating, Ventilation and Air Conditionii | ng 73,899 | SF | \$65.40 | \$4,833,156 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



12 Electrical Lighting, Power and Communications Service and Distribution Replace all Existing Zinsco Panels/Feeders LS 1 \$122,185.00 \$122,185 Replace all Existing Zinsco Distribution Boards in main electrical room (5 DBs) 1 LS \$90,000.00 \$90,000 Replace Existing MCC1 and MCC2 with Distribution board/add separate starters or VFDs (supplied by MC installed by EC) LS \$100,000.00 \$100,000 1 New Athletic Bldg - Service and Distribution 1 LS \$22,500.00 \$22,500 **HVAC** and Plumbing equipment connections HVAC and Plumbing equipment connections (Scheme 1) 1 LS \$315,000.00 \$315,000 New Athletic Bldg - Machine and Equipment Connections 1 LS \$16,500.00 \$16,500 Provide new disconnect and panel to serve elevator loads on new elevator machine rooms including new feeders LS \$18,500.00 \$18,500 1 Convenience Power Update with GFCI protected receptacles required for most restrooms, janitor's closets and kitchen spaces \$42,500.00 1 LS \$42,500 New Athletic Bldg - Convenience Power 1 LS \$12,000.00 \$12,000 Lighting and Lighting Controls Upgrade entire existing Lighting with LED fixtures and lighting controls with Title 24 code compliant controls SF 73,899 \$33.50 \$2,475,617 Upgrade existing Stage Theatrical Lighting with LED fixtures and lighting controls with Title 24 code compliant controls SF 73,899 \$4.75 \$351,020 Provide Theater Aisle Lighting with J-Box & wiring LS \$54,000.00 \$54,000 Theater Lighting package (per Salas O'Brien quote) 1 LS \$850,000.00 \$850,000 New Athletic Bldg - LED Lighting and Controls including Sports LED Lighting LS \$112,500.00 \$112,500 1 Temporary Power **Temporary Power** 73,899 SF \$1.50 \$110,849 Miscellaneous Start-up, Third party testing, commissioning assist, labels, firestopping, pipe penetrations, seismic and misc 73,899 SF \$2.00 \$147,798 General conditions / General requirements - Includes Small Tools, Office Staffing, Indirect Labor, Consumables, Equipment Rental & General Expenses 73,899 SF \$6.75 \$498,818 Communications Technology - provide dedicated Signal Rooms at North and South ends of the building. Provide MDF/MPOE and IDF room and fiber and copper backbone cabling. Install floor mounted data racks 73,899 SF \$92,374 \$1.25 New Athletic Bldg - Technology/Communications 1 LS \$15,000.00 \$15,000 Audio Visual Provide AV equipment in new AV control room. Provide projector and projector screen, speakers, wireless mic and assistive listening & wiring 73,899 SF \$2.50 \$184,748

SMMUSD Santa Monica Civic Auditorium



| Code | Quantity | Unit | Unit Rate | Total Cost |
|--|----------|------|---|--------------|
| Audio Visual - conduit rough-ins | 73,899 | SF | \$1.00 | \$73,899 |
| TV Broadcasting/Radio Infrastructure to record, edit and stream events | 1 | LS | \$35,000.00 | \$35,000 |
| AV Equipment for Theater (per Salas O'Brien quote) | 1 | LS | \$1,770,000.00 | \$1,770,000 |
| New Athletic Bldg - AV equipment and conduit rough-ins | 1 | LS | \$36,000.00 | \$36,000 |
| | _ | | 700,000 | +/ |
| Security Systems | | | | |
| Replace existing Security System - provide new keypads, access control on entry points and motion sensors & wiring | 73,899 | SF | \$1.75 | \$129,323 |
| New Athletic Bldg - Security system/connect to existing head end | 1 | LS | \$10,500.00 | \$10,500 |
| | | | , ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | , ,,,,,, |
| CCTV Systems | | | | |
| Provide new CCTV system with IP cameras & wiring/new head end equipment | 73,899 | SF | \$2.50 | \$184,748 |
| New Athletic Bldg - new CCTV system with IP cameras & wiring/connect to new head end equipment | 1 | LS | \$22,500.00 | \$22,500 |
| | | | , | · , |
| Fire Alarm Systems | | | | |
| Total replacement existing Fire alarm system, existing ansul fire alarm | | | | |
| suppression system to be removed | 73,899 | SF | \$6.50 | \$480,344 |
| New Athletic Bldg - consider and new FACP + voice evac for the existing | | | | |
| building. Include integration of a smoke control system with a smoke control | | | | |
| panel. | 1 | LS | \$38,000.00 | \$38,000 |
| Sub-Total: 12 Electrical Lighting, Power and Communications | 73,899 | SF | \$113.83 | \$8,412,221 |
| 13 Fire Protection Systems | | | | |
| Backflow preventer, red press | 1 | EA | \$7,209.00 | \$7,209 |
| Provide new sprinklers and piping (stage, seating, lobby, staircases) | 73,899 | SF | \$6.28 | \$464,086 |
| Sprinkler replacement, various areas (corroded, painted and outdated) | 73,899 | SF | \$2.91 | \$215,046 |
| Sub-Total: 13 Fire Protection Systems | 73,899 | SF | \$9.29 | \$686,341 |
| Total - D) Mechanical and Electrical (10-13) | 73,899 | SF | \$227.89 | \$16,841,048 |
| Total - D) Mechanical and Electrical (10-15) | 75,633 | ЭГ | 3227.65 | \$10,041,040 |
| E) Building Prep & Demo (14-15) | | | | |
| 44 Politika Paramatiana C Partestina | | | | |
| 14 Building Preparations & Protection | | | | |
| Allowance to protect existing to remain scope items | 1 | LS | \$150,000.00 | \$150,000 |
| Excavation at basement including backfill and recompact ion | 1 | LS | \$20,000.00 | \$20,000 |
| Sub-Total: 14 Building Preparations & Protection | 73,899 | SF | \$2.30 | \$170,000 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

15 Building Demolition

| 67,000,00 | |
|----------------|-------------------|
| \$ \$7,800.00 | \$7,800 |
| \$10.00 | \$70,000 |
| F \$8.00 | \$92,000 |
| F \$8.00 | \$34,120 |
| F \$75.00 | \$4,388 |
| GHT \$550.00 | \$550 |
| F \$30.00 | \$17,835 |
| | |
| F \$55.00 | \$24,640 |
| F \$55.00 | \$2,640 |
| F \$75.00 | \$1,800 |
| F \$15.00 | \$60,300 |
| F \$15.00 | \$6,000 |
| F \$15.00 | \$12,000 |
| F \$10.00 | \$3,000 |
| F \$5.00 | \$41,000 |
| F \$5.00 | \$10,000 |
| F \$5.00 | \$160,325 |
| | |
| \$ \$85,000.00 | \$85,000 |
| A \$500.00 | \$500 |
| A \$3,000.00 | \$3,00 |
| \$69,000.00 | \$69,000 |
| F \$20.00 | \$10,600 |
| F \$7.00 | \$405,993 |
| F \$10.00 | \$69,000 |
| F \$10.00 | \$20,000 |
| | |
| \$ \$11,220.00 | \$11,220 |
| \$ \$4,489.00 | \$4,489 |
| F \$2.81 | \$207,656 |
| \$ \$22,910.00 | \$22,910 |
| F \$3.20 | \$236,477 |
| F | \$3.20 \$22.82 |

Total - E) Building Prep & Demo (14-15)

73,899 SF

\$25.12

\$1,856,442

Construction Cost Detail - Site Development Scheme 1

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



F) Site Work (16-18) 16 Site Preparation and Demolition Selective demolition and removal Hardscape demolition allowance 121,130 SF \$2.00 \$242,260 Landscape demolition allowance 121.130 \$1.00 SF \$121.130 **General Site Grading** 121,130 SF \$2.00 \$242,260 **Erosion Control** 121,130 SF \$0.50 \$60,565 \$1,000,000 \$1,000,000.00 Phase 2 Clean-up 1 LS Sub-Total: 16 Site Preparation and Demolition 121,130 SF \$13.76 \$1,666,215 17 Site Paving, Structures & Landscaping Pedestrian paving allowance - includes asphalt / concrete paving 48,452 SF \$25.00 \$1,211,300 Structure Ramp and Stairs to building 1 LS \$50,000.00 \$50,000 3,000 Depress Slab and mosaic tile at entry SF \$350.00 \$1,050,000 Site furnishing and accessories 1 LS \$150,000.00 \$150,000 84,791 SF \$15.00 Landscape planting and maintenance \$1,271,865 **New Trees** \$4,000.00 \$60,000 EΑ 15 84.791 SF \$339.164 Irrigation \$4.00 121,130 New Stair south of fly space including shaft \$34.11 \$4,132,329 18 Utilities on Site Storm Drain Storm drain underground piping including drain inlets, replacement of 8" 1,000 LF \$350.00 \$350,000 existing SD pipe Storm Water management - Mitigate 6,500CF of storm water including underground cistern and pretreatment system 1 LS \$150,000.00 \$150,000 Domestic and Fire Water Replace existing domestic and fire water system including connections including 300 LF \$200.00 \$60.000 athletics building New Fire hydrant 1 EΑ \$20,000.00 \$20,000 Sanitary Sewer \$250.00 \$125,000 Replace existing Sewer system including connections 500 LF Site Electrical Upgrade emergency genset from 30kW to 150kW including 150A ATS to 400A \$197,000.00 \$197,000 ATS and upgrade feeders 1 LS Site Lighting Upgrade existing exterior Lighting with LED fixtures and lighting controls with Title 24 code compliant controls 1 LS \$75,000.00 \$75,000 Allowance for exterior lighting and power/data along north facades LS \$150,000.00 \$150,000

Sub-Total: 18 Utilities on Site

Total - F) Site Work (16-18)

121,130

121,130

SF

SF

\$57.17

\$9.30

\$6,925,544

\$1,127,000

Construction Cost Detail

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude July 13, 2023



Scheme 2

Direct Construction Cost Summary - Scheme 2

SMMUSD Santa Monica Civic Auditorium



| Element | | Building | | Site Developm | ent | Total Cost | : |
|---|-----------|---------------|----------|---------------|---------------|---------------|----------------|
| | | 91,098 SF | | 103,676 SF | | 91,098 SF | |
| | | Total | \$/SF | Total | \$/SF | Total | \$/SF |
| A) Shell (1-5) | | \$43,597,368 | \$478.58 | | | \$43,597,368 | \$478.58 |
| 1 Foundations | | \$11,349,822 | \$124.59 | | | \$11,349,822 | \$124.59 |
| 2 Vertical Structure | | \$15,810,375 | \$173.55 | | | \$15,810,375 | \$173.55 |
| 3 Floor & Roof Structures | | \$8,361,452 | \$91.79 | | | \$8,361,452 | \$91.79 |
| 4 Exterior Cladding | | \$5,757,094 | \$63.20 | | | \$5,757,094 | \$63.20 |
| 5 Roofing and Waterproofing | | \$2,318,625 | \$25.45 | | | \$2,318,625 | \$25.45 |
| B) Interiors (6-7) | | \$4,943,631 | \$54.27 | | | \$4,943,631 | \$54.27 |
| 6 Interior Partitions, Doors and Glazing | | \$1,911,888 | \$20.99 | | | \$1,911,888 | \$20.99 |
| 7 Floor, Wall and Ceiling Finishes | | \$3,031,743 | \$33.28 | | | \$3,031,743 | \$33.28 |
| C) Equipment and Vertical Transportation | (8-9) | \$4,741,832 | \$52.05 | | | \$4,741,832 | \$52.05 |
| 8 Function Equipment and Specialties | | \$3,982,832 | \$43.72 | | | \$3,982,832 | \$43.72 |
| 9 Stairs and Vertical Transportation | | \$759,000 | \$8.33 | | | \$759,000 | \$8.33 |
| D) Mechanical and Electrical (10-13) | | \$18,991,553 | \$208.47 | | | \$18,991,553 | \$208.47 |
| 10 Plumbing Systems | | \$3,395,666 | \$37.27 | | | \$3,395,666 | \$37.27 |
| 11 Heating, Ventilation and Air Condition | ing | \$5,465,885 | \$60.00 | | | \$5,465,885 | \$60.00 |
| 12 Electrical Lighting, Power and Commun | nications | \$9,285,603 | \$101.93 | | | \$9,285,603 | \$101.93 |
| 13 Fire Protection Systems | | \$844,400 | \$9.27 | | | \$844,400 | \$9.27 |
| E) Building Prep & Demo (14-15) | | \$1,536,157 | \$16.86 | | | \$1,536,157 | \$16.86 |
| 14 Building Preparations & Protection | | \$145,000 | \$1.59 | | | \$145,000 | \$1.59 |
| 15 Building Demolition | | \$1,391,157 | \$15.27 | | | \$1,391,157 | \$15.27 |
| F) Site Work (16-18) | | \$0 | \$0.00 | \$6,372,869 | \$61.47 | \$6,372,869 | \$69.96 |
| 16 Site Preparation and Demolition | | | | \$1,570,218 | \$15.15 | \$1,570,218 | \$17.24 |
| 17 Site Paving, Structures & Landscaping | | | | \$3,675,651 | \$35.45 | \$3,675,651 | \$40.35 |
| 18 Utilities on Site | | | | \$1,127,000 | \$10.87 | \$1,127,000 | \$12.37 |
| Sub-Total Direct Construction Cost | | \$73,810,540 | \$810 | \$6,372,869 | \$61 | \$80,183,409 | \$880 |
| Design/Cost Contingency | 20.00% | \$14,762,108 | \$162.05 | \$1,274,574 | \$12.29 | \$16,036,682 | \$176.04 |
| Market Escalation | 16.54% | \$14,647,609 | | \$1,264,688 | | \$15,912,297 | \$174.67 |
| | 10.5470 | | Ģ100.75 | | Ÿ12.20 | \$13,312,237 | Ψ174.07 |
| Total Direct Construction Cost | | \$103,220,258 | \$1,133 | \$8,912,130 | \$86 | \$112,132,388 | \$1,231 |
| General Conditions | 8.50% | \$8,773,722 | \$96.31 | \$757,531 | \$7.31 | \$9,531,253 | \$104.63 |
| General Requirements | 4.00% | \$4,128,810 | \$45.32 | \$356,485 | \$3.44 | \$4,485,296 | \$49.24 |
| Bonds | 1.00% | \$1,032,203 | \$11.33 | \$89,121 | \$0.86 | \$1,121,324 | \$12.31 |
| General Liability Insurance | 1.20% | \$1,393,473 | \$15.30 | \$120,314 | \$1.16 | \$1,513,787 | \$16.62 |
| Overhead & Profit | 4.00% | \$4,741,939 | \$52.05 | \$409,423 | \$3.95 | \$5,151,362 | \$56.55 |
| Sub-Total Indirect Construction Cost | | \$20,070,147 | \$220 | \$1,732,875 | \$17 | \$21,803,022 | \$239 |
| | | | | | | | |
| Total Construction Cost | | \$123,290,405 | \$1,353 | \$10,645,005 | \$103 | \$133,935,410 | \$1,470 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



Code Quantity Unit Unit Rate Total Cost

A) Shell (1-5)

1 Foundations

| 91,098 | SF | \$124.59 | \$11,349,822 |
|--------|-----|--------------|--------------|
| 1 | EA | \$250,000.00 | \$250,000 |
| 2 | EA | \$20,000.00 | \$40,000 |
| | | | |
| 30,000 | 3F | \$250.00 | \$7,500,000 |
| 30,000 | SF | \$250.00 | \$7.500.000 |
| | | | |
| 35 | CY | \$3,200.00 | \$110,933 |
| | | | |
| 142 | CY | \$2,200.00 | \$312,889 |
| | | | |
| 4,800 | VLF | \$420.00 | \$2,016,000 |
| 3,200 | VLF | \$350.00 | \$1,120,000 |
| | | | |
| - | , | , | , |

2 Vertical Structure

| Shear Walls | | | | |
|--|--------|----|-------------|--------------|
| New CIP concrete walls -24" thick | 11,116 | SF | \$175.00 | \$1,945,300 |
| CIP concrete wall strengthening - Shotcrete Reinforced Concrete doweled into | | | | |
| existing wall, 18" thick | 46,956 | SF | \$150.00 | \$7,043,400 |
| Elevator Shaft - 13'6" x 10', 80' high | 21,600 | SF | \$98.00 | \$2,116,800 |
| Elevator Shaft - 7' x 8'6", 25' high | 2,975 | SF | \$98.00 | \$291,550 |
| New CIP concrete walls -24" thick at new building addition | 16,411 | SF | \$175.00 | \$2,871,925 |
| New Steel Framing | | | | |
| New diagonal bracing from projector room to Lower chord Truss Framing | 13 | TN | \$12,000.00 | \$150,000 |
| New Steel allowance for Theater production grid, screens and speakers | 15 | TN | \$12,000.00 | \$180,000 |
| Primary structural steel columns at new building addition | 75 | TN | \$12,000.00 | \$900,000 |
| Shoring | | | | |
| Vertical Strong back shoring at Existing Concrete Screen panels | 5,190 | SF | \$60.00 | \$311,400 |
| Sub-Total: 2 Vertical Structure | 91,098 | SF | \$173.55 | \$15,810,375 |

SMMUSD Santa Monica Civic Auditorium

Cement Plaster at new building additions

Interior finish to exterior walls

Paint drywall

Rough Order of Magnitude SOPC July 13, 2023



3 Floor & Roof Structures Slab on grade Patch and repair existing SOG 69,820 SF \$3.80 \$265,316 6" SOG at new building addition 30,000 SF \$12.00 \$360,000 Suspended floors Concrete at tilt floor 11,500 SF \$35.00 \$402,500 Tilt Floor Lock pin allowance 11,500 SF \$25.00 \$287,500 Concrete at new stage floor 4,265 SF \$28.00 \$119,420 Miscellaneous concrete levelling at balcony and walkway ramps 280 SF \$25.00 \$7,000 **New Steel Framing** New tilt floor framing 40 TN \$12,000.00 \$483,000 New stage floor framing 15 TN \$12,000.00 \$179,130 **Lower Chord Truss Framing** \$12,000.00 \$768,000 64 TN Horizontal bracing at Canopy 30 TN \$12,000.00 \$360,000 Allowance for all connections 47 TN \$12,000.00 \$564,426 Roof **Upper Chord Truss Framing** 86 TN \$12,000.00 \$1,032,000 26,255 Acoustic metal deck at auditorium SF \$32.00 \$840,160 Roof Framing at New building addition 180 TN \$12,000.00 \$2,160,000 Miscellaneous 275 Seismic Separation LF \$120.00 \$33,000 New Catwalk systems Metal Catwalk and railing Allowance LS \$500,000.00 \$500,000 1 Sub-Total: 3 Floor & Roof Structures 91,098 SF \$91.79 \$8,361,452 4 Exterior Cladding Wall framing, furring and insulation Metal stud drywall interior of exterior wall 9,247 \$36.00 \$332,874 Exterior finishes FRP wrap existing precast conc. Pylons and Beams 10 EΑ \$306,250.00 \$3,062,500 Concrete block along north Façade 813 SF \$42.00 \$34,125 Clean and refinish all exposed concrete 9,247 SF \$10.00 \$92,465

13,129

9,247

SF

SF

\$328,220

\$332,874

\$25.00

\$36.00

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| | Quantity | Unit | Unit Rate | Total Cost |
|--|-----------------|----------|--------------------|---------------------|
| Fascias, bands, screens and trim | | | | |
| Cement plaster soffits at canopy | 5,630 | SF | \$35.00 | \$197,05 |
| Windows, glazing and louvers | | | | |
| New storefronts | 4,020 | SF | \$180.00 | \$723,60 |
| Clean and paint existing Louvers on south elevation | 1,680 | SF | \$8.00 | \$13,44 |
| Glazing at new building addition | 3,282 | SF | \$180.00 | \$590,79 |
| Exterior doors, frames and hardware | | | | |
| Glazed entry doors | 3 | EA | \$9,300.00 | \$27,90 |
| Replace all exterior HM doors | 5 | EA | \$4,250.00 | \$21,25 |
| Sub-Total: 4 Exterior Cladding | 91,098 | SF | \$63.20 | \$5,757,09 |
| | 3=,030 | 31 | | 1 - / - / - |
| ofing and Waterproofing | 31,030 | J. | | |
| ofing and Waterproofing Roofing | | SF | \$34.00 | |
| ofing and Waterproofing | 2,041 24,214 | | | \$69,39 \$920,13 |
| ofing and Waterproofing Roofing New Standing seam metal roof at main auditorium | 2,041 | SF | \$34.00 | \$69,39 |
| ofing and Waterproofing Roofing New Standing seam metal roof at main auditorium New TPO roofing at main auditorium - dome | 2,041 24,214 | SF SF | \$34.00 \$38.00 | \$69,39 \$920,13 |

Total - A) Shell (1-5) 91,098 SF \$478.58 \$43,597,368

Sub-Total: 5 Roofing and Waterproofing

B) Interiors (6-7)

Caulking and sealants

6 Interior Partitions, Doors and Glazing

| Partitions | |
|--|---|
| Metal Stud Framed full height partition | |
| | |
| Glazing | |
| Glass viewing wall | |
| | |
| Interior doors, frames and hardware | |
| HM doors allowance | |
| HM doors at stairs | |
| HM double door at orchestra pit | |
| HM double door at Mechanical Rooms in level 3 | |
| Sliding double door at auditorium entrance alongside existing historic door to | _ |
| remain - 16' wide, STC-53 | |

| SF |
|----|
| |
| |
| SF |
| |
| |
| EA |
| EA |
| EA |
| EA |
| |
| EA |
| |
| |

72,222

91,098

SF

| \$34.00 | \$378,208 |
|-------------|-----------|
| | |
| | |
| \$140.00 | \$48,300 |
| | |
| | |
| \$3,000.00 | \$39,000 |
| \$3,000.00 | \$30,000 |
| \$4,300.00 | \$8,600 |
| \$4,300.00 | \$4,300 |
| | |
| \$80,000.00 | \$160,000 |
| | |

\$2.66

\$25.45

\$192,111

\$2,318,625

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| ode | Quai | ntity | Unit | Unit Rate | Total Cost |
|---|------------|-------|------|-----------|-------------|
| Miscellaneous Allowances - Partitions including doors | | | | | |
| Ticket Sales | | 290 | SF | \$12.00 | \$3,480 |
| East Addition | 1 | 9,000 | SF | \$40.00 | \$760,000 |
| Student Lockers | | 5,434 | SF | | |
| Gender Neutral Lockers | | 250 | SF | | |
| Coach Office | | 1,000 | SF | | |
| Coach Lockers | | 750 | SF | | |
| Wrestling Storage | | 500 | SF | | |
| Wrestling | | 5,000 | SF | | |
| Athletic Trainers | | 400 | SF | | |
| Team Huddle | | 5,666 | SF | | |
| West Addition | | 8,000 | SF | \$60.00 | \$480,000 |
| FUD Offices | | 1,000 | SF | | |
| Community Room | | 3,400 | SF | | |
| Restrooms | | 620 | SF | | |
| Visitor Lockers | | 900 | SF | | |
| Official Changing | | 140 | SF | | |
| Kitchen | | 900 | SF | | |
| Corridor | | 1,040 | SF | | |
| Sub-Total: 6 Interior Partitions, Doors a | nd Glazing | 1,098 | SF | \$20.99 | \$1,911,888 |

7 Floor, Wall and Ceiling Finishes

| Flooring | | | | |
|--|--------|----|---------|------------------|
| Orchestra Lift floor finish | | | | included w/ lift |
| Hardwood sprung flooring system over tilted floor | 11,500 | SF | \$38.00 | \$437,000 |
| Premium for Gym floor area with integrated recessed fixed anchors for | | | | |
| netting posts | 4,700 | SF | \$18.00 | \$84,600 |
| Leveled wood platform at balconies | 820 | SF | \$32.00 | \$26,240 |
| Repair and restore existing terrazzo in lobby | 6,000 | SF | \$25.00 | \$150,000 |
| Ceramic floor tile at restrooms | 1,490 | SF | \$30.00 | \$44,700 |
| Polished concrete at Theater Dressing | 1,649 | SF | \$5.00 | \$8,245 |
| Sealed concrete at BOH | 38,649 | SF | \$2.50 | \$96,623 |
| Bases | | | | |
| New wall base throughout | 91,098 | SF | \$0.50 | \$45,549 |
| Ceramic tile cove base | 297 | LF | \$30.00 | \$8,910 |
| Wall Finishes | | | | |
| Wall protective Metal cladding on all exposed interior walls within auditorium | | | | |
| with acoustic backing - Allowance for acoustic metal panel and acoustic | | | | |
| perforated metal panel above 10' AFF and wall padding below | | | | 4 |
| | 2,550 | SF | \$68.00 | \$173,400 |
| Ceramic wall tile at restrooms and Lockers | 5,751 | SF | \$30.00 | \$172,538 |
| Paint Drywalls Walls | 22,248 | SF | \$1.50 | \$33,371 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| e | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|-----------|------------|
| | | | | |
| Ceilings | | | | |
| Acoustic perforated gypboard ceiling at Auditorium | 8,335 | SF | \$22.00 | \$183,3 |
| ACT at Auditorium Lobby & Theater Dressing | 7,649 | SF | \$12.00 | \$91,7 |
| Miscellaneous Finish Allowances | | | | |
| Ticket sales booth fit out | 290 | SF | \$25.00 | \$7,2 |
| Laundry - Sealed concrete floor, painted walls, Exp. ceiling | 300 | SF | \$8.00 | \$2,4 |
| East Addition | | | | |
| Student Lockers - Ceramic floor and wall tile, ACT ceiling | 5,684 | SF | \$45.00 | \$255, |
| Coach Offices - LVT Flooring, painted walls, ACT ceiling | 1,000 | SF | \$28.00 | \$28, |
| Coach Locker - Ceramic floor and wall tile, ACT ceiling | 750 | SF | \$45.00 | \$33, |
| Wrestling Storage - Sealed concrete floor, painted walls, Exp. Ceiling | 500 | SF | \$8.00 | \$4, |
| Wrestling - Wood floor, painted walls, ACT Ceiling | 5,000 | SF | \$50.00 | \$250, |
| Athletic Trainers - Wood floor, painted walls, ACT Ceiling | 400 | SF | \$50.00 | \$20, |
| Team Huddle - LVT floor, Wood specialty ceiling | 5,666 | SF | \$65.00 | \$368, |
| Athletics fit-out allowance | 3,400 | SF | \$32.00 | \$108, |
| West Addition | | | | |
| FUD Offices - Carpet & LVT floor, painted walls, ACT ceiling | 1,000 | SF | \$28.00 | \$28, |
| Community Room - Wood floor, acoustic treatment on 40% walls, painted wall finish, wood plank ceiling | 3,400 | SF | \$65.00 | \$221, |
| Restrooms - Ceramic floor and wall tile, ACT ceiling | 620 | SF | \$45.00 | \$27, |
| Visitor Lockers - Ceramic floor and wall tile, ACT ceiling | 900 | SF | \$45.00 | \$40, |
| Official Changing - LVT Flooring, painted walls, ACT ceiling | 140 | SF | \$28.00 | \$3, |
| Kitchen - Epoxy Floor, Stainless Steel wall cladding | 900 | SF | \$75.00 | \$67, |
| Corridor - Sealed concrete floor, painted walls, Exp. Ceiling | 1,040 | SF | \$8.00 | \$8, |
| Sub-Total: 7 Floor, Wall and Ceiling Finishes | 91,098 | SF | \$33.28 | \$3,031, |
| tal - B) Interiors (6-7) | 91,098 | SF | \$54.27 | \$4,943,6 |

C) Equipment and Vertical Transportation (8-9)

8 Function Equipment and Specialties

| Specialties |
|---|
| Restroom Specialties including phenolic partitions, Bobrick accessories, wall |
| hung mirror, air hand dryers |
| Unisex restroom specialties |
| Ladder |
| Motorized stage rigging |
| Fire curtain system at stage |
| Stage curtain package |
| Motor control infrastructure at new production grid over stage & court |
| Retractable bleacher seating |
| Movable basketball goals - 2 |
| Glass railing at Front row seating |

| 6 | EA |
|-----|----|
| 3 | EA |
| 1 | EA |
| 1 | LS |
| 180 | LF |

| \$3,500.00 | \$21,000 |
|--------------|-----------|
| \$2,000.00 | \$6,000 |
| \$1,500.00 | \$1,500 |
| \$550,000.00 | \$550,000 |
| \$55,000.00 | \$55,000 |
| \$100,000.00 | \$100,000 |
| \$125,000.00 | \$125,000 |
| \$200,000.00 | \$200,000 |
| \$40,000.00 | \$40,000 |
| \$450.00 | \$81.000 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|--------------|------------|
| End zone score board | 2 | EA | \$5,000.00 | \$10,00 |
| Temporary Carpet floor covering to cover wood sports floor in main auditorium | | | | |
| | 5,000 | SF | \$12.00 | \$60,00 |
| Audience seating in good condition- allowance for minor repairs | 1 | LS | \$100,000.00 | \$100,00 |
| Other Sport goals | 1 | LS | \$28,000.00 | \$28,0 |
| Blackout curtains in auditorium | 1 | LS | \$233,670.40 | \$233,6 |
| Deployable curtains at scoreboards | 1 | LS | \$2,500.00 | \$2,5 |
| Orchestra Pit lift , 470 SF, 20' travel, multiple stops | 1 | LS | \$730,000.00 | \$730,0 |
| Stage lift , 17'4" x 43'3", 20' travel, multiple stops | 1 | LS | \$730,000.00 | \$730,0 |
| Portable steps/platforms/ramps | 1 | LS | \$150,000.00 | \$150,0 |
| Display casework at viewing area | 1 | LS | \$30,000.00 | \$30,0 |
| Cabinets, countertops and casework allowances | | | | |
| Ticket Concessions | 2 | EA | \$5,000.00 | \$10,0 |
| Laundry | 300 | SF | \$10.00 | \$3,0 |
| East Addition | | | | |
| Team Huddle | 5,666 | SF | \$20.00 | \$113,3 |
| Coach Offices | 1,000 | SF | \$10.00 | \$10,0 |
| Wrestling Storage | 500 | SF | \$5.00 | \$2,5 |
| Athletic Trainers | 5,000 | SF | \$5.00 | \$25,0 |
| Athletics Room | 3,000 | SF | \$20.00 | \$60,0 |
| West Addition | | | | |
| Community Room | 3,400 | SF | \$10.00 | \$34,0 |
| Restroom Specialties | 620 | SF | \$5.00 | \$3,1 |
| Kitchen | 900 | SF | \$25.00 | \$22,5 |
| Lockers and bench | | | | |
| East Addition | | | | |
| Coach Lockers - 3 Full ht Lockers | 3 | EA | \$700.00 | \$2,1 |
| Student Lockers -2-tier metal lockers | 150 | EA | \$350.00 | \$52,5 |
| Locker room benches | 5 | EA | \$1,500.00 | \$7,5 |
| West Addition | | | . , | , - |
| Visitor Lockers2-tier metal lockers | 20 | EA | \$700.00 | \$14,0 |
| Official Changing - 3 Full ht Lockers | 3 | EA | \$750.00 | \$2,2 |
| Locker room benches | 2 | EA | \$1,500.00 | \$3,0 |
| Miscellaneous millwork allowance | 91,098 | SF | \$4.00 | \$364,3 |
| | | | | |
| Sub-Total: 8 Function Equipment and Specialties | 91,098 | SF | \$43.72 | \$3,982 |

9 Stairs and Vertical Transportation

| Stairs | | | | |
|---|----|--------|-------------|--------------|
| New Metal Pan/ conc. Treads Stair | | | | Not Required |
| New handrails and nosing on existing stairs at basement | 1 | FLIGHT | \$5,000.00 | \$5,000 |
| New handrails and nosing on existing stairs | 14 | FLIGHT | \$6,000.00 | \$84,000 |
| Lobby Stair retrofit | 2 | EA | \$40,000.00 | \$80,000 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| Quantity | Unit | Unit Rate | Total Cost |
|----------|-------------|----------------------------|--|
| | | | |
| | | | |
| 5 | STOPS | \$80,000.00 | \$400,000 |
| 2 | STOPS | \$75,000.00 | \$150,000 |
| 1 | EA | \$40,000.00 | \$40,000 |
| 91,098 | SF | \$8.33 | \$759,00 |
| | 5 2 1 | 5 STOPS 2 STOPS 1 EA | 5 STOPS \$80,000.00 2 STOPS \$75,000.00 1 EA \$40,000.00 |

Total - C) Equipment and Vertical Transportation (8-9)

91,098

SF

\$52.05

\$4,741,832

D) Mechanical and Electrical (10-13)

10 Plumbing Systems

| General Plumbing Equipment | | | | |
|---|--------|-----------|--------------|-----------|
| Domestic water heater replacement (Air source heat pump allowance) | 1 | EA | \$250,000.00 | \$250,000 |
| Domestic water heater | 1 | EA | \$50,000.00 | \$50,000 |
| Kitchen water heater | 1 | EA | \$16,900.00 | \$16,900 |
| Circulating pump | 1 | EA | \$2,095.00 | \$2,095 |
| Expansion tank | 1 | EA | \$558.90 | \$559 |
| Remove and replace grease interceptor | 1 | EA | \$37,550.00 | \$37,550 |
| Sanitary Fixtures | | | | |
| Fixture replacements, high eff | 1 | EA | \$95,000.00 | \$95,000 |
| Vacuum breakers and hose bibs | 1 | LS | \$2,500.00 | \$2,500 |
| Anti-scald tempering valves | 1 | LS | \$3,500.00 | \$3,500 |
| Drinking fountains, bottle filler | 1 | LS | \$5,368.00 | \$5,368 |
| Trap primer valve | 1 | LS | \$1,500.00 | \$1,500 |
| Domestic Cold Water | | | | |
| Domestic Cold Water Piping | 91,098 | SF | \$7.74 | \$705,099 |
| Water meter allowance | 1 | 20 risers | \$5,000.00 | \$5,000 |
| Domestic Hot Water | | | | |
| Domestic Hot Water Piping | 91,098 | SF | \$8.09 | \$736,983 |
| Water meter allowance | 1 | EA | \$5,000.00 | \$5,000 |
| Domestic Cold/Hot Water Connections | | | | |
| HW/CW connections to new fixtures | 1 | LS | \$17,379.00 | \$17,379 |
| Isolation valves on lateral lines | 1 | LS | \$5,369.00 | \$5,369 |
| Waste Piping | | | | |
| Waste Piping, SF | 91,098 | SF | \$9.15 | \$833,547 |
| Waste Piping, kitchen waste (allowance) | 1 | LS | \$85,000.00 | \$85,000 |
| Vent Piping | | | | |
| Vent Piping, SF | 91,098 | SF | \$2.82 | \$256,896 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| de | Quantity | Unit | Unit Rate | Total Cost |
|---------------------------------|------------|------|-------------|-------------|
| | | | | |
| Waste/Vent Connections | | | | |
| DMV connections to new fixtures | 1 | EA | \$11,877.00 | \$11,877 |
| Condensate Drainage | | | | |
| Trap and equipment connect | 11 | EA | \$421.50 | \$4,637 |
| 3/4" pipe, cu type L, in bldg | 275 | LF | \$38.55 | \$10,601 |
| Natural Gas | | | | |
| 4" seismic shut off valve | 1 | EA | \$4,527.00 | \$4,527 |
| Miscellaneous Plumbing | | | | |
| Test / clean plumbing | 150 | HR | \$112.23 | \$16,835 |
| Start-up/check-out | 180 | HR | \$134.67 | \$24,241 |
| Commissioning assist | 80 | HR | \$118.14 | \$9,451 |
| Access panels | 10 | EA | \$211.10 | \$2,111 |
| Piping identification | 25 | EA | \$26.70 | \$668 |
| Firestopping | 25 | EA | \$55.00 | \$1,375 |
| Seismic bracing | 1 | SF | \$45,000.00 | \$45,000 |
| Basement | 7,455 | SF | \$20.00 | \$149,100 |
| Sub-Total: 10 Plumbing Syste | ems 91,098 | SF | \$37.27 | \$3,395,666 |

11 Heating, Ventilation and Air Conditioning

| Chilled Water Equipment | | | | |
|---|--------|----|-------------|-----------|
| Chiller, air-cooled | 1 | EA | \$52,325.00 | \$52,325 |
| Glycol management system | 1 | EA | \$16,520.00 | \$16,520 |
| Relocate existing thermal energy storage system (allowance) | 1 | LS | \$40,800.00 | \$40,800 |
| CHW pump, end suction, 5 hp, 225 gpm | 2 | EA | \$5,099.00 | \$10,198 |
| VFD to CHW pump, 5 hp | 2 | EA | \$3,583.00 | \$7,166 |
| Heat exchanger | 1 | EA | \$8,006.00 | \$8,006 |
| Heating Hot Water Equipment | | | | |
| Hot water boiler, gas fired, condensing | 2 | EA | \$32,000.00 | \$64,000 |
| HW pump, end suction, 2 hp, 50 gpm | 2 | EA | \$4,267.00 | \$8,534 |
| VFD to HW pump, 3 hp | 2 | EA | \$3,339.00 | \$6,678 |
| Chilled Water Distribution | | | | |
| Chiller connect, weld, 6" | 1 | EA | \$9,327.00 | \$9,327 |
| CHW pump connect, weld, end suct, 4" | 2 | EA | \$9,051.00 | \$18,102 |
| CHW distribution | 91,098 | SF | \$7.39 | \$673,214 |
| Hot Water Distribution | | | | |
| Boiler connect, cu, 2" | 2 | EA | \$5,181.00 | \$10,362 |
| HHW pump connect, cu, 2" | 2 | EA | \$1,098.00 | \$2,196 |
| HHW coil connect, cu, 3-way, 1-1/4" | 8 | EA | \$1,266.00 | \$10,128 |
| HHW distribution | 91,098 | SF | \$7.04 | \$641,330 |

SMMUSD Santa Monica Civic Auditorium



| e | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|-------------|-------------|
| Air-Side Equipment | | | | |
| Hydronic Fancoils | | | | |
| AHUS / Fan coil, 4-pipe, horizontal | 8 | EA | \$97,110.00 | \$776,880 |
| Ductless split systems | 2 | EA | \$10,500.00 | \$21,000 |
| Fans | | L/ \ | 710,300.00 | 721,000 |
| Exhaust fans | 6 | EA | \$3,182.00 | \$19,092 |
| Kitchen exhaust fan | 1 | EA | \$13,300.00 | \$13,300 |
| MAU unit | 1 | EA | \$14,850.00 | \$14,850 |
| VFD to fan, 1.5 hp | 8 | EA | \$838.40 | \$6,707 |
| Air Distribution | | | | |
| Ductwork silencer allowance | 1 | LS | \$35,000.00 | \$35,000 |
| Ductwork, galv, purchased prefab'd | 99,268 | LBS | \$14.85 | \$1,474,130 |
| Grease duct | 2,500 | LBS | \$15.03 | \$37,575 |
| Duct insulation, wrap | 64,524 | SF | \$2.69 | \$173,570 |
| Firemaster rated insulation | 3,000 | SF | \$30.49 | \$91,470 |
| Manual volume damper | 472 | EA | \$75.24 | \$35,513 |
| Flexible duct, insulated, various sizes | 280 | LF | \$20.41 | \$5,715 |
| Grilles and diffusers | 200 | | 720.41 | 75,715 |
| Return Grilles | 30 | EA | \$140.70 | \$4,221 |
| Exhaust grilles | 10 | EA | \$131.00 | \$1,310 |
| Ceiling diffusers | 432 | EA | \$164.30 | \$70,978 |
| Miscellaneous | | | | |
| Test / balance HVAC | 450 | HR | \$131.31 | \$59,090 |
| Start-up/check-out | 375 | HR | \$119.38 | \$44,768 |
| Commissioning assist | 200 | HR | \$119.38 | \$23,876 |
| MEP Coordination | 275 | HR | \$119.38 | \$32,830 |
| Seismic bracing, pipe | 1 | LS | \$50,000.00 | \$50,000 |
| Seismic bracing, pipe Seismic bracing, duct | 1 | LS | \$50,000.00 | \$50,000 |
| Hoisting and rigging | 1 | LS | \$80,000.00 | \$80,000 |
| Basement | 7,455 | SF | \$55.00 | \$410,025 |
| HVAC Controls | | | | |
| DDC controls, chiller | 1 | EA | \$19,130.00 | \$19,130 |
| DDC controls, boiler | 1 | EA | \$15,310.00 | \$15,310 |
| DDC controls, pump wth vfd | 4 | EA | \$7,654.00 | \$30,616 |
| DDC controls, fancoil, 4-pipe | 8 | EA | \$30,000.00 | \$240,000 |
| DDC controls, general exhaust fan | 7 | EA | \$1,435.00 | \$10,045 |
| DDC controls, controls workstation | 1 | EA | \$40,000.00 | \$40,000 |
| Sub-Total: 11 Heating, Ventilation and Air Conditioning | 91,098 | SF | \$60.00 | \$5,465,885 |

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



12 Electrical Lighting, Power and Communications Service and Distribution Replace all Existing Zinsco Panels/Feeders 1 LS \$122,185.00 \$122,185 1 LS \$90,000.00 Replace all Existing Zinsco Distribution Boards in main electrical room (5 DBs) \$90,000 Replace Existing MCC1 and MCC2 with Distribution board/add separate starters or VFDs (supplied by MC installed by EC) \$100,000.00 \$100,000 1 LS Provide 400A rated kitchen Distribution Board to serve new all electric commercial kitchen including new feeder 1 LS \$25,920.00 \$25,920 **HVAC** and Plumbing equipment connections HVAC and Plumbing equipment connections (Scheme 2) 1 LS \$315,000.00 \$315,000 New kitchen equipment connections 1 LS \$55,000.00 \$55,000 Provide new disconnect and panel to serve elevator loads on new elevator machine rooms including new feeders 1 LS \$18,500.00 \$18,500 Convenience Power Update with GFCI protected receptacles required for most restrooms, janitor's closets and kitchen spaces 1 LS \$42,500.00 \$42,500 **Lighting and Lighting Controls** Upgrade entire existing Lighting with LED fixtures and lighting controls with Title 24 code compliant controls 91,098 SF \$33.50 \$3,051,783 Upgrade existing Stage Theatrical Lighting with LED fixtures and lighting controls with Title 24 code compliant controls 91,098 \$4.50 \$409,941 Provide Theater Aisle Lighting with J-Box & wiring \$54,000.00 1 LS \$54,000 Theater Lighting package (per Salas O'Brien quote) 1 LS \$850,000.00 \$850,000 Temporary Power **Temporary Power** 91,098 SF \$1.50 \$136,647 Miscellaneous Start-up, Third party testing, commissioning assist, labels, firestopping, pipe penetrations, seismic and misc SF 91,098 \$2.00 \$182,196 General conditions / General requirements - Includes Small Tools, Office Staffing, Indirect Labor, Consumables, Equipment Rental & General Expenses SF \$614,912 91,098 \$6.75 Communications Technology - provide dedicated Signal Rooms at North and South ends of the building. Provide MDF/MPOE and IDF room and fiber and copper backbone cabling. Install floor mounted data racks 91,098 SF \$1.25 \$113,873

SMMUSD Santa Monica Civic Auditorium



| | Quantity | Unit | Unit Rate | Total Cost |
|--|----------|------|----------------|--------------|
| Audio Visual | | | | |
| Provide AV equipment in new AV control room. Provide projector and projector | | | | |
| screen, speakers, wireless mic and assistive listening & wiring | 91,098 | SF | \$2.50 | \$227,745 |
| Audio Visual - conduit rough-ins | 91,098 | SF | \$1.00 | \$91,098 |
| TV Broadcasting/Radio Infrastructure to record, edit and stream events | 1 | LS | \$35,000.00 | \$35,000 |
| AV Equipment for Theater (per Salas O'Brien quote) | 1 | LS | \$1,770,000.00 | \$1,770,000 |
| | | | . , , | |
| Security Systems | | | | |
| Replace existing Security System - provide new keypads, access control on entry points and motion sensors & wiring | 91,098 | SF | \$1.75 | \$159,422 |
| CCTV Systems | | | | |
| Provide new CCTV system with IP cameras & wiring/new head end equipment | 91,098 | SF | \$2.50 | \$227,745 |
| Fire Alarm Systems | | | | |
| Replace defective Fire alarm devices such as detectors, speaker/strobes per the | | | | |
| fie alarm testing report, connection to replaced Ansul fire suppression system | 91,098 | SF | \$6.50 | \$592,137 |
| Sub-Total: 12 Electrical Lighting, Power and Communications | 91,098 | SF | \$101.93 | \$9,285,603 |
| Fire Protection Systems | | | | |
| Backflow preventer, red press | 1 | EA | \$7,209.00 | \$7,209 |
| Provide new sprinklers and piping (stage, seating, wooden warehouse, lobby) | 91,098 | SF | \$6.28 | \$572,095 |
| Sprinkler replacement, various areas (corroded, painted and outdated) | 91,098 | SF | \$2.91 | \$265,095 |
| Sub-Total: 13 Fire Protection Systems | 91,098 | SF | \$9.27 | \$844,400 |
| tal - D) Mechanical and Electrical (10-13) | 91,098 | SF | \$208.47 | \$18,991,553 |
| Building Prep & Demo (14-15) | | | | |
| Building Preparations & Protection | | | | |
| Allowance to protect existing to remain scope items | 1 | LS | \$125,000.00 | \$125,000 |
| Excavation at basement including backfill and recompact ion | 1 | LS | \$20,000.00 | \$20,000 |
| | | | | |
| Sub-Total: 14 Building Preparations & Protection | 91,098 | SF | \$1.59 | \$145,000 |

SMMUSD Santa Monica Civic Auditorium



| e e e e e e e e e e e e e e e e e e e | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|-------------|------------|
| Building Demolition | | | | |
| Structural Demolition | | | | |
| Demo two additions to south of building in entirety | 1 | LS | \$7,800.00 | \$7, |
| Selective Demolition of locker rooms, restroom, janitors closet at basement | 7,000 | SF | \$10.00 | \$70, |
| Demo existing flooring including framing | 11,500 | SF | \$8.00 | \$92, |
| Demo existing stage floor | 4,265 | SF | \$8.00 | \$34, |
| Make opening in interior concrete wall - 4'6" | 59 | SF | \$75.00 | \$4, |
| Demo slab for new elevator shaft | 135 | SF | \$75.00 | \$10, |
| Demo East Wing (Committee) in entirety | 6,900 | SF | \$12.00 | \$82, |
| Demo West Wing (Administration) in entirety | 2,000 | SF | \$12.00 | \$24, |
| Building Envelope Demolition | | | | |
| Remove existing Glazing at Auditorium building | 4,020 | SF | \$15.00 | \$60, |
| Remove existing Auditorium roof | 32,065 | SF | \$5.00 | \$160, |
| Interior Demolition | | | | |
| Remove all rigging systems | 1 | LS | \$85,000.00 | \$85, |
| Demo for new balcony - 3 rows of chairs and accessories | 1 | LS | \$69,000.00 | \$69, |
| Demo ticket and small kitchen | 530 | SF | \$20.00 | \$10, |
| Demo existing surface finishes at Auditorium building | 82,198 | SF | \$1.50 | \$123, |
| MEP Demolition | | | | |
| Remove fixtures, cap lines | 1 | LS | \$11,220.00 | \$11, |
| Remove fixtures and associated local pipe | 1 | LS | \$4,489.00 | \$4, |
| Remove ductwork & registers | 86,320 | SF | \$2.81 | \$242, |
| Remove HVAC equipment | 1 | LS | \$22,910.00 | \$22, |
| Selective trade demolition - Electrical and fire alarm | 86,320 | SF | \$3.20 | \$276, |
| Sub-Total: 15 Building Demolition | 91,098 | SF | \$15.27 | \$1,391, |
| al - E) Building Prep & Demo (14-15) | 91,098 | SF | \$16.86 | \$1,536,1 |

Construction Cost Detail - Site Development Scheme 2

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023

Total - F) Site Work (16-18)



F) Site Work (16-18) 16 Site Preparation and Demolition Selective demolition and removal Hardscape demolition allowance 103,676 SF \$2.00 \$207,352 Landscape demolition allowance 103.676 SF \$1.00 \$103,676 **General Site Grading** 103,676 SF \$2.00 \$207,352 **Erosion Control** 103,676 SF \$0.50 \$51,838 \$1,000,000.00 Phase 2 Clean-up LS \$1,000,000 1 Sub-Total: 16 Site Preparation and Demolition 103,676 SF \$15.15 \$1,570,218 17 Site Paving, Structures & Landscaping Pedestrian paving allowance - includes asphalt / concrete paving 41,470 SF \$25.00 \$1,036,760 Depress Slab and mosaic tile at entry 3,000 SF \$350.00 \$1,050,000 \$150,000.00 \$150,000 Site furnishing and accessories LS 1 Landscape planting and maintenance 72,573 SF \$15.00 \$1,088,598 \$4,000.00 **New Trees** 15 EΑ \$60,000 72,573 SF \$4.00 \$290,293 Irrigation \$35.45 Sub-Total: 17 Site Paving, Structures & Landscaping 103,676 \$3,675,651 18 Utilities on Site Storm Drain Storm drain underground piping including drain inlets, replacement of 8" 1,000 LF \$350.00 \$350,000 existing SD pipe Storm Water management - Mitigate 6,500CF of storm water including LS \$150,000.00 \$150,000 underground cistern and pretreatment system 1 Domestic and Fire Water Replace existing domestic and fire water system including connections LF 300 \$200.00 \$60,000 New Fire hydrant 1 EΑ \$20,000.00 \$20,000 Sanitary Sewer Replace existing Sewer system including connections 500 LF \$250.00 \$125,000 Site Electrical Upgrade emergency genset from 30kW to 150kW including 150A ATS to 400A ATS and upgrade feeders 1 LS \$197,000.00 \$197,000 Site Lighting Upgrade existing exterior Lighting with LED fixtures and lighting controls with Title 24 code compliant controls \$75,000.00 \$75,000 1 LS \$150,000.00 \$150,000 Allowance for exterior lighting and power/data along north facades 1 LS 103,676 Sub-Total: 18 Utilities on Site SF \$10.87 \$1,127,000

\$6,372,869

\$61.47

103,676

SF

Appendix

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude July 13, 2023



APPENDIX

Hazardous Material Abatement

SMMUSD Santa Monica Civic Auditorium

Rough Order of Magnitude SOPC July 13, 2023



| e | Quantity | Unit | Unit Rate | Total Cost |
|---|----------|------|--------------------|---------------|
| nestos and Lead Abatement | | | | |
| Asbestos containing materials removal and disposal (includes Asbestos removal | | | | |
| worker, restricted working space, waste handling, packing, PPE, dumpster rentals) | | | | |
| Stone & Tile | 1 | LS | \$19,575.00 | \$19,57 |
| Red terrazzo | 60 | SF | . , | . , |
| 12" Green floor tile with mastic | 700 | SF | | |
| 9" black floor tile with mastic | 545 | SF | | |
| Ceiling tiles | 1 | LS | \$122,280.00 | \$122,2 |
| 12" Pinhole ceiling tile mastic | 8,000 | SF | 7, | +,- |
| Coatings | 1 | LS | \$13,184.00 | \$13,1 |
| Black battleship flooring | 5,700 | SF | 7 - 2 / 2 2 11 2 2 | 7/- |
| Gray and black mastic | 10 | SF | | |
| Gray heat shield paper | 2 | SF | | |
| Puck mirror mastic | 400 | SF | | |
| Pipe & fittings | 1 | LS | \$7,200.00 | \$7,2 |
| Thermal system insulation / TSI | 200 | LF | \$7,200.00 | ۷,,۷ |
| Transite pipe | 40 | LF | | |
| Miscelleneous | 1 | LS | \$54,000.00 | \$54,0 |
| Fire rated doors | 600 | SF | \$34,000.00 | 334, 0 |
| Fire curtain | 2,500 | SF | | |
| TSI saddles between sleepers supporting stage | 500 | SF | | |
| | 500 | 31 | | |
| Lead-Based Paint Abatement (inculdes Lead removal worker, restricted working | | | | |
| space, waste handling, packing, PPE, dumpster rentals) | | | 4100 000 00 | 4.00 |
| Tile Substrate | 1 | LS | \$180,000.00 | \$180,0 |
| Porcelain / Ceramic Wall tile | | | | |
| Porcelain / Ceramic Floor tile | | _ | | |
| Metal Substrate | 1 | LS | \$440,000.00 | \$440,0 |
| Beams & Columns | | | | |
| Stairs | | | | |
| Doors including casing | | | | |
| Railings | | | | |
| Floor coating | | | | |
| HVAC ducts | | | | |
| Fire Riser | | | | |
| Wood Substrate | 1 | LS | \$160,000.00 | \$160,0 |
| Doors | | | | |
| Wall cabinet | | | | |
| Concrete and Plaster Substrate | 1 | LS | \$320,000.00 | \$320,0 |
| Walls | | | | |
| Posts | | | | |
| Allowance for HazMat removal under stage | 1 | LS | \$125,000.00 | \$125,0 |
| Allowance for site clean up due to potential impact of former on-site gasoline | | | | - |
| station, machine shop - allow 10% of total finished site area | 12,439 | SF | \$40.00 | \$497,5 |
| Contingency | 25% | | \$1,938,779 | \$484,6 |
| Indirect Cost Mark-ups | 19% | | \$2,423,474 | \$471,2 |
| munical cost iviain-ups | | | | 4/1,2 |
| Sub-Total: | 70,389 | SF | \$41.12 | \$2,894,6 |
| al Ashastas and Land Abstructut | 70.200 | | 644.43 | ć2.004.C |

Page 50 of 51

\$41.12

\$2,894,694

Schedule of Areas

SMMUSD Santa Monica Civic Auditorium



Rough Order of Magnitude SOPC July 13, 2023

| | Existing | Scheme 0 | Scheme 1 | Scheme 2 |
|-------------------------------------|-----------------|------------|------------|------------|
| | (Code Analysis) | | | |
| Basement | 7,456 SF | 7,456 SF | 7,456 SF | 7,456 SF |
| Lvl 1 - Bld * | 33,612 SF | 33,612 SF | 33,612 SF | 33,612 SF |
| Lvl 1 - Wings * | 9,291 SF | 9,546 SF | 9,546 SF | 30,000 SF |
| Lvl 2 | 3,743 SF | 3,743 SF | 3,743 SF | 3,743 SF |
| Lvl 3 | 15,262 SF | 15,262 SF | 15,262 SF | 15,262 SF |
| Lvl 4 | 1,025 SF | 1,025 SF | 1,025 SF | 1,025 SF |
| TOTAL | 70,389 SF | 70,644 SF | 70,644 SF | 91,098 SF |
| Civic Building only | 61,098 SF | 61,098 SF | 61,098 SF | 61,098 SF |
| Athletics Building * | | | 3,000 SF | |
| TOTAL - Civic + Athletics Buildings | 61,098 SF | 61,098 SF | 64,098 SF | 61,098 SF |
| Wings | 9,291 SF | 9,801 SF | 9,801 SF | 30,000 SF |
| TOTAL - Wings | 9,291 SF | 9,801 SF | 9,801 SF | 30,000 SF |
| TOTAL - Building + Wings | 70,389 SF | 70,899 SF | 73,899 SF | 91,098 SF |
| Total Site | 167,288 SF | 167,288 SF | 167,288 SF | 167,288 SF |
| Building + Wings Footprint | 42,903 SF | 43,158 SF | 46,158 SF | 63,612 SF |
| FINISHED SITE AREA | 124,385 SF | 124,130 SF | 121,130 SF | 103,676 SF |

^{*} Building Footprint Area





FINDINGS AND DETERMINATION OF THE LANDMARKS COMMISSION OF THE CITY OF SANTA MONICA IN THE MATTER OF THE DESIGNATION OF A LANDMARK

DESIGNATION OF LANDMARK FOR THE STRUCTURE LOCATED AT 1855 MAIN STREET (CIVIC AUDITORIUM) LANDMARKS COMMISSION HEARING LC-01LM-004

NOVEMBER 12, 2001

SECTION I. The Landmarks Commission of the City of Santa Monica, having filed an application on August 13, 2001 to designate the Civic Auditorium located at 1855 Main Street as a City Landmark, having determined that the application merits formal consideration on October 8, 2001, and a Public Hearing having been held before the Landmarks Commission of the City of Santa Monica on November 12, 2001, hereby makes the following findings regarding the Civic Auditorium:

(1) It exemplifies, symbolizes, or manifests elements of the cultural, social, economic, political, or architectural history of the City.

This building was constructed in 1958 in response to the development of the Santa Monica Civic Center. It was the third of three major 20th century Civic Center structures, beginning with the Art Deco style City Hall, designed by Los Angeles architect Donald Parkinson and completed in 1938 and the Los Angeles County Courthouse, which was added in 1951. It remains an excellent example of the International Style (Modern), a style that dominated the architectural face of the globe from the first decade of the 20th century until 1972. It is the only surviving institutional design in the City of Santa Monica. The Santa Monica Civic Auditorium replaced a classically inspired facility that had been located at Lick Pier, known as the Ocean Park Municipal Auditorium. In this way, its construction also served to strengthen the function of the Civic Center as a primary hub of activity. Therefore, this resource satisfies this criterion.

(2) It has aesthetic or artistic interest or value, or other noteworthy interest or value.

The Santa Monica Civic Auditorium is an excellent example of the mid-century International Style, and the only such example of the work of master architect Welton Becket in the City. Furthermore, it is significant for the unique engineering design of its hydraulic floor, the largest in the nation at the time. This was a landmark use of hydraulic technology for adapting an assembly space to

accommodate a vast variety of stage performances, athletic events, and exhibitions. It proved to be the forerunner to the retractable domes and flexible seating of contemporary stadiums (Alan Lieb, 2001). Finally, its acoustical design by world-renowned acoustical engineer, UCLA Chancellor Vern O. Knutsen, was described as, "the most perfect and...(deserving)...a rating higher than that of the Royal Festival Hall in London" (Becket, 2001, and *Progressive Architecture*, May 1959). Thus, as a truly remarkable resource, the Santa Monica Civic Auditorium meets this criterion.

(3) It is identified with historic personages or with important events in local, state or national history.

The Civic Auditorium is associated with its architect, Welton Becket, as well as its acoustical engineer Vern O. Knutsen, both internationally prominent professionals in the design of major institutions. Becket's work is found throughout the world with notable Commissions in Cairo, Havana, Manila, Honolulu, Tokyo, Boston, Philadelphia, Kansas City and Dallas, and includes numerous civic designs. Vern O. Knutsen, a professor and Chancellor of UCLA, was the world's leading authority on architectural acoustics, and a master designer of acoustically significant facilities. His principles in architectural acoustics became the foundation for the design of contemporary soundstages. Additionally, the Santa Monica Civic Auditorium is associated with countless events and public performances, like no other facility in the City. These performances have represented the diversity for which Santa Monica has become renown. A few prominent examples include an array of musicians from Andre Previn and Dave Brubeck in 1959 to Pete Seeger, Ella Fitzgerald, Tony Bennett, Joan Baez and Bob Dylan in the 1960's, to Elton John, Ray Charles, Arlo Guthrie, the Beach Boys and the Carpenters in the 1970's. The number of performances eventually reached a level of nearly 60 concerts annually in the peak years of the 1970s. The auditorium also hosted several prominent comedians in the early years of their careers, such as Bill Cosby, Jonathan Winters and Bob Hope, as well as a 1967 performance by Beatnik poet Allen Ginsburg. Therefore, this resource meets this criterion.

(4) It embodies distinguishing architectural characteristics valuable to a study of a period, style, method of construction, or the use of indigenous materials or craftsmanship, or is a unique or rare example of an architectural design, detail, or historical type to such a study.

The Civic Auditorium is an excellent example of the mid-century International Style in the City of Santa Monica. The style was a response to the industrialization of the late 19th and early 20th centuries. It advocated the use of the "machine", rather than historical precedents for building and product designs, as well as the use of contemporary materials such as steel, concrete and glass for their construction. The Civic Auditorium retains many significant character-defining elements of this style, including, a grand canopy, supported by parabolic pylons, a glass curtain wall, and brise-soleil.

The Civic Auditorium also retains a number of significant interior features that are integral to the overall concept of the Civic Auditorium's architecture. Conceived as a space for a variety of activities, Welton Beckett designed the Civic Auditorium for functionality and flexibility. Some intact features that are part of the public space include the original adjustable auditorium main hall hydraulic floor, touted as revolutionary for its time, the innovative acoustical design and the soundproof sliding doors to the east conference rooms. Additionally, although some alterations have been made, interior elements such as the wood paneling in the lobby, the auditorium entry doors, the volume and configuration of the lobby (both the first and second floors including the height and semi-circular shape of the lobby, the upper lobby's shape being reflective of the lower lobby, and the columns), all contributing to the overall light, open and modernistic feeling), the volume and configuration of the auditorium main hall, the metal acoustical panels and wall sconces in the auditorium main hall, and the two floating staircases in the lobby, all attributes of the building's integral design, remain intact and continue to be valuable to a study of this unique architectural style and method of construction.

The Civic Auditorium also includes some character-defining features in the backstage area that are not part of the public space, and thus not part of the landmark designation. These include the orchestra pit hydraulic lift mechanism, stage area and proscenium opening, stage rigging and historic signage along the east wall at the rear of the stage.

As a resource that still retains a comprehensive integrity of its original architectural design, the Santa Monica Civic Auditorium satisfies this criterion.

(5) It is a significant or a representative example of the work or product of a notable builder, designer, or architect.

The Civic Auditorium is the only surviving institutional design of master architect and Santa Monica resident Welton Becket in the City of Santa Monica. Becket is significant not only as a leading local designer, but, internationally. His work is found throughout the world with notable commissions in Cairo, Havana, Manila, Honolulu, Tokyo, Boston, Philadelphia, Kansas City, and Dallas, and includes numerous civic designs.

The Santa Monica Civic Auditorium is also significant for its association with internationally renowned acoustical engineer Vern O. Knutsen. Knutsen, a professor and Chancellor of UCLA, was the world's leading authority on architectural acoustics, and a master designer of acoustically significant facilities. An ardent researcher and author on architectural acoustics, Knutsen wrote two seminal books and over one hundred articles, which appeared in scientific and technical journals. As a consultant he was responsible for the acoustical design of over five hundred structures. His principles in architectural acoustics became the

foundation for the design of contemporary soundstages. The systems developed for the Civic Auditorium by Knutsen are still highly functional and have required minimal maintenance over the last 43 years. Therefore, the Civic Auditorium meets this designation criterion.

(6) It has a unique location, a singular physical characteristic, or is an established and familiar visual feature of a neighborhood, community or the City.

The Santa Monica Civic Auditorium has a unique location within the Civic Center, at the bend of Main Street. Its grand scale, and unique design with futuristic pylons, commands attention as one travels south along Main Street. Pigmy Date Palm trees frame the north entry to the building. The Civic Auditorium is also a familiar and integral part of the Civic Center complex. The Civic Auditorium is, thus, an important visual monument in the City of Santa Monica. Therefore, the Santa Monica Civic Auditorium satisfies this criterion.

SECTION II. The designation of the Civic Auditorium includes the exterior of the building, the remaining original pygmy palm trees as a secondary feature, and the following interior elements located in public areas of the resource:

- Configuration of lobby spaces (first and second floors) and auditorium entry doors (height and semi-circular shape of lobby, upper lobby shape reflective of lower lobby, and columns contributing to the overall light, open and modernistic feeling);
- Wood paneling along south wall of first floor lobby;
- Two original lobby staircases;
- Volume and configuration of auditorium main hall space;
- Adjustable auditorium main hall floor with hydraulic lift mechanism;
- Metal acoustical panels and wall sconces in auditorium main hall;
- Soundproof sliding doors to conference room (adjacent to the east elevation).

SECTION III. I hereby certify that the above Findings and Determination accurately reflect the final determination of the Landmarks Commission of the City of Santa Monica on November 12, 2001, as determined by the following vote:

AYES:

Fresco, Genser, Posek, Schnitzler, Lehrer, Alofsin

NAYES:

None

ABSENT:

Bolton

Respectfully Submitted December 10, 2001


Margot Alofsin, Chairperson

Attest:


Elizabeth Bar-El, AICP

Landmarks Commission Secretary


F:\PLAN\SHARE\Landmarks\Designations\2001\Determination Civic Auditorium.doc













INTERIOR HISTORIC PHOTOGRAPH CURRENT PHOTOGRAPH (HRG 2023) Basement, tilt floor hydrauling lifting mechanism Basement, tilt floor hydrauling lifting mechanism, view facing northeast Source & date: Santa Monica Public Library, 1958

INTERIOR HISTORIC PHOTOGRAPH CURRENT PHOTOGRAPH (HRG 2023) 1ST floor, main lobby, view facing northeast 1ST floor, main lobby, view facing northeast Source & date: Santa Monica Public Library, 1958

HISTORIC PHOTOGRAPH CURRENT PHOTOGRAPH (HRG 2023) 1st floor, auditorium, view facing southeast Source & date: Sonto Monica Public Library, 1958

HISTORIC PHOTOGRAPH CURRENT PHOTOGRAPH (HRG 2023) 1st floor, auditorium, view facing southwest Source & date: Santa Monica Public Library, c. 1960s





APPENDIX C

HISTORIC AERIAL PHOTOGRAPHS



1958 (Kelly-Holiday Mid-Century Aerial Collection)



1958 (Kelly-Holiday Mid-Century Aerial Collection)



1962 (University of California, Santa Barbara)



1971 (University of California, Santa Barbara)



1994 (Google Earth)

TABLE 1: CHARACTER-DEFINING FEATURES

| EXTERIOR | | | | | |
|------------------|---|--------------|---|---|---|
| OCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| Site | Overall site: Location at corner of Main St. and Pico Blvd. Flat, irregularly shaped site Deep setbacks along Main St. and Pico Blvd. | Primary | Alterations: • Hardscape and landscape substantially altered | | Pico Boulevard |
| Site | Hardscape and landscape: • Pygmy palm trees at northwest corner of site | Primary | | The trees were identified as of "primary" significance in the Landmark designation; therefore, that categorization is noted here. | Detail of pygmy palm trees, view facing northeast |
| Overall exterior | Form and massing: Curved canopy attached to primary (north) façade 3-story primary rectangular main building (main lobby, auditorium, stage, and concourse) 1-story rectangular east wing (committee rooms) Smaller 1-story rectangular west wing (administration) Raised rectangular fly tower at rear over stage | Primary | Two 1-story rear additions (addition at southwest corner constructed c. 1967-1971; addition at southeast corner constructed c. 1993-1994) | | East Wing Main Building West Wing |

| EXTERIOR | | | | | |
|---------------|---|--------------|---|---|---|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| rimary façade | Primary (north) façade: • Overall rectangular and minimally curved convex form • Canopy: eight smooth concrete beams (painted); six smooth concrete pylons (painted); minimally curved metal panel canopy (painted) • Concrete brise soleil (painted) • Aluminum frame curtain wall (frame painted); clear glass (1st floor); textured glass (2nd and 3rd floors) | Primary | Additions and alterations: • 1-story projecting box office addition underneath canopy • Several textured glass panels replaced (not exact matches) | Curtain wall at first floor has been boarded up | Primary façade, view facing south Detail of Bris-soleil, view facing south Detail of canopy, view facing east |

| EXTERIOR | | | | | |
|----------|----------------------------|--------------|-------------|----------|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| | | | | | |
| | | | | | Details of canopy, view facing east (left) and west (right) |
| | | | | | Interview view showing curtain wall at 1st floor, view facing northeast Interior detail of textured glass at 2st and 3st floors |

| EXTERIOR | | | | | |
|-----------------|---|--------------|-------------|---|---|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| Auditorium roof | Auditorium roof: | Primary | | | Aerial, view facing northeast |
| West façade | West (Main St.) façade: Overall rectangular and angled (at center) concave form Exterior cladding: vertically scored concrete Fenestration: aluminum frame storefronts (main lobby) | Secondary | | In general, features on secondary facades are identified as of secondary significance; alterations are typically more acceptable on secondary facades. In addition, the primary architectural statement elements on this building are limited to the primary façade while the other facades are more utilitarian in nature. | West façade, view facing east |
| | | | | | Inverior view of main lobby storefronts, view facing west |

| EXTERIOR | | | | | | |
|-------------|---|--------------|---|--|--|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH | |
| West wing | West wing: Overall rectangular form Exterior cladding: smooth cement plaster Fenestration: aluminum frame windows Flat roof surrounded by parapet | Secondary | Alterations: • Air conditioning units installed in west wing windows | Although the west wing is part of the original design, it is a relatively small, utilitarian space. | | |
| East façade | East (side) façade: • Overall rectangular and angled (at center) concave form • Exterior cladding: vertically scored concrete • Fenestration: aluminum frame storefronts (main lobby) | Secondary | | The storefronts are currently boarded up. In general, features on secondary facades are identified as of secondary significance; alterations are typically more acceptable on secondary facades. In addition, the primary architectural statement elements on this building are limited to the primary façade while the other facades are more utilitarian in nature. | West wing, view facing northeast East façade, view facing southwest | |

| EXTERIOR | | | | | |
|-----------|---|--------------|-------------|---|---|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| | | | | | Inverior view of main lobby storefronts, view facing east |
| East wing | East wing: Overall rectangular form Exterior cladding: smooth cement plaster Fenestration: aluminum frame storefronts Flat roof surrounded by parapet | Secondary | | The east wing has been boarded up. Although the east wing is part of the original design, it is a relatively small, utilitarian space. | East wing, view facing southwest |
| | | | | | Inverior view of east wing storefronts, view facing north |

| EXTERIOR | | | | | | |
|-------------|--|--------------|--|---|---|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH | |
| Rear façade | Rear (Pico Blvd., south) façade: Overall rectangular form Exterior cladding: vertically scored concrete Fenestration: paired aluminum-frame multi-light hopper windows (3 rd floor) concealed by horizontal aluminum louvers | Secondary | Additions (as noted above): • Two 1-story rear additions (addition at southwest corner constructed c. 1967-1972; addition at southeast corner constructed c. 1993-1994) | Only those features that are part of the original building are considered secondary character-defining features. The later additions were constructed after the period of significance of the building and do not contribute to its significance. | South façade, view facing northeast Interior detail of windows (3 rd floor) | |
| Fly Tower | Fly Tower: Raised rectangular fly tower at rear over stage Exterior cladding: smooth concrete with expansion joints Flat roof surrounded by parapet | Primary | | The interior of the fly tower space could be adaptively reused for other purposes, but the external volume is a primary exterior feature directly associated with the significance of the building. | Fly tower, view facing northeast | |

| INTERIOR | NTERIOR | | | | | | |
|-----------------------------------|---|--------------|---|---|---|--|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH | | |
| Basement | Tilt floor: • Hydraulic lifting mechanism | Primary | | The hydraulic equipment appears to be intact in its original location. Functionality to be confirmed. | Tilt floor lifting mechanism, view facing northeast | | |
| 1 st floor: main lobby | Overall height and configuration: Location, configuration, and spatial relationships 2-story height Curved floorplan Combination flat and sloped ceiling | Primary | Alterations: Original ticket sales room with telephone booths on north wall demolished and replaced with present, larger space Two circular concession stands at east and west ends of lobby removed Original floor materials (carpet and terrazzo) replaced with new terrazzo Pendent lighting fixtures removed | | Main lobby, view facing west | | |

| INTERIOR | | | | | | | |
|-----------------------------------|---|--------------|--|----------|--|--|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH | | |
| | | | | | Non-original ticket sales room, view northwest | | |
| 1 st floor: main lobby | Columns: | Primary | Alterations: | | | | |
| | Six square columns | | Original drawings specify "vinyl plastic" finish on columns (does not appear to be extant) | | Typical column | | |
| 1 st floor: main lobby | Vertical wood paneling (unpainted) on south wall (location of auditorium entrances) | Primary | Alterations: • Signage added | | General view of wood paneling, view facing southeast | | |

| INTERIOR | | | | | |
|-----------------------------------|---|--------------|-------------|---|---|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| | | | | | Details of wood paneling |
| 1 st floor: main lobby | Six identical metal double doors connecting main lobby and auditorium Metal hardware | Secondary | | These doors were identified in the Landmark designation and therefore are noted here as character-defining features; however, they are standard slab doors that do not appear to have been specifically designed for this building. | Typical auditoium entry door: lobby-facing (left) and auditorium-facing (right) sides |
| 1 st floor: main lobby | Staircases: Two identical concrete staircases (east and west) Each staircase features: closed concrete stringers (painted) and concrete risers and treads (terrazzo finish); two landings; metal rails and newels (painted); wood handrails and balusters (unpainted) | Primary | | Alterations to meet current code are acceptable. | East staircase, view facing north |

| CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
|----------------------------|----------------------------|---|---|--|
| | | | | |
| | | | | East staircase, view facing northeast |
| | | | | West staircase, view facing north West staircase, view facing northwest |
| | CHARACTER-DEFINING FEATURE | CHARACTER-DEFINING FEATURE SIGNIFICANCE | CHARACTER-DEFINING FEATURE SIGNIFICANCE ALTERATIONS | CHARACTER-DEFINING FEATURE SIGNIFICANCE ALTERATIONS COMMENTS |

| INTERIOR | | | | | | | |
|-----------------------------------|---|--------------|-------------|----------|--|--|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH | | |
| | | | | | Typical terrazzo finish on risers and treads | | |
| 1 st floor: auditorium | Overall height and configuration: | Primary | | | Typical terrazzo illishi oli risers and treads | | |
| | Location, configuration, and spatial relationships 3-story height Angled outer (east and west walls); curved rear (north) wall Sloped seating area above six corridors leading to main lobby entrances | | | | Auditorium, view facing south Auditorium, view facing north | | |

| INTERIOR | | | | | |
|----------|----------------------------|--------------|-------------|----------|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCÉ | ALTERATIONS | COMMENTS | Auditorium, view facing west Auditorium, view facing east |
| | | | | | Auditorium, view facing southwest |

| INTERIOR | | | | | |
|----------|----------------------------|--------------|-------------|----------|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| | | | | | Auditorium, view facing southeast Auditorium seating, view facing northeast |
| | | | | | Auditorium seating, view facing northwest |

| INTERIOR | | | | | |
|----------------------|--|--------------|-------------|--|---|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| | Auditorium and orchestra floors: • Auditorium floor: wood tilt floor operated by hydraulic system in basement (can be transformed from flat surface for convention purposes to raked floor for theater productions) • Orchestra floor: wood floor operated by hydraulic system in basement (can be lowered into orchestra pit) | Primary | ALTERATIONS | COMMENTS | PHOTOGRAPH Detail of orchestra (front) and auditorium (back) floors, view facing north |
| | | | | | Detail of orchestra (front) and auditorium (back) floors, view facing north |
| st floor: auditorium | Symmetrically arranged metal acoustical panels on upper portion of east and west walls Symmetrically arranged paired metal lighting fixtures on select acoustical panels | Secondary | | Some corrosion of acoustical panels and light fixtures observed. | Typical acoustical panels and wall sconces |

| INTERIOR | NTERIOR | | | | | | |
|---|--|--------------|-------------|--|---|--|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH | | |
| 1 st floor: stage and fly tower | Overall height and configuration: • 4-story height (3-stories + fly tower extending above roof level of auditorium) • Rectangular plan | Primary | | The stage and its relationship to the auditorium are of primary significance. As noted above, the exterior volume of the fly tower is significant; however, the interior, multistory fly space can be adaptively reused if needed. | Stage, view facing west | | |
| | | | | | | | |
| 1 st floor: committee rooms | Overall height and configuration: 1-story height Rectangular plan | Secondary | | | Stage, view facing east Committee rooms, view facing northeast | | |

| INTERIOR | INTERIOR | | | | | | |
|--|--|--------------|-------------|--|--|--|--|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH | | |
| | | | | | Committee rooms, view facing southwest | | |
| 1 st floor: auditorium & committee rooms | Sliding doors: Two identical soundproof insulated wood sliding doors: east wall of auditorium; and west wall of committee rooms Metal hanger/ceiling tracks and metal floor tracks | Secondary | | These doors are identified in the Landmark nomination as character-defining. | | | |
| | | | | | Sliding door on east wall of auditorium, view facing southwest from committee rooms Sliding door on west wall of committee rooms, view facing southwest | | |

| SCHMING TEXT OF THE CONTROL OF THE C | INTERIOR | | | | | |
|--|----------------------|---|--------------|---|-----------|---|
| Detail of typical sicking door floor rough Detail of typical sicking door colling bangur/mode 1 Story height Curved plant following main lobby below 1 lat ceiling Alterations Overall height and configuration: 1 Curved plant following main lobby below 1 lat ceiling Alterations Overall height and configuration: 1 Curved plant following main lobby below 1 lat ceiling Overall height and configuration: 1 Curved plant following main lobby below 1 lat ceiling | LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| 3 rd floor: concourse Overall height and configuration: 1 -story height Curved plan following main lobby below Flat ceiling Primary Alterations Original asphalt tile flooring replaced with tetrazzo Concession booth at center of south wall removed | | | | | | |
| 3 rd floor: concourse Overall height and configuration: 1story height Curved plan following main lobby below Flat ceiling Alterations Original asphalt tile flooring replaced with terrazzo Concession booth at center of south wall removed | | | | | | Detail of typical sliding door floor track |
| 3rd floor: concourse Overall height and configuration: 1 - story height Curved plan following main lobby below Flat ceiling Overall height and configuration: Original asphalt tile flooring replaced with terrazzo Concession booth at center of south wall removed | | | | | | |
| 1-story height Curved plan following main lobby below Flat ceiling Original asphalt tile flooring replaced with terrazzo Concession booth at center of south wall removed | o-1 61 | | | | | Detail of typical sliding door ceiling hanger/track |
| | 314 floor: concourse | 1-story heightCurved plan following main lobby below | Primary | Original asphalt tile flooring replaced w terrazzo Concession booth a center of south wa | ith nt | Concourse, view facing west |

| INTERIOR | | | | | |
|----------------------------------|---|--------------|-------------|----------|---------------------------------------|
| LOCATION | CHARACTER-DEFINING FEATURE | SIGNIFICANCE | ALTERATIONS | COMMENTS | PHOTOGRAPH |
| | | | | | |
| 3 rd floor: concourse | Stairwells: | Primary | | | Concourse, view facing east |
| | Two identical stairwells (east and west) Each stairwell features metal rails and newels (painted) and wood handrails and balusters (unpainted) to match staircases unpainted Two identical stairwells (east and west) Each stairwells (east and west) Parallel stairwells (east and west) Two identical stairwells (east and west) Each stairwells (east and west) Parallel stairwells (east and west) Two identical stairwells (east and west) Each stairwells (east and west) Parallel stairwe | | | | East stairwell, view facing northwest |
| | | | | | West stairwell, view facing northeast |



APPENDIX A - Structural

| Photo #: | Photo: | Observations/Comments: |
|---|--------|---|
| 1: North Front Entrance Canopy with Concrete Pylons | | Concrete elements appeared to be in good condition. Canopy and Pylons may need to be strengthen for conformance to new seismic standards. |
| 2: South Building Elevation | | Appeared to be in good general condition. One-story storage sheds south of the main auditorium wall were not part of the original construction and are planned to be removed as part of the renovation. |
| 3: West Building Elevation | | Appeared to be in good general condition. The one-story addition west of the main auditorium wall was part of the original construction and its roof is connected to the auditorium wall. |
| 4: East Building Elevation | | Appeared to be in good general condition. The one-story addition east of the main auditorium wall was part of the original construction but it is separated by a 2" gap from the main auditorium wall. |

| 5: Main Auditorium Roof over the Main Floor Area | Dome like shape formed by the top chord of the steel trusses supporting the roof. |
|---|---|
| 6: Steel Roof Truss | Appeared to be in good condition with bolt rivet connections. The trusses support a gypsum deck with bulb tees that may not be adequate for the new seismic upgrade criteria required for the renovation of the building. |
| 7: Basement Level below Stage | Appeared to be good general condition. No signs of notable cracks were observed. |
| 8: The main floor area with fixed sloped seating at the north end of the auditorium floor | The concrete seating steps appeared to be in good general condition. |

-

9: The tilt floor at the main floor of the auditorium. 10: Steel Girders at 11: The Lobby Area



The concrete fill of the tilt floor appeared to have multiple cracks over its floor area that have been repaired with some kind of epoxy product that filled the cracks. A large portion of the floor was covered with boxes and other storage items that prevented a complete observation of the entire floor area. The type of epoxy repair used is unknown and effective strengthening capacity may be uncertain.

the tilt floor below the Main Floor Area.



The steel members appeared to be in good condition. The main girders appeared to have been strengthen by an added steel section below the bottom flange.



Concrete elements appeared to be in good general condition.

12:

Exterior Sun Screen Precast Panel



Precast panels appeared to be in good physical condition from the observed areas at ground level.

APPENDIX B - Structural

ASCE 41-17 Tier 1 Seismic Evaluation

BUILDING DATA

Building Name: Santa Monica Civic Center Auditorium

Address: 1855 Main St, Santa Monica 90401

Site location coordinates: Latitude 34.0092266 Longitudinal -118.4899257



ASCE 41-17 Model Building Type:

a. Longitudinal Direction: C2: Concrete Shear Wall

b. Transverse Direction: C2: Concrete Shear Wall

Site-specific Ground Motion Study? No

Seismic Design Acceleration Parameters of Interest:

a. For BSE-1N 1.537g and 0.777gb. For BSE-2N 2.306g and 1.165g

Estimated Fundamental Period (seconds)

a. Longitudinal: 0.48sb. Transverse: 0.48s

Gross Square Footage: 52,000 ft²

Year Original Building was Constructed: Circa 1956 Original Building Design Code & Year: UBC-1955

Retrofit Building Design Code & Code (if applicable): N/A

SITE INFORMATION

Site Class: D (default) – Assumed

Geologic Hazards:

Fault Rupture: No Liquefaction: No Landslide: No

BUILDING COMPLEX PLAN

Shown below is a plan of the complex.



Attachments:

- A. ASCE 41-17 Tier 1 Checklists (CP Basic)
- B. ASCE 41-17 Tier 1 Checklist (CP Building Type C2 & C2A)

| | Buil | ding N | Nam | e: Santa Monica Civic Center Auditorium | Date: | | 05/22/23 | |
|-------------|----------------|--------|------|--|-------|-------|----------|------|
| В | uildir | ng Ad | dres | S: 1855 Main St, Santa Monica CA 90401 | Page: | 3 | of | 6 |
| Job Number: | | | ımbe | | Ву: | PK | Checked: | _AO_ |
| | | | | ASCE 41-17 - CP Basic | | | | |
| | LOW SEISMICITY | | | | | | | |
| BUI | LDI | NG S | SYS | TEMS - GENERAL | | | | |
| С | NC | N/A | U | Description | | Comme | nts | |
| | ⊠ | | | LOAD PATH: The structure shall contain a complete well-defined load path, including structural elements and connections that serves to transfer the inertial forces associated with the mass of all elements of the building to the foundation. (Commentary: §A.2.1.1. Tier 2: §5.4.1.1) | | | | |
| | ⊠ | | | ADJACENT BUILDINGS: The clear distance between the building being evaluated and any adjacent building is greater than 0.25% of the height of the shorter building in low seismicity, 0.5% in moderate seismicity, and 1.5% in high seismicity. (Commentary: Sec. A.2.1.2. Tier 2: Sec. 5.4.1.2) | | | | |
| | × | | | MEZZANINES: Interior mezzanine levels are braced independently from the main structure or are anchored to the seismic-force-resisting elements of the main structure. (Commentary: §A.2.1.3. Tier 2: §5.4.1.3) | | | | |
| BUI | LDI | NG S | SYS | TEMS - BUILDING CONFIGURATION | | | | |
| С | NC | N/A | U | Description | | Comme | nts | |
| ⊠ | | | _ | WEAK STORY: The sum of the shear strengths of the seismic- force-resisting system in any story in each direction is not less than 80% of the strength in the adjacent story above. (Commentary: §A2.2.2. Tier 2: §5.4.2.1) | | | | |
| | × | | | SOFT STORY: The stiffness of the seismic-force-resisting system in any story is not less than 70% of the seismic-force-resisting system stiffness in an adjacent story above or less than 80% of the average seismic-force-resisting system stiffness of the three stories above. (Commentary: §A.2.2.3. Tier 2: §5.4.2.2) | | | | |
| | ⊠ | | | VERTICAL IRREGULARITIES: All vertical elements in the seismic-force-resisting system are continuous to the foundation. (Commentary: §A.2.2.4. Tier 2: §5.4.2.3) | | | | |
| | ⊠ | | | GEOMETRY: There are no changes in the net horizontal dimension of the seismic-force-resisting system of more than 30% in a story relative to adjacent stories, excluding one-story penthouses and mezzanines. (Commentary: §A.2.2.5. Tier 2: §5.4.2.4) | | | | |
| | \boxtimes | | _ | MASS: There is no change in effective mass more than 50% from one story to the next. Light roofs, penthouses, and mezzanines need not be considered. (Commentary: §A.2.2.6. Tier 2: §5.4.2.5) | | | | |
| | × | | | TORSION: The estimated distance between the story center of mass and the story center of rigidity is less than 20% of the building width in either plan dimension. (Commentary: §A.2.2.7. Tier 2: §5.4.2.6) | | | | |

| Building Name: | Santa M | Ionica Civic Center A | Auditorium | Date: | 05/22/23 | | |
|-------------------|-------------------------------------|-----------------------|------------|-------|----------|----------|------|
| Building Address: | 1855 Main St, Santa Monica CA 90401 | | | Page: | 4 | of | 6 |
| Job Number: | 2300104 | _ Job Name: _ | SMMUSD | By: | _PK_ | Checked: | _AO_ |
| | - | | | | | | |
| | | | | | | | |

MODERATE SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR LOW SEISMICITY)

GEOLOGIC SITE HAZARD

| C NC N/A U | Description | Comments |
|------------|--|--------------------------|
| | LIQUIFACTION: Liquefaction-susceptible, saturated, loose granular soils that could jeopardize the building's seismic performance do not exist in the foundation soils at depths within 50 ft under the building. (Commentary: §A.6.1.1. Tier 2: §5.4.3.1) | Based on CGS Hazard Maps |
| | SLOPE FAILURE: The building is located away from potential earthquake-induced slope failures or rockfalls so that it is unaffected by such failures or is capable of accommodating any predicted movements without failure. (Commentary: §A.6.1.2. Tier 2: §5.4.3.1) | Based on CGS Hazard Maps |
| | SURFACE FAULT RUPTURE: Surface fault rupture and surface displacement at the building site are not anticipated. (Commentary: §A.6.1.3. Tier 2: §5.4.3.1) | Based on CGS Hazard Maps |


HIGH SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR MODERATE SEISMICITY)


FOUNDATION CONFIGURATION


| С | NC | N/A | U | Description | Comments |
|---|----|-----|---|---|----------|
| × | | | | OVERTURNING: The ratio of the least horizontal dimension of the seismic-force-resisting system at the foundation level to the building height (base/height) is greater than 0.6S _a . (Commentary: §A.6.2.1. Tier 2: §5.4.3.3) | |
| × | | | | TIES BETWEEN FOUNDATION ELEMENTS: The foundation has ties adequate to resist seismic forces where footings, piles, and piers are not restrained by beams, slabs, or soils classified as Site Class A, B, or C. (Commentary: §A.6.2.2. Tier 2: §5.4.3.4) | |


| Building Name: | | | | Santa Monica Civic Center Auditorium | _ Date: | | 05/22/23 | | |
|--------------------------------|---|------|-------|--|---------|-------|----------|------|--|
| Bui | ilding | g Ad | dress | S: 1855 Main St, Santa Monica CA 90401 | _ Page: | 5 | of | 6 | |
| | lob N | Num | ber: | 2300104 Job Name:SMMUSD | By: | _PK | Checked: | _AO_ | |
| | 2023-05-22 KPFF-S Draft Appendix B - Tier 1 Evaluation.docx | | | | | | | | |
| Low | Low And Moderate Seismicity | | | | | | | | |
| Seismic-Force-Resisting System | | | | | | | | | |
| С | NC | N/A | U | Description | | Comme | ents | | |
| \boxtimes | | | | COMPLETE FRAMES: Steel or concrete frames classified as secondary components form a complete vertical-load-carrying system. (Commentary: §A.3.1.6.1. Tier 2: §5.5.2.5.1) | | | | | |
| \boxtimes | | | | REDUNDANCY: The number of lines of shear walls in each principal direction is greater than or equal to 2. (Commentary: §A.3.2.1.1. Tier 2: §5.5.1.1) | | | | | |
| | × | | | SHEAR STRESS CHECK: The shear stress in the concrete shear walls, calculated using the Quick Check procedure of Section 4.4.3.3, is less than the greater of 100 lb/in. ² or $2\sqrt{r_{ci}}$. (Commentary: §A.3.2.2.1. Tier 2: §5.5.3.1.1) | | | | | |
| × | | | | REINFORCING STEEL: The ratio of reinforcing steel area to gross concrete area is not less than 0.0012 in the vertical direction and 0.0020 in the horizontal direction. (Commentary: §A.3.2.2.2. Tier 2: §5.5.3.1.3) | | | | | |
| Connections | | | | | | | | | |
| Con | nec | ctio | ns | | | | | | |
| | nec | | | Description | | Comme | ents | | |
| | | | | Description WALL ANCHORAGE AT FLEXIBLE DIAPHRAGMS: Exterior concrete or masonry walls that are dependent on flexible diaphragms for lateral support are anchored for out-of-plane forces at each diaphragm level with steel anchors, reinforcing dowels, or straps that are developed into the diaphragm. Connections have strength to resist the connection force calculated in the Quick Check procedure of Section 4.4.3.7. (Commentary: §A.5.1.1. Tier 2: §5.7.1.1) | | Comme | ents | | |
| С | NC | N/A | | WALL ANCHORAGE AT FLEXIBLE DIAPHRAGMS: Exterior concrete or masonry walls that are dependent on flexible diaphragms for lateral support are anchored for out-of-plane forces at each diaphragm level with steel anchors, reinforcing dowels, or straps that are developed into the diaphragm. Connections have strength to resist the connection force calculated in the Quick Check procedure of Section 4.4.3.7. | | Comme | ents | | |
| С | NC | N/A | | WALL ANCHORAGE AT FLEXIBLE DIAPHRAGMS: Exterior concrete or masonry walls that are dependent on flexible diaphragms for lateral support are anchored for out-of-plane forces at each diaphragm level with steel anchors, reinforcing dowels, or straps that are developed into the diaphragm. Connections have strength to resist the connection force calculated in the Quick Check procedure of Section 4.4.3.7. (Commentary: §A.5.1.1. Tier 2: §5.7.1.1) TRANSFER TO SHEAR WALLS: Diaphragms are connected for transfer of seismic forces to the shear walls. (Commentary: | | Comme | ents | | |
| c | NC 🗵 | N/A | | WALL ANCHORAGE AT FLEXIBLE DIAPHRAGMS: Exterior concrete or masonry walls that are dependent on flexible diaphragms for lateral support are anchored for out-of-plane forces at each diaphragm level with steel anchors, reinforcing dowels, or straps that are developed into the diaphragm. Connections have strength to resist the connection force calculated in the Quick Check procedure of Section 4.4.3.7. (Commentary: §A.5.1.1. Tier 2: §5.7.1.1) TRANSFER TO SHEAR WALLS: Diaphragms are connected for transfer of seismic forces to the shear walls. (Commentary: §A.5.2.1. Tier 2: §5.7.2) FOUNDATION DOWELS: Wall reinforcement is doweled into the foundation with vertical bars equal in size and spacing to the vertical wall reinforcing directly above the foundation. | | Comme | ents | | |
| c | NC 🗵 | N/A | | WALL ANCHORAGE AT FLEXIBLE DIAPHRAGMS: Exterior concrete or masonry walls that are dependent on flexible diaphragms for lateral support are anchored for out-of-plane forces at each diaphragm level with steel anchors, reinforcing dowels, or straps that are developed into the diaphragm. Connections have strength to resist the connection force calculated in the Quick Check procedure of Section 4.4.3.7. (Commentary: §A.5.1.1. Tier 2: §5.7.1.1) TRANSFER TO SHEAR WALLS: Diaphragms are connected for transfer of seismic forces to the shear walls. (Commentary: §A.5.2.1. Tier 2: §5.7.2) FOUNDATION DOWELS: Wall reinforcement is doweled into the foundation with vertical bars equal in size and spacing to the vertical wall reinforcing directly above the foundation. (Commentary: §A.5.3.5. Tier 2: §5.7.3.4) | | Comme | ents | | |


| Buildir | ng Nar | me: | Santa M | Santa Monica Civic Center Auditorium | | | | 05/22/23 | |
|----------|--|------|---|--|---------------------------------|--------|-------|----------|------|
| Building | g Addr | ress | : 1855 M | ain St, Santa Monica C | A 90401 | Page: | 6 | of | 6 |
| Job N | Numbe | er: | 2300104 | _ Job Name: | SMMUSD | By: | _PK_ | Checked: | _AO_ |
| | 202 | 3-0 | 5-22 KPFF-S | Draft Appen | dix B - Tier | 1 Eval | uatio | n.docx | |
| ⊠□ | — — COUPLING REAMS: The ends of both walls to which the counting | | | | | | | | |
| Diaphra | agms | s (S | tiff or Flexible) | | | | | | |
| C NC | N/A | U | | Description | | | Comme | nts | |
| | | | DIAPHRAGM CONTINUIT of split-level floors an (Commentary: §A.4.1.1. T | d do not have expa | | | | | |
| | | | OPENINGS AT SHEAR mediately adjacent to the wall length. (Commentary: | shear walls are less that | an 25% of the | | | | |
| Flexible | e Dia | phi | ragms | | | | | | |
| C NC | N/A | U | | Description | | | Comme | nts | |
| | | | CROSS TIES: There a diaphragm chords. (Comn | | | | | | |
| | | | STRAIGHT SHEATHING: aspect ratios less than 2- (Commentary: §A.4.2.1. T | to-1 in the direction bein | | | | | |
| | | | SPANS: All wood diaphr consist of wood structi (Commentary: §A.4.2.2. T | ural panels or diagon | | | | | |
| | | 3 | DIAGONALLY SHEATHE All diagonally sheathed diaphragms have horizon ratios less than or equal to §5.6.2) | or unblocked wood stratal spans less than 40 | ructural panel ft and aspect | | | | |
| | | | OTHER DIAPHRAGMS: system other than wood bracing. (Commentary: §A | , metal deck, concrete, | | | | | |
| Connec | ction | s | | | | | | | |
| C NC | N/A | U | | Description | | | Comme | nts | |
| | | | UPLIFT AT PILE CAPS: piles are anchored to the 2: §5.7.3.5) | | | | | | |

























LIMITED ASBESTOS AND LEAD-BASED PAINT SURVEY SANTA MONICA CIVIC CENTER

May 25, 2023

Prepared For:

Santa Monica-Malibu Unified School District 2828 West 4th Street Santa Monica, CA 90405



NV5 – Alta Environmental 3777 Long Beach Blvd, Annex Building Long Beach, CA 90807 Phone: 562.495.5777

SMSD-23-11460

EXECUTIVE SUMMARY

At the request of Santa Monica-Malibu Unified School District, Alta Environmental, LP an NV5 company (Alta/NV5) conducted a Limited Asbestos and Lead-Based Paint Survey Report at the Santa Monica Civic Center, located in Santa Monica, California. The survey was conducted in anticipation of a potential renovation project that will take place at the site. Our Certified Asbestos Consultant, Certified Site Surveillance Technician, and Certified Lead Sampling Technician conducted the following activities in areas affected by the scope of work to document the project:

- Review of existing records,
- Initial investigation to locate suspect ACM;
- Initial investigation to locate suspect LBP;
- Physical assessment of suspect materials;
- Collection of bulk samples from suspect materials; and
- Laboratory analysis of all collected samples.

TABLE OF CONTENTS

| 1.0 | Introduction | 1 |
|------------|---------------------------------|----------|
| 2.0 | Project Background | 1 |
| 3.0 | Scope Of Work | 1 |
| 4.0 | Methodology | |
| 4.1 4.2 | AsbestosLead | 2 |
| 5.0 | Results | 3 |
| 5.1 5.2 | AsbestosLead | |
| 6.0 | Conclusions And Recommendations | 10 |
| 6.1 6.2 | AsbestosLead | 10 11 |
| 7.0 | Assumptions And Limitations | 12 |
| 8.0 | Signatory | 12 |

Appendices

Appendix A: Material Inventory: Asbestos and Lead

Appendix B: Laboratory Analytical Report: Asbestos and Lead

Appendix C: Sample Location Maps: Asbestos and Lead

Appendix D: Employee Certifications

Appendix E: Historical Surveys and Data

1.0 INTRODUCTION

From May 2 to May 11, 2022, Alta Environmental, LP an NV5 company (Alta/NV5) conducted a hazardous materials investigation for the presence of asbestos-containing materials (ACM) and lead-based paint (LBP) at the Santa Monica Civic Center. The site is located at 1855 Main St, Santa Monica, CA 90401.

2.0 PROJECT BACKGROUND

The Santa Monica-Malibu Unified School District (District), retained Alta/NV5 for this investigation. Randy Flores, a Cal/OSHA Certified Site Surveillance Technicians (CSST) and California Department of Public Health (CDPH) Certified Lead Sampling Technician, and Erik Jimenez an AHERA certified Building Inspector and CDPH Lead Sampling Technician, both employed by Alta/NV5, conducted the sampling.

Alta/NV5 was provided the following by the Client for review prior to this survey:

Asbestos and Lead Materials Survey/Testing Report, dated May 10, 2012 by Bainbridge Environmental Consultants. Data from this report has been reviewed and, where applicable, incorporated into this current survey report.

SCOPE OF WORK 3.0

The survey included the performance of the following activities as part of the project. Destructive testing was not utilized as part of the survey.

- Review of existing records and reports,
- Initial investigation to locate suspect ACM;
- Initial investigation to locate suspect LBP;
- Physical assessment of suspect materials;
- Collection of bulk samples from suspect materials; and
- Laboratory analysis of all collected samples.

Due to the non-destructive nature of the survey, the following areas were unable to be accessed at the time of the survey:

- Underneath cabinetry in all permanent buildings. Older floor tiles and mastic may be present under cabinetry. These areas should be assessed after the buildings have been vacated and before the demolition process begins.
- Wall cavities. Pipe insulation was observed at the property. Due to the survey being non-destructive, wall cavities were not inspected. Prior to demolition, wall cavities containing plumbing should be inspected for the presence of pipe insulation after the building has been vacated.

4.0 METHODOLOGY

4.1 **ASBESTOS**

The sampling was conducted using guidelines set forth in Federal Register 40 CFR Part 763. Alta Environmental conducted an initial walkthrough of the site to develop a listing and sampling scheme of suspect materials. Samples were placed in sealable sample containers and assigned a unique sample identification number.

Bulk samples collected from the subject site were subsequently analyzed by polarized light microscopy (PLM) and by 1000 point-count analysis (if the initial analytical result was less than one percent asbestos) for asbestos content in accordance with the United States Environmental Protection Agency's (USEPA) Determination of Asbestos in Bulk Building Materials: EPA/600/R-93/116, July 1993, at AQ Environmental Labs, a laboratory accredited by the National Voluntary Laboratory Accreditation Program and located in Signal Hill, California.

Based on the requirements of the USEPA as set forth in 40 CFR 763, a homogeneous area is defined as "an area of surfacing material, thermal system insulation material or miscellaneous material that is uniform in color and texture." Furthermore, the regulation requires that a minimum number of samples be collected from each identified homogeneous area. If one sample in a homogeneous area is found to contain asbestos, the entire homogeneous area is considered asbestos-containing.

It is possible that one sample out of a set of samples collected from a homogeneous area can be positive for asbestos and the remaining samples in the homogeneous area are negative. However, the entire area must be considered asbestos-containing.

Caution is advised in interpreting results provided herein.

The limited survey was conducted to identify hazardous materials (asbestos and lead). The investigation did not include destructive testing (i.e., the opening of wall and ceiling cavities) and was limited to accessible areas. Prior to renovation or demolition, materials not identified in this report or materials subsequently discovered through destructive sampling should be tested for the presence of asbestos. An investigation below soil grade was outside the scope of this project, and additional material such as asbestos-cement pipes, electrical wiring insulation, or other materials may subsequently be discovered.

4.2 I FAD

Paint chips were collected to determine the weight percent concentration of lead in the painted surfaces. Paint chip samples were collected for construction safety as defined by Title 8 CCR Section 1532.1. Paint chip sample analysis was conducted by EPA Method SW846/7420 at AQ Environmental Labs, a laboratory accredited by the Environmental Laboratory Accreditation Program and located in Signal Hill, California.

5.0 RESULTS

5.1 **ASBESTOS**

If any materials were found to contain more than one percent asbestos by weight as determined by the PLM method of analysis, the USEPA mandates that the material(s) be treated as ACM, subject to regulation under 40 CFR 61.

The following materials were found to be asbestos-containing:

| Material | Sample No. | Material Location | Asbestos Content | Quantity |
|--|------------------------------------|---|---|----------|
| TSI saddles | RF-11 to RF-13 | Saddles under 4" pipe runs throughout building | 5% chrysotile 15% amosite | 500 SF |
| Red terrazzo | RF-107 to RF-109 | 1st and 2nd floor mezzanine | <1% chrysotile* | 60 SF |
| 12" Pinhole ceiling tile mastic | 15, 69, 75, 78** | 2 nd floor offices, audio room, mechanical rooms, projector room, boiler rooms, and dressing rooms | 2% anthophyllite | 8,000 SF |
| 12" Green floor tile with mastic | 33A, 34A, 35A** | Business office flooring throughout | 2% chrysotile | 700 SF |
| Black Battleship flooring | 79,80** | Mechanical and fan room flooring throughout | <1% chrysotile | 5,700 SF |
| Fire curtain | 52 - 54** | Stage fire curtain | 40% chrysotile | 2,500 SF |
| Thermal system insulation/TSI | 96, 97** | TSI Pipe-runs throughout | 8% chrysotile 12% amosite <1% crocidolite | 200 LF |
| 9" Black floor tile with black mastic | 102 - 104** 102A - 104A** | Sound room flooring only | 5% chrysotile - 6% chrysotile | 545 SF |
| Gray and black mastic | 111** | Stage roof at abandoned AHU Only | 8% chrysotile | 10 SF |

| Material | Sample No. | Material Location | Asbestos Content | Quantity |
|-------------------------------|------------|--|------------------|----------|
| Gray heat shield paper | 125** | 2nd floor wardrobe light fixtures and basement light fixtures only | 20% chrysotile | 2 SF |
| Fire Rated Doors (labeled) | N/A | Fire doors throughout | Assumed | 600 SF |
| Puck mirror mastic | N/A | Mirrors throughout | Assumed | 400 SF |
| Transite pipe | N/A | Transite flue pipes | Assumed | 40 LF |

^{*}currently being analyzed by 1000-point count method, results pending

The results for all other materials sampled in this current survey and previous surveys were reported as "none detected," based on the limitations of the analytical method. Please refer to the Material Inventory (Appendix A).

5.2 LEAD

Currently, the State of California, HUD and the USEPA define LBP as paint or other surface coating with lead content equal to or greater than 1.0 mg/cm2 of surface area by XRF or 5,000 parts per million (ppm) by paint chip analysis. However, a more stringent level is established by the Los Angeles County Department of Health Services, which defines "dangerous level of lead-bearing substances" as paint or other surface coating with lead content greater than 0.7 mg/cm² (Los Angeles County Code, Title 11, Chapter 11.28, Section 11.28.010 C).

The following tested surfaces were found to contain lead concentrations equal to or greater than 0.7 mg/cm².

Summary of LBP:

| Reading No. | Structure | Material Location | Paint Color & Condition | Substrate | Lead (mg/cm²) |
|-------------|-----------|-------------------------------|-------------------------|-----------------|------------------|
| 2183 | Urinal | Men's restroom northwest | White/intact | Porcelain | 5.3 |
| 2199 | Urinal | Northeast men's restroom | White/intact | Porcelain | 5.2 |
| 2215 | Wall | Kitchen | White/intact | 4" ceramic tile | 8.8 |
| 2237 | Wall | Main office men's restroom | Green/intact | 4" ceramic tile | 6.8 |

^{**}previously sampled

| Reading No. | Structure | Material Location | Paint Color & Condition | Substrate | Lead (mg/cm²) |
|-------------|----------------------------|---|-------------------------|----------------------------|------------------|
| 2240 | Urinal | Main office men's restroom | White/intact | Porcelain | 4.3 |
| 2249 | Wall | Women's restroom | Peach/intact | 4" ceramic tile | 4.8 |
| 2260 | Shower wall | Dressing room 1 | White/intact | 4" ceramic tile | 6.4 |
| 2279 | Wall | Dressing room | Tan/intact | 4" ceramic tile | 5.9 |
| 2280 | Wall | Men's dressing room | Green/intact | 4" ceramic tile | 6.4 |
| 2281 | Urinal | Men's restroom | White/intact | Porcelain | 6.4 |
| 2283 | Shower wall | Second floor east dressing room RM | Tan/intact | 4" ceramic tile | 5.9 |
| 2285 | Sink | Janitor's room | White/intact | Porcelain | 2.5 |
| 2287 | Wall | 2 nd floor south dressing room | Peach/intact | 4" ceramic tile | 5.0 |
| 2288 | Wall | 2 nd floor south dressing room | Tan/intact | 4" ceramic tile | 6.0 |
| 2301 | Attic | 3 rd floor attic | Orange/intact | Structure H Beams/South | 3.6 |
| 2303 | Structure H breams/east | Attic | Orange/intact | Metal | 7.5 |
| 2304 | Structure H beams/north | Attic | Orange/intact | Metal | 10.1 |
| 2309 | Wall | Basement men's restroom | Green/intact | 4" ceramic tile | 5.0 |
| 2312 | Sink | Basement janitor's room | White/intact | Porcelain | 2.6 |
| 2313 | Wall | Basement women's restroom | Peach/intact | 4" ceramic tile | 5.0 |

| Reading No. | Structure | Material Location | Paint Color & Condition | Substrate | Lead (mg/cm²) |
|-------------|-------------|-----------------------|-------------------------|-----------|------------------|
| 2316 | Double door | Orchestra pit door | Gray/intact | Metal | 10.1 |

The following are painted surfaces with results equal to or greater than 5,000 ppm of lead as tested by paint chip analysis. These surfaces are subject to regulation by Los Angeles County, the CDPH and the USEPA.

| Component | Sample No. | Substrate | Paint Color | Paint Color Material Location | |
|-------------|-------------------|-----------|-------------|--|---------|
| Beams | PC-18 (5/3/23) | Metal | Red | Basement 1st floor | 280,000 |
| Door | 3 (5/5/23) | Metal | Blue | Sound equipment room | 14,000 |
| Door casing | 4 (5/5/23) | Metal | Blue | Sound equipment room | 21,000 |
| HVAC | 7 (5/5/23) | Metal | Dark gray | Dark gray Sound equipment room | |
| Door | 10 (5/5/23) | Metal | Black | All entry doors | 76,000 |
| Door | 12 (5/4/23) | Wood | Light blue | Entry to hallway book storage, Light blue dressing room 3, stagehand dressing room | |
| Post | 4005 | Concrete | Yellow | Exterior only | 53,000 |
| Railing | 4009 | Metal | Blue/gray | Catwalk hallway | 88,000 |
| Column | 4011 | Metal | Red | Catwalk | 330,000 |

The following are results of painted surfaces with any detectable levels of lead in paint below 5,000 ppm that were determined by paint chip sampling. When disturbed for construction purposes these surfaces are subjected to Cal/OSHA exposure assessment requirements set forth in Title 8 CCR, Section 1532.1(d). This regulation requires initial employee exposure monitoring to evaluate work exposure during work that disturbs paint with any detectable level of lead. If airborne lead levels are above the established Cal/OSHA action limit or permissible exposure limit, additional monitoring and respiratory protection are required.

| Component | Sample No. | Substrate | Paint Color Material Location | | Results (ppm) |
|-------------|-------------------|-----------|-------------------------------|---|------------------|
| Fire riser | PC-6 (5/2/23) | Metal | Red | Exterior southeast corner | 410 |
| Railing | PC-15 (5/2/23) | Metal | Blue | Exterior southwest | 130 |
| Door | PC-1 (5/3/23) | Metal | Gray | Basement electrical room, water heater room | 470 |
| Wall | PC-5 (5/3/23) | Concrete | Yellow | Maintenance shop | 250 |
| Wall | PC-6 (5/3/23) | Plaster | Yellow | Maintenance shop | 250 |
| Wall | PC-7 (5/3/23) | Plaster | Tan | Basement hallway | 250 |
| Wall | PC-8 (5/3/23) | Concrete | Tan | Tan Basement hallway | |
| Hatch | PC-11 (5/3/23) | Metal | Tan | Basement | 63 |
| Wall | PC-12 (5/3/23) | Plaster | Green | Janitor room | 880 |
| Wall | PC-13 (5/3/23) | Concrete | Black | Basement 1st floor | 550 |
| Column | PC-14 (5/3/23) | Concrete | Black | Basement 1st floor | 740 |
| Beams | PC-17 (5/3/23) | Metal | Green | Basement 1st floor | 1,300 |
| Door | 1 (5/5/23) | Metal | Tan | Stairway and hallway | 4,000 |
| Door casing | 2 (5/5/23) | Metal | Tan | Stairway and hallway | 3,600 |
| Pole | 6 (5/5/23) | Metal | Dark gray | Sound equipment room | 6,100 |

| Component | Sample No. | Substrate | Paint Color | Material Location | Results (ppm) |
|-------------|----------------|-----------|-------------|--------------------------------------|------------------|
| HVAC duct | 8 (5/5/23) | Metal | Dark gray | Fan room 2 | 330 |
| Door casing | 11 (5/5/23) | Metal | Black | All entry doors | 350 |
| Railing | 12 (5/5/23) | Metal | Tan | 2nd floor stairs | 3,700 |
| Wall | 14 (5/5/23) | Concrete | White | Hallway 2nd floor | 79 |
| Wall | 15 (5/5/23) | Plaster | White | All rooms | 98 |
| Countertop | 16 (5/5/23) | Wood | Black | All dressing rooms | 350 |
| Wall | 17 (5/5/23) | Plaster | Blue | 2nd floor hallway janitor | 64 |
| Wall | 3 (5/5/23) | Plaster | White | Upper mezzanine hallway | 180 |
| Door | 4 (5/5/23) | Wood | White | Upper mezzanine hallway | 86 |
| Door casing | 5 (5/5/23) | Metal | White | Upper mezzanine hallway | 92 |
| Railing | 7 (5/5/23) | Metal | Gray | West and east stairwell | 1,900 |
| Door | 8 (5/5/23) | Wood | Blue | Seating area | 2,700 |
| Door casing | 10 (5/5/23) | Metal | Tan | Stairway projectors | 1,700 |
| Door | 11 (5/5/23) | Wood | Tan | Stairway projectors | 710 |
| Door | 12 (5/5/23) | Wood | Gray | Gray Janitors closet upper mezzanine | |
| Door casing | 13 (5/5/23) | Metal | Gray | Janitors closet upper mezzanine | 2,900 |

| Component | Sample No. | Substrate | ubstrate Paint Color Material | | Results (ppm) |
|---------------|----------------|-----------|-------------------------------|--|------------------|
| Wall | 14 (5/5/23) | Plaster | Gray | Janitors closet upper mezzanine | 1,700 |
| Door casing | 1 (5/4/23) | Metal | Dark gray | West side exit door of stage | 600 |
| Door casing | 2 (5/4/23) | Metal | Dark gray | West side exit door of stage | 2,000 |
| Wall | 4 (5/4/23) | Concrete | Dark gray | Stage, book of stage, seating area | 120 |
| Conduit | 5 (5/4/23) | Metal | Light blue | Throughout stage and back of stage | 160 |
| Conduit | 6 (5/4/23) | Metal | Dark gray | Throughout stage and back of stage | 61 |
| Door | 14 (5/4/23) | Metal | Light blue | Stage | 260 |
| Door casing | 15 (5/4/23) | Metal | Light blue | Hallway, dressing room 4, stagehand, electrical room | 160 |
| Countertop | 19 (5/4/23) | Wood | Light blue | Dressing room 5, 4 | 310 |
| Stall divider | 24 (5/4/23) | Metal | White | Back stage restroom | 84 |
| Door casing | 26 (5/4/23) | Metal | Orange | Dressing room 3ABC stagehand | 64 |
| Pipe | 28 (5/4/23) | Metal | Orange | Dressing Room 3A | 110 |
| Countertop | 30 (5/4/23) | Wood | Gray | Stagehand room | 440 |
| Door | 38 (5/4/23) | Wood | Gray | All doors to room Gray underneath seating section | |
| Wall | 40 (5/4/23) | Plaster | Light blue | Section 3 seating area, office 2 | 61 |

| Component | Sample No. | Substrate | Paint Color | Material Location | Results (ppm) |
|---------------|----------------|-----------|--|---|------------------|
| Wall | 41 (5/4/23) | Plaster | Gray | East wing meeting area section seating areas 2, 3, 4, 5 | 1,800 |
| Door case | 55 (5/4/23) | Metal | White | Main floor interior janitor's closet | 2,000 |
| Door | 56 (5/4/23) | Wood | White | Main floor interior janitor's closet | 150 |
| Wall | 57 (5/4/23) | Concrete | White Main floor interior janitor's closet | | 2,100 |
| Railing | 4001 | Metal | Tan | All stairways | 810 |
| Stairs | 4002 | Metal | Tan | All stairs in hallways | 1,900 |
| Wall cabinet | 4003 | Wood | Blue/gray | Audio room and project room | 130 |
| Door | 4004 | Wood | Gray | Fan room only | 4,900 |
| Door | 4006 | Wood | Green | Air handler room #3 | 1,300 |
| Floor coating | 4010 | Metal | Red/Brown | Catwalk | 61 |

6.0 CONCLUSIONS AND RECOMMENDATIONS

6.1 ASBESTOS

Asbestos-containing materials (ACM) were discovered during course of this inspection. Refer to Section 5 in this report for a summary of ACMs. If, during project, materials are found or added to the scope of work that are not listed in this report as being sampled, they must be treated as asbestos-containing until subsequent sampling and laboratory analysis prove otherwise.

Materials assumed to contain asbestos in this report should be properly sampled and analyzed by or under the direction of a Certified Asbestos Consultant to determine asbestos content prior to construction, demolition or renovation. These materials were inaccessible for sampling during this inspection or would be substantially damage by such sampling.

Any damaged asbestos materials should be removed, repaired, encapsulated or enclosed. The USEPA requires that all asbestos materials be removed prior to any renovation or demolition activities that may impact the material. The USEPA recommends that a proactive, management- in-place program be developed and

implemented whenever asbestos is discovered in a building. Asbestos materials that are not damaged may be managed in place with a good operations and maintenance (0&M) program.

Certain notification requirements apply to owners of buildings constructed prior to 1979 where asbestos is known to be present. California Health and Safety Code 25915-25915.7 requires that all employees working within a building known to contain asbestos be informed, in writing, initially and annually thereafter of its presence, location, procedures and handling restrictions, results for any sampling conducted in the building and potential health risks of asbestos. In addition, notification shall be provided to contractors, maintenance workers or others.

One hundred square feet or more of materials containing greater than 1/10th of one percent asbestos must be properly removed by a licensed asbestos abatement contractor using isolation control methods and disposed of appropriately. Workers handling materials containing asbestos must be properly trained and must wear the appropriate personal protective equipment (PPE).

Furthermore, when asbestos is present in any amount, be advised that certain provisions of Cal-OSHA regulation Title 8 Section 1529 still apply. These include, but are not limited to, exposure assessments, air monitoring, hazard communication, prohibitions and work practices, such as wet methods and HEPA vacuuming.

6.2 LEAD

Lead-based paint was reported during this inspection. Refer to Section 5 in this report for a summary of LBP.

An O&M program is recommended to properly manage-in-place identified or assumed LBP until the buildings are demolished. An O&M program is a set of measures designed to reduce lead exposure to humans and the environment. Such measures may include specialized cleaning, repairs, maintenance, painting, temporary containment, education programs, and on-going visual monitoring by owners and/or reevaluations by risk assessors. An initial evaluation of potential LBP and hazards by a certified inspector/assessor is recommended for successful implementation of an O&M program.

Workers handling Lead-Based Paint or Lead-Containing Paint must be have appropriate Lead Training and must wear the appropriate personal protective equipment.

Waste generated during removal or demolition of LBP components must be properly segregated into separate waste streams. Each waste stream should be randomly sampled and each sample analyzed for lead by the California Waste Extraction Test for comparison to the Total Threshold Limit Concentration (TTLC), and Soluble Threshold Limit Concentration (STLC) and by Toxicity Characteristic Leaching Procedure (TCLP) as required, to determine the final disposition of the waste.

Disturbances of paints and/or component with any detectable amount of lead are subject to regulation under *Title 8 CCR*, *Section 1532.1 (d)*. These requirements include awareness training, and monitoring to determine worker exposure. This regulation requires initial and on-going (if necessary) employee exposure monitoring to evaluate lead work exposure that disturbs paint with any detectable level of lead. Alta Environmental suggests that engineering controls, respiratory protection and personal protective equipment be employed during any project that disturbs painted surfaces.

All other painted surfaces not listed above are considered lead-containing until confirmatory paint chip sampling proves otherwise.

7.0 ASSUMPTIONS AND LIMITATIONS

This report was prepared exclusively for use by Santa Monica-Malibu School District and may not be relied upon by any other person or entity without Alta/NV5 's express written permission. The information, conclusions and recommendations described in this report apply to conditions existing at certain locations when services were performed and are intended only for the specific purposes, locations, time frames and project parameters indicated. Alta/NV5 cannot be responsible for the impact of any changes in environmental standards, practices or regulations after performance of services.

In performing our professional services, we have applied present engineering and scientific judgment and used a level of effort consistent with the current standard of practice for similar types of studies.

As applicable, Alta/NV5 has relied in good faith upon representations and information furnished by individuals with respect to operations and existing property conditions, to the extent that they have not been contradicted by data obtained from other sources. Accordingly, Alta/NV5 accepts no responsibility for any deficiencies, omissions, misrepresentations, or fraudulent acts of persons interviewed.

Alta/NV5 will not accept any liability for loss, injury claim, or damage arising directly or indirectly from any use or reliance on this report. Alta/NV5 makes no warranty, expressed or implied

This report is issued with the understanding that the client, the property owner, or its representative is responsible for ensuring that the information, conclusions, and recommendations contained herein are brought to the attention of the appropriate regulatory agencies, as required.

If you have any questions, please do not hesitate to contact the undersigned at (562) 495-5777. We appreciate the opportunity to be of service to Santa Monica-Malibu School District.

8.0 SIGNATORY

Respectfully submitted by:

James C Byers Je

James C. Byers

Senior Consultant/Project Manager Certified Asbestos Consultant

Cal/OSHA Cert. #06-4122

Lead Inspector/Assessor

CDPH #LRC-00001746

Reviewed by:

Christine Jordan

Certified Asbestos Consultant

Cal/OSHA Cert. #92-0215

CDPH-Lead in Construction Inspector/Assessor

CDPH-#LRC-00002523

Appendix A

Material Inventory: Asbestos and Lead

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|----------------------|------------|------------------|------------------------------------|----------------------------------|--------------|---------|--------|
| Skim coat | 2-1 | None detected | Southwest storage southwest corner | | | | |
| Skim coat | 2-2 | None detected | Southwest storage southeast corner | Southwest corner storage | 800 SF | No | No |
| Skim coat | 2-3 | None detected | Southwest storage east center | | | | |
| Duct sealant | 2-4 | None detected | West center north door entry | | | | |
| Duct sealant | 2-5 | None detected | West center north door entry | West center of building exterior | 10 LF | No | No |
| Duct sealant | 2-6 | None detected | West center north door entry | | | | |
| Window sealant | 2-7 | None detected | West center windows | | | | |
| Window sealant | 2-8 | None detected | West center windows | Exterior west center | 150 LF | No | No |
| Window sealant | 2-9 | None detected | West center windows | | | | |
| Built up roof (core) | 0502-1 | None detected | High roof west center | | | | |
| Built up roof (core) | 0502-2 | None detected | Large portion center | Upper roof (large portion) | 33,000 SF | No | No |
| Built up roof (core) | 0502-3 | None detected | Large portion north center | | | | |
| Parapet capsheet | 0502-4 | None detected | West center | | | | |
| Parapet capsheet | 0502-5 | None detected | South center | High roof | 300 LF | No | No |
| Parapet capsheet | 0502-6 | None detected | East center | | | | |
| Kicksheet with cap | 0502-7 | None detected | West center | | | | |
| Kicksheet with cap | 0502-8 | None detected | Center | Storage roof | 1,500 SF | No | No |
| Kicksheet with cap | 0502-9 | None detected | East center | | | | |

Page 1 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|--------------------------------|------------|------------------|--|--|--------------|---------|--------|
| Built up roof with gravel core | 0502-10 | None detected | West roof, northwest | | | | |
| Built up roof with gravel core | 0502-11 | None detected | Southeast roof, center | 1st floor roofs west east, and southeast roof | 8,000 SF | No | No |
| Built up roof with gravel core | 0502-12 | None detected | East roof southeast | | | | |
| Vibration reducer | 0502-13 | None detected | West center (southeast roof) | ist noor roots, west, east, | | | |
| Vibration reducer | 0502-14 | None detected | West center (southeast roof) | and southeast roofs, southeast roof, east roof | 200 SF | No | No |
| Vibration reducer | 0502-15 | None detected | Southeast corner (east roof) | (HVAC) | | | |
| White sealant | 0502-16 | None detected | West center | | | | |
| White sealant | 0502-17 | None detected | Southeast | All flashing on roofs | 1,200 LF | No | No |
| White sealant | 0502-18 | None detected | East center | | | | |
| Duct sealant | 0502-19 | None detected | Southeast roof, east center | | | | |
| Duct sealant | 0502-20 | None detected | Southeast roof south east | HVAC duct seams on roof | 300 SF | No | No |
| Duct sealant | 0502-21 | None detected | East roof southeast | | | | |
| Walk pad roof | 0502-22 | None detected | West | | | | |
| Walk pad roof | 0502-23 | None detected | Center | South east roof | 300 SF | No | No |
| Walk pad roof | 0502-24 | None detected | East | | | | |
| 2'x2' fissured ceiling tile | 4 | None detected | Southwest hallway between meeting area and dressing room | All east wing building except restroom hallway | 2,000 SF | Yes | No |
| 2'x2' fissured ceiling tile | 5 | None detected | Meeting area north center | and kitchen | | | |
| 2'x2' fissured ceiling tile | 6 | None detected | Meeting area southeast | 1 | | | |

Page 2 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|-----------------------------|------------|------------------|--|---|--------------|---------|--------|
| 1'x4' ceiling tile | 7 | None detected | 2nd floor mezzanine north center door BB | 1st floor lobby north | | | |
| 1'x4' ceiling tile | 8 | None detected | 2nd floor mezzanine north center door CC | section 2nd floor lobby mezzanine ceiling | 2,000 SF | Yes | No |
| 1'x4' ceiling tile | 9 | None detected | 40' north of door east | | | | |
| Red caulk fire guard | RF-8 | None detected | Storage southeast | Basement storage and | | | |
| Red caulk fire guard | RF-9 | None detected | Storage northwest | electrical | 20 SF | No | No |
| Red caulk fire guard | RF-10 | None detected | Electrical southwest | electrical | | | |
| TSI saddles | RF-11 | 5% chrysotile | Catwalk above ceiling - | | | | |
| 1 SI Saudies | KF-II | 15% amosite | north | Saddles under 4" pipe | | | |
| TSI saddles | RF-12 | Not analyzed - | Catwalk above ceiling - | runs throughout | 500 SF | Yes | No |
| i di saudies | KF-1Z | positive stop | center | | 300 SF | 163 | NO |
| TSI saddles | RF-13 | Not analyzed - | Catwalk above ceiling - | building | | | |
| i Si Saddies | KF-13 | positive stop | south | | | | |
| Drywall with joint | RF-14 | None detected | Kitchen east center | | | | |
| Drywall with joint compound | RF-15 | None detected | Chilled water supply room northwest | | | | |
| Drywall with joint compound | RF-16 | None detected | Snack bar center | Kitchen wall east, snack bar walls and west wing dividing walls and | 4,000 SF | No | No |
| Drywall with joint compound | RF-17 | None detected | West wing south center | restroom ceiling | | | |
| Drywall with joint compound | RF-18 | None detected | West wing northeast | | | | |
| FRP with glue | RF-19 | None detected | South | East hallway to east wing | | | |
| FRP with glue | RF-20 | None detected | Center | 1st floor | 400 SF | No | No |
| FRP with glue | RF-21 | None detected | North | 150 11001 | | | |
| Tectum | RF-22 | None detected | North | | | | |
| Tectum | RF-23 | None detected | Center | 3rd floor ceiling | 10,000 SF | No | No |
| Tectum | RF-24 | None detected | South |] | | | |

Page 3 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|-------------------------------------|------------|------------------|-----------------|---------------------------------------|--------------|----------|--------|
| White mastic | RF-25 | None detected | North | Seams/joint of tectum | | | |
| White mastic | RF-26 | None detected | Center | ceiling | 1,800 LF | No | No |
| White mastic | RF-27 | None detected | South | Ceiling | | | |
| White panel board ceiling | RF-28 | None detected | West center | | | | |
| White panel board ceiling | RF-29 | None detected | Northeast | 3rd floor ceiling west and east pitch | 5,000 SF | No | No |
| White panel board ceiling | RF-30 | None detected | Southeast | | | | |
| Blue stair tread | RF-37 | None detected | West | | | | |
| Blue stair tread | RF-38 | None detected | Center | Aisle at seating area | 800 LF | No No | No |
| Blue stair tread | RF-39 | None detected | East | | | | |
| Black stair tread | RF-40 | None detected | West | | 800 LF | | |
| Black stair tread | RF-41 | None detected | Center | Aisle at seating area | | | No |
| Black stair tread | RF-42 | None detected | East | | | | |
| Gray epoxy | RF-43 | None detected | West | | | | |
| Gray epoxy | RF-44 | None detected | Center | Seating area | 8,000 SF | No | No |
| Gray epoxy | RF-45 | None detected | East | | | | |
| 16"x16" green vinyl tiles with glue | RF-46 | None detected | West | | | | |
| 16"x16" green vinyl tiles with glue | RF-47 | None detected | Center | Aisle steps at seating area | 2,600 SF | No | No |
| 16"x16" green vinyl tiles with glue | RF-48 | None detected | East | | | | |

Page 4 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|--|------------|------------------|------------------------------------|---|--------------|---------|--------|
| 6" brown cove base with tan mastic | RF-49 | None detected | West wing restroom 1 northwest | 1st floor west wing | | | |
| 6" brown cove base with tan mastic | RF-50 | None detected | West wing restroom 2 southeast | restroom (entry) 1st floor east of stage dress rooms | 100 LF | No | No |
| 6" brown cove base with tan mastic | RF-51 | None detected | Dress room east of stage southwest | least of stage dress rooms | | | |
| 6" dark blue cove base with tan mastic | RF-52 | None detected | South stage dress room southeast | | | | |
| 6" dark blue cove base with tan mastic | RF-53 | None detected | South stage dress room northeast | 1st floor, 2 dress rooms southeast of stage | 150 LF | No | No |
| 6" dark blue cove base with tan mastic | RF-54 | None detected | Southeast dress room northwest | | | | |
| 6" black cove base with brown mastic | RF-55 | None detected | 1st west storage southwest | 1st and 2nd floors, 1st | | | |
| 6" black cove base with brown mastic | RF-56 | None detected | 1st floor east storage | floor east storage, 1st floor west storage and | 450 LF | No | No |
| 6" black cove base with brown mastic | RF-57 | None detected | 2nd floor hallway southwest | 2nd floor hallway and dressing rooms | | | |
| 6" blue cove base with tan mastic | RF-58 | None detected | Southeast | | | | |
| 6" blue cove base with tan mastic | RF-59 | None detected | Center | 1st floor southeast hallway | 200 LF | No | No |
| 6" blue cove base with tan mastic | RF-60 | None detected | Northeast | | | | |

Page 5 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|---|------------|------------------|-------------------------------------|---|--------------|---------|--------|
| 6" light gray cove base with tan mastic | RF-61 | None detected | 2nd floor west | 2nd floor mezzanine and | | | |
| 6" light gray cove base with tan mastic | RF-62 | None detected | 2nd floor east | 1st floor dressing room 1 with restroom | 500 LF | No | No |
| 6" light gray cove base with tan mastic | RF-63 | None detected | 1st floor dressing room 1 northwest | - With restroom | | | |
| 4" black covebase with brown mastic | RF-64 | None detected | Northeast | | | | |
| 4" black covebase with brown mastic | RF-65 | None detected | Southeast | 2nd floor audio room | 280 LF | No | No |
| 4" black covebase with brown mastic | RF-66 | None detected | Southwest | | | | |
| Acoustical floor with blue coat | RF-67 | None detected | Northwest | | | | |
| Acoustical floor with blue coat | RF-68 | None detected | North center | | | No | |
| Acoustical floor with blue coat | RF-69 | None detected | Northeast | Above box office/snack bar | 2,000 SF | | No |
| Acoustical floor with blue coat | RF-70 | None detected | Southwest | | | | |
| Acoustical floor with blue coat | RF-71 | None detected | Southeast | | | | |
| Black coating | RF-80 | None detected | West | On boiler 1 and 2 in boiler | | | |
| Black coating | RF-81 | None detected | Center | room on 2nd floor | 300 SF | Yes | Yes |
| Black coating | RF-82 | None detected | North | southwest | | | |

Page 6 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|-----------------------------------|------------|------------------|------------------------|--|--------------|----------|--------|
| Fiberboard insulation with mastic | RF-89 | None detected | North | | | | |
| Fiberboard insulation with mastic | RF-90 | None detected | Center | 3rd floor double door to mechanical room | 20 SF | No | Yes |
| Fiberboard insulation with mastic | RF-91 | None detected | South | | | | |
| Black terrazzo with small specks | RF-98 | None detected | Northwest | | | | |
| Black terrazzo with small specks | RF-99 | None detected | Southwest | 1st and 2nd floor mezzanine | 1,500 SF | No No | No |
| Black terrazzo with small specks | RF-100 | None detected | 1st floor northeast | | | | |
| Beige terrazzo with large specks | RF-101 | None detected | Northwest | | | | |
| Beige terrazzo with large specks | RF-102 | None detected | Southwest | 2nd floor mezzanine west and east ends | 1,000 SF | | No |
| Beige terrazzo with large specks | RF-103 | None detected | Northeast | | | | |
| Beige terrazzo with less specks | RF-104 | None detected | Northwest | | | | |
| Beige terrazzo with less specks | RF-105 | None detected | 2nd floor north center | 1st and 2nd floor mezzanine | 5,000 SF | No | No |
| Beige terrazzo with less specks | RF-106 | None detected | Northeast | | | | |
| Red terrazzo | RF-107 | <1% chrysotile* | 1st floor west | 1st and 2nd floor | | | |
| Red terrazzo | RF-108 | <1% chrysotile* | 2nd floor west | mezzanine | 60 SF | No | No |
| Red terrazzo | RF-109 | <1% chrysotile* | 2nd floor east | mczzamie | | | |

Page 7 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|----------------------|------------|------------------|------------------------------|--|--------------|---------|--------|
| Green terrazzo | RF-110 | None detected | East | | | | |
| Green terrazzo | RF-111 | None detected | East | 2nd floor mezzanine | 60 SF | No | No |
| Green terrazzo | RF-112 | None detected | West | | | | |
| Pink terrazzo | RF-114 | None detected | 2nd floor center | 1st and 2nd floor | | | |
| Pink terrazzo | RF-115 | None detected | 1st floor center | mezzanine | 60 SF | No | No |
| Pink terrazzo | RF-116 | None detected | 1st floor center | mezzanine | | | |
| Yellow terrazzo | RF-117 | None detected | 1st floor east storage | 1st and 2nd floor | | | |
| Yellow terrazzo | RF-118 | None detected | 1st floor east storage | mezzanine | 300 SF | No | No |
| Yellow terrazzo | RF-119 | None detected | 2nd floor west | mezzanine | | | |
| Light beige terrazzo | RF-120 | None detected | Basement restroom center | mezzanine stairs, | | | |
| Light beige terrazzo | RF-121 | None detected | Mezzanine stairs east | restroom at basement, | 3,000 SF | No | No |
| Light beige terrazzo | RF-122 | None detected | 1st floor west wing restroom | east wing restroom 1st floor, west wing restroom | 3,000 3F | INO | INO |

^{*}analyzed by 1000 point count

Page 8 of 8

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|----------------------------------|------------|---|--|--|--------------|---------|--------|
| 12" Pinhole ceiling tile mastic | 15 | 2% anthophyllite | Lobby ceiling | Out floor off and autic | | | |
| 12" Pinhole ceiling tile mastic | 69 | 2% anthophyllite | Fan room #2 wall | 2nd floor offices, audio room, mechanical rooms, | 40,000 05 | NI- | Na |
| 12" Pinhole ceiling tile mastic | 75 | 2% anthophyllite | Ballet dressing room ceiling | projector room, boiler rooms, and dressing | 12,000 SF | No | No |
| 12" Pinhole ceiling tile mastic | 78 | 2% anthophyllite | Fan Room #5 wall | rooms | | | |
| 12" Green floor tile with mastic | 33A | 2% chrysotile | Floor-South | | | | |
| 12" Green floor tile with mastic | 34A | <1% chrysotile | Floor-North | Business office flooring throughout | 700 SF | No | No |
| 12" Green floor tile with mastic | 35A | <1% chrysotile | Floor-East | | | | |
| Battleship flooring black | 79 | <1% chrysotile | Fan Room #2 floor | Mechanical and fan room | 5,700 SF | No | No |
| Battleship flooring black | 80 | <1% chrysotile | Fan Room #3 floor | flooring throughout | 5,700 31 | INO | INO |
| Fire curtain | 52 | 40% chrysotile | Stage at fire curtain - east | | | | |
| Fire curtain | 53 | 40% chrysotile | Stage at fire curtain - west | Stage fire curtain | 2,500 SF | No | No |
| Fire curtain | 54 | 40% chrysotile | Stage at fire curtain - center | Stage ine curtain | 2,500 01 | 140 | NO |
| Thermal system insulation/TSI | 96 | 8% chrysotile 12% amosite <1% crocidolite | Catwalk/upper part of auditorium at overhead pipe runs | TOI Ding was the second | 200 15 | Vac | Na |
| Thermal system insulation/TSI | 97 | 8% chrysotile 12% amosite <1% crocidolite | Catwalk/upper part of auditorium at overhead pipe runs | TSI Pipe-runs throughout | 200 LF | Yes | No |

Page 1 of 2

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Material | Sample No. | Asbestos Content | Sample Location | Material Location | Approx. Qty. | Friable | Damage |
|---------------------------------|------------|------------------|---------------------------------|--|--------------|---------|--------|
| 9" floor tile with black mastic | 102 | 5% chrysotile | Sound equipment room floor | | | | |
| 9" floor tile with black mastic | 102A | 5% chrysotile | Sound equipment room floor | | | | |
| 9" floor tile with black mastic | 103 | 5% chrysotile | Sound equipment room floor | | 545 SF | No | No |
| 9" floor tile with black mastic | 103A | 6% chrysotile | Sound equipment room floor | Sound room flooring only | 545 SF | INO | INO |
| 9" floor tile with black mastic | 104 | 5% chrysotile | Sound equipment room floor | | | | |
| 9" floor tile with black mastic | 104A | 6% chrysotile | Sound equipment room floor | | | | |
| Gray and black mastic | 111 | 8% chrysotile | Abandoned AHU surface | Stage roof at abandoned AHU Only | 10 SF | No | No |
| Gray heat shield paper | 125 | 20% chrysotile | Wardrobe room at light fixtures | 2nd floor wardrobe light fixtures and basement light fixtures only | 2 SF | No | No |
| Fire Rated Doors (labeled) | N/A | Assumed | N/A | Fire doors throughout | 600 SF | No | No |
| Puck mirror mastic | N/A | Assumed | N/A | Mirrors throughout | 400 SF | No | No |
| Transite pipe | N/A | Assumed | N/A | Transite flue pipes | 40 LF | No | No |

Page 2 of 2

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|-------------|-------------------|-----------|-------------|------------------------------|---------------------------|---------------|--------|---------------------|
| Railing | PC-1 (5/2/23) | Metal | White | Southeast corner of building | Exterior southeast corner | <49 | No | N/A |
| Door casing | PC-2 (5/2/23) | Metal | White | Southeast corner of building | Exterior southeast corner | <50 | No | N/A |
| Door | PC-3 (5/2/23) | Metal | White | Southeast corner of building | Exterior southeast corner | <68 | No | N/A |
| Wall | PC-4 (5/2/23) | Concrete | White | Southeast corner of building | Exterior southeast corner | <47 | No | N/A |
| Conduit | PC-5 (5/2/23) | Metal | White | 30' west of southeast corner | Exterior southeast corner | <49 | No | N/A |
| Fire riser | PC-6 (5/2/23) | Metal | Red | 30' west of southeast corner | Exterior southeast corner | 410 | No | N/A |
| Wall | PC-7 (5/2/23) | Concrete | Blue | 50' west of southeast corner | Exterior southeast corner | <48 | No | N/A |
| Door casing | PC-8 (5/2/23) | Metal | Blue | 50' west of southeast corner | Exterior southeast corner | <58 | No | N/A |
| Door | PC-9 (5/2/23) | Metal | Blue | 50' west of southeast corner | Exterior southeast corner | <110 | No | N/A |
| Wall | PC-10 (5/2/23) | Plaster | White | Southwest storage | Southwest storage | <49 | No | N/A |
| Wall | PC-11 (5/2/23) | Plaster | Blue | Southwest storage | Southwest storage | <47 | No | N/A |
| Wall | PC-12 (5/2/23) | Wood | Blue | South center | Southwest storage | <47 | No | N/A |
| Wall | PC-13 (5/2/23) | Wood | White | South center storage | South corner storage | <48 | No | N/A |

Page 1 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|-------------|-------------------|-----------|-------------|-----------------------------------|---|---------------|--------|---------------------|
| Door casing | PC-14 (5/2/23) | Metal | Blue | South center gate | Exterior south center | <48 | No | N/A |
| Railing | PC-15 (5/2/23) | Metal | Blue | 30' north of southwest corner | Exterior southwest | 130 | No | N/A |
| Column | PC-16 (5/2/23) | Concrete | White | Exterior northwest column | Exterior north of building | <49 | No | N/A |
| Conduit | PC-17 (5/2/23) | Metal | Blue | East center | Exterior east center of building | <240 | No | N/A |
| Door | PC-1 (5/3/23) | Metal | Gray | Basement electrical room at entry | Basement electrical room, water heater room | 470 | No | N/A |
| Door casing | PC-2 (5/3/23) | Metal | Gray | Basement electrical room at entry | Basement electrical room, water heater room | <150 | No | N/A |
| Wall | PC-5 (5/3/23) | Concrete | Yellow | Maintenance shop northwest | Maintenance shop | 250 | No | N/A |
| Wall | PC-6 (5/3/23) | Plaster | Yellow | Maintenance shop southeast | Maintenance shop | 250 | No | N/A |
| Wall | PC-7 (5/3/23) | Plaster | Tan | Basement hallway south center | Basement hallway | 250 | No | N/A |
| Wall | PC-8 (5/3/23) | Concrete | Tan | Basement hallway north center | Basement hallway | 80 | No | N/A |
| Hatch | PC-11 (5/3/23) | Metal | Tan | Basement hallway south center | Basement | 63 | No | N/A |
| Wall | PC-12 (5/3/23) | Plaster | Green | Basement 1st room southwest | Janitor room | 880 | No | N/A |
| Wall | PC-13 (5/3/23) | Concrete | Black | Basement 1st room southwest | Basement 1st floor | 550 | No | N/A |

Page 2 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. |
|-------------|-------------------|-----------|-------------|---|----------------------|---------------|--------|-----------------|
| Column | PC-14 (5/3/23) | Concrete | Black | Basement 1st room southwest | Basement 1st floor | 740 | No | Damage Qty. N/A |
| Conduit | PC-15 (5/3/23) | Metal | Tan | East stairwell basement | Basement 1st floor | <110 | No | N/A |
| Wall | PC-16 (5/3/23) | Drywall | Tan | East basement hallway | Basement 1st floor | <49 | No | N/A |
| Beams | PC-17 (5/3/23) | Metal | Green | Hydraulic floor basement | Basement 1st floor | 1,300 | No | N/A |
| Beams | PC-18 (5/3/23) | Metal | Red | Hydraulic floor basement | Basement 1st floor | 280,000 | No | N/A |
| Door | 1 (5/5/23) | Metal | Tan | Stairway into sound equipment room at entry | Stairway and hallway | 4,000 | No | N/A |
| Door casing | 2 (5/5/23) | Metal | Tan | Stairway into sound equipment room at entry | Stairway and hallway | 3,600 | No | N/A |
| Door | 3 (5/5/23) | Metal | Blue | Interior sound equipment room at | Sound equipment room | 14,000 | No | N/A |
| Door casing | 4 (5/5/23) | Metal | Blue | Interior sound equipment room at | Sound equipment room | 21,000 | No | N/A |

Page 3 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|-------------|----------------|-----------|-------------|---|----------------------|---------------|--------|---------------------|
| Wall | 5 (5/5/23) | Drywall | Tan | Interior sound equipment room south center | Sound equipment room | <47 | No | N/A |
| Pole | 6 (5/5/23) | Metal | Dark gray | Interior sound equipment room south center | Sound equipment room | 6,100 | No | N/A |
| HVAC | 7 (5/5/23) | Metal | Dark gray | Interior sound equipment room | Sound equipment room | 5,400 | No | N/A |
| HVAC duct | 8 (5/5/23) | Metal | Dark gray | Fan room 2 west center | Fan room 2 | 330 | No | N/A |
| Wall | 9 (5/5/23) | Plaster | Off-white | Fan room 2 north center | Fan room 2 | <49 | No | N/A |
| Door | 10 (5/5/23) | Metal | Black | 2nd floor hallway exterior of fan room at | All entry doors | 76,000 | No | N/A |
| Door casing | 11 (5/5/23) | Metal | Black | 2nd floor hallway exterior of fan room at entry | All entry doors | 350 | No | N/A |
| Railing | 12 (5/5/23) | Metal | Tan | 2nd floor stairs | 2nd floor stairs | 3,700 | No | N/A |
| Wall | 13 (5/5/23) | Plaster | Tan | Stair hallway to 2nd floor north center | Hallway stairs | <49 | No | N/A |
| Wall | 14 (5/5/23) | Concrete | White | Hallway east center | Hallway 2nd floor | 79 | No | N/A |

Page 4 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|-------------|----------------|-----------|-------------|-------------------------------|----------------------------|---------------|--------|---------------------|
| Wall | 15 (5/5/23) | Plaster | White | Hallway 2nd floor west center | All rooms | 98 | No | N/A |
| Counter top | 16 (5/5/23) | Wood | Black | Dressing room 24 northwest | All dressing rooms | 350 | No | N/A |
| Wall | 17 (5/5/23) | Plaster | Blue | Janitor's closet east center | 2nd floor hallway janitor | 64 | No | N/A |
| Conduit | 1 (5/5/23) | Metal | White | 2' west of AA | Upper mezzanine hallway | <49 | No | N/A |
| Pole | 2 (5/5/23) | Metal | White | 3' west of AA | Upper mezzanine hallway | <47 | No | N/A |
| Wall | 3 (5/5/23) | Plaster | White | South center of hallway wall | Upper mezzanine hallway | 180 | No | N/A |
| Door | 4 (5/5/23) | Wood | White | Southeast FF int. door | Upper mezzanine hallway | 86 | No | N/A |
| Door casing | 5 (5/5/23) | Metal | White | Southeast FF int. door | Upper mezzanine hallway | 92 | No | N/A |
| Wall trim | 6 (5/5/23) | Wood | White | Entry to EE seating area | Upper mezzanine hallway | <56 | No | N/A |
| Railing | 7 (5/5/23) | Metal | Gray | East stairwell | West and east stairwell | 1,900 | No | N/A |
| Door | 8 (5/5/23) | Wood | Blue | Interior of seating area DD | Seating area | 2,700 | No | N/A |
| Wall | 9 (5/5/23) | Concrete | White | South center 4' west of CC | Upper mezzanine hallway | <47 | No | N/A |

Page 5 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|-------------|----------------|-----------|-------------|---|------------------------------------|---------------|--------|---------------------|
| Door casing | 10 (5/5/23) | Metal | Tan | Interior door to projector rooms | Stairway projectors | 1,700 | No | N/A |
| Door | 11 (5/5/23) | Wood | Tan | Interior door to projector rooms | Stairway projectors | 710 | No | N/A |
| Door | 12 (5/5/23) | Wood | Gray | Janitor's closet 40' east of west center | Janitor closet upper mezzanine | 2,100 | No | N/A |
| Door casing | 13 (5/5/23) | Metal | Gray | Janitor's closet 40' east of west center | Janitor closet upper mezzanine | 2,900 | No | N/A |
| Wall | 14 (5/5/23) | Plaster | Gray | Janitor's closet 40' east of west center | Janitor closet upper mezzanine | 1,700 | No | N/A |
| Door casing | 1 (5/4/23) | Metal | Dark gray | Single door 50' north of southwest corner | West side exit door of stage | 600 | No | N/A |
| Door casing | 2 (5/4/23) | Metal | Dark gray | Single door 50' north of southwest corner | West side exit door of stage | 2,000 | No | N/A |
| Wall | 3 (5/4/23) | Concrete | Light blue | 30' east southwest corner | Back of stage, dressing room 1B | <49 | No | N/A |
| Wall | 4 (5/4/23) | Concrete | Dark gray | 40' east southwest corner | Stage, book of stage, seating area | 120 | No | N/A |
| Conduit | 5 (5/4/23) | Metal | Light blue | 15' east of northwest corner of stage | Throughout stage and back of stage | 160 | No | N/A |
| Conduit | 6 (5/4/23) | Metal | Dark gray | 15' east of northwest corner of stage | Throughout stage and back of stage | 61 | No | N/A |

Page 6 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|-------------|----------------|-----------|-------------|---|---|---------------|--------|---------------------|
| Column | 7 (5/4/23) | Concrete | Light blue | 40 feet east of northwest corner of stage | Stage, back of stage | <48 | No | N/A |
| Column | 8 (5/4/23) | Concrete | Dark gray | 40 feet east of northwest corner of stage | Stage, back of stage | <46 | No | N/A |
| Wall | 9 (5/4/23) | Plaster | Dark gray | 10' east of south center door gate | Back of stage, seating area 3 beneath | <48 | No | N/A |
| Wall | 10 (5/4/23) | Plaster | Off-white | North of southeast stairwell | Stage hallway, office 2, kitchen, dressing room 3, stagehand rooms, lobby | <49 | No | N/A |
| Railing | 11 (5/4/23) | Metal | Tan | Southeast stairwell | Southeast stairwell | <50 | No | N/A |
| Door | 12 (5/4/23) | Wood | Light blue | 4' east of east stairwell | Entry to hallway book storage, dressing room 3, stage hand dressing room | 18,000 | No | N/A |
| Door casing | 13 (5/4/23) | Metal | Light gray | Entry to back stage hallway from stage | Back stage hallway, west wing office 1 | <49 | No | N/A |
| Door | 14 (5/4/23) | Metal | Light blue | Entry to back stage hallway from stage | Stage | 260 | No | N/A |

Page 7 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|---------------|----------------|-----------|-------------|--|--|---------------|--------|---------------------|
| Door casing | 15 (5/4/23) | Metal | Light blue | Hallway northwest | Hallway, dressing room 4, stage hand, electrical | 160 | No | N/A |
| Wall | 16 (5/4/23) | Concrete | Light gray | Back stage hallway north 2' east of stage door | Room 4, book stage hallway, dressing room 5, 4, beneath seating area 2, 3 | <49 | No | N/A |
| Wall | 17 (5/4/23) | Plaster | Light gray | Back stage hallway south 2' east of stage door | Hallway, dressing room, rooms 5, 9, west wing hallway | <48 | No | N/A |
| Counter top | 18 (5/4/23) | Wood | White | Dressing room 5 southeast | Dressing room 5 | <49 | No | N/A |
| Counter top | 19 (5/4/23) | Wood | Light blue | Dressing room 5 southeast | Dressing room 5, 4 | 310 | No | N/A |
| Door casing | 20 (5/4/23) | Wood | Light blue | Dressing room 5 northeast corner door | Back stage restroom | <49 | No | N/A |
| Door casing | 21 (5/4/23) | Wood | White | Restroom back stage northwest | Back stage restroom | <46 | No | N/A |
| Wall | 22 (5/4/23) | Plaster | White | Restroom back stage southwest | Kitchen, back storage restroom | <47 | No | N/A |
| Stall divider | 24 (5/4/23) | Metal | White | Back stage restroom east center | Back stage restroom | 84 | No | N/A |
| Door | 25 (5/4/23) | Wood | White | Dressing room 4 interior | Dressing room 3, 4, hallway, room 4 | <46 | No | N/A |

Page 8 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|---------------------------|----------------|-----------|-------------|--------------------------------------|--|---------------|--------|---------------------|
| Door casing | 26 (5/4/23) | Metal | Orange | Dressing room 3A southwest | Dressing room 3ABC stage hands | 64 | No | N/A |
| Counter top | 27 (5/4/23) | Wood | Orange | Dressing room 3A southwest | Dressing room 3ABC | <49 | No | N/A |
| Pipe | 28 (5/4/23) | Metal | Orange | Dressing room 3A southwest | Dressing Room 3A | 110 | No | N/A |
| Wall | 29 (5/4/23) | Drywall | White | Northwest | Snack bar | <50 | No | N/A |
| Counter top | 30 (5/4/23) | Wood | Gray | Stage hand rooms east center | Stage hand room | 440 | No | N/A |
| Sound panel | 32 (5/4/23) | Metal | Gray | Seating area northwest | Seating area northwest | <47 | No | N/A |
| Wall | 33 (5/4/23) | Concrete | Gray | Seating area northeast | Seating area | <49 | No | N/A |
| Railing | 34 (5/4/23) | Metal | Gray | Seating area northeast | Seating area | <48 | No | N/A |
| Railing | 35 (5/4/23) | Metal | Blue/gray | Seating area northeast | Seating area | <49 | No | N/A |
| Fire extinguisher cabinet | 36 (5/4/23) | Wood | Blue/gray | Seating area northeast | Seating area | <49 | No | N/A |
| Door casing | 37 (5/4/23) | Metal | Gray | Door to underneath of seating area 1 | All doors to underneath seating sections | <47 | No | N/A |

Page 9 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|-------------|----------------|-----------|-------------|---|---|---------------|--------|---------------------|
| Door | 38 (5/4/23) | Wood | Gray | Northeast door to underneath seating | All doors to room underneath seating | 300 | No | N/A |
| Door | 39 (5/4/23) | Wood | Dark blue | Northeast door to underneath seating | nderneath seating underneath seating | | No | N/A |
| Wall | 40 (5/4/23) | Plaster | Light blue | Northwest underneath seating room section 3 | · · · · · · · · · · · · · · · · · · · | | No | N/A |
| Wall | 41 (5/4/23) | Plaster | Gray | Underneath seating area 5 west center | nderneath seating area East wing meeting area | | No | N/A |
| Column | 42 (5/4/23) | Concrete | White | Lobby east center | obby east center Lobby, F restroom, F restroom, kitchen | | No | N/A |
| Wall | 43 (5/4/23) | Plaster | White | 4' west of entry F south center | Lobby, F restroom, F restroom, kitchen | <50 | No | N/A |
| Door | 45 (5/4/23) | Metal | White | Snack bar entry | Kitchen | <48 | No | N/A |
| Door casing | 46 (5/4/23) | Metal | White | Entry to ticket known | Ticket booth | <48 | No | N/A |
| Wall | 47 (5/4/23) | Wood | Tan | West wing hallway west center | West wing hallway | <48 | No | N/A |
| Wall | 48 (5/4/23) | Drywall | Purple | West wing hallway west of office 3 | West wing hallway | <47 | No | N/A |
| Column | 50 (5/4/23) | Plaster | Light gray | East meeting room east center | Meeting room east | <48 | No | N/A |

Page 10 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|--------------|----------------|-----------|-------------|------------------------------------|--------------------------------------|---------------|--------|---------------------|
| Conduit | 51 (5/4/23) | Metal | Gray | Northwest meeting room east | East meeting room | <49 | No | N/A |
| Conduit | 52 (5/4/23) | Metal | White | Lobby east center | Lobby | <48 | No | N/A |
| Hatch | 53 (5/4/23) | Metal | Purple | West wing hallway east of office 3 | West wing hallway | <47 | No | N/A |
| Wall | 54 (5/4/23) | Drywall | White | Lobby janitor closet interior | Main floor interior janitor's closet | <47 | No | N/A |
| Door case | 55 (5/4/23) | Metal | White | Lobby janitor closet interior | Main floor interior janitor's closet | 2,000 | No | N/A |
| Door | 56 (5/4/23) | Wood | White | Lobby janitor closet interior | Main floor interior janitor's closet | 150 | No | N/A |
| Wall | 57 (5/4/23) | Concrete | White | Lobby janitor closet interior | Main floor interior janitor's closet | 2,100 | No | N/A |
| Railing | 4001 | Metal | Tan | Rail to stairwell | All stairways | 810 | No | N/A |
| Stairs | 4002 | Metal | Tan | Stairs | All stairs in hallways | 1,900 | No | N/A |
| Wall cabinet | 4003 | Wood | Blue/gray | Audio control room | Audio room, projector room | 130 | No | N/A |
| Door | 4004 | Wood | Gray | Interior fan room | Fan room only | 4,900 | No | N/A |

Page 11 of 12

CLIENT: Santa Monica Malibu School District

PROJECT NO: SMSD-23-11460

PROJECT NAME: Civic Center Due Diligence

| Component | Sample No. | Substrate | Paint Color | Sample Location | Material Location | Results (PPM) | Damage | Approx. Damage Qty. |
|----------------|------------|-----------|-------------|---|------------------------------|---------------|--------|---------------------|
| Post | 4005 | Concrete | l Yellow | Exterior 30ft north of southwest corner | Exterior only | 53,000 | No | N/A |
| Door | 4006 | Wood | I (∃reen | Interior air handler room #3 northeast | Air handler room #3 | 1,300 | No | N/A |
| Wall | 4007 | Plaster | Off-white | Air handler room northeast | Air handler room return room | <48 | No | N/A |
| Boiler coating | 4008 | Metal | Black | Boiler room #2 southeast | Boiler room | <49 | No | N/A |
| Railing | 4009 | Metal | Blue/gray | Catwalk center | Catwalk hallway | 88,000 | No | N/A |
| Floor coating | 4010 | Metal | Red/Brown | Catwalk entry | Catwalk | 61 | No | N/A |
| Column | 4011 | Metal | Red | Catwalk entry | Catwalk | 330,000 | No | N/A |

Page 12 of 12

Appendix B

Laboratory Analytical Report: Asbestos and Lead



3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test F | Report | | | |
|-----------------------------|--|---------------------|---|--------------------|-----------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | | (%) | Asbestos Type | (%) |
| 2353936-001 | | | | | | |
| RF-8 | Caulk Fire Guard, Red, Homogeneous | LAYER 1 100% | Fibrous Glass Perlite Binder/Filler | 5% 55% 40% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353936-002 RF-9 | Caulk Fire Guard, Red, Homogeneous | LAYER 1 100% | Fibrous Glass Perlite Binder/Filler | 5% 55% 40% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353936-003 RF-10 | Caulk Fire Guard, Red, Homogeneous | LAYER 1 100% | Fibrous Glass Perlite Binder/Filler | 5% 55% 40% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353936-004 RF-11 | TSI- Saddles, White, Homogeneous | LAYER 1 100% | Binder/Filler | 80% | Chrysotile Amosite | 5% 15% |
| | Asbestos Present: Yes | Tota | al % Non-Asbestos: | 80.0% Tota | l %Asbestos: | 20.0% |
| 2353936-005 RF-12 | TSI- Saddles, Note: Not Analyzed- Positive Stop | | | | | |
| | Asbestos Present: | Tota | al % Non-Asbestos: | Not Analyzed Total | l %Asbestos: | Not Analyzed |
| 2353936-006 RF-13 | TSI- Saddles, Note: Not Analyzed- Positive Stop | | | | | |
| | Asbestos Present: | Tota | al % Non-Asbestos: | Not Analyzed Total | l %Asbestos: | Not Analyzed |
| 2353936-007 RF-19A | FRP, Gray, Homogeneous | LAYER 1 100% | Vinyl Binder/ Filler | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |

PAGE: 1 of 23



05/19/2023

05/19/2023

05/19/2023

Alta Environmental

Attn.: Jim Byers

Date Received

Date Analyzed

Date Reported

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353936

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Sampled

Randy Flores Sampled By

Total Samples 131

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Method of Analysis

| Test Report | | | | | | | | | | |
|-----------------------------|---|-----------------------|--|-------------------------|------------------|-------------------------|--|--|--|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | | (%) | Asbestos Type | (%) | | | | |
| 2353936-008 RF-19B | Glue, Colorless, Homogeneous | LAYER 1 100% | Adhesive Binders | 100% | None Detected | | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T c | otal %Asbestos: | No Asbestos Detected | | | | |
| 2353936-009 RF-20A | FRP, Gray, Homogeneous | LAYER 1 100% | Vinyl Binder/ Filler | 100% | None Detected | | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T c | otal %Asbestos: | No Asbestos Detected | | | | |
| 2353936-010 RF-20B | Glue, Colorless, Homogeneous | LAYER 1 100% | Adhesive Binders | 100% | None Detected | | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tc | otal %Asbestos: | No Asbestos Detected | | | | |
| 2353936-011 RF-21A | FRP, Gray, Homogeneous | LAYER 1 100% | Vinyl Binder/ Filler | 100% | None Detected | | | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% Total %Asbestos: | | No Asbestos Detected | | | | |
| 2353936-012 RF-21B | Glue, Colorless, Homogeneous | LAYER 1 100% | Adhesive Binders | 100% | None Detected | | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T c | otal %Asbestos: | No Asbestos Detected | | | | |
| 2353936-013 RF-22 | Tectum, Gray/White, Non- homogeneous | LAYER 1 100% | Wood Fiber Calcium Carbonate Binder/Filler | 40% 50% 10% | None Detected | | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tc | otal %Asbestos: | No Asbestos Detected | | | | |

PAGE: 2 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials

| | Test Report | | | | | | | |
|-----------------------------|---|-----------------------|--|-------------------------|------------------|-------------------------|--|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) | | |
| 2353936-014 | | | | | | | | |
| RF-23 | Tectum, Gray/White, Non- homogeneous | LAYER 1 100% | Wood Fiber Calcium Carbonate Binder/Filler | 40% 50% 10% | None Detected | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | | |
| 2353936-015 | | | | | | | | |
| RF-24 | Tectum, Gray/White, Non- homogeneous | LAYER 1 100% | Wood Fiber Calcium Carbonate Binder/Filler | 40% 50% 10% | None Detected | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% Total %Asbestos: | | No Asbestos Detected | | |
| 2353936-016 | | | | | | | | |
| RF-25 | Mastic, White, Homogeneous | LAYER 1 100% | Wood Fiber Gypsum/Binder/Filler | <1% 100% | None Detected | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% Total %Asbestos: | | No Asbestos Detected | | |
| 2353936-017 | | | | | | | | |
| RF-26 | Mastic, White, Homogeneous | LAYER 1 100% | Wood Fiber Gypsum/Binder/Filler | <1% 100% | None Detected | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | | |
| 2353936-018 RF-27 | Mastic, White, Homogeneous | LAYER 1 100% | Wood Fiber Gypsum/Binder/Filler | <1% 100% | None Detected | | | |
| | Asbestos Present: No | | al % Non-Asbestos: | | tal %Asbestos: | No Asbestos Detected | | |
| 2353936-019 | | | | | | | | |
| RF-28 | Panel Board Ceiling, White | LAYER 1 100% | Wood Fiber Gypsum | <1% 100% | None Detected | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% To | tal %Asbestos: | No Asbestos Detected | | |

PAGE: 3 of 23



05/19/2023

05/19/2023

05/19/2023

Alta Environmental

Attn.: Jim Byers

Date Received

Date Analyzed

Date Reported

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353936

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Sampled

Sampled By Randy Flores

Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|---|--|-------------------------|-------------------------|--|--|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Non-Asbestos Layer % Components | Asbestos (%) Type | (%) | | | |
| 2353936-020 RF-29 | Panel Board Ceiling, White | LAYER 1 Wood Fiber 100% Gypsum | <1% None Detected 100% | | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected | | | |
| 2353936-021 RF-30 | Panel Board Ceiling, White | LAYER 1 Wood Fiber 100% Gypsum | <1% None Detected 100% | | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected | | | |
| 2353936-022 RF-37A | Stair Tread, Blue, Homogeneous | LAYER 1 100% Vinyl Binder/ Filler | None Detected 100% | | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected | | | |
| 2353936-023 RF-37B | Glue, Cream, Homogeneous | LAYER 1 100% Adhesive Binders/Filler | None Detected | | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected | | | |
| 2353936-024 RF-38A | Stair Tread, Blue, Homogeneous | LAYER 1 100% Vinyl Binder/ Filler | None Detected 100% | | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected | | | |
| 2353936-025 RF-38B | Glue, Cream/Yellow, Non- homogeneous | LAYER 1 100% Adhesive Binders/Filler | None Detected | | | | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected | | | |

PAGE: 4 of 23



Alta Environmental

Attn.: Jim Byers

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353936

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Fax: 562-20

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials

| Test Report | | | | | | | |
|-----------------------------|---|----------------------|----------------------------|--------------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) | |
| 2353936-026 RF-39A | Stair Tread, Blue, Homogeneous | LAYER 1 100% Vir | ıyl Binder/ Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % | Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected | |
| 2353936-027 RF-39B | Glue, Cream, Homogeneous | LAYER 1 100% Ad | hesive Binders/Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % | Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected | |
| 2353936-028 RF-40A | Stair Tread, Black, Homogeneous | LAYER 1 100% Vir | ıyl Binder/ Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % | Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected | |
| 2353936-029 RF-40B | Glue, Cream, Homogeneous | LAYER 1 100% Ad | hesive Binders/Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % | Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected | |
| 2353936-030 RF-41A | Stair Tread, Black, Homogeneous | LAYER 1 100% Vir | ıyl Binder/ Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % | Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected | |
| 2353936-031 RF-41B | Glue, Cream/Yellow, Non- homogeneous | LAYER 1 100% Ad | hesive Binders/Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % | Non-Asbestos: | 100.0% Tota | I %Asbestos: | No Asbestos Detected | |

PAGE: 5 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|---|---|----------------------|-------------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | • | -Asbestos ponents | (%) | Asbestos Type | (%) | |
| 2353936-032 RF-42A | Stair Tread, Black, Homogeneous | LAYER 1 100% Vinyl Bin | der/ Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % Non | | | otal %Asbestos: | No Asbestos Detected | |
| 2353936-033 RF-42B | Glue, Tan, Homogeneous | LAYER 1 100% Adhesive | e Binders | 100% | None Detected | | |
| | Asbestos Present: No | Total % Non | -Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-034 RF-43 | Epoxy, Gray, Non-homogeneous | LAYER 1 100% Quartz Calcium Binder/F | Carbonate iller | 50% 35% 15% | None Detected | | |
| | Asbestos Present: No | Total % Non | -Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-035 RF-44 | Epoxy, Gray, Non-homogeneous | LAYER 1 100% Quartz Calcium Binder/F | Carbonate iller | 60% 30% 10% | None Detected | | |
| | Asbestos Present: No | Total % Non | -Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-036 RF-45 | Epoxy, Gray, Non-homogeneous | LAYER 1 100% Quartz Calcium Binder/F | Carbonate iller | 40% 45% 15% | None Detected | | |
| | Asbestos Present: No | Total % Non | -Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-037 RF-46A | 16"x16" Vinyl Tile, Green, Homogeneous | LAYER 1 100% Vinyl Bin | der/ Filler | 100% | None Detected | | |
| | Asbestos Present: No | Total % Non | -Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |

PAGE: 6 of 23



Alta Environmental

Attn.: Jim Byers

3777 Long Beach Blvd.

Long Beach CA 90807

Report Number 2353936

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|---|----------------------|-----------------------------------|-----------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) | |
| 2353936-038 RF-46B | Glue, Lt. Yellow, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-039 RF-47A | 16"x16" Vinyl Tile, Green, Homogeneous | LAYER 1 100% | Vinyl Binder/ Filler | 100% | None Detected | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-040 RF-47B | Glue, Yellow, Homogeneous | LAYER 1 100% | Adhesive Binders | 100% | None Detected | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-041 RF-48A | 16"x16" Vinyl Tile, Green, Homogeneous | LAYER 1 100% | Vinyl Binder/ Filler | 100% | None Detected | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-042 RF-48B | Mastic, Yellow, Homogeneous | LAYER 1 100% | Adhesive Binders | 100% | None Detected | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-043 RF-49A | 6" Cove Base, Brown, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |

PAGE: 7 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | |
|-----------------------------|--|-----------------------|-----------------------------------|------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353936-044 RF-49B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | |
| | Asbestos Present: No | Tota | Il % Non-Asbestos: | 100.0% To | otal %Asbestos: | No Asbestos Detected |
| 2353936-045 RF-50A | 6" Cove Base, Brown, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% To | otal %Asbestos: | No Asbestos Detected |
| 2353936-046 RF-50B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% To | otal %Asbestos: | No Asbestos Detected |
| 2353936-047 RF-51A | 6" Cove Base, Brown, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% To | otal %Asbestos: | No Asbestos Detected |
| 2353936-048 RF-51B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% To | otal %Asbestos: | No Asbestos Detected |
| 2353936-049 RF-52A | 6" Cove Base, Dk. Blue, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Tota | Il % Non-Asbestos: | 100.0% To | otal %Asbestos: | No Asbestos Detected |

PAGE: 8 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | |
|-----------------------------|--|----------------------|-----------------------------------|------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353936-050 RF-52B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-051 RF-53A | 6" Cove Base, Dk. Blue, Homogeneous | | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-052 RF-53B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-053 RF-54A | 6" Cove Base, Dk. Blue, Homogeneous | | Calcium Carbonate /inyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-054 RF-54B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-055 RF-55A | 6" Cove Base, Black, Homogeneous | | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |

PAGE: 9 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test F | Report | | | |
|-----------------------------|----------------------------------|-----------------------|-----------------------------------|-------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | | (%) | Asbestos Type | (%) |
| 2353936-056 | | | | | | |
| RF-55B | Mastic, Dk. Brown, Homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders | 5% 95% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-057 RF-56A | 6" Cove Base, Black, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-058 RF-56B | Mastic, Dk. Brown, Homogeneous | LAYER 1 100% | Fibrous Glass Adhesive Binders | 5% 95% | None Detected | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-059 RF-57A | 6" Cove Base, Black, Homogeneous | LAYER 1 100% | Vinyl Binder/ Filler | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T o | otal %Asbestos: | No Asbestos Detected |
| 2353936-060 RF-57B | Glue, Dk. Brown, Homogeneous | LAYER 1 100% | Adhesive Binders | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-061 RF-58A | 6" Cove Base, Blue, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T o | otal %Asbestos: | No Asbestos Detected |

PAGE: 10 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|---|---------------------|--|-----------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | | (%) | Asbestos Type | (%) | |
| 2353936-062 RF-58B | Mastic, Brown/ Tan, Non- homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders/Filler | <1% 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-063 RF-59A | 6" Cove Base, Blue, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-064 RF-59B | Mastic, Brown/ Tan, Non- homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders/Filler | <1% 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-065 RF-60A | 6" Cove Base, Blue, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-066 RF-60B | Mastic, Brown/ Tan, Non- homogeneous | LAYER 1 100% | Fibrous Glass Adhesive Binders/Filler | <1% 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-067 RF-61A | 6" Cove Base, Lt. Gray, Homogeneou | s LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |

PAGE: 11 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|------------------------------------|---------------------|-----------------------------------|-----------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) | |
| 2353936-068 RF-61B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-069 RF-62A | 6" Cove Base, Lt. Gray, Homogeneou | s LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-070 RF-62B | Mastic, Tan, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-071 RF-63A | 6" Cove Base, Lt. Gray, Homogeneou | s LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-072 RF-63B | Mastic, Tan, Homogeneous | LAYER 1 100% | Adhesive Binders/Filler | 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-073 RF-64A | 4" Cove Base, Black, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |

PAGE: 12 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|--------------------------------------|-----------------------|--|-------------------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) | |
| 2353936-074 | | | | | | | |
| RF-64B | Mastic, Dk. Brown, Homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders | 5% 95% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | |
| 2353936-075 | 4ll Court Book Block House was a | LAVED 4 | | | Nama Datastad | | |
| RF-65A | 4" Cove Base, Black, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | |
| 2353936-076 | | | | -0/ | | | |
| RF-65B | Mastic, Dk. Brown, Homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders | 5% 95% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | |
| 2353936-077 | | | | | | | |
| RF-66A | 4" Cove Base, Black, Homogeneous | LAYER 1 100% | Calcium Carbonate Vinyl Binder | 40% 60% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | |
| 2353936-078 | | | | | | | |
| RF-66B | Mastic, Dk. Brown, Homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders | 5% 95% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | |
| 2353936-079 | A C I El B I I | LAVED 4 | luta Eilaan | -10/ | Nama Datastad | | |
| RF-67A | Acoustical Floor, Beige, Homogeneous | 100% | Jute Fiber Quartz Vermiculite Gypsum/Binder/Filler | <1% 5% 40% 55% | None Detected | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% | Total %Asbestos: | No Asbestos Detected | |

PAGE: 13 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|--------------------------------------|---------------------|---|-------------------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) | |
| 2353936-080 RF-67B | Coating, Dk. Blue, Homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-081 RF-68A | Acoustical Floor, Beige, Homogeneous | LAYER 1 100% | Jute Fiber Quartz Vermiculite Gypsum/Binder/Filler | <1% 5% 40% 55% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-082 RF-68B | Coating, Dk. Blue, Homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-083 RF-69A | Acoustical Floor, Beige, Homogeneous | LAYER 1 100% | Jute Fiber Quartz Vermiculite Gypsum/Binder/Filler | <1% 5% 40% 55% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-084 RF-69B | Coating, Dk. Blue, Homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |
| 2353936-085 RF-70A | Acoustical Floor, Beige, Homogeneous | LAYER 1 100% | Quartz Vermiculite Gypsum/Binder/Filler | 10% 40% 50% | None Detected | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | |

PAGE: 14 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test Ro | eport | | | |
|-----------------------------|------------------------------------|----------------------|---|-------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353936-086 RF-70B | Coating, Dk. Blue, Homogeneous | LAYER 1 100% N | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% Tot | al %Asbestos: | No Asbestos Detected |
| 2353936-087 RF-71A | Acoustical Floor, Beige, Homogeneo | 100% C | Quartz /ermiculite Gypsum/Binder/Filler | 10% 40% 50% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% Tot | al %Asbestos: | No Asbestos Detected |
| 2353936-088 RF-71B | Coating, Dk. Blue, Homogeneous | LAYER 1 100% N | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% Tot | al %Asbestos: | No Asbestos Detected |
| 2353936-089 RF-80 | Coating, Black, Homogeneous | LAYER 1 100% N | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% Tot | al %Asbestos: | No Asbestos Detected |
| 2353936-090 RF-81 | Coating, Black, Homogeneous | LAYER 1 100% N | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% Tot | al %Asbestos: | No Asbestos Detected |
| 2353936-091 RF-82 | Coating, Black, Homogeneous | LAYER 1 100% N | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% Tot | al %Asbestos: | No Asbestos Detected |

PAGE: 15 of 23



Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770

Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Civic Center Location

PO Number WO Number

Date Received 05/19/2023 **Date Sampled**

05/19/2023 Randy Flores **Date Analyzed** Sampled By

Date Reported 05/19/2023 **Total Samples** 131

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

Determination of Asbestos in Bulk Building Materials.

| | | Test F | Report | | | |
|-----------------------------|---|----------------------------|----------------------------------|-------------------|-------------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | | (%) | Asbestos Type | (%) |
| 2353936-092 | | | | | | |
| RF-89A | Fiber Board Ins., Brown, Homogeneous | LAYER 1 Wood Fiber 100% | | 100% | None Detected | |
| | Asbestos Present: No Total % Non-Asbe | | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-093 | | | | | | |
| RF-89B | Mastic, Dk. Brown, Homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders | 5% 95% | None Detected | |
| | Asbestos Present: No | : No Total % Non-Asbestos: | | 100.0% T | No Asbestos Detected | |
| 2353936-094 | | | | | | |
| RF-90A | Fiber Board Ins., Brown, Homogeneous | LAYER 1 100% | Wood Fiber | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-095 | | | | | | |
| RF-90B | Mastic, Brown, Homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders | 5% 95% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-096 | | | | | | |
| RF-91A | Fiber Board Ins., Brown, Homogeneous | LAYER 1 100% | Wood Fiber | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-097 | | | | | | |
| RF-91B | Mastic, Brown, Homogeneous | LAYER 1 100% | Fibrous Talc Adhesive Binders | 5% 95% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected |

PAGE: 16 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test Report | | |
|-----------------------------|---|--|--------------------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Non-Asbestos Layer % Components | Asbestos (%) Type | (%) |
| 2353936-098 RF-98 | Terrazzo w/ small specks, Black, Homogeneous | LAYER 1 100% Calcium Carbonate Binder/Filler | None Detected 80% 20% | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected |
| 2353936-099 RF-99 | Terrazzo w/ small specks, Black, Homogeneous | LAYER 1 100% Calcium Carbonate Binder/Filler | None Detected 80% 20% | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected |
| 2353936-100 RF-100 | Terrazzo w/ small specks, Black, Homogeneous | LAYER 1 100% Calcium Carbonate Binder/Filler | None Detected 80% 20% | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected |
| 2353936-101 RF-101 | Terrazzo w/ large specks, White/Black, Non-homogeneous | LAYER 1 100% Calcium Carbonate Binder/Filler | None Detected 85% 15% | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected |
| 2353936-102 RF-102 | Terrazzo w/ large specks, White/Black, Non-homogeneous | LAYER 1 100% Calcium Carbonate Binder/Filler | None Detected 85% 15% | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected |
| 2353936-103 RF-103 | Terrazzo w/ large specks, White/black, Non-homogeneous | LAYER 1 100% Calcium Carbonate Binder/Filler | None Detected 90% 10% | |
| | Asbestos Present: No | Total % Non-Asbestos: | 100.0% Total %Asbestos: | No Asbestos Detected |

PAGE: 17 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test R | eport | | | |
|-----------------------------|--|---|------------------------------------|------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353936-104 RF-104 | Terrazzo w/ large specks, | LAYER 1 | Onlying Only work | 000/ | None Detected | |
| | White/black, Non-homogeneous | | Calcium Carbonate Binder/Filler | 90% 10% | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-105 | | | | | | |
| RF-105 | Terrazzo w/ large specks, | LAYER 1 | Calairum Caubanata | 000/ | None Detected | |
| | White/black, Non-homogeneous | 100% Calcium Carbonate Binder/Filler | | 90% 10% | | |
| | Asbestos Present: No | Tota | I % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-106 | | | | | | |
| RF-106 | Terrazzo w/ large specks, White/black, Non-homogeneous | LAYER 1 100% | Calcium Carbonate | 90% | None Detected | |
| | white/black, Non-homogeneous | | Binder/Filler | 10% | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% To | tal %Asbestos: | No Asbestos Detected |
| 2353936-107 | | | | | | |
| RF-107 | Terrazzo, Red/Black/Dk. Green, Non- homogeneous Note: Sample includes serpentenite aggregate. | | Calcium Carbonate Binder/Filler | 80% 20% | Chrysotile | <1% |
| | Asbestos Present: Yes | Tota | I % Non-Asbestos: | 100.0% To | tal %Asbestos: | <1% |
| 2353936-108 | | | | | | |
| RF-108 | Terrazzo, Red, Non-homogeneous | | Calcium Carbonate Binder/Filler | 90% 10% | Chrysotile | <1% |
| | Asbestos Present: Yes | Tota | I % Non-Asbestos: | 100.0% To | tal %Asbestos: | <1% |
| 2353936-109 | | | | | | |
| RF-109 | Terrazzo, Red/Black/Dk. Green, Non- homogeneous Note: Sample includes serpentenite aggregate. | | Calcium Carbonate Binder/Filler | 80% 20% | Chrysotile | <1% |
| | Asbestos Present: Yes | | | | | |

PAGE: 18 of 23



Alta Environmental

Attn.: Jim Byers

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353936

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

etermination of Ashestos in Bulk Building Materials

| | | Test F | Report | | | |
|-----------------------------|---|---------------------|---|-------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | | (%) | Asbestos Type | (%) |
| 2353936-110 RF-110 | Terrazzo, Green/Colorless, Non- homogeneous | LAYER 1 100% | Calcium Carbonate Glass Binder/Filler | 80% 10% 10% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353936-111 RF-111 | Terrazzo, Green/Colorless, Non- homogeneous | LAYER 1 100% | Calcium Carbonate Glass Binder/Filler | 80% 10% 10% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353936-112 RF-112 | Terrazzo, Green/Colorless, Non- homogeneous | LAYER 1 100% | Calcium Carbonate Binder/Filler | 85% 15% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353936-113 RF-114 | Terrazzo, Pink/Black/White, Non- homogeneous | LAYER 1 100% | Calcium Carbonate Binder/Filler | 80% 20% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353936-114 RF-115 | Terrazzo, Pink/Black/White, Non- homogeneous | LAYER 1 100% | Calcium Carbonate Binder/Filler | 80% 20% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |

PAGE: 19 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test R | eport | | | | |
|-----------------------------|---|--|------------------------------------|------------------|------------------|-------------------------|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Non-Asbestos Layer % Components | | (%) | Asbestos Type | (%) | |
| 2353936-115 | | | | | | | |
| RF-116 | Terrazzo, Yellow/Black, Non- homogeneous | | Calcium Carbonate Binder/Filler | 75% 25% | None Detected | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | |
| 2353936-116 | | | | | | | |
| RF-117 | Terrazzo, Yellow/Black, Non- homogeneous | | Calcium Carbonate Binder/Filler | 75% 25% | None Detected | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | |
| 2353936-117 RF-118 | Terrazzo, Yellow/Black, Non- homogeneous | | Calcium Carbonate Binder/Filler | 75% 25% | None Detected | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | |
| 2353936-118 RF-119 | Terrazzo, Yellow/Black, Non- homogeneous | | Calcium Carbonate Binder/Filler | 75% 25% | None Detected | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | |
| 2353936-119 | | | | | | | |
| RF-120 | Terrazzo, White/Beige, Non- homogeneous | | Calcium Carbonate Binder/Filler | 90% 10% | None Detected | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | |
| 2353936-120 RF-121 | Terrazzo, White/Beige, Non- homogeneous | | Calcium Carbonate Binder/Filler | 90% 10% | None Detected | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To | tal %Asbestos: | No Asbestos Detected | |

PAGE: 20 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770

Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 **Date Sampled**

05/19/2023 Randy Flores **Date Analyzed** Sampled By

Date Reported 05/19/2023 **Total Samples** 131

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

Determination of Asbestos in Bulk Building Materials.

| | | Test F | Report | | | |
|-----------------------------|----------------------------------|-----------------------|--------------------------------------|-------------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353936-121 | | | | | | |
| RF-122 | Terrazzo, White/Beige, Non- | LAYER 1 | | | None Detected | |
| | homogeneous | 100% | Calcium Carbonate Binder/Filler | 90% 10% | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T o | otal %Asbestos: | No Asbestos Detected |
| 2353936-122 | | | | | | |
| RF-14A | Drywall, Pink/Brown, Non- | LAYER 1 | Cellulose Fiber | 15% | None Detected | |
| | homogeneous | 100% | Fibrous Glass | <1% 85% | | |
| | | | Gypsum/Filler | 65% | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% Total %Asbestos: | | No Asbestos Detected |
| 2353936-123 | | | | | | |
| RF-14B | JC, White, Non-homogeneous | LAYER 1 | | | None Detected | |
| | | 100% | Calcium Carbonate Binder/Filler | 70% 30% | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected |
| 2353936-124 | | | | | | |
| RF-15A | Drywall, White/ Brown, Non- | LAYER 1 | Cellulose Fiber | 10% | None Detected | |
| | homogeneous | 100% | Fibrous Glass Gypsum/Filler | <1% 90% | | |
| | | | Cypsulli/Tillel | <i>30 /</i> 0 | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353936-125 | | | | | | |
| RF-15B | JC, Black/White, Non-homogeneous | LAYER 1 | | | None Detected | |
| | | 100% | Perlite | 5% | | |
| | | | Mica Calcium Carbonate Binder/Filler | 10% 65% 20% | | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% T (| otal %Asbestos: | No Asbestos Detected |

PAGE: 21 of 23



Long Beach CA 90807

Report Number 2353936

Attn.: Jim Byers

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Received 05/19/2023 Date Sampled

Date Analyzed 05/19/2023 Sampled By Randy Flores

Date Reported 05/19/2023 Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test F | Report | | | |
|-----------------------------|--|-----------------------|---|--------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353936-126 | | | | | | |
| RF-16A | Drywall, Pink/Brown, Non- homogeneous | LAYER 1 100% | Cellulose Fiber Fibrous Glass Gypsum/Filler | 15% <1% 85% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353936-127 | | | | | | |
| RF-16B | JC, White, Non-homogeneous | LAYER 1 100% | Calcium Carbonate Binder/Filler | 70% 30% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353936-128 | Daniell Milita / Daniel Mari | LAYER 1 | Cellulose Fiber | 20% | None Detected | |
| RF-17A | Drywall, White/ Brown, Non- homogeneous | 100% | Fibrous Glass Gypsum/Filler | <1% 80% | None Detected | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353936-129 RF-17B | IC Deign / White New home govern | LAYER 1 | | | None Detected | |
| KF-17B | JC, Beige/ White, Non-homogeneous | 100% | Mica Calcium Carbonate Binder/Filler | 10% 70% 20% | None Detected | |
| | Asbestos Present: No | Total % Non-Asbestos: | | 100.0% Tota | I %Asbestos: | No Asbestos Detected |
| 2353936-130 | | | | | | |
| RF-18A | Drywall, White/ Brown, Non- homogeneous | LAYER 1 100% | Cellulose Fiber Fibrous Glass Gypsum/Filler | 15% <1% 85% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | I %Asbestos: | No Asbestos Detected |

PAGE: 22 of 23



05/19/2023

05/19/2023

05/19/2023

Alta Environmental

Attn.: Jim Byers

Date Received

Date Analyzed

Date Reported

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353936

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460

Project Name Santa Monica Civic Center

Location Civic Center

PO Number WO Number

Date Sampled

Sampled By Randy Flores

Total Samples 131

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | | |
|-----------------------------|-----------------------------------|---------------------|--|--------------------|------------------|-------------------------|--|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) | | |
| 2353936-131 RF-18B | JC, Beige/ White, Non-homogeneous | LAYER 1 | | | None Detected | | | |
| | | 100% | Mica Calcium Carbonate Binder/Filler | 10% 70% 20% | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% To 1 | tal %Asbestos: | No Asbestos Detected | | |

Analysts: CET (001-097, 122-131); FDC (098-121)

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

CA-FLAP #2823

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt

NVLAP Lab Code 500044-0

PAGE: 23 of 23



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

| | CUSTOMER INF | ORMATION | | Turnaround Tir | ne a | Shipper | d Bv | Repo | rt Send Via | |
|--|--------------------|---|---------|--------------------------|---------------------------------|------------|----------------------|------------|--------------|--------|
| Company | Alta Environment | al/NV5 | | Same Day 1 | 6 | Fedex | | Web | | |
| Address | 3777 Long Beach | Blvd., Anne | x Bldg. | - | | UPS | | Email | 1 | |
| City/State/Zip | Long Beach, Ca 9 | 90807 | | 2 Day | | USPS | | Fax 🗆 | | |
| Contact | Jim Byers | | | 3 Day D | | Drop Off | B | Verbal | | |
| Office Phone | 562-495-5777 | | | 5 Day | ar. | Drop Box | 0 | Mail | 1000 | |
| Cell | | | | Weekend Other Pick up | | | | | | |
| Fax | 562-495-5877 | | | Special Instru | uctions: | | | | | |
| Email | jim,byers@nv5.co | m | | Layered ana | lysis on | drywall/je | oint comp | pound | | |
| | | | | cc therese.riz | arri@n5. | | | | m on resu | Its |
| | | | ROJECT | INFORMATIO | N | | | | | - 1 |
| Project Name: | Santa Moinca Civic | Center | | PO Number: | | | | | | |
| Project Number: | SMSD-23-11460 | | | Work Order No.: | | | | | | |
| Location: | _ Civiz Cen | Ler | | Sampled By: Randy Flores | | | | | | |
| PLM EPA 600/M4 PLM 400 Pt. Cou PLM 1000 Pt. Co | nt (<0.25%) | PCI NIOSH 740 NIOSH 740 w/ TWA | DA 🗆 | Sport Tape | OLD e Trap Lift Sample | 000 | Air Paint Wipe | LEAD | (Pb) TTLC | 0 |
| | | | | Swa | b | | Soil | | - 9 | |
| SAMPLE ID | SAMPLE TY | PE | | LOCATION | | | Date | Start Time | Avg | Volume |
| RF- 8 | Red Car | | civ | ez Cu | La | | Sampled | Stop Time | Flow Rate | (L) |
| RF - 9 | | | | 1 | | | | | | |
| RF-10 | 7 | | | | | | | | | |
| RF - 11 | TSI - Sad | dles | | | | | | | | |
| RF-12 | | | | | | | | | | |
| RF- 13 | 1 | | | | | | | | | |
| RF-19 | FRP W/GI | ,v.L | | | | | | | | |
| RF. 20 | | | | | | | | | | |
| RF-21 | ل | | | | | | | | | |
| R- 22 | Tecto | m | | 5 | | | | | | |
| Relinquished By: | Randy | le | | Received By: | | An | | dic | | ~ ~ |
| Printed Name - | | -lores | - 1 | Printed Name | 1 | idic T | 7499 | | | |
| Date/Time: 5/1 | 7/2023 1 | 240 | | Date/Time: | | 5/19/23 | 12: | 40 | | |
| Relinquished By: | | | - 3 | Received By: | | - | | | | |
| Printed Name | | | | Printed Name | | | | | | |
| Date/Time: | | | | Date/Time: | | | | | | - 8 |
| ar a | | | | Control 1 minus | | | | | | 17 |



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

| Company: | Alta Environmental/NV5 | |
|-----------------|---------------------------|------|
| Project Number: | SMSD-23-11460 | |
| Designat Manage | Santa Malana Chila Cantas | - 77 |

| Project Name: | Santa Moinca Civic Center | | | | | |
|------------------|---------------------------|--------------|-----------------|-------------------------|------------------|--------------|
| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volum (L) |
| RF- 23 | Tectum | | | | | |
| RF 24 | | | | | | |
| RF-25 | white mastic | | | | | |
| RF-26 | | - | | | | |
| Rf- 27 | | | | | | |
| RF-28 | Board Celling | | | | | |
| RF-29 | | | | | | |
| RF. 30 | + | | | | | |
| RF - 37 | BIVE STAIR TREAD | | | | | |
| RF 38 | | | | | | |
| RF-39 | 1 | | | | | |
| RF-40 | BLACK STAIR TREAD | | | | | |
| R-F-41 | 1 | | | | | |
| RF- 42 | 1 | | | | | |
| RE- 43 | Gray, Epoxy | | | | | |
| RF. 44 | J. T. OPONY | | | | | |
| RF. 45 | 1 | | | | | |
| RF. 46 | 115x16" Green/alu | | | | | |
| RF. 47 | Ving Tik 76 CCC | | | | | |
| RF 48 | | | | | | |
| Relinquished By: | 12 2 2 7 | Received By: | ava | _ | | _ |
| Printed Name | ZANDOLPH FLORES | | | 24 | | |
| Date/Time: | 5/19/2027 1240 | Date/Time: | Shalza | J 2:4 | 0 | |
| Relinquished By: | 21111000 1640 | Received By: | - Indian | | | |
| Printed Name | | Printed Name | | | | |
| Date/Time: | | Date/Time: | | | | |



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tell 562-206-2773 Fax services@AQenvlabs.com

Company: Alta Environmental/NV5

Project Number: SMSD-23-11460

Project Name: Santa Moinca Civic Center

| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volum (L) |
|------------------|---------------------------------------|----------------------|-----------------|-------------------------|------------------|--------------|
| ю | 100 1 n w/= | " Martie Civil Cente | | Stop Time | Flow reade | (L) |
| RF. 49 | 6: Drown Cove Bate /Ta | " Martic Conte | 4 | | | |
| RF-50 | | | | | | |
| Rp- 51 | , + | | | | | |
| RF- 52 | 6 Dark Blue (ove Base W/Ton Mastic | | | | | |
| RF- 53 | | | | | | |
| RF-54 | 1 | 1 | | | | |
| RF - 55 | W Brown Mastic | | | | | |
| RF - 56 | 1 | | | | | |
| RF- 57 | | | | | | |
| PK- 58 | TAN MASTIC | | | | | |
| RF. 59 | 7 (40 1051110 | | | | | |
| .2. | | | | | | |
| 10 | 6 L. Caray Love Base w/ Ton Mastra | | | | | |
| 0 | in Tain Mastia | | | | | |
| RF- 62 | 1 | | | | | |
| RF- 63 | 4"Brow Love Bese W/Brow Mastre | | | | | |
| | Tw/Brow Mastre | | | | | |
| V-1 | | | | | | |
| RF- 66 | Acoustical floor | | - | | | |
| RF- 67 | W/BIVE, COATING | | + | | - | |
| KG- 68 | 1 | 2 | | | 1 | |
| Relinquished By: | 12 da | Received By: | | | | |
| Printed Name | KANDOLDM FLORES | Printed Name | lackie T | | 215 | |
| Date/Time: 5 | 119/2023 1240 | | 1/23 | 7 6 | 2:40 | |
| Relinquished By: | | Received By: | | | | |
| Printed Name | | Printed Name | | | | |
| Date/Time: | | Date/Time: | | | | FURINS |



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

Company: Alta Environmental/NV5

Project Number: SMSD-23-11460

Project Name: Santa Moinca Civic Center

| Project Name: S | anta Moinca Civic Center | | | | | |
|------------------|-------------------------------------|-----------------|-----------------|-------------------------|------------------|---------------|
| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volume (L) |
| | ACOUSTICAL FLOOR W/BLUE, LOATING | | | | | 2000 |
| 25-70 | 1 | | | | | |
| 2F - 71 | 1 | | | | | |
| RF- 40 | BLACK | | | | | |
| RF. 81 | 1 | | | | | |
| RF - 82 | 2 | | | | | |
| RF-89 F | WBrown MASTIL | | | | | |
| BF-90 | | | | | | |
| RF-91 | | | | | | |
| 25 00 | DLACK TERRAZZO W/ SMALL SPECKS | | | | | |
| Pt-99 | | | | | | |
| RF- 100 | , L | | | | | |
| | Beige Ferinzeo Warge Species | | | | | |
| RF-102 | | | | | | |
| PF- 107 | 1 | | | | - | |
| | Beige Terrazzo WLESS SPECKS | | | | | |
| RF- 105 | 1 | | 100 | | - | |
| RF-106 | | | | | | |
| RF-107 | REP TERRAZZO | | | | | |
| RF - 108 | - | | | | | |
| Relinquished By: | h de | Received By: | 17 | | | |
| Printed Name 72 | ANDOURH FLORES | Printed Name | lackie TA | 1419 | | |
| Date/Time: 5/1 | 9/2022 1240 | Date/Time: 5/14 | 1/23 12 | 40 | | |
| Relinquished By: | | Received By: | | | | |
| Printed Name | | Printed Name | | | | |
| Date/Time: | | Date/Time: | | | | CHINS |



Project Name:

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

 Company:
 Alta Environmental/NV5

 Project Number:
 SMSD-23-11460

Santa Moinca Civic Center

(Lab) Order No. 2353936

| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time | Avg Elow Pate | Volum (L) |
|------------------|------------------|---------------------|-----------------|-------------------------|------------------|--------------|
| RF-109 | Red Terrazão | envic Center | Samples | Stop Time | Flow Rate | (L) |
| RR-110 | Green Terraco | 1 | | | | |
| KP-1/1 | J J J | | | | | |
| 2F- 112 | | | | | | |
| RF-114 | Pink terrare | | | | | |
| RF-115 | , Janes | | | | | |
| RF 116 | 1 | | | | | |
| Rp-117 | Yellow Terrazzo | | | | | |
| Re-118 | | | | | | |
| RP-119 | 1 | | | | | |
| 4-120 | L. Bige Terrazzo | | | | | |
| RF- 121. | 1 | | | | | |
| RF-122 | + | 1 | | | | |
| | | | | | | |
| RF- 14 | Dry Wall of. C. | civiz com | | | | |
| RF-15 | | | | | | |
| 12F-16 | | | | | | |
| RP-17 | | | | | | |
| KF- (8 | 9 | 4 | | | | |
| 70. 01 | 1 | | | | | |
| Relinquished By: | Ran | Received By: | w | | | |
| Printed Name | RANDOLAL FLURES | Printed Name Jacks | TAY11 | | | |
| Date/Time: 5 | 119/2023 1740 | Date/Time: 5/14/2-3 | 12:40 | | | |
| Relinquished By: | 7 | Received By: | | | | |
| Printed Name | | Printed Name | | | | |
| Date/Time: | | Date/Time: | | | | |

Ver. 2016-06-27



Alta Environmental

Attn.: Jim Byers

3777 Long Beach Blvd.

Long Beach CA 90807

Report Number 2353935

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460
Project Name Civic Center

Location 1855 Main St. Santa Monica

PO Number WO Number

 Date Received
 05/19/2023
 Date Sampled
 05/08/2023

 Date Analyzed
 05/19/2023
 Sampled By
 Randy Flores

Date Reported 05/19/2023 Total Samples 6

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test F | Report | | | |
|-----------------------------|--|----------------------|---|-------------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | • | (%) | Asbestos Type | (%) |
| 2353935-001 4 | Civic Center 2'x2' Fissured CT, White/Beige, Non- homogeneous | LAYER 1 100% | Mineral Wool Cellulose Fiber Perlite Binder/Filler | 40% 20% 35% 5% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353935-002 5 | Civic Center 2'x2' Fissured CT, White/Beige, Non- homogeneous | LAYER 1 100% | Mineral Wool Cellulose Fiber Perlite Binder/Filler | 40% 20% 35% 5% | None Detected | |
| | Asbestos Present: No | Tota | Il % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353935-003 6 | Civic Center 2'x2' Fissured CT, White/Beige, Non- homogeneous | LAYER 1 100% | Mineral Wool Cellulose Fiber Perlite Binder/Filler | 40% 20% 35% 5% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353935-004 7 | Civic Center 1'x4' Straight Hole CT, Grey/Brown, Non-homogeneous | LAYER 1 100% | Wood Fiber Binder/Filler | 95% 5% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353935-005 8 | Civic Center 1'x4' Straight Hole CT, Grey/Brown, Non-homogeneous | LAYER 1 100% | Wood Fiber Binder/Filler | 95% 5% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |
| 2353935-006 9 | Civic Center 1'x4' Straight Hole CT, Grey/Brown, Non-homogeneous | LAYER 1 100% | Wood Fiber Binder/Filler | 95% 5% | None Detected | |
| | Asbestos Present: No | Tota | Il % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected |

PAGE: 1 of 2



Alta Environmental 3777 Long Beach Blvd. Long Beach CA 90807

Attn.: Jim Byers

Report Number 2353935

Date Received 05/19/2023
 Date Analyzed 05/19/2023
 Date Reported 05/19/2023

Project Number SMSD-23-11460
Project Name Civic Center

Location 1855 Main St. Santa Monica

PO Number WO Number

Date Sampled 05/08/2023 Sampled By Randy Flores

Total Samples 6

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

Test Report

Laboratory IDSample LocationLayer No.Non-AsbestosAsbestosSample No.DescriptionLayer %Components(%)Type(%)

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

CA-ELAP #2823

Analyst - Fred Anappelear

Approved Signatory Cristina E. Tabatt

TESTING UNVLAP Lab Code 500044-0

1508 East 33rd Street Signal Hill, CA 90755

Tel: 562-206-2770

Fax: 562-206-2773

PAGE: 2 of 2



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab) Order No. 2353935

| | CUSTOMER INFORMATION | Turnaround Time | Shipped By | Report Send Via: |
|--------------------------------------|--|-------------------------|-------------|---|
| Company | Alta Env. NVS | Same Day 🗹 🗜 | edex 🗆 | Web 🗆 |
| Address | 3777 Long Beach Blod. | 1 Day 🗆 L | JPS | Email (12/ |
| City/State/Zip | Long Beach eq 1. | 2 Day | JSPS | Fax 🗆 |
| Contact | Jim/Dave | 3 Day 🗆 🗈 | Orop Off DE | Verbal |
| Office Phone | 562-495-5777 | 5 Day 🗆 🗈 | Prop Box 🗆 | Mail 🗆 |
| Cell | | Weekend | Other | Pick up |
| Fax | = 0 | Special Instructions: | | |
| Email | Jim. By eus (PAVT.C | om | | |
| | | INFORMATION | | |
| Project Name: | Civix center | PO Number: | | |
| Project Number: | SMSD-27-11460 | Work Order No.: | | |
| Location: | 1855 Main St. Santamon | Sempled By: | RANDY 7 | DMEZ |
| PL | / | MOLD | | LEAD (Pb) |
| PLM EPA 600/M4 | | Spore Trap | | □ TLC □ |
| PLM 400 Pt. Cour PLM 1000 Pt. Cor | | Tape Lift C | 7.000 | |
| F LW 1000 F L 001 | unt (=0.1%) | Bulk Sample C Swab C | | |
| SAMPLE ID | SAMPLE TYPE | LOCATION | Date | Start Time Avg Volume |
| | / | | Sampled | *************************************** |
| ч | ZXZ fissone C.T. a | vic Center | 5/8/22 | |
| 5 | | | 14 | |
| 6 | — | | | |
| 7 | 1x4 , Straight hole C | т. | | |
| 8 | 7. 2. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. | | | |
| 9 | | J | 1 | |
| - 1 | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| Relinquished By: | RANZOLPH FLOR | Received By: | my Jacki | i tayon |
| Date/Time: 4 | 19/2023 1250 | | J 11 | 2:50 |
| Relinquished By: | 5 | Received By: | 1000 | |
| Date/Time: | | Date/Time: | | |

Page ___ of ___



Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460 Alta Environmental Civic Center **Project Name** 3777 Long Beach Blvd. Long Beach CA 90807 Location Santa Monica Attn.: Jim Byers **PO Number WO Number** Report Number 2353807

Date Received 05/04/2023 **Date Sampled** 05/02/2023 05/11/2023 Randy Flores **Date Analyzed** Sampled By **Date Reported** 05/12/2023 **Total Samples** 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

| | · | Test F | Report | | | |
|-----------------------------|---|---------------------|---|----------------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353807-001 0502-1A | High Roof West Center Built-up Roof (Core) - Membrane, White/Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Cellulose Fiber Bituminous Matrix/Filler Other Non-Fibrous Materia | 5% <1% 75% al 20% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | | ıl %Asbestos: | No Asbestos Detected |
| 2353807-002 0502-1B | High Roof West Center Built-up Roof (Core) - Layered Felt/Tar, Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler | 10% 90% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353807-003 0502-1C | High Roof West Center Built-up Roof (Core) - Mastic, Black, Non-homogeneous | LAYER 1 100% | Cellulose Fiber Bituminous Matrix/Filler | 10% 90% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353807-004 0502-1D | High Roof West Center Built-up Roof (Core) - Insulation, Brown, Non-homogeneous | LAYER 1 100% | Wood Fiber | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353807-005 0502-2A | Large Portion Center Built-up Roof (Core) - Membrane, White/Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Cellulose Fiber Bituminous Matrix/Filler Other Non-Fibrous Materia | 5% <1% 75% al 20% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | l %Asbestos: | No Asbestos Detected |
| 2353807-006 0502-2B | Large Portion Center Built-up Roof (Core) - Mastic, Black, Non-homogeneous | LAYER 1 100% | Cellulose Fiber Fibrous Glass Bituminous Matrix/Filler | 10% 5% 85% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% Tota | ıl %Asbestos: | No Asbestos Detected |

PAGE: 1 of 8



Tel: 562-206-2770 Fax: 562-206-2773

Alta Environmental 3777 Long Beach Blvd. Long Beach CA 90807

Attn.: Jim Byers

Report Number 2353807

Date Received 05/04/2023 **Date Analyzed** 05/11/2023 **Date Reported** 05/12/2023

Project Number SMSD-23-11460 **Project Name** Civic Center Location Santa Monica PO Number **WO Number**

05/02/2023 **Date Sampled** Sampled By Randy Flores

Total Samples 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis** Determination of Asbestos in Bulk Building Materials.

Test Report Layer No. Laboratory ID Sample Location Non-Asbestos **Asbestos** Sample No. Description Layer % Components (%) Type (%) 2353807-007 Large Portion Center 15% 0502-2C Built-up Roof (Core) - Layered LAYER 1 Fibrous Glass None Detected Felt/Tar, Black, Non-homogeneous 100% Bituminous Matrix/Filler 85% Asbestos Present: No Total % Non-Asbestos: 100.0% Total %Asbestos: No Asbestos Detected 2353807-008 Large Portion North Center Fibrous Glass 0502-3A Built-up Roof (Core) - Membrane, LAYER 1 5% None Detected Cellulose Fiber <1% White/Black, Non-homogeneous 100% Bituminous Matrix/Filler 75% Other Non-Fibrous Material 20% Total % Non-Asbestos: 100.0% Total %Asbestos: No Asbestos Asbestos Present: No Detected 2353807-009 Large Portion North Center 15% 0502-3B LAYER 1 Fibrous Glass None Detected Built-up Roof (Core) - Layered Felt/Tar, Black, Non-homogeneous 100% Bituminous Matrix/Filler 85% Asbestos Present: No Total % Non-Asbestos: 100.0% Total %Asbestos: No Asbestos Detected 2353807-010 Large Portion North Center 0502-3C Built-up Roof (Core) - Insulation, LAYER 1 Wood Fiber 100% None Detected Brown, Non-homogeneous 100% Asbestos Present: No Total % Non-Asbestos: 100.0% Total %Asbestos: No Asbestos Detected 2353807-011 West Center 4% 0502-4A Parapet Capsheet - Membrane, LAYER 1 Synthetic Fiber None Detected White, Homogeneous 100% Non-Fibrous Material 96% Asbestos Present: No Total % Non-Asbestos: 100.0% Total %Asbestos: No Asbestos Detected 2353807-012 West Center LAYER 1 Cellulose Fiber 10% None Detected 0502-4B Parapet Capsheet - Mastic, Grey/Black, Homogeneous 100% **Bituminous Matrix** 15% Adhesive Binders/Filler 75% Asbestos Present: No Total % Non-Asbestos: 100.0% Total %Asbestos: No Asbestos Detected

PAGE: 2 of



Civic Center

Santa Monica

Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460 Alta Environmental **Project Name** 3777 Long Beach Blvd. Long Beach CA 90807 Location Attn.: Jim Byers **PO Number**

WO Number Report Number 2353807

Date Received 05/04/2023 **Date Sampled** 05/02/2023 05/11/2023 Randy Flores **Date Analyzed** Sampled By **Date Reported** 05/12/2023 **Total Samples** 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

| | Test Report | | | | | | | | |
|-----------------------------|--|---------------------|--|---------------------|------------------|-------------------------|--|--|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) | | | |
| 2353807-013 0502-5A | South Center Parapet Capsheet - Membrane, White, Homogeneous | LAYER 1 100% | Synthetic Fiber Non-Fibrous Material | 4% 96% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-014 0502-5B | South Center Parapet Capsheet - Mastic, Grey/black, Homogeneous | LAYER 1 100% | Cellulose Fiber Bituminous Matrix Adhesive Binders/Filler | 10% 15% 75% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-015 0502-6A | East Center Parapet Capsheet - Membrane, White, Homogeneous | LAYER 1 100% | Synthetic Fiber Non-Fibrous Material | 4% 96% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-016 0502-6B | East Center Parapet Capsheet - Mastic, Grey/Black, Homogeneous | LAYER 1 100% | Cellulose Fiber Bituminous Matrix Adhesive Binders/Filler | 10% 15% 75% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-017 0502-7A | West Center Kick Sheet w/ Cap - Membrane, White/Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Materia | 5% 65% al 30% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-018 0502-7B | West Center Kick Sheet w/ Cap - Layered Felt/Tar, Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler | 15% 85% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T | otal %Asbestos: | No Asbestos Detected | | | |

PAGE: 3 of



Tel: 562-206-2770 Fax: 562-206-2773

Alta Environmental 3777 Long Beach Blvd. Long Beach CA 90807

Attn.: Jim Byers

Report Number 2353807

Date Received 05/04/2023 05/11/2023 **Date Analyzed Date Reported** 05/12/2023 Project Number SMSD-23-11460 Civic Center **Project Name** Location Santa Monica **PO Number WO Number**

Date Sampled 05/02/2023 Sampled By Randy Flores

Total Samples 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

Determination of Asbestos in Bulk Building Materials

| Test Report | | | | | | | | |
|-----------------------------|---|---------------------|---|-------------------|------------------|-------------------------|--|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | Non-Asbestos Components | (%) | Asbestos Type | (%) | | |
| 2353807-019 0502-7C | West Center Kick Sheet w/ Cap - Roofing Paper, Pink, Non-homogeneous | LAYER 1 100% | Cellulose Fiber | 100% | None Detected | | | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | | |
| 2353807-020 0502-8A | Center Kick Sheet w/ Cap - Membrane, White/Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material | 5% 65% 30% | None Detected | | | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | | |
| 2353807-021 0502-8B | Center Kick Sheet w/ Cap - Layered Felt/Tar, Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler | 15% 85% | None Detected | | | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | | |
| 2353807-022 0502-9A | East Center Kick Sheet w/ Cap - Membrane, White/Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material | 5% 65% 30% | None Detected | | | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | | |
| 2353807-023 0502-9B | East Center Kick Sheet w/ Cap - Layered Felt/Tar, Black, Non-homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Fiiller | 15% 85% | None Detected | | | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | | |
| 2353807-024 0502-10A | West Roof, N/W Built-up Roof w/ Gravel (Core) - Membrane, White/Black, Non- homogeneous | LAYER 1 100% | Synthetic Fiber Bituminous Matrix Other Non-Fibrous Material | 35% 20% 45% | None Detected | | | |
| | Asbestos Present: No | Tota | Il % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected | | |

PAGE: 4 of



1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770

Fax: 562-206-2773

Alta Environmental 3777 Long Beach Blvd. Long Beach CA 90807

Attn.: Jim Byers

Report Number 2353807

Date Received 05/04/2023 05/11/2023 **Date Analyzed**

Date Reported 05/12/2023 Project Number SMSD-23-11460 Civic Center **Project Name** Location Santa Monica **PO Number WO Number**

Date Sampled 05/02/2023 Randy Flores Sampled By

Total Samples 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

| | Test Report | | | | | | | | |
|-----------------------------|--|---------------------|---|-------------------|------------------|-------------------------|--|--|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) | | | |
| 2353807-025 0502-10B | West Roof, N/W Built-up Roof w/ Gravel (Core) - Mastic, Black, Non-homogeneous | LAYER 1 100% | Cellulose Fiber Bituminous Matrix | 5% 95% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-026 0502-11A | Southeast Roof, Center Built-up Roof w/ Gravel (Core) - Cap Sheet, White/Grey/Black, Non- homogeneous | LAYER 1 100% | Cellulose Fiber Bituminous Matrix Non-Fibrous Aggregate | 20% 35% 45% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-027 0502-11B | Southeast Roof, Center Built-up Roof w/ Gravel (Core) - Layered Felt/Tar, Black, Non- homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler | 15% 85% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-028 0502-11C | Southeast Roof, Center Built-up Roof w/ Gravel (Core) - Insulation, Brown, Non-homogeneous | LAYER 1 100% | Wood Fiber | 100% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-029 0502-12A | East Roof, Southeast Built-up Roof w/ Gravel (Core) - Cap Sheet, White/Grey/Black, Non- homogeneous | LAYER 1 100% | Cellulose Fiber Bituminous Matrix Non-Fibrous Aggregate | 20% 35% 45% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected | | | |
| 2353807-030 | East Roof, Southeast | | | | | | | | |
| 0502-12B | Layered Felt/Tar, Black, Non- homogeneous | LAYER 1 100% | Fibrous Glass Bituminous Matrix/Filler | 15% 85% | None Detected | | | | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T (| otal %Asbestos: | No Asbestos Detected | | | |

PAGE: 5 of



05/04/2023

05/11/2023

05/12/2023

Alta Environmental

Attn.: Jim Byers

Date Received

Date Analyzed

Date Reported

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353807

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770

Fax: 562-206-2773

Project Number SMSD-23-11460 Civic Center **Project Name** Santa Monica Location

PO Number WO Number

Date Sampled 05/02/2023 Randy Flores Sampled By

Total Samples 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis** Determination of Asbestos in Bulk Building Materials.

| | | Test F | Report | | | |
|-----------------------------|--|-------------------------|--|----------------------|---------------------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | | (%) | Asbestos Type | (%) |
| 2353807-031 0502-12C | East Roof, Southeast Insulation, Brown, Non-homogeneous | LAYER 1 100% | Wood Fiber | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-032 0502-13 | West Center (Southeast Roof) Vibration Reducer, Grey, Non- homogeneous Asbestos Present: No | LAYER 1 100% Tota | Fibrous Glass Binder/Filler al % Non-Asbestos: | 60% 40% 100.0% | None Detected Total %Asbestos: | No Asbestos |
| | | | | | | Detected |
| 2353807-033 0502-14 | West Center (Southeast Roof) Vibration Reducer, Grey, Non- homogeneous | LAYER 1 100% | Fibrous Glass Binder/Filler | 60% 40% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-034 0502-15 | (East Roof) Southeast Corner Vibration Reducer, Black, Homogeneous | LAYER 1 100% | Synthetic Fiber Binder/Filler | 50% 50% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-035 0502-16 | West Center Sealant, White/Black, Non- homogeneous | LAYER 1 100% | Cellulose Fiber Bituminous Matrix/Filler Other Non-Fibrous Materia | 5% 20% I 75% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-036 0502-17 | Southeast Sealant, White, Homogeneous | LAYER 1 100% | Cellulose Fiber Non-Fibrous Material | 8% 92% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |

PAGE: 6 of



Report Number 2353807

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770

Fax: 562-206-2773

Project Number SMSD-23-11460 Alta Environmental Civic Center **Project Name** 3777 Long Beach Blvd. Long Beach CA 90807 Santa Monica Location Attn.: Jim Byers **PO Number**

Date Received 05/04/2023 **Date Sampled** 05/02/2023 05/11/2023 Randy Flores **Date Analyzed** Sampled By

Date Reported 05/12/2023 **Total Samples** 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis** Determination of Asbestos in Bulk Building Materials.

WO Number

| | | Test F | Report | | | |
|-----------------------------|---|----------------------|--|-------------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No. Layer % | | (%) | Asbestos Type | (%) |
| 2353807-037 0502-18 | East Center Sealant, White, Homogeneous | | Cellulose Fiber Non-Fibrous Material | 8% 92% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-038 0502-19 | Southeast Roof East Center Duct Sealant, Grey, Homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-039 0502-20 | Southeast Roof Southeast Duct Sealant, Grey, Homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-040 | East Roof Southeast | | | | | |
| 0502-21 | Duct Sealant, Grey, Homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-041 0502-22 | West Walk Pad Roof, White/Black, Non- homogeneous | | Cellulose Fiber Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material | 5% <1% 70% 25% | None Detected | |
| | Asbestos Present: No | Tota | il % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |
| 2353807-042 0502-23 | Center Walk Pad Roof, White/Black, Non- homogeneous | LAYER 1 100% | Cellulose Fiber Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material | 5% <1% 70% 25% | None Detected | |
| | Asbestos Present: No | Tota | ıl % Non-Asbestos: | 100.0% | Total %Asbestos: | No Asbestos Detected |

PAGE: 7 of



05/04/2023

05/11/2023

05/12/2023

Alta Environmental

Attn.: Jim Byers

Date Received

Date Analyzed

Date Reported

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353807

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770

Fax: 562-206-2773

Project Number SMSD-23-11460 **Project Name** Civic Center Location Santa Monica

> **PO Number WO Number**

05/02/2023 **Date Sampled** Randy Flores Sampled By

Total Samples 43

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

Determination of Asbestos in Bulk Building Materials.

| Test Report | | | | | | | |
|-----------------------------|--|---------------------|--|------------|------------------|-----|--|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) | |
| 2353807-043 0502-24 | East Walk Pad Roof, White/Black, Non-homogeneous | LAYER 1 100% | Cellulose Fiber Fibrous Glass | 5% <1% | None Detected | | |
| | | | Bituminous Matrix/Filler Other Non-Fibrous Material | 70% 25% | | | |

Asbestos Present: No Total % Non-Asbestos: 100.0% Total %Asbestos: No Asbestos

Detected

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Analyst - Fred Onappelear

Approved Signatory Cristina E. Tabatt

NVLAP Lab Code 500044-0

PAGE: 8 of



1508 E. 33rd Street Signal Hill, CA 90765 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

| (Lab) Order No. | 2352807 |
|-----------------|---------|
|-----------------|---------|

| | CUSTOMER INFORMATION | Turnaround Time | Shipped By Report Send Via: | |
|---|--|------------------------------|--|---------------------|
| Company | Alta Environmental/NV5 | Same Day 🖂 Fee | fex 🗆 Web 🗆 | |
| Address | 3777 Long Beach Blvd., Annex Bldg. | 1 Day 🗆 UP | S 🗆 Email 🖭 | |
| City/State/Zip | Long Beach, AA 90807 | 2 Day 🗆 US | PS 🗆 Fax 🗆 | |
| Contact | Jim Byers | 3 Day 🗆 Dro | p Off 🗹 Verbal 🗆 | |
| Office Phone | 562-425-5777 | 5 Day 🔯 Dro | p Box Mail | |
| Cell | | Weekend □ Oth | er 🗆 Pick up 🖂 | |
| Fax | 562-425-5777 | Special Instructions: | | |
| Email | Jim. Byers (NV5.C | 4 | * | |
| | PROJEC | TINFORMATION | | |
| Project Name: | Civic Center | PO Number: | | |
| Project Number: | The state of the s | Work Order No.: | | - 1 |
| Location: | Santa Manica | Sampled By: | RANDY Flore | |
| PLM EPA 600/M PLM 400 Pt. Cou PLM 1000 Pt. Co | int (<0.25%) NIOSH 7400B | Tape Lift Bulk Sample Swab | LEAD (Pb) Air | Company of the last |
| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Start Time Avg Volum | 25.5 |
| 0502-1 | Built up Roof | Civic Center | Sampled Stop Time Flow Rate (L) | |
| / a | | | 7 | |
| 3 | | | | |
| 1 | Parapet | | | _ |
| 4 | (apsheet | | | |
| 5 | | | | |
| 6 | L | | | |
| 7 | Kich sheet Weap | | | |
| 8 | | | | |
| .9 | | | | į |
| 1 10 | Built up Roof Waravel (core) | 5 | 1 | |
| Relinquished By: | Rosen | Received By: | rr | |
| Printed Name: | RANDY Flures | Printed Name: J4c | 08:00 J | |
| Date/Time: | 5/4/0866 | Date/Time: 5/4/2.2 | 08:00 7 | |
| Relinquished By: | | Received By: | Laboration of the Control of the Con | - 1 |
| Date/Time: | | Date/Time: | Lab Forms | |
| | | | 32 5010 50 50 | |



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-208-2773 Fax services@AQenvlabs.com

| Company: | Alta Environmental | | (Lab) Order No. | 22524 | |
|------------------|--------------------------------|------------------|-----------------|-----------------------------|---------------------------|
| Project Number: | SMSD-23-11460 | | (Lab) Order No. | 23538 | 101 |
| Project Name: | Santa Monica | | | | |
| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time Fli | Avg Volume ow Rate (L) |
| 0502-11 | Built up Roof Warque (core) | Civic Center | 5/2/23 | | |
| 12 | | | 1 | | |
| 13 | Vibration Reducer | | | | |
| 14 | | | | | |
| 13 | 1 | | | | |
| 16 | WHite Sealant | | | | |
| 17 | | | | | |
| /8 | 1 | | | | |
| 19 | Duct Sealout | | | | |
| 20 | | | | | |
| 21 | 4 | | | | |
| 22 | WALK PAD ROOF | | | | |
| 23 | | 1 | | | |
| 1 24 | 1 | 1 | | | |
| | | | 1 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | - | | | | |
| Relinquished By: | Rudle | Received By: 07 | 2mg | | |
| | ZANDY FIDERS | Printed Name: 3/ | 123 0800 J | | |
| Date/Time: | 5/4/2023 0800 | Date/Time: 5/4 | 123 0800 | | |
| Relinquished By: | | Received By: | | | |
| Printed Name: | | Printed Name: | | | |
| Date/Time: | | Date/Time: | | | Lab Farme |



3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353726

Attn.: Jim Byers

Date Received

Date Analyzed

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770

Fax: 562-206-2773

Project Number SMSD-23-11460 **Project Name** Civic Center Survey

1855 Main St. Santa Monica, CA Location

PO Number WO Number

05/04/2023 **Date Sampled** 05/02/2023 Erik Jimenez 05/11/2023 Sampled By

Date Reported 05/11/2023 **Total Samples**

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 **Method of Analysis**

| | | Test F | Report | | | |
|-----------------------------|--|---------------------|---|-------------------|------------------|-------------------------|
| Laboratory ID Sample No. | Sample Location Description | Layer No Layer % | . Non-Asbestos Components | (%) | Asbestos Type | (%) |
| 2353726-001 2-1 | S/W Storage Ext. S/W Skim Coat, White, Homogeneous | LAYER 1 100% | Wood Fiber Calcium Carbonate Gypsum | 5% 25% 70% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T o | otal %Asbestos: | No Asbestos Detected |
| 2353726-002 2-2 | S/W Storage Ext. S/W Skim Coat, White, Homogeneous | LAYER 1 100% | Wood Fiber Calcium Carbonate Gypsum | 5% 25% 70% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T o | otal %Asbestos: | No Asbestos Detected |
| 2353726-003 2-3 | S/W Storage Ext. S/E Skim Coat, White, Homogeneous | LAYER 1 100% | Wood Fiber Calcium Carbonate Gypsum | 5% 25% 70% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T c | otal %Asbestos: | No Asbestos Detected |
| 2353726-004 2-4 | West Center of Bldg N Door Door Sealant, White/ Gray, Non- homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T c | otal %Asbestos: | No Asbestos Detected |
| 2353726-005 2-5 | West Center of Bldg N Door Door Sealant, White/ Gray, Non- homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T o | otal %Asbestos: | No Asbestos Detected |
| 2353726-006 2-6 | West Center of Bldg N Door Door Sealant, White/ Gray, Non- homogeneous | LAYER 1 100% | Non-Fibrous Material | 100% | None Detected | |
| | Asbestos Present: No | Tota | al % Non-Asbestos: | 100.0% T o | otal %Asbestos: | No Asbestos Detected |

PAGE: 1 of 2



05/04/2023

05/11/2023

05/11/2023

Alta Environmental

Attn.: Jim Byers

Date Received

Date Analyzed

Date Reported

3777 Long Beach Blvd. Long Beach CA 90807

Report Number 2353726

1508 East 33rd Street Signal Hill, CA 90755 Tel: 562-206-2770 Fax: 562-206-2773

Project Number SMSD-23-11460
Project Name Civic Center Survey

Location 1855 Main St. Santa Monica, CA

PO Number WO Number

Date Sampled 05/02/2023
Sampled By Erik Jimenez

Total Samples 9

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116

Determination of Asbestos in Bulk Building Materials.

| | | Test Re | eport | | | |
|---------------|---------------------------------|------------------------|----------------------|--------------------|----------------|-------------------------|
| Laboratory ID | Sample Location | Layer No. Non-Asbestos | | Asbestos | | |
| Sample No. | Description | Layer % | Components | (%) | Туре | (%) |
| 2353726-007 | West Center of Bldg | | | | | |
| 2-7 | Door Sealant, White/Cream, Non- | LAYER 1 | | | None Detected | |
| | homogeneous | 100% N | Ion-Fibrous Material | 100% | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To t | tal %Asbestos: | No Asbestos Detected |
| 2353726-008 | West Center of Bldg | | | | | |
| 2-8 | Door Sealant, White/Cream, Non- | LAYER 1 | | | None Detected | |
| | homogeneous | 100% N | Ion-Fibrous Material | 100% | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To t | tal %Asbestos: | No Asbestos Detected |
| 2353726-009 | West Center of Bldg | | | | | |
| 2-9 | Door Sealant, White/Cream, Non- | LAYER 1 | | | None Detected | |
| | homogeneous | 100% N | Ion-Fibrous Material | 100% | | |
| | Asbestos Present: No | Total | % Non-Asbestos: | 100.0% To t | tal %Asbestos: | No Asbestos Detected |

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

CA-ELAP #2823

Analyst - Cristina Tabatt

Approved Signatory Cristina E. Tabatt

TESTING NVLAP Lab Code 500044-0


PAGE: 2 of 2



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab) Order No. 2353726

| | CUSTOMER INFORMATION | Turnaround Time St | hipped By Report Send Via: |
|-----------------|---|-------------------------|---------------------------------|
| Company | Alta Environmental/NV5 | Same Day Fede | x 🗆 Web 🗆 |
| Address | 3777 Long Beach Blvd., Annex E | Bldg. 1 Day 🗆 UPS | □ Email 02/ |
| City/State/Zip | Long Beach, AA 90807 | 2 Day 🗆 USP | S 🗆 Fax 🗆 |
| Contact | Jim Byers | 3 Day 🗆 Drop | Off 🗹 Verbal 🗆 |
| Office Phone | 562-425-5777 | 5 Day 🖾 Drop | Box Mail |
| Cell | | Weekend □ Othe | r 🗆 Pick up 🗆 |
| Fax | 562-425-5777 | Special Instructions: | |
| Email | Jim. Byers CN | V6 | |
| | PRO | OJECT INFORMATION | |
| Project Name: | civic Center | PO Number: | |
| Project Number: | | Work Order No.: | |
| Location: | 1855 Main St. San | ta M. Sampled By: | RANDY Flores |
| P | LM PCM | MOLD | LEAD (Pb) |
| PLM EPA 600/M | B. 유리 및 100 및 | | Air TTLC |
| PLM 400 Pt. Cou | | | Paint Wipe |
| PLM 1000 Pt. Co | ount (<0.1%) | □ Bulk Sample □ Swab □ | Wipe Soil |
| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Start Time Avg Volume |
| | 8 40-00-417 (100-65) | 1 134 1350000000 | Sampled Stop Time Flow Rate (L) |
| 2-1 | Skim Coat | Civic Center | 5/2/23 |
| 7-2 | | | |
| 2 - 3 | | | |
| 2-4 | Door Seglant | | |
| 2-5 | | | |
| 2.6 | 1 | | |
| 2-7 | Sealant | | |
| 2-8 | 1 | | |
| 2-9 | 1 | 1 | 7 |
| | - 0 1 | | |
| Relinquished By | The other | Received By: | |
| Printed Name: | RANDY Flores | Printed Name: Jackie T. | TYPA |
| Date/Time: | 2/4/2023 0860 | Date/Time: 5/4/23 | 08:00 |
| Relinquished By | | Received By: | |
| | | | |
| Date/Time: | | Date/Time: | Lab Forms |
| | | | Ver. 2016-06-27 |





Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460

Project Name: Santa Monica Civic Center

Location: 1855 Main St. Santa Monica, CA

Report Number: 2353966

 Date Received:
 5/22/2023

 Date Analyzed:
 5/22/2023

 Date Reported:
 5/22/2023

Date Sampled: 5/9/2023 Sampled By: Erik Jimenez

Total Samples: 6

Analytical Method: EPA 7420/3050 Reporting Limit: 5.0 µg Pb

| Lead (Pb) in Paint by Flame AAS | | | | | |
|---------------------------------|--------------------------------|----------------------|--------------------------------|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | |
| 2353966-001 4006 | Paint Chip- 3rd Floor/Cat Walk | 0.1083 | 1300 | | |
| 2353966-002 4007 | Paint Chip- 3rd Floor/Cat Walk | 0.1039 | < 48 | | |
| 2353966-003 4008 | Paint Chip- 3rd Floor/Cat Walk | 0.1018 | < 49 | | |
| 2353966-004 4009 | Paint Chip- 3rd Floor/Cat Walk | 0.1014 | 88000 | | |
| 2353966-005 4010 | Paint Chip- 3rd Floor/Cat Walk | 0.1073 | 61 | | |
| 2353966-006 4011 | Paint Chip- 3rd Floor/Cat Walk | 0.0524 | 330000 | | |

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.


CA ELAP Cert #2823



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

| (Lab) Order No. 2 | 353966 |
|-------------------|--------|
|-------------------|--------|

| | CUSTOMER INF | ORMATION | | Turnaround | Time | Shinn | ed By | Pene | rt Send Via: | -0 |
|--|--------------------|--------------|---------|---------------------------|------------|------------|----------|-------------|------------------|---------------|
| Company | Alta Environmen | tal/NV5 | | Same Day | | Fedex | | Web | | ACC. |
| Address | 3777 Long Beach | Blvd., Anne: | x Bidg. | 1 Day | 6 | UPS | | Email | 110000 | |
| City/State/Zip | Long Beach, Ca | 90807 | | 2 Day | | USPS | | 0.000 | | - |
| Contact | Jim Byers | | | 3 Day | | Drop Of | | Verbal | | 7 |
| Office Phone | 562-495-5777 | | | 596 | 02 | Drop Bo | | Mail | The second | - |
| Cell | | | | Weekend | | Other | | Pick up | | |
| Fax | 562-495-5877 | | | Special In | structions | 3: | | | | 100 |
| Email | jim.byers@nv5.c | mo | | Layered a | nalysis | on drywall | joint co | mpound | | |
| | | | | cc therese | .rizarri@r | | | hack@nv5.co | m on resu | Its |
| | | | ROJECT | INFORMA | TION | | | | sol leave | S31. |
| Project Name: | Santa Moinca Civio | Center | | PO Numbe | r. | | | | | |
| Project Number: | SMSD-23-11460 | | A4 . | Work Orde | r No.: | | | | | - 0 |
| Location: | 1855 Main S | 9 Sertal | Driza | Sampled B | y: | | Erk | Jimenes | 4 | |
| PL | .M | PCM | | Т- | MOLD | | 1 | LEAD | (Ph) | |
| PLM EPA 600/M4 | | NIOSH 7400 | A D | S | pore Trap | | Air | | TTLC | 0 |
| PLM 400 Pt. Cou | | NIOSH 7400 | | | spe Lift | | Paint | 488 | | 555 |
| PLM 1000 Pt. Co | unt (<0.1%) | w/ TWA | | | ulk Sample | | Wipe | | | |
| SAMPLE ID | SAMPLE T | VDE | | LOCAT | dawi | | Soil | 0 | | |
| COMMITTEE ID | SPARIT CE 1 | 17.0 | | LUCAT | ION | | Sample | ********* | Avg Flow Rate | Volume (L) |
| 4006 4007 4008 4009 4010 4011 | Point C | hip 3 | Ka (Jun | - /cot (| -a) k/ | | 5-9.3 | 3 | | |
| Relinquished By: | Eaile Jim | an E | | Pageline P | e cha | N. C. Art | h. | | | |
| | | | | Received B | | megn | | | | 10 |
| Printed Name Date/Time: 5 | Prik Jine | 100 | | Printed Nar Date/Time: | | Stine Pa | | Ilee | | |
| Relinquished By: | aa-03 | 100 | | Received B | | 5/22 | 100 | 1100 | | |
| Printed Name | | | | Printed Nar | | | | | | |
| Date/Time: | | | | Date/Time: | | | | | | |
| - Color Facility | | | | Dotter Hillie. | | | | | | |





Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460

Project Name: Santa Monica Civic Center

Location: 1855 Main St. Santa Monica, CA

Report Number: 2353965

 Date Received:
 5/22/2023

 Date Analyzed:
 5/22/2023

 Date Reported:
 5/22/2023

Date Sampled: 5/9/2023 Sampled By: Erik Jimenez

Total Samples: 5

Analytical Method: EPA 7420/3050 Reporting Limit: 5.0 µg Pb

| Lead (Pb) in Paint by Flame AAS | | | | |
|---------------------------------|---------------------------------|----------------------|--------------------------------|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | |
| 2353965-001 4001 | Paint Chip- Projector Rooms/Ext | 0.1061 | 810 | |
| 2353965-002 4002 | Paint Chip- Projector Rooms/Ext | 0.1022 | 1900 | |
| 2353965-003 4003 | Paint Chip- Projector Rooms/Ext | 0.1050 | 130 | |
| 2353965-004 4004 | Paint Chip- Projector Rooms/Ext | 0.1028 | 4900 | |
| 2353965-005 4005 | Paint Chip- Projector Rooms/Ext | 0.1036 | 53000 | |

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

CA ELAP Cert #2823



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

| (Lab) Order No. | 2353965 | |
|-----------------|---------|--|
|-----------------|---------|--|

| | CUSTOMER INFO | PMATION | Turnaround Tim | | Shipped | Ву | | Report | Send Via: | |
|-------------------------------------|--------------------|--------------------|----------------|---------------|------------|--------|--------|------------|------------|--------|
| | Alta Environmental | | Same Day | | Fedex | | | Web | | - 1 |
| Company | 3777 Long Beach E | | 1 Day | | UPS | | | Email | er) | |
| Address | | | 2 Day | | USPS | | | Fax | | |
| City/State/Zip | Long Beach, Ca 90 | 1007 | 3 Day | | Drop Off | | | Verbal | | |
| Contact | Jim Byers | | 104 E | 24 (4 | Drop Box | 0 | | Mail | _ | |
| Office Phone | 562-495-5777 | | コンプ ニ | 36 3 | Other | | | Pick up | - | |
| Cell | | | 1100100110 | | Outer | | _ | 1 ion up | _ | |
| Fax | 562-495-5877 | | Special Instru | | doougliji | ales e | omn | hound | | |
| Email | jim_byers@nv5.cor | n | Layered anal | ysis on | arywaiiiji | ount o | chac | k@nv5.com | n on resul | ts |
| | | PRO JEC | T INFORMATIO | | com and d | aviu.s | Citaci | agenro.con | | |
| Designat Mannas | Santa Moinca Civic | | PO Number: | | | | | | | |
| Project Name: | | Center | Work Order No | 62 | | | | | | |
| Project Number: Location: | | Sorta Monico C | | | | En | E | Jimes | 2 | |
| | | SHOP DUTY THE | 161 | | _ | - | | LEAD (| | |
| | LM | PCM NIOSH 7400A | 7.55-0.00 | OLD e Trap | _ | A | | LEAD | TTLC | |
| PLM EPA 600/M | | | | | 0 | Pa | | 43 | | |
| PLM 400 Pt. Co. PLM 1000 Pt. Co. | | W/TWA | 38.500.500 | Sample | | Wi | 5.55 | | | |
| PLM 1000 Pt. C | ount (<0.1%) | W.IWA | Swa | | | Sc | 0.00 | | | |
| SAMPLE ID | SAMPLE TY | PE | LOCATION | | | De | te | Start Time | Avg | Volume |
| | | | | | | Sam | pled | Stop Time | Flow Rate | (L) |
| 4004 | | | | | | | 0000 | | | |
| 4001 | Paint Ch | in Pray | ctor row | ns/F | tx | 5.9 | . 23 | | | |
| 4002 | | | 1 | | | | | | | |
| 4003 | | | | | | | | | | |
| 4004 | | | | | | | | | | |
| 4005 | 1 | | | | | | | | | |
| 4000 | | | 0 | | | | | | | |
| | 1 | | | | | | | | | |
| | | - | | | | | | | | |
| | | | | | - | | | | | |
| | | | | | | | | | | |
| Relinquished B | v. Edde Sim | nal | Received By: | a | muel | 971 A | 4- | | | |
| | Brib Sims | | Printed Name | | ustine | Pal | do | | | |
| Printed Name Date/Time: \$ | | 00 | Date/Time: | | 5/22/2 | | | 00 | | |
| Relinquished B | | 70 | Received By: | | 1 | | | | | |
| Printed Name | | T. T. T. C. T Dy | Printed Name | 1 | | | | | | |
| Date/Time: | | | Date/Time: | | | | | | | |
| | | | | | | | | | | |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807

Attention: Jim Byers

Project Number: SMSD-23-11460
Project Name: Civic Center Survey

Location: 1855 Main St. Santa Monica

Report Number: 2353802

 Date Received:
 5/8/2023

 Date Analyzed:
 5/15/2023

 Date Reported:
 5/15/2023

Date Sampled: 5/4/2023 Sampled By: Erik Jimenez

Total Samples: 53

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 µg

| | Lead (Pb) in P | aint by Flame AAS | |
|---------------------|-------------------------------------|----------------------|--------------------------------|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) |
| 2353802-001 1 | Paint Chip- Civic Center Main Floor | 0.1013 | 600 |
| 2353802-002 2 | Paint Chip- Civic Center Main Floor | 0.1038 | 2000 |
| 2353802-003 3 | Paint Chip- Civic Center Main Floor | 0.1024 | < 49 |
| 2353802-004 4 | Paint Chip- Civic Center Main Floor | 0.1068 | 120 |
| 2353802-005 5 | Paint Chip- Civic Center Main Floor | 0.1078 | 160 |
| 2353802-006 6 | Paint Chip- Civic Center Main Floor | 0.1019 | 61 |
| 2353802-007 7 | Paint Chip- Civic Center Main Floor | 0.1043 | < 48 |
| 2353802-008 8 | Paint Chip- Civic Center Main Floor | 0.1080 | < 46 |
| 2353802-009 9 | Paint Chip- Civic Center Main Floor | 0.1050 | < 48 |
| 2353802-010 10 | Paint Chip- Civic Center Main Floor | 0.1025 | < 49 |
| 2353802-011 11 | Paint Chip- Civic Center Main Floor | 0.1001 | < 50 |
| 2353802-012 12 | Paint Chip- Civic Center Main Floor | 0.1001 | 18000 |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460
Project Name: Civic Center Survey
Location: 1855 Main St.

Santa Monica

| Lead in Paint by Flame AAS | | | | | | |
|----------------------------|-------------------------------------|----------------------|--------------------------------|--|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | | |
| 2353802-013 13 | Paint Chip- Civic Center Main Floor | 0.1018 | < 49 | | | |
| 2353802-014 14 | Paint Chip- Civic Center Main Floor | 0.1049 | 260 | | | |
| 2353802-015 15 | Paint Chip- Civic Center Main Floor | 0.1018 | 160 | | | |
| 2353802-016 16 | Paint Chip- Civic Center Main Floor | 0.1019 | < 49 | | | |
| 2353802-017 17 | Paint Chip- Civic Center Main Floor | 0.1035 | < 48 | | | |
| 2353802-018 | Paint Chip- Civic Center Main Floor | 0.1019 | < 49 | | | |
| 2353802-019 19 | Paint Chip- Civic Center Main Floor | 0.1068 | 310 | | | |
| 2353802-020 | Paint Chip- Civic Center Main Floor | 0.1028 | < 49 | | | |
| 2353802-021 | Paint Chip- Civic Center Main Floor | 0.1080 | < 46 | | | |
| 2353802-022 | Paint Chip- Civic Center Main Floor | 0.1061 | < 47 | | | |
| 2353802-023 24 | Paint Chip- Civic Center Main Floor | 0.0957 | 84 | | | |
| 2353802-024 25 | Paint Chip- Civic Center Main Floor | 0.1084 | < 46 | | | |
| 2353802-025 26 | Paint Chip- Civic Center Main Floor | 0.1017 | 64 | | | |
| 353802-026 7 | Paint Chip- Civic Center Main Floor | 0.1025 | < 49 | | | |
| 2353802-027 28 | Paint Chip- Civic Center Main Floor | 0.1069 | 110 | | | |
| 353802-028 9 | Paint Chip- Civic Center Main Floor | 0.1008 | < 50 | | | |
| 353802-029 0 | Paint Chip- Civic Center Main Floor | 0.1050 | 440 | | | |
| 2353802-030 | Paint Chip- Civic Center Main Floor | 0.1071 | < 47 | | | |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460
Project Name: Civic Center Survey
Location: 1855 Main St.

Santa Monica

| | Lead in Paint I | by Flame AAS | |
|---------------------|-------------------------------------|----------------------|--------------------------------|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) |
| 2353802-031 33 | Paint Chip- Civic Center Main Floor | 0.1022 | < 49 |
| 2353802-032 34 | Paint Chip- Civic Center Main Floor | 0.1043 | < 48 |
| 2353802-033 85 | Paint Chip- Civic Center Main Floor | 0.1014 | < 49 |
| 2353802-034 36 | Paint Chip- Civic Center Main Floor | 0.1015 | < 49 |
| 2353802-035 37 | Paint Chip- Civic Center Main Floor | 0.1058 | < 47 |
| 2353802-036 88 | Paint Chip- Civic Center Main Floor | 0.1012 | 300 |
| 2353802-037 39 | Paint Chip- Civic Center Main Floor | 0.1010 | < 50 |
| 2353802-038 40 | Paint Chip- Civic Center Main Floor | 0.1060 | 61 |
| 2353802-039 11 | Paint Chip- Civic Center Main Floor | 0.1036 | 1800 |
| 2353802-040 12 | Paint Chip- Civic Center Main Floor | 0.0515 | < 97 |
| 2353802-041 43 | Paint Chip- Civic Center Main Floor | 0.1002 | < 50 |
| 2353802-042 45 | Paint Chip- Civic Center Main Floor | 0.1051 | < 48 |
| 2353802-043 46 | Paint Chip- Civic Center Main Floor | 0.1031 | < 48 |
| 2353802-044 17 | Paint Chip- Civic Center Main Floor | 0.1046 | < 48 |
| 2353802-045 48 | Paint Chip- Civic Center Main Floor | 0.1053 | < 47 |
| 2353802-046 | Paint Chip- Civic Center Main Floor | 0.1031 | < 48 |
| 2353802-047 | Paint Chip- Civic Center Main Floor | 0.1014 | < 49 |
| 353802-048 | Paint Chip- Civic Center Main Floor | 0.1051 | < 48 |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460
Project Name: Civic Center Survey
Location: 1855 Main St.

Santa Monica

| | Lead in Paint by Flame AAS | | | | | | |
|---------------------|-------------------------------------|----------------------|--------------------------------|--|--|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | | | |
| 2353802-049 53 | Paint Chip- Civic Center Main Floor | 0.1068 | < 47 | | | | |
| 2353802-050 54 | Paint Chip- Civic Center Main Floor | 0.1069 | < 47 | | | | |
| 2353802-051 55 | Paint Chip- Civic Center Main Floor | 0.0895 | 2000 | | | | |
| 2353802-052 56 | Paint Chip- Civic Center Main Floor | 0.0518 | 150 | | | | |
| 2353802-053 57 | Paint Chip- Civic Center Main Floor | 0.0483 | 2100 | | | | |

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

CA ELAP Cert #2823

Approved Signatory- Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

| | | (Lau) | Oluer No. | 2353 | 805 | | J | | | |
|---|--|--------------------------|-----------|--------------|--|---------|------------------------------|-------------------------|------------------|---------------|
| | CUSTOMER | NFORMAT | ION | Turnaround | Time | Shine | ed By | Reny | ort Send Vis | 41 |
| Company | | NV5 | | Same Day | | Fedex | | | b 🗆 | |
| Address | A STATE OF THE PARTY OF THE PAR | g Beach B | | 1 Day | | UPS | | E 40-0999743 | | |
| City/State/Zip | Long E | Beach, CA | 90807 | 2 Day | | USPS | | 50,000,000,000 | | |
| Contact | Jim 0 | yess | | 3 Day | | Drop Of | | Verba | | |
| Office Phone | 56 | 2/495-577 | 7 | 5 Day | 0 | Drop Bo | × 🗅 | Mai | - CONTRACTOR | |
| Cell | | | | Weekend | | Other | | Pick up | | |
| Fax | | 2/495-587 | | Special In | structio | ns: | | | | |
| Email | Jim Bye | ISOM. | S.Cur | - | | | | | | |
| | | | | INFORMAT | ION | | | | | |
| Project Name: | Civic Cente | v Surv | ey | PO Number | | | | | | |
| Project Number: | 5m5D-23 | -11460 | | Work Order | No.: | | | | | |
| Location: | 1855 Min | 51. SUM | a Mine | Sampled By | | 53 | Brib | Jine | ME | |
| PLM EPA 600/M4 PLM 400 Pt. Cou PLM 1000 Pt. Cou | nt (<0.25%) | NIOSH NIOSH w/ TW/ | 7400B 🗆 | Sp Ta | MOLD ore Trap pe Lift ilk Sampl | | Air Paint Wipe Soll | LEAD | (Pb) TTLC | 0 |
| SAMPLE ID | SAMPLE | TYPE | | LOCATIO | 104 | | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volume (L) |
| 1 | Paint C | いか | (ivi) | cester, | mail | flor | - | | 1 1011 1 10110 | 107 |
| ے | | - 1 | | | Former's Microsoft and | | | | | |
| 3 | | | | | | | | | | |
| 9 | | | | | | | | | | |
| 5 | | | | | | | | | | |
| 6 | | | | | | | | | | |
| 7 | | | | | | | | | | |
| 6 | | | | | | | | | | |
| 9 | | | | | | | | | | |
| 10 | | | | 1 | | | | | | |
| elinquished By | al Joen | ,2 | | Received By: | 9 | 5/8/2 | Jacki | e TAYA | 4 | |
| ste/Time: 5-7 | .93 | 1140 | | Date/Time: | | 5/8/2 | 2 08 | 00 |) | |

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com



Company: NV5
Project Number: SMSD~ 23-11460

Analysis:

TAT:

(Lab) Order No. 2353802

| SAMPLE ID | SAMPLE TYPE | | LOCATION | | Date Sample | | Avg Flow Rate | Volum (L) |
|-------------------|-------------|---------|-------------|------------|----------------|---------|------------------|--------------|
| 11 | Point Chip | Civic C | enter 1 | noin flour | 5-4-2 | 3 | | |
| 12 | 1 | | | | | | | |
| 13 | | | | | | | | |
| 19 | | | | | | | | |
| 15 | | | | | | | | |
| 16 | | | | | | | | |
| 17 | | | | | | | | |
| 18 | | | | | | | | |
| 19 | | | | | | | | |
| 90 | | | | Y | | | | |
| 21 | | | | | | | | |
| ja | | | | | | | | |
| 24 | | | | | | | | |
| 25 | | | | | | | | |
| 26 | | | | | | | | |
| 27 | | | | | | | | |
| 26 | J | | | | | | | |
| 29 | | | | | | | | |
| 30 | | | | | | | | |
| 32 | 1 | |) | | 1 | | | |
| elinquished By: S | in Jine = | | eceived By: | 90 | 18123 | Jackie- | 7419 | |

Lab Forms Ver. 082411

Page 2 of 9

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com



Project Number: SMSD-23-//460

Project Number: Civic Co. slop Co. slop

Analysis:

TAT:

Center Scruey (Lab) Order No. 2353802

| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volum (L) |
|-----------|-------------|------------------|----------------------|-------------------------|------------------|--------------|
| 33 | Point Chip | Civic Center Sur | vey 5.4-23 | | | |
| 34 | | | / / | | | |
| 35 | | | | | | |
| 36 | | | | | | |
| 77 | | | | | | |
| 38 | | | | | | |
| 39 | | | | | | |
| 90 | | | | | 5 - 1 | |
| 41 | | | | | | |
| 42 | | | | | | |
| 43 | | | | | | |
| 45 | | | | | | |
| 46 | | | | | | |
| 47 | | | | | | |
| 48 | | | | | | |
| So | 10 | | | | | |
| 71 | | | | | | |
| 52 | | | | | | |
| 53 | 1 | 1 | 1 | | | |
| | | | | | | |
| | 4.27 N | Received By: C | 17-20 Jack 5/8/23 | Te TAY. | 11 | |

Ver. 082411



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

| Company: | Alta Environmental/NV5 | (Lab) Order No. | 2253002 | |
|-----------------|---------------------------|-----------------|---------|--|
| Project Number: | SMSD-23-11460 | (Lab) Order No. | C222807 | |
| Project Name: | Santa Moinca Civic Center | | | |

| SAMPLE ID | SAMPLE TYPE | | LOCA | TION | | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volum (L) |
|------------------|-------------|-------|-----------------------|-------|-------|-----------------|-------------------------|------------------|--------------|
| 59 | Point Chip | Civic | center | ran | for | 5-4-23 | | | |
| 55 | 1 | | | 1 | | 1 | | | |
| 56 | | | | | | | | | |
| 57 | 1 | | < | | | | | | |
| NO Sore | + 23.314 | 14.49 | | | | | | | |
| NO SUPP | 13 03,04 | 1 | | _ | | | | | |
| | | | | _ | | | | | |
| | | + | | - | | | | | |
| | | - | | | | | | | |
| | | + | | | _ | | | | |
| | | - | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | + | | | | | | | |
| | | + | | | | | | | - |
| | | + | | | | | | | |
| | | - | | | | | | | |
| | | | | | | | | | |
| elinquished By: | Erst Sineux | | Received | 12000 | gran | | 20 | | |
| rinted Name | ZI SIMEUN | 140 | Printed Na | | Flota | ic Taya | 1 | | |
| telinquished By: | 7.27 1 | M | Date/Time Received | | 5/8/2 | 08-0 | 0 | _ | _ |
| rinted Name | | | Printed Na | | | | | | |
| ate/Time: | | | Date/Time | | | | | | |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460
Project Name: Civic Center Survey
Location: 1855 Main St.

Santa Monica

Report Number: 2353801


Date Received: 5/8/2023 Date Sampled: 5/3/2023
Date Analyzed: 5/15/2023 Sampled By: Eirk Jimenez

Date Reported: 5/15/2023 Total Samples: 15

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 µg

| | Lead (Pb) in P | aint by Flame AAS | |
|----------------------|-----------------------------------|----------------------|--------------------------------|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) |
| 2353801-001 PC-1 | Paint Chip- Civic Center Basement | 0.0306 | 470 |
| 2353801-002 PC-2 | Paint Chip- Civic Center Basement | 0.0324 | < 150 |
| 2353801-003 PC-5 | Paint Chip- Civic Center Basement | 0.0818 | 250 |
| 2353801-004 PC-6 | Paint Chip- Civic Center Basement | 0.1004 | 250 |
| 2353801-005 PC-7 | Paint Chip- Civic Center Basement | 0.1002 | 250 |
| 2353801-006 PC-8 | Paint Chip- Civic Center Basement | 0.1006 | 80 |
| 2353801-007 PC-11 | Paint Chip- Civic Center Basement | 0.0831 | 63 |
| 2353801-008 PC-12 | Paint Chip- Civic Center Basement | 0.1039 | 880 |
| 2353801-009 PC-13 | Paint Chip- Civic Center Basement | 0.0440 | 550 |
| 2353801-010 PC-14 | Paint Chip- Civic Center Basement | 0.0395 | 740 |
| 2353801-011 PC-15 | Paint Chip- Civic Center Basement | 0.0476 | < 110 |
| 2353801-012 PC-16 | Paint Chip- Civic Center Basement | 0.1026 | < 49 |





Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460
Project Name: Civic Center Survey
Location: 1855 Main St.

Santa Monica

| Lead in Paint by Flame AAS | | | | | | |
|----------------------------|---|----------------------|--------------------------------|--|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | | |
| 2353801-013 PC-17 | Paint Chip- Civic Center Basement | 0.0544 | 1300 | | | |
| 2353801-014 PC-18 | Paint Chip- Civic Center Basement | 0.0740 | 280000 | | | |
| 2353801-015 PC-19 | Paint Chip- Civic Center Basement- Not Submitted | | | | | |

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results

CA ELAP Cert #2823

Approved Signatory- Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQerviabs.com

| | | (Lab) C | Order No. | 235 | 3801 | | | | | |
|-------------------|--------------|-----------|-----------|-------------|-----------|---|-----------------|---|-------------|--------|
| | CUSTOMER INF | ORMATI | ON | Turnaround | Time | Shippe | ed By | Repo | rt Send Vla | c |
| Company | | NV5 | | Same Day | | Fedex | | 1 1 1 1 1 1 1 1 1 1 | | |
| Address | 3777 Long | Beach Bo | ulevard | 1 Day | | UPS | | Email | | |
| City/State/Zip | Long Bea | ach, CA 9 | 0807 | 2 Day | | USPS | | 1 1 1 1 1 1 1 1 1 1 | | |
| Contact | Jim B) | cers | | 3 Day | | Drop Off | | Verbal | | |
| Office Phone | 562/ | 495-5777 | | 5 Day | 3 | Drop Bo | 11777 | Mail | | |
| Cell | | | | Weekend | | Other | | Pick up | | |
| Fax | 562/ | 495-5877 | | Special In | | | - | T ron op | | |
| Email | Jim Bye | N PO N | VI.COM | | | | | | | |
| | | | | INFORMA | TION | | | | | |
| Project Name: | Civic conte | | vey | PO Number | C. | | | | | |
| Project Number: | SMSD-B- | 11460 | | Work Order | No.: | | | | | |
| Location: | 1855 Mains | 51. Son | te monita | Sampled By | y: | | Erila | Dina | 2 | |
| PL | 0.54 | | PCM | | MOLD | | | LEAD | (Pb) | |
| PLM EPA 600/M4- | | NIOSH 7 | | | pore Trap | A 100 A | Air | | TTLC | |
| PLM 400 Pt. Count | | NIOSH 7 | | 100 | ape Lift | | Paint | 100 | | |
| PLM 1000 Pt. Cour | nt (<0.1%) | w/ TVVA | | B | ulk Samp | le 🗆 | Wipe | | | |
| SAMPLE ID | SAMPLE TY | PE | | LOCATI | ON | | Date Sampled | Start Time Stop Time | Avg | Volume |
| DC- 1 | Dist of | | - | | | | | Stop Time | Flow Rate | (L) |
| 12-1 | Paint Ch | P | CIVIC . | conter. | baser | 4nt | 5-303 | 100000000000000000000000000000000000000 | | |
| -2 | | | | | | | | | | |
| -5 | | | | | | | | | | |
| 1-6 | | | | | | | | | | |
| -7 | | | | | | | | | | |
| -8 | | | | | | | | | | |
| -11 | | | | | | | | | | |
| 1-12 | | | | | | | | | | |
| - 13 | | | | | | | | | | |
| - 14 | 7 | | | | | | | | | |
| Relinquished By: | vid In | | | Received By | | maya, | Jack | ic TAYA | 11 | |
| Date/Time: J. 7 | -23 11 | 44 | | Date/Time: | _ | 1. 0. 5/8 | 2/23 | 08:00 |) | |

Lab Forms Ver. 082411

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com



Company: NV5 Analysis: Project Number: TAT: Project Name: (Lab) Order No. 2353801 SAMPLE ID SAMPLE TYPE LOCATION Start Time Avg Volume Sampled Stop Time Flow Rate (L) Cilic conter basement Point Chro 10 Sample # 3,49,10 Relinquished By Collet June Received By: lackie TAYAA 1144 Date/Time: Date/Time:

Page 2 of 2

Lab Forms Ver. 082411



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807

Attention: Jim Byers

Report Number: 2353800

 Date Received:
 5/8/2023

 Date Analyzed:
 5/15/2023

 Date Reported:
 5/15/2023

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 μg

Project Number: SMSD-23-11460


Project Name: Santa Monica Civic Survey

Location:

Date Sampled: 5/5/2023 Sampled By: Erik Jimenez

Total Samples: 14

| Lead (Pb) in Paint by Flame AAS | | | | | | | |
|---------------------------------|-----------------------|----------------------|--------------------------------|--|--|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | | | |
| 2353800-001 1 | Paint Chip- Mezzanine | 0.1029 | < 49 | | | | |
| 2353800-002 2 | Paint Chip- Mezzanine | 0.1074 | < 47 | | | | |
| 2353800-003 3 | Paint Chip- Mezzanine | 0.1014 | 180 | | | | |
| 2353800-004 1 | Paint Chip- Mezzanine | 0.1015 | 86 | | | | |
| 2353800-005 | Paint Chip- Mezzanine | 0.0922 | 92 | | | | |
| 2353800-006 | Paint Chip- Mezzanine | 0.0893 | < 56 | | | | |
| 2353800-007 | Paint Chip- Mezzanine | 0.1038 | 1900 | | | | |
| 353800-008 | Paint Chip- Mezzanine | 0.1042 | 2700 | | | | |
| 2353800-009 | Paint Chip- Mezzanine | 0.1061 | < 47 | | | | |
| 2353800-010 0 | Paint Chip- Mezzanine | 0.1011 | 1700 | | | | |
| 353800-011 1 | Paint Chip- Mezzanine | 0.1078 | 710 | | | | |
| 353800-012 2 | Paint Chip- Mezzanine | 0.1063 | 2100 | | | | |





Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460

Project Name: Santa Monica Civic Survey

Location:

| Lead in Paint by Flame AAS | | | | | | | |
|----------------------------------|-----------------------|----------------------|--------------------------------|--|--|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | | | |
| 2353800-013 Paint Chip- Mezzanin | | 0.1016 | 2900 | | | | |
| 2353800-014 14 | Paint Chip- Mezzanine | 0.1023 | 1700 | | | | |

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

CA ELAP Cert #2823

Approved Signatory- Cristina E. Tabat



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab) Order No. 2353800

| | | [[| | | 2.77 | | | Cond Wise | 2. |
|-----------------|--|--|--------|--|----------|--------------|------------|-----------|--------|
| | CUSTOMER INF | and the second s | | Turnaround Time | 30000 | ed By | 1000 | Send Via: | |
| Company | Alta Environment | | 3 | Same Day | Fedex | | Web | | |
| Address | 3777 Long Beach | AND RESIDENCE OF THE PARTY OF T | Bldg. | 1 Day | UPS | | Email | EE | |
| City/State/Zip | Long Beach, Ca 9 | 90807 | | 2 Day | USPS | | Fax | | |
| Contact | Jim Byers | | | 3 Day | Drop Of | | Verbal | | |
| Office Phone | 562-495-5777 | | | 5 Day | Drop Bo | | Mail | | |
| Cell | Comment of the Commen | | | Weekend | Other | | Pick up | | |
| Fax | 562-495-5877 | The | | Special Instructions: | | | | | |
| Email | jim_byers@nv5.co | om: | | Layered analysis o | | | | | |
| SCASH - | | | | cc therese.rizarri@n5 | .com and | david.schad | k@nv5.co | n on resu | lts |
| | | PI | ROJECT | INFORMATION | | | | _ | _ |
| Project Name: | Santa Moinca Civid | Center | | PO Number: | | | | | _ |
| Project Number: | SMSD-23-11460 | | | Work Order No.: | | | - | . , | |
| Location: | | | | Sampled By: | | Poll | Simen | 66 | |
| PI | LM | PCN | A | MOLD | 70-10 | | LEAD | | |
| PLM EPA 600/M- | 70.7 | NIOSH 7400 | | Spore Trap | | Air | | TTLC | |
| PLM 400 Pt. Cou | int (<0.25%) | NIOSH 7400 | | Tape Lift | | Paint | 8 | | |
| PLM 1000 Pt. Co | ount (<0.1%) | w/TWA | | Bulk Sample | | Wipe Soil | | | |
| | 0,110,57 | une I | | Swab | | Date | Start Time | Ava | Volume |
| SAMPLE ID | SAMPLE T | TPE | | LUCATION | | Sampled | Stop Time | | (L) |
| | | | | | | Campio | | | - |
| | Point ch | 200 | 1100 | Forine | | 5-5-22 | | | |
| - | FOUR CE | 42 | PIEC | TOPING | | 13 | | | |
| 9 | | | | | | - | | | |
| 3 | | | 2 | | | | | | |
| И | | | | | | | | | |
| 7 | | 1 | | Tu Tu | | | | | |
| 6 | | | | | | 1/ | | | |
| 9 | | | | | | + | | | |
| | | | | | _ | + | | | |
| 6 | | | | | | - | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |
| | Erik Jin | 0.02 | | Received By: | man | Y | | | |
| Printed Name | Erik Jimne | 2 | | Printed Name | Jan | kic TAY. | 11 | | |
| Date/Time: S - | 7.23 | 1148 | | Date/Time: | 5/8/20 | 08:00 | 7 | - | |
| Relinquished By | | | | Received By: | - 0 | | 515 | 7 | |
| Printed Name | | | | Printed Name | | | | | |
| Date/Time: | | | | Date/Time: | | | | | |



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

Company: Alta Environmental/NV5

Project Number: SMSD-23-11460

Project Name: Santa Moinca Civic Center

(Lab) Order No. 2353800

| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volum (L) |
|------------------|-----------------|---------------|-----------------|---|------------------|--------------|
| 1. | 1 | 10 Tay 10 Tay | | 0.0000000000000000000000000000000000000 | T ION TODIO | (4) |
| | point chip | me-2-70nine | 5-5-23 | | | |
| 12 | 1 1 | | | | | |
| 13 | | | | | | |
| 14 | | | | | | |
| | | | | | | |
| | | | | | | |
| | 8 | | | | | |
| | | | | | | |
| | | | | | | |
| | - | - Social | | | | |
| | | | | | - 5 | |
| | | | | | 1 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | Since | | | |
| Relinquished By: | City Day | Received By: | And was | | 10.0 | |
| rinted Name | - Cole Tinene & | Printed Name | Jackie | TOVAL | .2 | |
| ate/Time: | 5.7.23 1145 | Date/Time: | Jakie 5/8/23 01 | (00) | | |
| Relinquished By: | | Received By: | And the second | | | |
| Printed Name | | Printed Name | | | | |
| Date/Time: | | Date/Time: | | | | |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers

ratefulen. ein Byere

2353776

Date Received: 5/8/2023
Date Analyzed: 5/15/2023
Date Reported: 5/15/2023

Report Number:

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 µg

Project Number: SMSD-23-11460

Project Name: Santa Monica Civic Center

Location: 1855 Main St. Santa Monica

Date Sampled: 5/5/2023 Sampled By: Erik Jimenez

Total Samples: 17

| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) |
|---------------------|------------------------------------|----------------------|--------------------------------|
| 2353776-001 1 | Paint Chip- 2nd Floor Civic Survey | 0.0750 | 4000 |
| 2353776-002 2 | Paint Chip- 2nd Floor Civic Survey | 0.0945 | 3600 |
| 2353776-003 3 | Paint Chip- 2nd Floor Civic Survey | 0.0504 | 14000 |
| 2353776-004 4 | Paint Chip- 2nd Floor Civic Survey | 0.0210 | 21000 |
| 2353776-005 5 | Paint Chip- 2nd Floor Civic Survey | 0.1063 | < 47 |
| 2353776-006 6 | Paint Chip- 2nd Floor Civic Survey | 0.0346 | 6100 |
| 2353776-007 7 | Paint Chip- 2nd Floor Civic Survey | 0.0504 | 5400 |
| 2353776-008 8 | Paint Chip- 2nd Floor Civic Survey | 0.0943 | 3300 |
| 2353776-009 9 | Paint Chip- 2nd Floor Civic Survey | 0.1025 | < 49 |
| 2353776-010 10 | Paint Chip- 2nd Floor Civic Survey | 0.1078 | 76000 |
| 2353776-011 11 | Paint Chip- 2nd Floor Civic Survey | 0.1086 | 350 |
| 2353776-012 12 | Paint Chip- 2nd Floor Civic Survey | 0.1053 | 3700 |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers

Location: 1855 Main St. Santa Monica

Project Number: SMSD-23-11460

Project Name: Santa Monica Civic Center

| Ledd iii i diiit by i laine AAO | | | | | | | |
|---------------------------------|------------------------------------|----------------------|--------------------------------|--|--|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | | | |
| 2353776-013 13 | Paint Chip- 2nd Floor Civic Survey | 0.1013 | < 49 | | | | |
| 2353776-014 14 | Paint Chip- 2nd Floor Civic Survey | 0.1012 | 79 | | | | |
| 2353776-015 15 | Paint Chip- 2nd Floor Civic Survey | 0.1019 | 98 | | | | |
| 2353776-016 16 | Paint Chip- 2nd Floor Civic Survey | 0.1072 | 350 | | | | |
| 2353776-017 17 | Paint Chip- 2nd Floor Civic Survey | 0.1013 | 64 | | | | |

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

CA ELAP Cert #2823

Approved Signatory- Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab) Order No. 2353776

| | CUSTOMER INF | ORMATION | | Turnaround | Time | Shipped | ву | | Report | Send Via: | |
|-----------------|--------------------|--------------|---------|--------------|-------------------|-----------|----------|------|---|-----------|--------|
| Company | Alta Environment | al/NV5 | | Same Day | | Fedex | | | Web | | |
| Address | 3777 Long Beach | Blvd., Annex | Bldg. | 1 Day | | UPS | | | Email | 100 | |
| City/State/Zip | Long Beach, Ca 9 | 90807 | 1100.11 | 2 Day | | USPS | | | Fax | | |
| Contact | Jim Byers | | | 3 Day | | Drop Off | | | Verbal | | |
| Office Phone | 562-495-5777 | | | 5 Day | 60 | Drop Box | 800 | 5 | Mail | | |
| Cell | | | | Weekend | | Other | | S-5. | Pick up | | |
| Fax | 562-495-5877 | | | Special Ins | structions: | 100 | | - " | | | |
| Email | jim,byers@nv5.co | om | | Layered a | | | | | | | |
| 10048010 | | | | cc therese. | | com and d | avid.s | chac | k@nv5.cor | n on resu | lts |
| | 77 | | OJECT | INFORMAT | | | | | | | |
| Project Name: | Santa Moinca Civid | Center | | PO Number | | | _ | - | | | |
| Project Number: | SMSD-23-11460 | | h . | Work Order | | | T . | 1.0 | _ | , | |
| Location: | 1855 Main | St. Souta | FLINRO | Sampled By | <i>y</i> - | 3 | Fre | E | Jinge | 6 | |
| PI | LM | PCM | | | MOLD | | | | LEAD | | 160 |
| PLM EPA 600/M | | NIOSH 7400/ | | 0.17 | pore Trap | | Ai | | | TTLC | |
| PLM 400 Pt. Cou | | NIOSH 74008 | | | spe Lift | | Pai | | | | |
| PLM 1000 Pt. Co | ount (<0.1%) | w/TWA | | (1) | ulk Sample wab | | Wig | | | | |
| SAMPLE ID | SAMPLE T | VPE | | LOCAT | - | | Da | _ | Start Time | Avg | Volume |
| SAMPLE ID | Grani CE 1 | | | - | | | Same | pled | Stop Time | Flow Rate | (L) |
| 1 | | | | 0 | | | | | | | |
| 1 | Paint C | 6.0 | 201 | 1/20 | - ria | 's Store | 7.7 | . 13 | | | |
| | I MILLY C | 111 | auro | 1001 | 1 | - AND | | - | | | |
| 2 | | | | | 1 | | | | | | |
| 0 | | | | | | | | | | | |
| | | | | | - | | _ | 1 | | | - |
| CI | | | | | | | | 1 | | i. | |
| 7 | 1 | _ | | | | | | + | · · | | |
| T | | | | - 1 | | | | 1 | *************************************** | | |
| 0 | | | | | | | | | | | |
| 50 | | | | | | | | | | | _ |
| 7 | | | | | | | | | | | |
| | | _ | | - | | | \vdash | _ | | | |
| 8 | | | | | | | | | | | |
| | | | | | | | | | | | |
| 9 | | | | | | | | | | | |
| 10 | | | | | | | | | | | |
| 10 | (17) | الرس | | Deschart | - / | 200 | - | _ | | | _ |
| Relinquished By | Esit Jime | | | Received E | | 11-dr | | 7 | | | |
| Printed Name , | Clip Jime | 200 | | Printed Na | | 000 | -le | MA | 19:00 | | |
| Date/Time: 5 | .7.23 | 1147 | | Date/Time: | 8 | 4/8/ | 23 | 08 | 00,00 | - | |
| Relinquished By | r. | (4/0746/c) | | Received 8 | Ву: | | -3. | | 2 2 2 | 7 | |
| Printed Name | | | | Printed Name | | | | | | | |
| Date/Time: | | | | Date/Time: | | | | | | | |



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

Company: Alta Environmental/NV5

Project Number: SMSD-23-11460

Santa Moinca Civic Center

2353776 (Lab) Order No.

| Santa Moinca Civic Center | | | | | |
|---------------------------|------------------------|--|--|--|--|
| SAMPLE TYPE | LOCATION | Date Sampled | | Avg Flow Rate | Volum (L) |
| Paint Chio | 2nd floor civic survey | 5-5-20 | | | |
| 1 | | 1 | | | |
| | | | | | |
| | | | | | |
| L 10 31 | 4 - 7 - 8 - 3 | 1/ | | | |
| | | + | | | |
| 100 | | + | | | |
| | + | - | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | - | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | - | _ | | | |
| | | - | | | |
| | | | | | |
| | | | | | |
| trik dra | Received By: | | | - | |
| TIC JIMEN ? | Printed Name JACGC T | | | | |
| | | 08.00 | | | |
| | | | | | |
| | | | | | |
| | Paint Chip | Frir Januar Printed Name Julic T. 7.33 Received By: Printed Name Julic T. 7.33 Date/Time: 5/5/23 | Received By: SAMPLE TYPE LOCATION Date Sampled Paint Chip And flour civic Survey 5-5-0 Received By: Printed Name JULIE TAY19 Printed Name JULIE TAY19 Received By: Received By: | SAMPLE TYPE LOCATION Date Sampled Stop Time Paint Chip 2 nd flour Civic Survey 3-5-22 Received By: Printed Name July 17111 Date Time: 5/0/2-3 08 00 Received By: | SAMPLETYPE LOCATION Date Start Time Avg Stop Time Flow Rate Paint Chip 2 flow Civic Survey 5-522 Flow Rate Paint Chip 2 flow Rate Received By: Printed Name Received By: Printed Name Received By: Printed Name Received By: Printed Name |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460
Project Name: Civic Center Survey
Location: 1855 Main St.

Santa Monica, CA

Report Number: 2353727

 Date Received:
 5/4/2023

 Date Analyzed:
 5/11/2023

 Date Reported:
 5/11/2023

Date Sampled: 5/3/2023 Sampled By: Erik Jimenez

Total Samples: 17

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 µg

| Lead (Pb) in Paint by Flame AAS | | | | | | | |
|---------------------------------|--|--------|--------------------------------|--|--|--|--|
| Lab ID Client ID | Location/Description Sample Weight (g) | | Lead Concentration ppm (mg/kg) | | | | |
| 2353727-001 PC-1 | Paint Chip- Ext of Bldg | 0.1028 | < 49 | | | | |
| 2353727-002 PC-2 | Paint Chip- Ext of Bldg | 0.1009 | < 50 | | | | |
| 2353727-003 PC-3 | Paint Chip- Ext of Bldg | 0.0732 | < 68 | | | | |
| 2353727-004 PC-4 | Paint Chip- Ext of Bldg | 0.1053 | < 47 | | | | |
| 2353727-005 PC-5 | Paint Chip- Ext of Bldg | 0.1028 | < 49 | | | | |
| 2353727-006 PC-6 | Paint Chip- Ext of Bldg | 0.1048 | 410 | | | | |
| 2353727-007 PC-7 | Paint Chip- Ext of Bldg | 0.1034 | < 48 | | | | |
| 2353727-008 PC-8 | Paint Chip- Ext of Bldg | 0.0860 | < 58 | | | | |
| 2353727-009 PC-9 | Paint Chip- Ext of Bldg | 0.0478 | < 110 | | | | |
| 2353727-010 PC-10 | Paint Chip- Ext of Bldg | 0.1013 | < 49 | | | | |
| 2353727-011 PC-11 | Paint Chip- Ext of Bldg | 0.1064 | < 47 | | | | |
| 2353727-012 PC-12 | Paint Chip- Ext of Bldg | 0.1063 | < 47 | | | | |



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Jim Byers Project Number: SMSD-23-11460
Project Name: Civic Center Survey
Location: 1855 Main St.
Santa Monica, CA

| Lead in Paint by Flame AAS | | | | | | | | |
|----------------------------|-------------------------|----------------------|--------------------------------|--|--|--|--|--|
| Lab ID Client ID | Location/Description | Sample Weight (g) | Lead Concentration ppm (mg/kg) | | | | | |
| 2353727-013 PC-13 | Paint Chip- Ext of Bldg | 0.1038 | < 48 | | | | | |
| 2353727-014 PC-14 | Paint Chip- Ext of Bldg | 0.1035 | < 48 | | | | | |
| 2353727-015 PC-15 | Paint Chip- Ext of Bldg | 0.0610 | 130 | | | | | |
| 2353727-016 PC-16 | Paint Chip- Ext of Bldg | 0.1023 | < 49 | | | | | |
| 2353727-017 PC-17 | Paint Chip- Ext of Bldg | 0.0206 | < 240 | | | | | |

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

CA ELAP Cert #2823

Approved Signatory- Cristina E. Tabatt

deTabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab) Order No. 2353727

| | CUSTOMER INFORMATION | N | Turnaround Time | Shippe | d By | Repo | rt Send Via | |
|-------------------------------|----------------------------|------------|--------------------------------------|----------|-----------------|-------------------------|------------------|---------------|
| Company | Alta Environmental/NV5 | | Same Day | Fedex | | Web | | |
| Address | 3777 Long Beach Blvd., Ann | ex Bldg. | 1 Day 🗆 | UPS | | Email | DE- | |
| City/State/Zip | Long Beach, AA 90807 | | 2 Day | USPS | | Fax | | |
| Contact | Jim Byers | 144- | 3 Day | Drop Off | 283 | Verbal | | |
| Office Phone | 562-425-5777 | | 5 Day 🐯 | Drop Box | | Mail | | |
| Cell | | | Weekend | Other | | Pick up | 200 | |
| Fax | 562-425-5777 | | Special Instructions | s: | | - | | |
| Email | Jim. Byerr @ W | - | | | | | | |
| | | PROJECT | INFORMATION | | | | | |
| Project Name: | Civic Center | PO Number: | | | | | | |
| Project Number: 5M3D-23-11460 | | | Work Order No.: | | | | | |
| Location: | 1855 main St. Sa | ma mio | ာနိန်းက pled By: | | Rano | ly Flo | KET | |
| PI | LM PC | CM | MOLD | | | LEAD | | |
| PLM EPA 600/M4 | | | Spore Trap | | Air | | TTLC | |
| PLM 400 Pt. Cou | | | Tape Lift | | Paint | DEF | | |
| PLM 1000 Pt. Co | unt (<0.1%) | | Bulk Sample | | Wipe | | | N. |
| SAMPLE ID | SAMPLE TYPE | | Swab LOCATION | | Soil | Ct-d Ti | A | Maluma |
| SAMPLE ID | SAMPLE ITPE | | LOCATION | | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volume (L) |
| PC-1 | Paint chip | Ex- | lector. | | 5/2/29 | | | |
| 7 | (| | | | 7 | | | |
| 3 | | | | | | | | |
| 4 | | | | | \top | | | |
| 5 | | | | | + | | | |
| 3 | | | | | +- | | | |
| 6 | | | | | | | | |
| 7 | | | | | | | | |
| 8 | | | | | | | | |
| 9 | | | | | | | | |
| lo | 2 | | 7 | | 7 | | | |
| Relinquished By: | RANNY Flores | | Received By: | An | | | | |
| Printed Name: RANDY Flore 5 | | | Printed Name: Jackie TAVA 1 | | | | | |
| Date/Time: 5 | RANDY Flores | | Date/Time: 5/4/2 | 3 08.0 | 97 | | | |
| Relinquished By: | | | Received By: | | | | | |
| | | | | | | | | |
| Date/Time: | | | Date/Time: Lab Forms Ver. 2016-06-27 | | | | | |




1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com


Ver. 2016-06-27


| Company: | Alta Environmental | // // | ah) Order No | 2353727 | | | | | |
|---|-----------------------------|-------------------|-----------------|-------------------------|------------------|---------------|--|--|--|
| [13] [4] [4] [4] [4] [4] [5] [5] [6] [6] [6] [6] [6] [6] [6] [6] [6] [6 | SMSD-23-1146 | 0 | b) Order No. | 2353 | 2353721 | | | | |
| Project Name: | Civic Center | | | | | | | | |
| SAMPLE ID | SAMPLE TYPE | LOCATION | Date Sampled | Start Time Stop Time | Avg Flow Rate | Volume (L) | | | |
| PC- 11 | Paint Chip | Exterior | 5/2/23 | | | | | | |
| 12 | | | 1 | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 1 17 | 7 | | 1 ± | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | - | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | - | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | - | | | | |
| | | | | | | | | | |
| Relinquished By: | 1202- | Received By: | 1 | | _ | | | | |
| | | | | | | | | | |
| Date/Time: | 12 ANDY Flore 5 5/4/2023 | Date/Time: 5/4/23 | OB:00 | | | | | | |
| Relinquished By: | | Received By: | | | | | | | |
| Printed Name: | | | Printed Name: | | | | | | |
| Date/Time: | | Date/Time: | | | | | | | |

Appendix C


Sample Location Maps: Asbestos and Lead










SANTA MONICA CIVIC AUDITORIUM INTERIOR SCHEMATIC WITH DIMENSIONS







Mezzanine FE





Scale_


| Sheet | of | |
|---------|----|--|
| 211/2/2 | V1 | |


Project Name


Project No./Task No.

Calculated by ______ Date _____

Checked by _____ Date ____







N|V|5

Appendix D

Employee Certifications

State of California Division of Occupational Safety and Health Certified Site Surveillance Technician

Randolph J Flores

Certification No. __17-6019

This certification was issued by the Division of Occupational Safety and Health as arthorized by Sections 7180 et seq. of the Business and Professions Code.



STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL: CER

CERTIFICATE TYPE:

NUMBER:

EXPIRATION DATE:

3


Lead Sampling Technician

LRC-00004340

11/28/2023

Randolph flores

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.edph.ca.gov/programs/clppb or calling (800) 597-LEAD



This is to certify that

Erik Jimenez

SS# 7300

Has completed course work that meets the criteria required for EPA/AHERA (TSCA Title II) Approved Reaccreditations and NESHAPs Regulations Training *

Asbestos in Buildings: Building Inspector Refresher

September 13, 2022

Course Date

222-155-BIR

Certificate Number

CA - 023 - 06

September 13, 2023

Expiration Date

Course Approval Number

Mario Virgen Course Director

> 1520 W. Cameron Ave., Suite 103 * West Covina, CA 91790 (626) 962-4436 *This course meets California requirements



STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL: CERTIFICATE TYPE: NUMBER: EXPIRATION DATE:


Lead San

Lead Sampling Technician LRC-00007394 6/28/2023

Lead Worker LRC-00006537 3/23/2023

Erik Jimenez

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD





STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL: CERTIFICATE TYPE:

NUMBER:

EXPIRATION DATE:



Lead Inspector/Assessor

LRC-00001746

8/24/2023

James Byers

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD

State of California
Division of Occupational Safety and Health
Certified Asbestos Consultant

Christine Jordan

Certification No. _92-0215_

Expires on 07/09/23

This certification was issued by the Division of Occupational Safety and Health as authorized by Sections 7180 et seq. of the Business and Professions Code.



STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:

CERTIFICATE TYPE:

NUMBER:

EXPIRATION DATE:



Lead Inspector/Assessor

LRC-00002523

9/25/2023

Christine Jordan

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD

Appendix E

Historical Surveys and Data

ASBESTOS AND LEAD MATERIALS SURVEY/TESTING REPORT

CIVIC CENTER AUDITORIUM 1855 MAIN STREET SANTA MONICA, CA 90401



THE CITY OF SANTA MONICA PROJECT 1437 4TH STREET, SUITE 300 SANTA MONICA, CA 90401



2670 North Main Street, Suite 320 Santa Ana, CA 92705 Ph: (714) 247-0024 Fax: (714) 247-0025

Bainbridge Project No.: 12034087.10

BAINBRIDGE

May 10, 2012

Ms. Yolanda Nunez The City of Santa Monica 1855 Main Street Santa Monica, CA 90401

RE: Asbestos and XRF lead based paint survey/testing consulting services for the Special Provision number SP2173 Project located at City of Santa Monica Civic Auditorium located at 1855 Main Street in Santa Monica, CA 90401.

Ms. Nunez:

At the request of the City of Santa Monica, Bainbridge Environmental Consultants, Inc. (Bainbridge Environmental) conducted asbestos bulk sampling and lead XRF testing at Santa Monica Civic Center Auditorium located at the above mentioned address. The survey was conducted on April 10th – 13th, 2012.

This document has been prepared for the sole use of the City of Santa Monica, their authorized agents, any State, or local agencies involved in this project. No other party should rely on the information contained herein without prior written consent of Bainbridge Environmental.

Thank you for the opportunity to provide services to the City of Santa Monica. Please do not hesitate to call us with any questions. We look forward to assisting you in the future.

Sincerely,

BAINBRIDGE ENVIRONMENTAL CONSULTANTS, INC.

Henry A. Moreno

Principal/Program Manager

CAC #92-0618/03-3494/DPH I/A 9970

HAM/nm

Bainbridge Job #12034087.10

TABLE OF CONTENTS

| Section | <u>on</u> | <u>Page</u> |
|---------|--|-------------|
| 1.0 | ASBESTOS SURVEY/INVESTIGATION | 2 |
| 1.1 | Asbestos Findings | 2 |
| 1.2 | Asbestos Recommendations | 3 |
| 1.3 | Disclaimer and Limitations for Asbestos Related Projects | 3 |
| 2.0 | LEAD PAINT XRF TESTING OF PAINTED SURFACES | 5 |
| 2.1 | Lead Findings | 5 |
| 2.2 | | 6 |
| 2.3 | Disclaimer and Limitations for Lead-Based Paint and Components | 6 |

APPENDICES

APPENDIX

- A ASBESTOS FIELD DATA AND LABORATORY RESULTS
- B LEAD XRF FIELD DATA AND RESULTS
- C ASBESTOS AND LEAD INSPECTOR'S CERTIFICATES
- D FLOOR PLANS

1.0 Asbestos Survey/Investigation

Karlin Cisco (CSST) of Bainbridge Environmental, under the supervision of Henry Moreno (CAC), performed the asbestos inspection/survey activities and collected the asbestos bulk samples for laboratory analysis of the Civic Center Auditorium located at 1855 Main Street, Santa Monica, CA 90401. The survey was performed on April 10th, 11th, 12th, and 13th, 2012. The survey consisted of a walk-through of the building and sample collection of suspect asbestos containing materials (ACM). This report reviews and summarizes the findings outlined in the attached asbestos sample summary and laboratory report, as well as previous sampling performed in the subject building.

The Civic Auditorium Building located at 1855 Main Street Santa Monica, California appears to be multiple poured- in- place reinforced concrete and steel supported structure under built-up asphalt/ rolled roofing system. Interior ceilings are primarily suspended and finished with various sized lay-in tiles. Interior walls are either concrete or metal studs with a plaster finish. The floors are covered with ceramic tiles, floor tiles, carpet, or vinyl flooring. The subject building is heated and cooled by a central HVAC system.

During this inspection, several criteria including bulk testing were used to properly assess areas sampled. Visual and tactile assessments of suspect materials provided the basis for these criteria and allowed the inspector to group the materials into homogenous areas.

1.1 Asbestos Findings

A total of one-hundred and sixty-three (163) bulk samples were collected and submitted under the chain of custody protocol to EMSL Analytical, Inc., San Diego, CA. EMSL Analytical, Inc. is certified with the NVLAP registration and approved for asbestos bulk sample analysis in state of California. The sample analysis was performed by EPA Polarized Light Microscopy (PLM) coupled with dispersion staining, method 600/R-93/116, July 1993. All PLM analyses are derived from a calibrated visual estimate unless otherwise noted.

Two (2) of the 163 samples were selected to be re-analyzed using the 1000-point count method. As a result of the point count re-analysis, the samples collected contain more than .1% asbestos. California Labor Code, Section 6501.8 defines "asbestos containing construction materials (ACCM)" as any manufactured construction material that contains more than one tenth of one percent (0.1%) by weight.

As a result, the materials tested below contain asbestos containing materials (ACM> .1%).

| Sample No. | Area | Sample Location | Material Description/Color | Material Location | *TBV Approximate Quantities | Asbestos Detected |
|---------------|------------|------------------------------|-----------------------------------|---|-----------------------------------|----------------------|
| 4 | Basement | Janitor's Closet Floor | 9 " Floor Tile w/ Mastic/Green | Basement Janitor's Closet Flooring Only | 16sf | 5% Chrysotile |
| 4A | Basement | Janitor's Closet Floor | | | | 7% Chrysotile |
| 9 | Main Floor | Dressing Room Ceiling | Ceiling Tile Puck Mastic | Ceilings & | *TBV by | 2% Anthophyllite |
| 12 | Main Floor | West Side Exit Foyer Ceiling | | Walls Throughout | Contractor | 2% Anthophyllite |

| Sample No. | Area | Sample Location | Material Description/Color | Material Location | TBV Approximate Quantities | Asbestos Detected |
|---------------|------------------------|--|----------------------------------|--|----------------------------------|---|
| 15 | Main Floor | Lobby Ceiling | Ceiling Tile Puck Mastid | Walls Throughout | *TBV by Contractor | 2% Anthophyllite |
| 69 | 2 nd Floor | Fan Room #2 Wall | Puck Mastic | 12-inch Ceiling | | 2% Anthophyllite |
| 75 | 2 nd Floor | Baltet Dressing Room Ceiling | | Tile | Contractor | 2% Anthophyllite |
| 78 | 3 rd Floor | Fan Room # 5 Wall | | | | 2% Anthophyllite |
| 33A | Business Office | Floor-South | Mastic/Green | Business Office Flooring | 700 sf | 2% Chrysotile |
| 34A | Business Office | Floor-North | Floor Tile | Throughout | See Sample | <1% Chrysotile |
| 35A | Business Office | Floor-East | | | #33A | <1% Chrysotile |
| 79 | 2 nd Floor | Fan Room # 2 Floor | Battleship Flooring/Black | Mech. & Fan Room Flooring Throughout | 5,700sf | <1% Chrysotile |
| 80 | 3 rd Floor | Fan Room #3 Floor | | Ů | | <1% Chrysotile |
| 52 | Main Floor | Stage at Fire Curtain-East | | | | 40% Chrysotile |
| 53 | Main Floor | Stage at Fire Curtain-West | Fire Curtain | Stage Fire Curtain | 2,500sf | 40% Chrysotile |
| 54 | Main Floor | Stage at Fire Curtain-Center | | | | 40% Chrysotile |
| 96 | 3 rd Floor | Catwalk/Upper Part of Auditorium at Overhead Pipe-Runs | Thermal System Insulation/TSI | TSI Pipe-Runs Throughout | 200lf (Visible) | 8% Chrysotile 12% Amosite <1% Crocidolite |
| 97 | 3 rd Floor | Catwalk/Upper Part of Auditorium at Overhead Pipe-Runs | | | *TBV by Contractor | 8% Chrysotile 12% Amosite <1% Crocidolite |
| 102 | 2 nd Floor | Sound Equip. Room Floor | | | | 5% Chrysotile |
| 102A | 2 nd Floor | Sound Equip. Room Floor | | | | 5% Chrysotile |
| 103 | 2 nd Floor | Sound Equip. Room Floor | | | | 5% Chrysotile |
| 103A | 2 nd Floor | Sound Equip, Room Floor | 9" Floor Tile w Mastic/Black | Sound Room Flooring Only | 545sf | 6% Chrysotile |
| 104 | 2 nd Fioor | Sound Equip. Room Floor | | | · ! | 5% Chrysotile |
| 104A | 2 nd Floor | Sound Equip. Room Floor | | | | 6% Chrysotile |
| 111 | Stage Upper Roof | Abandoned AHU Surface | Mastic/Gray & Black | Stage Roof at Abandoned AHU Only | 10sf | 8% Chrysotile |
| 125 | 2 nd Floor | Wardrobe Room at Light Fixtures | Heat Shield Paper/Gray | 2 [™] Fioor Wardrobe Light Fixtures and Basement Light Fixtures Only | 2sf | 20% Chrysotile |

^{*}TBV To Be Verified by Contractor

The following building materials were Assumed to be asbestos-containing:

| Sample No. | Material Description/Color | Material Location | Approximate Quantities | *TBV Asbestos Detected | Inspection Status |
|---------------|----------------------------|-----------------------------------|---------------------------|------------------------------|--|
| n/a | (Labeled) Fire Rated Doors | Fire Doors Throughout | 600sf | ASSUMED | Material not disturbed or sampled |
| n/a | Puck Mirror Mastic | Mirrors Throughout | 400sf | ASSUMED | Material not disturbed or sampled |
| n/a | Terrazzo Flooring | Terrazzo Flooring Throughout | 4,000sf | ASSUMED | Material not disturbed or sampled |
| n/a | Transite Pipe | Transite Flue Pipes Throughout | 40if | ASSUMED | Material not found during investigation, but if discovered during demo/reno activities Assume to be asbestoscontaining |

^{*}TBV To Be Verified by Contractor

In the event that other materials are found to be similar or homogenous to the materials sampled and determined to contain asbestos, those similar or homogenous materials will be considered assumed asbestos containing materials. Prior to bid, contractor is responsible for field verification of those materials, their quantities and measurements.

Federal regulations define asbestos-containing materials as any material containing more than one percent (1%) by weight. California Labor Code, Section 6501.8 defines "asbestos containing construction materials (ACCM)" as any manufactured construction material that contains more than one tenth of one percent (0.1%) by weight.

1.2 Asbestos Recommendations

Based on the available information gathered during the performance of this survey and the conclusions, Bainbridge Environmental recommends the following:

- Identified asbestos-containing materials must be removed prior to any scheduled renovation or demolition in adherence with South Coast Air Quality Management District regulations.
- Bainbridge Environmental recommends the preparation of specifications for the removal of identified asbestos materials and Cal/OSHA regulated (samples greater than .1% asbestos), as necessary. A State of California Certified Asbestos Consultant should be retained to properly document, inspect, and monitor the removal of the asbestos materials. This is to ensure both adherence to applicable State and federal regulations and the safety of building occupants in the vicinity of the abatement areas.
- Bainbridge Environmental recommends that a Cal/OSHA registered and state contractor
 perform the abatement of the above-mentioned asbestos containing materials. Any asbestos
 related work must be conducted in accordance with all applicable federal, state, and local
 regulations. Firms performing the asbestos-related work must follow proper engineering
 practices and must use state-of-the-art techniques whenever possible.

1.3 Disclaimer and Limitations for Asbestos Related Projects

This document is prepared for the sole use of the City of Santa Monica and its authorized representatives and any agencies directly involved in this project. No other party should rely on the information contained herein without prior written consent of Bainbridge Environmental.

The information in this report or portions there of may be required to be included in notifications to employees, contractors or other visitors to the building(s). The owner or its agents shall not use this report as a specification or work plan for any of the work suggested or recommended in the report.

This report is based upon conditions and practices observed at the property and information made available to Bainbridge Environmental Consultants, Inc. This report does not identify all hazards or unsafe practices, nor does it indicate that other hazards or unsafe practices exist at the premises.

The conclusions and summary presented in this report are based on a review of pertinent regulations, and guidelines or requirements commonly followed by industry standards, data collected during the site inspection, and information provided by the City of Santa Monica, their clients, agents, and representatives.

The work has been conducted in an objective and unbiased manner and in accordance with generally accepted professional practice for this type of work. Bainbridge believes the data and analysis to be accurate and relevant, but cannot accept responsibility for the accuracy or completeness of available documentation or possible withholding of information by other parties.

Any observations of asbestos containing materials represent the conditions at the specified locations and times of the site inspection survey only. The selection of sample areas was limited to accessible areas of the property.

2.0 Lead Paint XRF Testing of Painted Surfaces

Hector Gonzalez, of Bainbridge Environmental, under the supervision of Henry Moreno, DPH of Bainbridge conducted a lead-based paint (LBP) inspection survey of the City of Santa Monica Civic Center Auditorium at 1855 Main Street, Santa Monica, CA 90401. The lead inspection/survey was conducted on April 13th, 2012.

Bainbridge Environmental conducted the lead-based paint inspection of the site building(s) and property in compliance with the following Federal, State, and Local regulations:

- 24 CFR Part 35.80-35.98 and 35.3120(b) U.S. Department of Housing and Urban Development (HUD)
- Toxic Substances Control Act (TOSCA) Section 406
- 40 CFR 745.103 Environmental Protection Agency (EPA)
- Title 17 Section 35000 Code of California Regulations
- Cal/OSHA Title 8 Section 1532.1 California Occupational Safety and Health Administration
- Cal/OSHA Title 8 Section 5194 California Occupational Safety and Health Administration

In compliance with Title 17, CCR, Division 1, Chapter 8 and 24 CFR Subtitle A, Part 35.125, Bainbridge filed the 8552 form as required to notify the California Department of Health Services the findings of the lead inspection/assessment conducted on the site.

Currently, the State of California, HUD, and the Environmental Protection Agency (EPA) define lead-based paint as paint or other surface coating with lead content equal to or greater than 1.0 milligram per square centimeter (mg/cm²) of surface area or 5,000 parts per million lead on the surface area.

XRF Paint Readings: XRF measurements were collected. Bainbridge Environmental conducted the survey using a Niton XL 309 Spectrum Analyzer, X-ray Fluorescence (XRF) detector. All survey activities and XRF measurements were performed in accordance with the United States Department of Housing and Urban Development's guidance document, entitled Guidelines for the Evaluation and Control, (HUD Guidance Document).

2.1 Lead Findings

XRF Testing: The field data and results for XRF testing are included in Appendix B. Of one-hundred and fifty-two (152) XRF readings collected, lead was detected in twenty one (21) of the samples at or greater than concentrations at or above 0.7 milligrams per square centimeter (0.06%) by weight.

Lead based paint was found in the following locations:

| XLNo | Side | Building | Room | Source | Substrate | Color | Result |
|------|------|----------|---------------------|--------|-----------------|-------|--------|
| 2183 | А | Interior | Men R/R North-West | Urinal | Porcelain | White | 5.3 |
| 2199 | Α | Interior | North East/Men R/R | Urinal | Porcelain | White | 5.2 |
| 2215 | Α | Interior | Kitchen | Wall | 4" Ceramic Tile | White | 8.8 |
| 2237 | А | Interior | Main Office/Men R/R | Wall | 4" Ceramic Tile | Green | 6.8 |
| 2240 | С | Interior | Main Office/Men R/R | Urinal | Porcelain | White | 4.3 |
| 2249 | А | Interior | Women R/R | Wall | 4" Ceramic Tile | Peach | 4.8 |

| 2260 | А | Interior | Dressing Room 1 | Shower Wall | 4" Ceramic Tile | White | 6.4 |
|------|---|----------|-----------------------------------|-------------------------|----------------------------|--------|------|
| 2279 | В | Interior | Dressing Room | Wall | 4" Ceramic Tile | Tan | 5.9 |
| 2280 | А | Interior | Men Dressing Room | Wall | 4" Ceramic Tile | Green | 6.4 |
| 2281 | Α | Interior | Men Dressing Room | Urinal | Porcelain | White | 6.4 |
| 2283 | D | Interior | Second Floor East Dressing RM | Shower Wall | 4" Ceramic Tile | Tan | 5,9 |
| 2285 | С | Interior | Janitor Room | Sink | Porcelain | White | 2.5 |
| 2287 | А | Interior | 2nd. Floor South Dressing Room | Wal! | 4" Ceramic Tile | Peach | 5.0 |
| 2288 | С | Interior | 2nd. Floor South Dressing Room | Wall | 4" Ceramic Tile | Tan | 6.0 |
| 2301 | С | Interior | 3 rd . Floor. | Attic | Structure H Beams/South | Orange | 3.6 |
| 2303 | В | Interior | Attic | Structure H Beams/East | Metal | Orange | 7.5 |
| 2304 | Α | Interior | Attic | Structure H Beams/North | Metal | Orange | 10.1 |
| 2309 | А | Interior | Basement Men R/R | Wall | 4' Ceramic Tile | Green | 5.0 |
| 2312 | В | Interior | Basement Janitor Room | Sink | Porcelain | White | 2.6 |
| 2313 | Α | Interior | Basement Women R/R | Wall | 4" Ceramic Tile | Peach | 5.0 |
| 2316 | Α | Interior | Orchestra Pit Door | Double Door | Metal | Gray | 10.1 |
| | | | | | | | |

In the event that other materials are found to be similar or homogenous to the materials sampled and determined to contain lead, those similar or homogenous materials will be considered assumed lead containing materials. Prior to bid, contractor is responsible for field verification of those materials, their quantities and measurements.

2.2 Lead Recommendations

Based on the results of the LBP Inspection Bainbridge Environmental recommends:

- The removal of the identified lead components from the subject building prior to renovation. We further recommend the utilization of a licensed lead abatement contracting company to remove, transport and dispose of the lead waste according to applicable regulations.
- The Occupational Safety and Health Administration promulgated legislation (29 CFR 1926.62 and 8 CCR1532.1) entitled "Lead Exposure in Construction Industry", requires that any job that may potentially expose workers to any concentration of lead (i.e., >0.01 mg/cm²) be monitored by the employer to determine workers eight-hour time weighted average (TWA) exposure to lead.

2.3 Disclaimer and Limitations for Lead-Based Paint and Components

This document is prepared for the sole use of The City of Santa Monica and its authorized representatives and any agencies directly involved in this project. No other party should rely on the information contained herein without prior written consent of Bainbridge.

The information in this report or portions there of may be required to be included in notifications to employees, contractors or other visitors to the building(s). The City of Santa Monica or its agents shall not use this report as a specification or work plan for any of the work suggested or recommended in the report.

This report is based upon conditions and practices observed at the property and information made available to Bainbridge Environmental Consultants, Inc. This report does not identify all hazards or unsafe practices, nor does it indicate that other hazards or unsafe practices exist at the premises.

This inspection and assessment was planned, developed, and patterned after the *HUD Guidelines in Chapter* 7. Bainbridge utilized state-of-the-art practices and techniques in accordance with regulatory standards while performing this inspection. Bainbridge's evaluation of the relative risk of exposure to lead identified during this inspection/risk assessment is based on conditions observed at the time of the inspection. Bainbridge cannot be responsible for changing conditions that may alter the relative exposure risk or for future changes in accepted methodology.

The conclusions and summary presented in this report are based on a review of pertinent regulations, and guidelines or requirements commonly followed by industry standards, data collected during the site inspection, and information provided by the City of Santa Monica, their clients, agents, and representatives.

The work has been conducted in an objective and unbiased manner and in accordance with generally accepted professional practice for this type of work. Bainbridge believes the data and analysis to be accurate and relevant, but cannot accept responsibility for the accuracy or completeness of available documentation or possible withholding of information by other parties.

Any observations of lead-based paint and lead containing materials represent the conditions at the specified locations and times of the site inspection survey only. The selection of sample areas was limited to accessible areas of the property.

APPENDIX A ASBESTOS FIELD DATA AND LABORATORY RESULTS

SANTA MONICA CIVIC AUDITORIUM INVENTORY OF BUILDING MATERIALS

| Material Description | Suspect or Non-Suspect | Inspection Status |
|-------------------------------------|------------------------|-------------------------------|
| Cement | Suspect | Tested |
| Glass | Non-Suspect | Not Tested |
| Aluminum | Non-Suspect | Not Tested |
| Stucco | Suspect | Tested |
| Plaster | Suspect | Tested |
| 9-inch Floor Tile | Suspect | Tested |
| 12-inch Ceiling Tile | Suspect | Tested |
| Ceiling Tile Puck Mastic | Suspect | Tested |
| Fire Rated Gypsum Board | Suspect | Tested |
| Copper Pipes | Non-Suspect | Not Tested |
| Fiberglass Insulated Pipes & Elbows | Non-Suspect | Not Tested |
| Galvanized Steel Ducting | Non-Suspect | Not Tested |
| Vinyl Sheet Flooring | Suspect | Tested |
| Vinyl Cove Base | Suspect | ⊤ested |
| Vinyl Floor Tiles | Suspect | Tested |
| Drywail w Joint Compound | Suspect | Tested |
| Thermal System Insulation (TSI) | Suspect | Tested |
| TSI Cork Insulation | Suspect | Tested |
| AHU Canvas Material | Suspect | Tested |
| Fire Curtain | Suspect | Tested |
| Plastic | Non-Suspect | Not Tested |
| Tar Membrane Roofing | Suspect | Tested |
| Roof Mastics | Suspect | Tested |
| Rubber Caulking | Non-Suspect | Not Tested |
| Vapor Barrier | Suspect | Tested |
| Battleship Flooring (Coating) | Suspect | Tested |
| Heat Shield | Suspect | Tested |
| Boiler Furnace Pads | Suspect | Tested |
| Boiler Insulation | Suspect | Tested |
| Catwalk Vinyl Flooring | Suspect | Tested |
| Fiberglass Insulation | Non-Suspect | Not Tested |
| Wood | Non-Suspect | Not Tested |
| Structural Steel | Non-Suspect | Not Tested |
| Particle Board | Suspect | Tested |
| HVAC Cloth Tape | Suspect | Tested |
| Thermal System Canvas Insulation | Suspect | Tested |
| Asphalt | Non-Suspect | Not Tested |
| Terrazzo Flooring | Suspect | Not Tested at clients request |
| Fire Doors | Suspect | Not Tested at clients request |
| Ceramic Tiles | Non-Suspect | Not Tested |
| Ceramic Flooring | Non-Suspect | Not Tested |
| Furniture | Non-Suspect | Not Tested |
| Mechanical Equipment Internal Parts | Suspect | Inaccessible |
| Metal Pipes | Non-Suspect | Not Tested |
| Wood Countertops | Non-Suspect | Not Tested |

Client: City Of Santa Monica

Project Name: Santa Monica Civic Auditorium

Address: 1855 Main Street

Santa Monica, Ca.90401

BEC Project Number: 12034087.10

Inspector/Sampler: K. Cisco

Date Sampled: 4/10/2012



| Sample Number | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|------------------|--|------------------------------|--|----------------------|---------------------|
| н | Basement Stairwell Wall-West | Plaster | | | None Detected |
| 2 | Basement Men's Bath Wall-East | Plaster | Walls & Ceilings Throughout | TBV by Contractor | None Detected |
| 3 | Basement Musician's Room Wall-East | Plaster | | | None Detected |
| 4 | Basement Janitor's Closet Floor | 9-inch floor Tile | | | 5% Chrysotíle |
| 4A | Basement Janitor's Closet Floor | Mastic/Green | Basement Janitor's Closet Floor Only | 16sf | 7% Chrysotile |
| 5 | Basement Storage at Cement Pillar-West | Cement | | | None Detected |
| 9 | Main Floor South Stairwell Wall | Cement | Interior & Exterior Walls, Floors, & Ceilings Throughout | TBV by Contractor | None Detected |
| 7 | 2 nd Floor -South- Stairwell Wall | Cement | | | None Detected |
| 8 | Main Floor Dressing Room Ceiling | 12-inch Pinhole Ceiling Tile | | | None Detected |
| თ | Main Floor Dressing Room Ceiling | Puck Mastic | | | 2% Anthophyllite |
| 10 | Main Floor Dressing Room Ceiling | Fire Rated Gypsum Board | | | None Detected |
| 11 | Main Floor West Side Exit Foyer Ceiling | 12-inch Pinhole Ceiling Tile | Ceilings Throughout | TBV by Contractor | None Detected |

ASBESTOS BULK SAMPLE Name of Project



| Sample Number | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|------------------|---|------------------------------|---------------------|---------------------|---------------------|
| 12 | Main Floor West Side Exit Foyer Ceiling | Puck Mastic | | | 2% Anthophyllite |
| 13 | Main Floor West Side Exit Foyer Ceiling | Fire Rated Gypsum Board | | | None |
| | | 11 4 - 12 4 7 | | | None |
| * | ividiri Floor Loddy Celling | 12-inch Pinhole Ceiling Tile | | | Detected |
| 15 | Main Floor Lobby Ceiling | Puck Mastic | | | 2% |
| | | | | | Anthophyllite |
| 16 | Main Floor Lobby Ceiling | Fire Rated Gypsum Board | | | None Detected |
| 17 | Main Floor Lobby East Stairwell Undercarriage | Plaster | | | None |
| | | | | | Detected |
| 18 | Main Floor Phone Room Wall | Plaster | | | None |
| | | | | | nananan |
| 19 | Main Floor Committee Room Wall | Plaster | | | None |
| | | | | | Detected |
| 20 | Main Floor South Stairwell Wall | Plaster | Walls & Ceilings | TBV by | None |
| | | | าแบนซูเบดแ | Contractor | Detected |
| 21 | Auditorium Ceiling-East | Plaster | | | None Detected |
| 22 | Auditorium Ceiling-West | Dlactar | | | None |
| | | 101001 | | | Detected |
| 23 | Auditorium Ceiling in front of Projection Booth | Plaster | | | None |
| | | | | | Detected |
| 24 | Auditorium Seating Stairway Floor-East | Vinyl Sheet Flooring/Green | | | None |
| | | | | | Detected |
| 25 | Auditorium Seating Stairway Floor-West | Vinyl Sheet Flooring/Green | Auditorium Stairway | 2,200sf | None |
| | | | riootilig Olliy | | nelecten |
| 26 | Auditorium Seating Stairway Floor-North | Vinyl Sheet Flooring/Green | | | None Detected |

2 of 11

(714) 247-0024 Fax (714) 247-0025



Name of Project

| Sample Number | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|------------------|---|-------------------------------------|--|---------------------|-------------------|
| 27 | Auditorium Seating Stairway at Kickboard/Cove Base | 6" Vinyl Cove Base/Green | | | None Detected |
| 28 | Auditorium Seating Stairway at Kickboard/Cove Base | 6" Vinyl Cove Base/Green | Auditorium Stairway Kickboards Only | 600lf | None Detected |
| 29 | Auditorium Seating Stairway at Kickboard/Cove Base | 6" Vinyl Cove Base/Green | | | None Detected |
| 30 | Auditorium Seating Area Floor-East | Textured Vinyl Sheet Flooring/Beige | Auditorium Seating Area Flooring Only | 5,000sf | None Detected |
| 31 | Auditorium Seating Area Floor-West | Textured Vinyl Sheet Flooring/Beige | | | None Detected |
| 32 | Auditorium Seating Area Floor-North | Textured Vinyl Sheet Flooring/Beige | | | None Detected |
| 33 | Business Office Floor-South | 12-inch Vinył Tile | | | None Detected |
| 33A | Business Office Floor-South | Mastic/Green | | | 2% Chrysotile |
| 34 | Business Office Floor-North | 12-inch Vinyl Tile | Business Office Flooring Throughout | 700sf | None Detected |
| 34A | Business Office Floor-North | Mastic/Green | | | <1% Chrysotile |
| 35 | Business Office Floor-East | 12-inch Vinyl Tile | | | None Detected |
| 35A | Business Office Floor-East | Mastic/Green | | | <1% Chrysotile |
| 36 | Business Office-Reception Lobby Floor | 6-inch Parquet Flooring | Reception Office Flooring Only | 2.16sf | None Detected |
| 37 | Business Office Men's Bath Foyer Pipe Access Hatch | Vapor Barrier/Black | Vapor Barrier Paper Throughout | TBV | None Detected |
| 38 | Business Office Reception Area Wall | Drywall with Joint Compound | | | None |
| | | | | | |

(714) 247-0024 Fax (714) 247-0025



| Sample Number | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|------------------|---|----------------------------------|--|----------------------|-------------------|
| | | | | | Detected |
| 39 | Main Floor Concession Stand Wall | Drywalł with Joint Compound | Drywall Walls & Ceilings Throughout | TBV by Contractor | None Detected |
| 40 | Main Floor Concession Stand Wall | Drywall with Joint Compound | | | None Detected |
| 41 | 2 nd Floor Fan Room # 2 at Pipe Elbow | TSI Pipe Elbow Insulation | | | None Detected |
| 42 | 3 rd Floor Fan Room # 3 at Pipe Elbow | TSI Pipe Elbow Insulation | | | None Detected |
| 43 | 3 rd Floor Fan Room # 4 at Pipe Elbow | TSI Pipe Elbow Insulation | Pipe Elbows Throughout | TBV by Contractor | None Detected |
| 44 | 3 rd Floor Fan Room # 5 at Pipe Elbow | TSI Pipe Elbow Insulation | | | None Detected |
| 45 | 3 rd Floor Fan Room # 6 at Pipe Elbow | TSI Pipe Elbow Insulation | | | None Detected |
| 46 | 3 rd Floor Fan Room # 5 at AHU # 5 Pipe-Run | TSI Cork Insulation/Gray & Brown | | | None Detected |
| 47 | 3 rd Floor Fan Room # 4 at Vertical Pipe-Run | TSI Cork Insulation/Gray & Brown | Insulated Pipe-Runs Throughout | TBV by Contractor | None Detected |
| 48 | 3'd Floor Fan Room # 5 at Vertical Pipe-Run | TSI Cork Insulation/Gray & Brown | | | None Detected |
| 49 | 2 nd Floor Fan Room # 2 at HVAC Duct | AHU Canvas Material | | | None Detected |
| 50 | 3 rd Floor Fan Room # 3 at HVAC Duct | AHU Canvas Material | AHU Canvas Material Throughout | 500sf | None Detected |
| 51 | 3 rd Floor Fan Room # 6 at HVAC Duct | AHU Canvas Material | | | None Detected |
| 52 | Main Floor Stage at Fire Curtain-East | Fire Curtain | | | 40% Chrysotile |

Name of Project



| Sample | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|--------|--|--|--|---------------------|-------------------|
| 53 | Main Floor Stage at Fire Curtain-West | Fire Curtain | Stage Fire Curtain | 2,500sf | 40% Chrysotile |
| 54 | Main Floor Stage at Fire Curtain-Center | Fire Curtain | | | 40% Chrysotile |
| 55 | Exterior Wood Storage Structure at Roof Surface | Tar Membrane Roofing Material/White | | | None Detected |
| 56 | Exterior Wood Storage Structure at Roof Surface | Tar Membrane Roofing Material/White | Wood Storage Structure Roof | 1,705sf | None Detected |
| 57 | Exterior Wood Storage Structure at Roof Surface | Tar Membrane Roofing Material/White | | | None Detected |
| 58 | Exterior Wood Storage Structure-Exterior Wall-E | Plaster | | | None Detected |
| 59 | Exterior Wood Storage Structure-Exterior Wall-W | Plaster | Wood Storage Structure Ext. Walls | 1,240sf | None Detected |
| 09 | Exterior Wood Storage Structure-Exterior Wall-S | Plaster | | | None Detected |
| 61 | Exterior Wood Storage Structure-Ceiling-North | Drywall w Joint Compound | | | None Detected |
| 62 | Exterior Wood Storage Structure-Interior Wall-E | Drywall w Joint Compound | Wood Storage Structure Interior Walls & Ceilings | 2,000sf | None Detected |
| 63 | Exterior Wood Storage Structure-Interior Wall-W | Drywall w Joint Compound | | | None Detected |
| 64 | Exterior Wood Storage Structure-at Exposed Interior Wall Cavity | Vapor Barrier/Brown | Wood Storage Structure Wall Cavities | TBV | None Detected |
| 65 | Main Floor Corridor at Basecove | 6" Rubber Basecove w Adhesive Glue | | | None Detected |
| 99 | 2 nd Floor Dressing Room at Basecove | 6" Rubber Basecove w Adhesive Glue | Basecoves Throughout | 15,000lf | None Detected |
| | | | | | |



Name of Project

| Sample | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|--------|--|------------------------------------|---|----------------------|---------------------|
| 29 | 3 rd Floor Dressing Room at Basecove | 6" Rubber Basecove w Adhesive Glue | | | None Detected |
| 89 | 2 nd Floor Fan Room # 2 Wall | 12-inch Pinhole Ceiling Tile | | | None Detected |
| 69 | 2 nd Floor Fan Room # 2 Wall | Puck Mastic | | | 2% Anthophyllite |
| 70 | 2 nd Floor Fan Room # 2 Wall | Fire Rated Gypsum Board | | | None Detected |
| 71 | 2 nd Floor Dressing Room # 2 Ceiling | 12-inch Pinhole Ceiling Tile | | | None Detected |
| 72 | 2 nd Floor Dressing Room # 2 Ceiling | Puck Mastic | | | None Detected |
| 73 | 2 nd Floor Dressing Room # 2 Ceifing | Fire Rated Gypsum Board | 12-inch Ceiling Tile Throughout | TBV by Contractor | None Detected |
| 74 | 2 nd Floor Ballet Dressing Room Ceiling | 12-inch Pinhole Ceiling Tile | | | None Detected |
| 75 | 2 nd Floor Ballet Dressing Room Ceiling | Puck Mastic | | | 2% Anthophyllite |
| 76 | 2 nd Floor Ballet Dressing Room Ceiling | Fire Rated Gypsum Board | | | None Detected |
| 77 | 3 rd Floor Fan Room # 5 Wall | 12-inch Pinhole Ceiling Tile | | | None Detected |
| 78 | 3 rd Floor Fan Room # 5 Wall | Puck Mastic | | | 2% Anthophyllite |
| 79 | 2 nd Floor Fan Room # 2 Floor | Battleship Flooring/Black | | | <1% Chrysotile |
| 80 | 3 rd Floor Fan Room # 3 Floor | Battleship Flooring/Black | Mech. & Fan Room Flooring Throughout | 5,700sf | <1% Chrysotile |
| 81 | 3 rd Floor Mech. Equip. Room Floor | Battleship Flooring/Black | | | None Detected |
| | | | | | |



Name of Project

| Sample Location Sample Location 3 ^{1/4} Floor Mech. Equip. Room at Ceramic Boiler 2 ^{1/4} Floor Mech. Equip. Room at Ceramic Boiler 2 ^{1/4} Floor Mech. Equip. Room at Ceramic Boiler 2 ^{1/4} Floor Mech. Equip. Room at Ceramic Boiler 2 ^{1/4} Floor Mech. Equip. Room at Ceramic Boiler 2 ^{1/4} Floor Fan Room # 2 Wall 3 ^{1/4} Floor Ballet Dressing Room # 2 Wall 3 ^{1/4} Floor Ballet Dressing Room # 3 Wall 3 ^{1/4} Floor Fan Room # 3 Wall 3 ^{1/4} Floor Fan Room # 6 at Exposed & Abandoned Boiler 3 ^{1/4} Floor Fan Room # 6 at Spigot Box Insulation Boiler Main Floor Phone Booth Floor Wain Floor Part of Auditorium Catwalk Flooring/Vinyl/Red 3 ^{1/4} Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 ^{1/4} Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | Sample | | | | Approx. | 241.140 |
|---|--------|---|-------------------------------|--|----------------------|------------------------------|
| 3" Floor Mech. Equip. Room at Ceramic Boiler Boiler Insulation/White 2" Floor Mech. Equip. Room # 2 Wall Boiler Insulation/White 2" Floor Fan Room # 2 Wall Plaster 2" Floor Dressing Room # 2 Wall Plaster 3" Floor Ballet Dressing Room Wall Plaster 3" Floor Ballet Dressing Room Wall Plaster 3" Floor Stair # 11 Wall Plaster 3" Floor Fan Room # 6 Wall Plaster Boiler Boiler Furnace Pad/Insulation Main Floor Fan Room # 6 at Spigot Box Insulation Insulation Cloth/Canvas Main Floor Phone Booth Floor Vinyl Sheet Flooring/Vinyl/Red Main Floor Phone Booth Floor Catwalk Flooring/Vinyl/Red 3" Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3" Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | umber | Sample Location | Sample Description/Color | Material Location | Quantity | Results |
| 3"d Floor Mech. Equip. Room at Ceramic Boiler Boiler Insulation/White 2"d Floor Fan Room # 2 Wall Plaster 2"d Floor Dressing Room # 2 Wall Plaster 2"d Floor Ballet Dressing Room Wall Plaster 3"d Floor Fan Room # 6 Wall Plaster 3"d Floor Fan Room # 6 Wall Plaster 3"d Floor Fan Room # 6 at Exposed & Abandoned Boiler Furnace Pad/Insulation Boiler Insulation Cloth/Canvas Main Floor Phone Booth Floor Vinyl Sheet Flooring/Vinyl/Red Main Floor Phone Booth Floor Vinyl Sheet Flooring/Vinyl/Red 3"d Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3"d Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 82 | 3 rd Floor Mech. Equip. Room at Ceramic Boiler | Boiler Insulation/White | 3 rd Floor Ceramic Boiler | 200sf | None Detected |
| 2 nd Floor Fan Room # 2 Wall 2 nd Floor Dressing Room # 2 Wall 2 nd Floor Ballet Dressing Room Wall 3 nd Floor Stair # 11 Wall 3 nd Floor Fan Room # 6 Wall 3 nd Floor Fan Room # 6 Wall Boiler 3 nd Floor Fan Room # 6 Abandoned Boiler 3 nd Floor Fan Room # 6 at Exposed & Abandoned Boiler 3 nd Floor Fan Room # 6 at Spigot Box Insulation Main Floor Phone Booth Floor Vinyl Sheet Flooring/Vinyl/Red 3 nd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 nd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 83 | 3 rd Floor Mech. Equip. Room at Ceramic Boiler | Boiler Insulation/White | | | None Detected |
| 2 nd Floor Dressing Room # 2 Wall 2 nd Floor Ballet Dressing Room Wall 3 nd Floor Stair # 11 Wall 3 nd Floor Stair # 11 Wall 3 nd Floor Fan Room # 6 Wall 3 nd Floor Fan Room # 6 Wall 3 nd Floor Fan Room # 6 Abandoned Boiler 3 nd Floor Fan Room # 6 at Exposed & Abandoned Boiler Furnace Pad/Insulation Boiler Main Floor Phone Booth Floor Main Floor Phone Booth Floor 3 nd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 nd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 84 | 2 nd Floor Fan Room # 2 Wall | Plaster | | | None Detected |
| 3 rd Floor Ballet Dressing Room Wall 3 rd Floor Stair # 11 Wall 3 rd Floor Fan Room # 6 Wall 3 rd Floor Fan Room # 6 at Exposed & Abandoned Boiler 3 rd Floor Fan Room # 6 at Spigot Box Insulation Main Floor Phone Booth Floor Wain Floor Phone Booth Floor 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 85 | 2 nd Floor Dressing Room # 2 Wall | Plaster | | | None Detected |
| 3td Floor Stair # 11 Wall Plaster 3td Floor Fan Room # 6 Wall Plaster 3td Floor Fan Room # 6 at Exposed & Abandoned Boiler Boiler Furnace Pad/Insulation 3td Floor Fan Room # 6 at Spigot Box Insulation Insulation Cloth/Canvas Main Floor Phone Booth Floor Vinyl Sheet Flooring/Vinyl/Red 3td Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3td Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 98 | 2 nd Floor Ballet Dressing Room Wall | Plaster | Plaster Walls & Ceilings Throughout | TBV by Contractor | None Detected |
| 3 rd Floor Fan Room # 6 Wall 3 rd Floor Fan Room # 3 Wall 3rd Floor Fan Room # 6 at Exposed & Abandoned Boiler Boiler Main Floor Phone Booth Floor Main Floor Catwalk/Upper Part of Auditorium 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red Catwalk Flooring/Vinyl/Red | 87 | 3 rd Floor Stair # 11 Wall | Plaster | | | None Detected |
| 3rd Floor Fan Room # 3 Wall 3rd Floor Fan Room # 6 at Exposed & Abandoned Boiler 3rd Floor Fan Room # 6 at Spigot Box Insulation Main Floor Phone Booth Floor Main Floor Phone Booth Floor 3rd Floor Catwalk/Upper Part of Auditorium 3rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red Catwalk Flooring/Vinyl/Red | 88 | 3 rd Floor Fan Room # 6 Wall | Plaster | | | None Detected |
| 3rd Floor Fan Room # 6 at Exposed & Abandoned Boiler 3rd Floor Fan Room # 6 at Spigot Box Insulation Main Floor Phone Booth Floor Main Floor Catwalk/Upper Part of Auditorium 3rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red Catwalk Flooring/Vinyl/Red | 89 | 3 rd Fan Room # 3 Wall | Plaster | | | None Detected |
| 3 rd Floor Fan Room # 6 at Spigot Box Insulation Insulation Cloth/Canvas Main Floor Phone Booth Floor S rd Floor Catwalk/Upper Part of Auditorium S rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red S rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red Catwalk Flooring/Vinyl/Red | 06 | 3rd Floor Fan Room # 6 at Exposed & Abandoned Boiler | Boiler Furnace Pad/Insulation | Boilers Throughout | | None Detected |
| Main Floor Phone Booth Floor 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 91 | 3 rd Floor Fan Room # 6 at Spigot Box Insulation | insulation Cloth/Canvas | Spigot Canvas Insulation Throughout | 100sf | Fiberglass Insul. Beneath |
| 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 92 | Main Floor Phone Booth Floor | Vinyl Sheet Flooring/Red | Phone Booth Flooring Only | 8sf | None Detected |
| 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red 3 rd Floor Catwalk/Upper Part of Auditorium Catwalk Flooring/Vinyl/Red | 93 | 3 rd Floor Catwalk/Upper Part of Auditorium | Catwalk Flooring/Vinyl/Red | | | None Detected |
| 3 rd Floor Catwalk/Upper Part of Auditorium | 94 | 3 rd Floor Catwalk/Upper Part of Auditorium | Catwaik Flooring/Vinyl/Red | Catwalk Flooring Throughout | 2,000sf | None Detected |
| | 95 | 3 rd Floor Catwalk/Upper Part of Auditorium | Catwalk Flooring/Vinyl/Red | | | None Detected |



Name of Project

| Sample Number | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|------------------|--|--|-------------------------------------|---|--|
| 96 | 3 rd Floor Catwalk/Upper Part of Auditorium at Overhead Pipe-Runs | Thermal System Insulation/TSI | | | 8% Chrysotile 12% Amosite <1% Crocidolite |
| 97 | 3 rd Floor Catwalk/Upper Part of Auditorium at Overhead Pipe-Runs | Thermal System Insulation/TSI | TSI Pipe-Runs Throughout | 200lf (Visible) TBV by Contractor | Some Pipe- runs and elbows are concealed behind wall cavities |
| 86 | 3 rd Floor Catwalk/Upper Part of Auditorium at Overhead Pipe-Run Elbow | Thermal System Insulation/TSI | | | None Detected |
| 66 | 3 rd Floor Catwalk/Upper Part of Auditorium Ceiling | Particle Board Pane!/White & Brown | | | None Detected |
| 100 | 3 rd Floor Stair # 11 Ceiling | Particle Board Panel/White & Brown | Particle Board Panels Throughout | TBV by Contractor | None Detected |
| 101 | 3 rd Floor Stair # 10 Ceiling | Particle Board Panel/White & Brown | | | None Detected |
| 102 | 2 nd Floor Sound Equip. Room Floor- | 9" Floor Tile w Mastic/Black | | | 5% Chrysotile |
| 102A | 2 nd Floor Sound Equip. Room Floor- | Mastic/Black | | | 6% Chrysotile |
| 103 | 2 nd Floor Sound Equip. Room Floor- | 9" Floor Tile w Mastic/Black | Sound Room Flooring Only | 545sf | 5% Chrysotile |
| 103A | 2 nd Floor Sound Equip. Room Floor- | Mastic/Black | | | 6% Chrysotile |
| 104 | 2 nd Floor Sound Equip. Room Floor- | 9" Floor Tile w Mastic/Black | | | 5% Chrysotile |
| 104A | 2 nd Floor Sound Equip. Room Floor- | Mastic/Black | | | 6% Chrysotile |
| 105 | Auditorium Roof at Surface-Center | Membrane Roofing w Insulation/White | | | None Detected |
| | | | | | |



| Auditorium Roof Southside above Fan Room Stage Upper Roof at Surface Auditorium Roof Southside at Pipe Penetration Pip Stage Upper Roof at Abandoned AHU Surface 112 Southeast Entrance Ext. Foyer/Overhang Ceiling Committee Room Ext. Overhang Ceiling-North 114 Committee Room Ext. Overhang Ceiling-North 115 3 rd Floor Rooftop at Surface T/G 116 Catering Kitchen Rooftop at Surface T/G 117 Committee Room Rooftop at Surface T/G 118 Canopy Rooftop at the Front of Facility T/G | sample Number | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|---|------------------|--|--|--------------------------------------|----------------------------------|------------------|
| Auditorium Rooftop at Pipe Penetration-North Auditorium Roof Southside at Pipe Penetration Auditorium Roof Southside at Pipe Penetration Stage Upper Roof at Abandoned AHU Surface Southeast Entrance Ext. Foyer/Overhang Ceiling Committee Room Ext. Overhang Ceiling-North Committee Room Ext. Overhang Ceiling-North 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | | ditorium Roof Southside above Fan Room | Membrane Roofing w Insulation/White | Membrane Roofing Throughout | 43,000sf TBV by Contractor | None Detected |
| Auditorium Rooftop at Pipe Penetration-North Auditorium Roof Southside at Pipe Penetration Auditorium Roof Southside at Pipe Penetration Stage Upper Roof at Abandoned AHU Surface Southeast Entrance Ext. Foyer/Overhang Ceiling Committee Room Ext. Overhang Ceiling-North Committee Room Ext. Overhang Ceiling-North 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | 7 | Stage Upper Roof at Surface | Membrane Roofing w Insulation/White | | | None Detected |
| Auditorium Roof Southside at Pipe Penetration Stage Upper Roof at Abandoned AHU Surface Southeast Entrance Ext. Foyer/Overhang Ceiling Committee Room Ext. Overhang Ceiling-North Committee Room Ext. Overhang Ceiling-North 31 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Catering Althe Front of Facility | | litorium Rooftop at Pipe Penetration-North | Pipe Penetration Mastic/Black | | | None Detected |
| Auditorium Roof Southside at Pipe Penetration Stage Upper Roof at Abandoned AHU Surface Southeast Entrance Ext. Foyer/Overhang Ceiling Committee Room Ext. Overhang Ceiling-North Committee Room Ext. Overhang Ceiling-North 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | | itorium Roof Southside at Pipe Penetration | Pipe Penetration Mastic/Black | Roof Pipe Penetrations of Auditorium | 50sf | None Detected |
| Stage Upper Roof at Abandoned AHU Surface Southeast Entrance Ext. Foyer/Overhang Ceiling Committee Room Ext. Overhang Ceiling-North Committee Room Ext. Overhang Ceiling-North 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Committee Room Rooftop at Surface | | itorium Roof Southside at Pipe Penetration | Pipe Penetration Mastic/Black | | | None Detected |
| Southeast Entrance Ext. Foyer/Overhang Ceiling Committee Room Ext. Overhang Ceiling-North Committee Room Ext. Overhang Ceiling-North 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Committee Room Rooftop at Surface | | ge Upper Roof at Abandoned AHU Surface | Mastic/Gray & Black | Stage Roof at Abandoned AHU Only | 10sf | 8% Chrysotile |
| Committee Room Ext. Overhang Ceiling-North Committee Room Ext. Overhang Ceiling-North 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | | heast Entrance Ext. Foyer/Overhang Ceiling | Stucco/White | | | None Detected |
| Committee Room Ext. Overhang Ceiling-North 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | | nmittee Room Ext. Overhang Ceiling-North | Stucco/White | Textured Overhangs Throughout | 1,000sf | None Detected |
| 3 rd Floor Rooftop at Surface Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | | nmittee Room Ext. Overhang Ceiling-North | Stucco/White |) | | None Detected |
| Catering Kitchen Rooftop at Surface Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | 5 | 3 rd Floor Rooftop at Surface | T/G Rolled Roofing w Insulation | | | None Detected |
| Committee Room Rooftop at Surface Canopy Rooftop at the Front of Facility | 9 | Catering Kitchen Rooftop at Surface | T/G Rolled Roofing w Insulation | T/G Roofing Throughout | 7,000sf | None Detected |
| Canopy Rooftop at the Front of Facility | 7 | Committee Room Rooftop at Surface | T/G Rolled Roofing w Insulation | | | None Detected |
| | ∞ | Canopy Rooftop at the Front of Facility | T/G Rolled Roofing w Insulation | | | None Detected |
| 3' ^d Floor Rooftop at Footing Penetration Pipe Pe | | 3 rd Floor Rooftop at Footing Penetration | Pipe Penetration Mastic/Gray & Black | | | None Detected |

ASBESTOS BULK SAMPLE Name of Project



| Sample | | | | Accept | |
|--------|---|--|---|----------------------------|-------------------|
| Number | Sample Location | Sample Description/Cofor | Material Location | Quantity | Results |
| 120 | Catering Kitchen Rooftop at HVAC Penetration | Pipe Penetration Mastic/Gray & Black | Mastics Throughout T/G Roofs | 50sf | None |
| 121 | Committee Room Rooftop at Footing Penetration | Pipe Penetration Mastic/Gray & Black | | | None |
| 122 | Catering Kitchen Rooftop at HVAC Duct Joints | HVAC Duct Cloth/Tape-White | | | None |
| 123 | Catering Kitchen Rooftop at HVAC Duct Joints | HVAC Duct Cloth/Tape-White | Catering Kitchen Rooftop HVAC Equipment Only | 40sf | None Detected |
| 124 | Catering Kitchen Rooftop at HVAC Duct Joints | HVAC Duct Cloth/Tape-White | | | None Detected |
| 125 | 2 nd Floor Wardrobe Room at Light Fixtures | Heat Shield Paper/Gray | 2 nd Floor Wardrobe Light Fixtures Only | 1sf | 20% Chrysolite |
| 126 | Catering Kitchen Wall | Drywall w Joint Compound | | | None |
| 127 | Committee Room Hallway Wall | Drywall w Joint Compound | Committee Room and Kitchen Walls & Ceilings | TBV by Contractor | None Detected |
| 128 | Catering Kitchen Wall | Drywall w Joint Compound | | | None Detected |
| 1 | Throughout | Assume (Labeled) Fire Rated Doors Throughout | (Labeled) Fire Rated Doors Throughout | 600sf TBV by Contractor | Assumed |
| ı | Throughout | Mirror Mastics Not Investigated at Clients Request. Assume until further investigation can be conducted. | 1 | 91 | Assumed |
| 1 | Throughout | Terrazzo Flooring at front lobby entrance of the Building was not sampled/inspected at Client's Request. This Material will have to be investigated at another time. | 1 | 1 | Assumed |
| | | | | | |

10 of 11

ASBESTOS BULK SAMPLE Name of Project



| Sample | Section of Section 2 | Samulo Description/Color | Material Location | Approx. | Results |
|--------|----------------------|---|-------------------|----------|---------|
| Number | Sample Foration | Sample Describeral color | | Quantity | |
| | | Assume Transite Pipes Throughout (Transite Pipes Not Found During | | | |
| H | Throughout | Inspection, but if discovered during | ı | 1 | Assumed |
| | | demo/reno workAssume to be asbestos-containing | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsl.com EMSL Order:

431200811 32BAIN21

CustomerID: CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Received:

(714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** % Type Description % Non-Fibrous Sample Appearance Fibrous 1-Finish Coat plaster/ basement 100% Non-fibrous (other) None Detected White stairwell wall-west Non-Fibrous 431200811-0001 Homogeneous None Detected 1A-Base Coat plaster/ basement 100% Non-fibrous (other) Beige stairwell wall-west Non-Fibrous 431200811-0001A Homogeneous 100% Non-fibrous (other) None Detected 2-Finish Coat plaster/baesment White men's bath wall-Non-Fibrous 431200811-0002 east Homogeneous 100% Non-fibrous (other) None Detected 2A-Base Coat plaster/baesment Beige men's bath wall-Non-Fibrous 431200811-0002A east Homogeneous 100% Non-fibrous (other) None Detected 3-Finish Coat plaster/basement White musician's room Non-Fibrous 431200811-0003 wall-east Homogeneous None Detected 100% Non-fibrous (other) 3A-Base Coat plaster/basement Beige musician's room Non-Fibrous 431200811-0003A wall-east Homogeneous 5% Chrysotile 95% Non-fibrous (other) 4-Floor Tile 9-inch floor tile w Green mastic/green-Non-Fibrous 431200811-0004 basement janitor Homogeneous 7% Chrysotile 93% Non-fibrous (other) 4A-Mastic 9-inch floor tite w Black mastic/green-Non-Fibrous 431200811-0004A basement janitor Homogeneous

| Analyst(s | ŝ |
|-----------|---|
|-----------|---|

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegotab@emsl.com

EMSL Order: CustomerID: 431200811 32BAIN21

CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone: Fax: (714) 247-0024

Received:

(714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-As | bestos | <u>Asbestos</u> |
|----------------------|--|---|-----|-----------|--------------------------|------------------|
| ample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type |
| 5 431200811-0005 | cement/basement storage at cement pillar-west | Gray Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 6 431200811-0006 | cement/main floor south stairwell wall | Gray Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 7 491200811-0007 | cement/2nd floor- south-stairwell wall | Gray Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 8 | 12-inch pinhole ceiling tile/main floor dressing r | Brown/White Fibrous Heterogeneous | 90% | Cellulose | 18% Non-fibrous (other) | None Detected |
| 9 431200811-0009 | puck mastic/main floor dressing room ceiling | Brown Non-Fibrous Hamogeneous | | | 98% Non-fibrous (other) | 2% Anthophyllite |
| 10 43†200811-0010 | fire rated gypsum board/main floor dressing room c | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 11 431200811-0011 | 12-inch pinhole ceiling tile/main floor west side | Brown/White Fibrous Heterogeneous | 90% | Cellutose | 10% Non-fibrous (other) | None Detected |
| 12 431200811-0012 | puck mastic/main floor west side exit foyer ceilin | Brown Non-Fibrous Homogeneous | | | 98% Non-fibrous (other) | 2% Anthophyllite |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Defected = <1%

Initial report from 04/17/2012 14:10:24

Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304

http://www.emsl.com <u>sandiegolab@emst.com</u> EMSL Order:

431200811 32BAIN21

CustomerID: CustomerPO:

ProjectID:

Atin: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Non Anhantan

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-Asi | <u>bestos</u> | <u>Asbestos</u> |
|----------------------------------|--|---|-----|-------------|--------------------------|------------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type |
| 13 431200811-0013 | fire rated gypsum board/main floor west side exit | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 14 431200811-0014 | 12-inch pinhole ceiling tile/main floor lobby ceil | Brown/White Fibrous Heterageneous | 90% | o Celíulose | 10% Non-fibrous (other) | None Detected |
| 15 431200811-0015 | puck mastic/main floor lobby ceiling | Brown Non-Fibrous Homogeneous | | | 98% Non-fibrous (other) | 2% Anthophyllite |
| 16 431200811-0016 | fire rated gypsum board/main floor lobby ceiling | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Defected |
| 17-Finish Coat 431200811-0017 | plaster/main floor lobby east stairwell undercarri | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 17A-Base Coat 431200811-0017A | plaster/main floor lobby east stairwell undercarri | Beige Non-Fibrous Homageneous | | | 100% Non-fibrous (other) | None Detected |
| 18-Finish Coat 431200811-0018 | plaster/main floor phone room wall | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 18A-Base Coat 431200811-0018A | plaster/main floor phone room wall | Beige Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |

| Analyst(s |
|-----------|
|-----------|

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method timitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-finable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request, Unless requested by the client, building materials manufactured with multiple layers (i.e. linolaum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304

http://www.emsl.com

sandiegolab@emst.com

EMSL Order:

431200811

CustomerID:

32BAIN21

CustomerPO: ProjectID:

Atta: Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax: Received: (714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description Appearance **Fibrous** % Non-Fibrous % Type 19-Finish Coat plaster/main floor White 100% Non-fibrous (other) None Detected committee room Non-Fibrous 431200811-0019 wall Homogeneous 19A-Base Coat plaster/main floor Beige 100% Non-fibrous (other) None Detected committee room Non-Fibrous 431200811-0019A Homogeneous 20-Finish Coat plaster/main floor Beige 100% Non-fibrous (other) None Detected south stairwell wall Non-Fibrous 431200811-0020 Homogeneous 20A-Base Coat plaster/main floor Beige 100% Non-fibrous (other) None Detected south stairwell wall Non-Fibrous 431200811-0020A Homogeneous 21-Finish Coat plaster/auditorium 100% Non-fibrous (other) White None Detected ceiling-east Non-Fibrous 431200811-0021 Homogeneous 21A-Base Coat plaster/auditorium Beige 100% Non-fibrous (other) None Detected ceiling-east Non-Fibrous 431200811-0021A Homogeneous 22-Finish Coat plaster/auditorium White 100% Non-fibrous (other) None Detected ceiling-west Non-Fibrous 431200811-0022 Homogeneous 22A-Base Coat plaster/auditorium Beige 100% Non-fibrous (other) None Detected ceiling-west Non-Fibrous 431200811-0022A Homogeneous

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304

http://www.einst.com sandiegolab@emsl.com

EMSL Order: CustomerID:

431200811 32BAIN21

CustomerPO: ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Cívic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-As | sbestos | <u>Asbestos</u> |
|-------------------------------------|--|-------------------------------------|---|---------|--------------------------|-----------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type |
| 23-Finish Coat 431200811-0023 | plaster/auditorium ceiling in front of projection | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 23A-Base Coat 431200811-0023A | plaster/auditorium ceiling in front of projection | Beige Non-Fibrous Homogeneous | | | 100% Non-fibraus (other) | None Detected |
| 24-Sheet Flooring 431200811-0024 | vinyl sheet flooring/green- auditorium seating stai | Green Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 24A-Mastic 431200811-0024A | vinyl sheet flooring/green- auditorium seating stai | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 25-Sheet Flooring 431200811-0025 | vinyl sheet flooring/green- auditorium seating stai | Green Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 25A-Mastic 431200811-0025A | vinyl sheet flooring/green- auditorium seating stai | Beige Non-Fibrous Homegeneous | | | 100% Non-fibrous (other) | None Detected |
| 26 431200811-0026 | viny! sheet flooring/green- auditorium seating stai | Green Non-Fibrous Homogeneous | | | 100% Noл-fibrous (other) | None Detected |

| Analyst(s |
|-----------|
|-----------|

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager

or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no EMSL maintains insuring annuel to cost or analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304 Phone/Fax:

sandiecolab@emsl.com http://www.emst.com

EMSL Order:

431200811 32BAIN21

CustomerID: CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705 Project: Santa Monica Civic Auditorium Phone:

(714) 247-0024

Fax: Received: (714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Asbestos Non-Asbestos % Type % Non-Fibrous **Fibrous** Sample Description Appearance None Detected 100% Non-fibrous (other) 6" vinyl cove 27 base/green-Non-Fibrous 431200811-0027 auditorium seating Homogeneous stairw 100% Non-fibrous (other) None Detected 6" vinyl cove Green 28 base/green-Non-Fibrous 431200811-0028 auditorium seating Homogeneous stairw None Detected 100% Non-fibrous (other) 6" vinyl cove Green 29 base/green-Non-Fibrous 431200811-0029 auditorium sealing Homogeneous stairw None Detected 100% Non-fibrous (other) 30 textured vinyl sheet Gray flooring/beige-Non-Fibrous 431200811-0030 auditorium sea Homogeneous None Detected 100% Non-fibrous (other) textured viny! sheet 31 Gray flooring/beige-Non-Fibrous 431200811-0031 auditorium sea Homogeneous None Detected 100% Non-fibrous (other) textured vinyl sheet Gray 32 flooring/beige-Non-Fibrous 431200811-0032 auditorium sea Homogeneous None Detected 100% Non-fibrous (other) 12-inch vinyl tile w 33-Floor Tile Gray mastic/green-Non-Fibrous 431200811-0033 business office Homogeneous

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsl.com

EMSL Order:

431200811 32BAIN21

<u>Asbestos</u>

CustomerID: CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Received:

(714) 247-00**25** 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Non-Asbestos

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

% Non-Fibrous % Type Fibrous Sample Description Appearance 98% Non-fibrous (other) 2% Chrysotile 33A-Mastic 12-inch vinyl tile w Black/Yellow mastic/green-Non-Fibrous 431200811-0033A business office Heterogeneous 100% Non-fibrous (other) None Detected 12-inch vinyl tile w 34-Floor Tile Gray mastic/green-Non-Fibrous 431200811-0034 business office Homogeneous <1% Chrysotile 100% Non-fibrous (other) Black/Yellow 34A-Mastic 12-inch vinyl tite w mastic/green-Non-Fibrous 431200811-0034A business office Heterogeneous None Detected 100% Non-fibrous (other) 35-Floor Tile 12-inch vinyl tile w Gray mastic/green-Non-Fibrous 431200811-0035 business office Homogeneous 100% Non-fibrous (other) <1% Chrysotile Black/Yellow 35A-Mastic 12-inch vinyl tile w mastic/green-Non-Fibrous 431200811-0035A business office Heterogeneous None Detected 100% Non-fibrous (other) 6-inch parquet 36-Flooring Brown flooring w Non-Fibrous 431200811-0036 mastic/brown-Homogeneous business of 100% Non-fibrous (other) None Detected 6-inch parquet Brown 36A-Mastic flooring w Non-Fibrous 431200811-0036A mastic/brown-Homogeneous business of 60% Cellulose 40% Non-fibrous (other) None Detected vapor barrier/black-Black 37 business office **Fibrous** 431200811-0037 men's bath foy Homogeneous

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager

or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method timitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimentic reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoteum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, inc. San Diego, CA NVLAP Lab Code 209855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsl.com EMSL Order: CustomerID:

431200811 32BAIN21

CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone: Fax:

(714) 247-0024

Received:

(714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Callected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | Non | | | bestos | <u>Asbestos</u> | |
|--|--|-------------------------------------|------------|--------------------|--------------------------|-----------------|--|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type | |
| 38-Drywall 431200811-0038 | drywall with joint compound/busines s office recept | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected | |
| 38A-Joint Compound 431200811-0038A | drywall with joint compound/busines s office recept | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected | |
| 39-Drywall 431200811-0039 | drywall with joint compound/main floor concession | White Non-Fibrous Homogeneous | | | 180% Non-fibrous (other) | None Detected | |
| 39A-Joint Compound 431200811-0039A | drywall with joint compound/main floor concession | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected | |
| 40-Drywall 431200811-0040 | drywall with joint compound/main floor concession | Tan Fibrous Homogeneous | <1% <1% | Cellulose Glass | 100% Non-fibrous (other) | None Detected | |
| 40A-Joint Compound 431200811-0040A | drywall with joint compound/main floor concession | White Non-Fibrous Homogeneous | | | 108% Non-fibrous (other) | None Detected | |
| 41 431200811-0041 | TSI pipe elbow insulation/2nd floor fan room #2 at | Tan Fibrous Homogeneous | 30% | Glass | 70% Non-fibrous (other) | None Detected | |

| Analyst(s) |
|------------|
|------------|

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of lest results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-frable organically bound materials present a problem matrix and therefore EMSL recommends gravimalitic reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e., binoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsl.com EMSL Order:

431200811 32BAIN21

CustomerID: CustomerPO:

ProjectID:

Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date: Collected:

4/17/2012

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | <u>No</u> | n-Asbestos | <u>Asbestos</u> |
|-----------------------------|---|-------------------------------------|-----|-----------|--------------------------|-----------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type |
| 42 431200811-0042 | TSI pipe elbow insulation/2nd floor fan room #3 at | Tan Fibrous Homogeneous | 25% | Glass | 75% Non-fibrous (other) | None Detected |
| 43 431200811-0043 | TSI pipe elbow insulation/2nd floor fan room #4 at | Tan Fibrous Homogeneous | 25% | Glass | 75% Non-fibrous (other) | None Detected |
| 431200811-0044 | TSI pipe elbow insulation/2nd floor fan room #5 at | Tan Fibrous Homogeneous | 25% | Glass | 75% Non-fibrous (other) | None Detected |
| 45 431200811-0045 | TSI pipe elbow insulation/2nd floor fan room #6 at | Tan Fibrous Homogeneous | 25% | Glass | 75% Non-fibrous (other) | None Detected |
| 46 431200811-0046 | TSI cork insulation/gray&bro wn-3rd floor fan room | Black Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 47 431200811-0047 | TSI cork insulation/gray&bro wn-3rd floor fan room | Black Non-Fibrous Homogeneous | | - :: | 100% Non-fibrous (other) | None Detected |
| 48 431200811-0048 | TSI cork insulation/gray&bro wn-3rd floor fan room | Black Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |

| A١ | naj | ys | t(| s |) |
|----|-----|----|----|---|---|
|----|-----|----|----|---|---|

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials prosent a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linotaum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com

sandiegolab@emsl.com

EMSL Order:

431200811

CustomerID:

32BAIN21

CustomerPO: ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax: Received: (714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | Non- | <u>Asbestos</u> | <u>Asbestos</u> |
|---------------------------|---|--------------------------------------|---------------|-------------------------|-----------------|
| Sample | Description | Appearance | % Fibrous | % Non-Fibrous | % Type |
| 49 431200811-0049 | AHU canvas material/2nd floor fan room #2 at HVAC | Gray/Cream Fibrous Homogeneous | 30% Synthetic | 70% Non-fibrous (other) | None Detected |
| 50 431200811-0050 | AHU canvas material/2nd floor fan room #3 at HVAC | Gray/Cream Fibrous Homogeneous | 30% Synthetic | 70% Nan-fibrous (other) | None Detected |
| 51 431200811-0051 | AHU canvas material/2nd floor fan room #6 at HVAC | Gray/Cream Fibrous Homogeneous | 30% Synthetic | 76% Non-fibrous (other) | None Detected |
| 52 431200811-0052 | fire curtain/main floor stage at fire curtain-east | Gray/White Fibrous Homogeneous | 10% Synthetic | 50% Non-fibrous (other) | 40% Chrysotile |
| 53 431200811-0053 | fire curtain/main floor stage at fire curtain-west | Gray/White Fibrous Homogeneous | | 60% Non-fibrous (other) | 40% Chrysotile |
| 54 431200811-0054 | fire curtain/main floor stage at fire curtain-cent | Gray/White Fibrous Homogeneous | 10% Synthetic | 50% Non-fibrous (other) | 40% Chrysotile |
| 55 431200811-00 65 | tar membrane roofing material/white- exterior wood | Black Fibrous Homogeneous | 15% Glass | 85% Non-fibrous (other) | None Detected |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report retates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method fimilations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. lineleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVEAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304 Phone/Fax:

sandicgolab@ems..com blip://www.emsl.com

EMSL Order:

431200811 32BAIN21

CustomerID: CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax: Received: (714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Asbestos Non-Asbestos % Туре Description Appearance Fibrous % Non-Fibrous Sample 85% Non-fibrous (other) None Detected 15% Glass tar membrane Black 56 roofing Fibrous 431200811-0056 material/white-Homogeneous exterior wood None Detected 85% Non-fibrous (other) tar membrane Black 15% Glass 57 roofing Fibrous 431200811-0057 material/white-Homogeneous exterior wood 100% Non-fibrous (other) None Detected plaster/exterior 58-Finish Coat Gray wood storage Non-Fibrous 431200811-0058 structure-exterior w Homogeneous None Detected 58A-Base Coat plaster/exterior White 100% Non-fibrous (other) wood storage Non-Fibrous 431200811-0058A structure-exterior w Homogeneous 100% Non-fibrous (other) None Detected plaster/exterior Gray wood storage Non-Fibrous 431200811-0059 structure-exterior w Homogeneous 100% Non-fibrous (other) None Detected 60-Finish Coat plaster/exterior Gray wood storage Non-Fibrous 431200811-0060 structure exterior w Homogeneous None Detected 100% Non-fibrous (other) 60A-Base Coat plaster/exterior White wood storage Non-Fibrous 431200811-0060A structure-exterior w Homogeneous

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains flability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of fest results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSt. recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsl.com EMSL Order:

431200811

CustomerID:

32BAIN21

CustomerPO: ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-Asi | <u>Asbestos</u> | | |
|--------------------------------|--|-------------------------------------|------------|--------------------|--------------------------|---------------|--|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type | |
| 61 431200811-0061 | drywall w joint compound/exterior wood storage str | White Fibrous Homogeneous | <1% <1% | Cellulose Glass | 100% Non-fibrous (other) | None Detected | |
| | | | No JC pre | sent for analysis. | | | |
| 62 431200811-0062 | drywall w joint compound/exterior wood storage str | White Fibrous Homogeneous | <1% <1% | Cellulose Glass | 100% Non-fibrous (other) | None Detected | |
| | | | No JC pre | sent for analysis. | | | |
| 63 431200811-0063 | drywall w joint compound/exterior wood storage str | White Fibrous Homogeneous | <1% | Cellulose Glass | 100% Non-fibrous (other) | None Defected | |
| | | | | sent for analysis. | | | |
| 64 431200811-0064 | vapor barrier/brown- exterior wood storage structur | Brown Fibrous Homogeneous | 90% | Cellulose | 10% Non-fibrous (other) | None Detected | |
| 65-Base Cove 431200811-0085 | 6" rubber basecove w adhesive glue/main floor corr | Blue Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected | |
| 65A-Glue 431200811-0065A | 6" rubber basecove w adhesive glue/main floor com | Cream Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected | |
| 66-Base Cove 431200811-0066 | 6" rubber basecove w adhesive glue/2nd floor dress | Red Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected | |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-triable organically bound materials present a problem metrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emst.com EMSL Order:

431200811 328AIN21

CustomerID; CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received: Analysis Date: 04/12/12 4:00 PM 4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-As | <u>Asbestos</u> | |
|--------------------------------|---|-------------------------------------|-----|-----------|--------------------------|------------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type |
| 66A-Glue 431200811-0066A | 6" rubber basecove w adhesive glue/2nd floor dress | Cream Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 67-Base Cove 431200811-0067 | 6" rubber basecove w adhesive glue/3rd floor dress | Blue Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 67A-Glue 431200811-0067A | 6" rubber basecove w adhesive glue/3rd floor dress | Cream Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |
| 68 431200811-0068 | 12-inch pinhole ceiling tile-2nd floor fan room #2 | Tan Fibrous Homogeneous | 90% | Cellulose | 10% Non-fibrous (other) | None Detected |
| 69 431200811-0069 | puck mastic/2nd floor fan room #2 wall | Brown Non-Fibrous Homogeneous | | | 98% Non-fibrous (other) | 2% Anthophyllite |
| 70 431200811-0070 | fire rated gypsum board/2nd floor fan room #2 wall | White Fibrous Homogeneous | 5% | Cellulose | 95% Non-fibrous (other) | None Detected |
| 71 431200811-0071 | 12-inch pinhole ceiling tile/2nd floor dressing ro | Tan Fibrous Homogeneous | 90% | Cellulose | 10% Non-fibrous (other) | None Detected |

| Anaty | ret/e | 2 |
|--------|-------|---|
| Wildl. | 100 | - |

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains flability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-fritable organically bound materials present a problem materials and therefore EMSL recommends gravimentic reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200865-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com saudiegolab@emsl.com EMSL Order: CustomerID:

431200811 32BAIN21

ProjectID:

CustomerPO:

Attn: Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax: Received: (714) 247-0025

Analysis Date:

04/12/12 4:00 PM 4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-A | sbestos | <u>Asbestos</u> | |
|----------------------|---|--|-----|-----------|--------------------------|-----------------|---------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % | Type |
| 72 431200811-0072 | puck mastic/2nd floor dressing room #2 ceiling | Beige Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | | None Detected |
| 73 431200811-0073 | fire rated gypsum board/2nd floor dressing room #2 | White Fibrous Homogeneous | 5% | Cellulose | 95% Non-fibrous (other) | | None Detected |
| 74 431200811-0074 | 12-inch pinhole ceiling tile/2nd floor ballet dres | Tan Fibrous Homogeneous | 90% | Cellulose | 10% Non-fibrous (other) | | None Detected |
| 75 431200811-0075 | puck mastic/2nd floor ballet dressing room ceiling | Brown Non-Fibrous Homogeneous | | | 98% Non-fibrous (other) | 2% | Anthophyllite |
| 76 431200811-0076 | fire rated gypsum board/2nd floor ballet dressing | White Fibrous Homogeneous | 5% | Cellulose | 95% Non-fibrous (other) | | None Detected |
| 77 431200811-0077 | 12-inch pinhole ceiling tile/3rd floor fan room #5 | Tan Fibrous Homogeneous | 90% | Cellulose | 10% Non-fibrous (other) | | None Detected |
| 78 431200811-0078 | puck mastic/3rd floor fan room #5 wall | Brown Non-Fibrous Homogeneous | | -11 | 98% Non-fibrous (other) | 2% | Anthophyllite |
| 79 431200811-0079 | battleship flooring/black-2nd floor fan room #2 fl | Gray/Black Fibrous Heterogeneous | 80% | Cellulose | 20% Non-fibrous (other) | <1% | Chrysotile |

Analyst(s) Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304 Phone/Fax:

http://www.emsl.com

sandiegolab@entsl.com

EMSL Order:

431200811 32BAIN21

CustomerID:

CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received: Analysis Date: 04/12/12 4:00 PM 4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos

<u>Asbestos</u>

| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type |
|-----------------------------------|---|--|-----|------------------------|--------------------------|----------------|
| 80 431200811-0080 | battleship flooring/black-3rd floor fan room #3 fl | Gray/Black Non-Fibrous Heterogeneous | 80% | Cellulose | 20% Non-fibrous (other) | <1% Chrysotile |
| 81 431200811-0081 | battleship flooring/black-3rd floor mech. Equip ro | Black Fibrous Homogeneous | | Cellulose Synthetic | 20% Non-fibrous (other) | None Detected |
| 82-Wrap 431200811-0082 | boiler insulation/white- 3rd floor mech.equip.room | White Fibrous Homogeneous | 40% | Synthetic | 60% Non-fibrous (other) | None Detected |
| 82A-Insulation 431200811-0082A | boiler insulation/white- 3rd floor mech.equip.room | Yellow Fibrous Homogeneous | 95% | Min. Wool | 5% Non-fibrous (other) | None Detected |
| 83 431200811-0083 | boiler insulation/white- 3rd floor mech.equip.room | White Fibrous Homogeneous | 40% | Synthetic | 60% Non-fibrous (other) | None Detected |
| 84 431200811-0084 | plaster/2nd floor fan room #2 wall | Beige Non-Fibrous Homogeneous | | | 100% Non-fibraus (other) | None Detected |
| 85-Finish Coat 431200811-0085 | plaster/2nd floor dressing room #2 wall | White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | None Detected |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains tiability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analysis. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the chent, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

sandiegolab@emsl.com http://www.emsl.com

EMSL Order:

431200811

CustomerID:

32BAIN21

CustomerPO: ProjectID:

Karlin Cisco

Bainbridge Environmental Consultants 2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received: Analysis Date: 04/12/12 4:00 PM 4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | Non-Asbestos | | <u>Asbestos</u> | |
|----------------------------------|--|---------------------------------------|--------------|--------------------------|-----------------|--|
| Sample | Description | Appearance | % Flbrous | % Non-Fibrous | % Type | |
| 85A-Base Coat 431200811-0085A | plaster/2nd floor dressing room #2 wall | Beige Non-Fibrous Homogeneous | | 100% Non-fibrous (other) | None Detected | |
| 86-Finish Coat 431200811-0086 | plaster/2nd floor ballet dressing room wall | White Non-Fibraus Homageneous | | 100% Non-fibrous (other) | None Detected | |
| 86A-Base Coat 431200811-0086A | plaster/2nd floor ballet dressing room wall | Beige Non-Fibrous Homogeneous | | 100% Non-fibrous (other) | None Detected | |
| 87 431200811-0087 | plaster/3rd floor stair #11 wall | Beige Non-Fibrous Homogeneous | | 100% Non-fibrous (other) | None Detected | |
| 88-Finish Coat 431200811-0088 | plaster/3rd floor fan room #6 wall | White Non-Fibrous Heterogeneous | | 100% Non-fibrous (other) | None Detected | |
| 88A-Base Coat 431200811-0088A | plaster/3rd floor fan room #6 wall | Beige Non-Fibrous Homogeneous | | 100% Non-fibraus (other) | None Detected | |
| 89 431200811-0089 | plaster/3rd fan room #3 wall | Beige Non-Fibrous Homegeneous | | 100% Non-fibrous (other) | None Detected | |
| 90 431200811-0090 | boiler furnace pad/insulation-3rd floor fan room # | Tan Fibrous Homogeneous | 25% Glass | 75% Non-fibrous (other) | None Detected | |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-finable organically bound materials present a problem matrix and therefore EMSL recommends graviments reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e., linoteum, walthoard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsi.com EMSL Order: CustomerID:

431200811 32BAIN21

CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025 04/12/12 4:00 PM

Received: Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | Non-Asbestos | | | <u>Asbestos</u> | | |
|-----------------------------|--|-------------------------------------|--------------|-----------|-------------------------|-----------------|--------------------------------------|--|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % | Туре | |
| 91 431200811-0091 | insulation cloth/canvas-3rd floor fan room #6 at s | White Fibrous Homogeneous | 30% | Synthetic | 78% Non-fibrous (other) | | None Detected | |
| 92 431200811-0092 | vinyl sheet flooring/red-main floor phone booth fl | Red Non-Fibrous Homogeneous | 15% | Cellulose | 85% Non-fibrous (other) | | None Detected | |
| 93 431200811-0093 | catwalk flooring/vinyl/red- 3rd floor catwalk/upper | Red/Black Fibrous Homogeneous | 25% | Cellulose | 75% Non-fibrous (other) | | None Detected | |
| 94 431200811-0094 | catwalk flooring/vinyl/red- 3rd floor catwalk/upper | Red/Black Fibrous Homogeneous | 25% | Cellulose | 75% Non-fibrous (other) | | None Detected | |
| 95 431200811-0095 | catwalk flooring/vinyl/red- 3rd floor catwalk/upper | Red/Black Fibrous Homogeneous | 25% | Cellulose | 75% Non-fibrous (other) | | None Detected | |
| 96 431200811-0096 | thermal system insulation/TSI-3rd floor catwalk/up | White Fibrous Homogeneous | | | 80% Non-fibrous (other) | 12% | Chrysotile Amosite Crocidolite | |
| 97 431200811-0097 | thermal system insulation/TSI-3rd floor catwalk/up | White Fibrous Homogeneous | | | 80% Non-fibrous (other) | 12% | Chrysotile Amosite Crocidolite | |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager

or other approved signatory

EMSL maintains flability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities of analytical method trimitations. Interpretation and use of lest results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoteum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304

http://www.emst.com sandjegolab@emst.com EMSL Order:

431200811

CustomerID:

328AIN21

CustomerPO: ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-A | <u>sbestos</u> | A | <u>sbestos</u> |
|----------------------------------|---|---|---|---------|--------------------------|----|----------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % | Туре |
| 98 431200811-0098 | thermal system insulation/TSI-3rd floor catwalk/up | Tan Fibrous Homogeneous | 20% | Glass | 80% Non-fibrous (other) | | None Detected |
| 99 431200811-0099 | particle board panel/white&brown- 3rd floor catwalk | Tan/White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | | None Detected |
| 100 431200811-0100 | particle board panel/white&brown- 3rd floor stair # | Tan/White Non-Fibrous Homogeneous | | | 109% Non-fibrous (other) | | None Detected |
| 101 431200811-0101 | particle board panel/white&brown- 3rd floor stair # | Tan/White Non-Fibrous Homogeneous | | | 100% Non-fibrous (other) | | None Detected |
| 102-Floor Tite 431200811-0102 | 9" floor tile w mastic/black-2nd floor sound equip | Black Non-Fibrous Homogeneous | ======================================= | | 95% Non-fibrous (other) | 5% | Chrysotile |
| 102A-Mastic 431200811-0102A | 9" floor tile w mastic/black-2nd floor sound equip | Błack Non-Fibrous Homogeneous | | | 94% Non-fibrous (other) | 6% | Chrysotile |
| 103-Floor Tile 431200811-0103 | 9" floor tile w mastic/black-2nd floor sound equip | Black Non-Fibrous Homogeneous | | | 95% Non-fibrous (other) | 5% | Chrysotile |
| 103A-Mastic 431200811-0103A | 9" floor tile w mastic/black-2nd floor sound equip | Black Non-Fibrous Homogeneous | | | 94% Non-fibrous (other) | 6% | Chrysotile |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL. recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiecolab@emsl.com

EMSL Order:

431200811 32BAIN21

CustomerID: CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date: Collected: 4/17/2012

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos <u>Asbestos</u> % Type Description Appearance **Fibrous** % Non-Fibrous Sample 5% Chrysotile 95% Non-fibrous (other) 104-Floor Tile 9º floor tile w Black mastic/black-2nd Non-Fibrous 431200811-0104 floor sound equip Homogeneous 94% Non-fibrous (other) 6% Chrysotile 104A-Mastic 9" floor tile w Black mastic/black-2nd Non-Fibrous 431200811-0104A floor sound equip Homogeneous 88% Non-fibrous (other) None Detected 105 membrane roofing Brown/Black 10% Glass w insulation/white-Fibrous 2% Cellulose 431200811-0105 auditorium roo Heterogeneous 88% Non-fibrous (other) None Detected membrane roofing Brown/Black 10% Glass 106 w insulation/white-Fibrous 2% Cellulose 431200811-0106 auditorium roo Heterogeneous None Detected Brown/Black 10% Glass 88% Non-fibrous (other) 107 membrane roofing w insulation/white-Fibrous 2% Cellulose 431200811-0107 stage upper ro Heterogeneous 85% Non-fibrous (other) None Detected 108 pipe penetration Black 10% Cellulose mastic/black-Fibrous 5% Glass 431200811-0108 auditorium rooftop Homogeneous 90% Non-fibrous (other) None Detected pipe penetration Black 10% Cellulose 109 mastic/black-Fibrous 431200811-0109 auditorium roof Homogeneous sout

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. tinoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0. CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304 Phone/Fax:

http://www.emst.com sandiegoiab@emsl.com EMSL Order: CustomerID:

431200811 32BAIN21

CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date: Collected:

4/17/2012

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-Asi | <u>bestos</u> | <u>A</u> | sbestos |
|-----------------------|--|---|-------------|-------------------------|--------------------------|----------|---------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % | Type |
| 110 431200811-0110 | pipe penetration mastic/black- auditorium roof sout | Black Fibrous Homogeneous | 10% | Cellulose | 90% Non-fibrous (other) | | None Defected |
| 111 431200811-0111 | mastic/gray&black- stage upper roof at abandoned AH | | | | 92% Non-fibrous (other) | 8% | Chrysotlie |
| 112 431200811-0112 | stucco/white- southeast entrance ext.foyer/overhang | Gray/White Fibrous Heterogeneous | | | 100% Non-fibrous (other) | | None Detected |
| | | | Inseparabl | e paint / coating layer | included in analysis | | |
| 113 431200811-0113 | stucco/white- committee room ext.overhang ceiling-N | White Non-Fibrous Heterogeneous | | | 100% Non-fibrous (other) | | None Detected |
| | | | Inseparable | e paint / coating layer | included in analysis | | |
| 114 431200811-0114 | stucco/white- committee room ext.overhang ceiling-N | White Non-Fibrous Heterogeneous | | | 100% Non-fibrous (other) | | None Detected |
| | | | Inseparable | paint / coating layer | included in analysis | | |
| 115 431200811-0115 | T/G rolled roofing w insulation-3rd floor rooftop | Brown/Black Fibrous Heterogeneous | 10% 2% | Glass Cellulose | 88% Non-fibrous (other) | | None Detected |
| 116 431200811-0116 | T/G rolled roofing w insulation- catering kitchen r | Brown/Black Fibrous Heterogeneous | 10% 2% | Glass Cellulose | 88% Non-fibrous (other) | | None Detected |

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL, EMSL bears no responsibility for sample collection activities or analysis. Interport actions, interported and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

858-499-1303 / (858) 499-1304

http://www.emsl.com

sandiegolab@emsl.com

EMSL Order:

431200811

CustomerID:

32BAIN21

CustomerPO:

ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Рћоле:

(714) 247-0024

Received:

(714) 247-0025 04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

| | | | | Non-Asl | <u>cestos</u> | <u>Asbestos</u> |
|-----------------------|--|---|-----------|--------------------|-------------------------|-----------------|
| Sample | Description | Арреагалсе | % | Fibrous | % Non-Fibrous | % Type |
| 117 431200811-0117 | T/G rolled roofing w insulation- committee room roo | Brown/Black Fibrous Heterogeneous | 10% 2% | Glass Cellulose | 88% Non-fibrous (other) | None Detected |
| 118 431200811-0118 | T/G rolled roofing w insulation- canopy rooftop at | Brown/Black Fibrous Heterogeneous | 10% 2% | Glass Cellulose | 88% Non-fibrous (other) | None Detected |
| 119 431200811-0119 | pipe penetration mastic/gray&black- 3rd floor rooft | Black Fibrous Homogeneous | 15% | Cellulose | 85% Non-fibrous (other) | None Detected |
| 120 431200811-0120 | pipe penetration mastic/gray&black- catering kitche | Black Fibrous Homogeneous | 15% | Cellulose | 85% Non-fibrous (other) | None Detected |
| 121 431200811-0121 | pipe penetration mastic/gray&black- committee room | Black Fibrous Homogeneous | 15% | Cellulose | 85% Non-fibrous (other) | None Detected |
| 122 431200811-0122 | HVAC duct cloth/lape- white/catering kitchen roofto | White Fibrous Homogeneous | 20% | Synthetic | 80% Non-fibrous (other) | None Detected |
| 123 431200811-0123 | HVAC duct cloth/tape- white/catering kitchen roofto | White Fibrous Homogeneous | 20% | Synthetic | 80% Non-fibrous (other) | None Detected |

| An | al | ys: | (S |
|----|----|-----|----|
| | | - | |

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no EMBL Infantiation and in the cost of analysis. This report craises only to the samples reported and may not be reproduced, except in our, without written approved by Cost of analysis and the responsibility for sample collection activities or analysis an method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be defined to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimelnic reduction prior to analysis. Samples received in good condition unless otherwise noted, Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsl.com

EMSL Order: CustomerID: 431200811 32BAIN21

CustomerPO: ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received: Analysis Date: 04/12/12 4:00 PM

Collected:

4/17/2012

Project:

Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description % Non-Fibrous % Type <u>Appearance</u> **Fibrous** Sample HVAC duct 80% Non-fibrous (other) None Detected 124 White 20% Synthetic cloth/tape-Fibrous 431200811-0124 white/catering Homogeneous kitchen roofto heat shield Silver/Beige 80% Non-fibrous (other) 20% Chrysotile 125 paper/gray-2nd Fibrous 431200811-0125 floor wardrobe Homogeneous room at 126-Drywall drywail w joint White 100% Non-fibrous (other) None Detected compound-Non-Fibrous 431200811-0126 catering kitchen Homogeneous None Detected drywall w joint White 100% Non-fibrous (other) 126A-Joint Compound compound-Non-Fibrous catering kitchen 431200811-0126A Homogeneous None Detected 127-Drywall drywall w joint White 100% Non-fibrous (other) compound-Non-Fibrous 431200811-0127 committee room Homogeneous hallway wa None Detected 127A-Joint White 100% Non-fibrous (other) drywall w joint Compound compound-Non-Fibrous committee room 431200811-0127A Homogeneous haliway wa 100% Non-fibrous (other) None Detected 128-Drywall drywall w joint White compound-Non-Fibrous 431200811-0128 catering kitchen Homogeneous wall

| Ar |)al | уs | t{ | \$, |
|----|-----|----|----|---------|
| | | | | |

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL baars no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimentic reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, inc. San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emst.com sandiegolab@cmst.com EMSL Order:

431200811

CustomerID:

32BAIN21

CustomerPO: ProjectID:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax:

(714) 247-0025

Received:

04/12/12 4:00 PM

Analysis Date:

4/17/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos

<u>Asbestos</u>

Sample Description Appearance Fibrous % Non-Fibrous % Type 128A-Joint drywall w joint White 100% Non-fibrous (other) None Detected compound-Compound Non-Fibrous catering kitchen 431200811-0128A wall Heterogeneous

Analyst(s)

Rebecca Luu (163)

Michelle LaVallee, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e., linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc., San Diego, CA NVLAP Lab Code 200855-0, CA ELAP 2713

1000 POINT COUNT ASBESTOS BULK SAMPLE

Client: City Of Santa Monica

Project Name: Santa Monica Civic Auditorium

Address: 1855 Main Street

Santa Monica, Ca.90401

BEC Project Number: 12034087.10

Inspector/Sampler: K. Cisco

Date Sampled: 4/12/2012



| ample lumber | Sample Location | Sample Description/Color | Material Location | Approx. Quantity | Results |
|-----------------|--|---------------------------|---------------------|---------------------|---------------------|
| 79 | 2 nd Floor Fan Room # 2 Floor | Battleship Flooring/Black | Mech. & Fan Room | | 0.30% Chrysotile |
| 80 | 3 rd Floor Fan Room # 3 Floor | Battleship Flooring/Black | Flooring Throughout | 5,700sf | 0.20% Chrysotile |



7916 Convoy Court, Building 4, Suite A, San Diego, CA 92111

Phone/Fax: 858-499-1303 / (858) 499-1304

http://www.emsl.com sandiegolab@emsl.com EMSL Order: 431200811 CustomerID: 32BA!N21 CustomerPO: auth#:178576

Project!D:

Attn: Karlin Cisco

Bainbridge Environmental Consultants

2670 North Main Street

Suite 320

Santa Ana, CA 92705

Phone:

(714) 247-0024

Fax: Received: (714) 247-0025 04/12/12 4:00 PM

Analysis Date:

5/10/2012

Collected:

Project: Santa Monica Civic Auditorium

Test Report: Asbestos Analysis of Bulk Material via EPA 600/R-93/116. Quantitation using the 1,000 Point Count Procedure

| | | | | Non- | -Asbestos | <u>Asbestos</u> |
|----------------|--------------------------|---------------|---|---------|----------------------------|-------------------|
| Sample | Description | Appearance | % | Fibrous | % Non-Fibrous | % Type |
| 79 | battleship | Gray/Black | | | 99.70% Non-fibrous (other) | 0.30% Chrysotile |
| 431200811-0079 | flooring/black-2nd | Fibrous | | | | oloo // Onlysoule |
| | floor fan room #2 fl | Heterogeneous | | | | |
| 80 | battleship | Gray/Black | | | 99.80% Non-fibrous (other) | 0.20% Chrysotile |
| 431200811-0080 | flooring/black-3rd floor | Fibrous | | | ,, | |
| | fan room #3 fl | Heterogeneous | | | | |

Analyst(s)

Rebecca Luu (2)

Michelle LaVallee, Laboratory Manager or other approved signatory

Some samples may contain asbestos fibers present in dimensions below PLM resolution limits. The limit of detection as stated in the method is 0.1%. EMSL Analytical Inc suggests that samples reported Some samples may contain aspestos tibers present in dimensions below PLM resolution limits. The limit of detection as stated in the method is 0.1%. EMSL Analytical inc suggests that samples reported as <0.1% or none detected undergo additional analysis via TEM. The above test report relates only to the items tested. This report may not be reproduced, except in full, without written approval EMSL Analytical Inc. This test report must not be used by the client to claim product endorsement by NVLAP or any agency of the United States Government. EMSL Analytical Inc. bears no responsibility for sample collection activities, analytical method limitations, or the accuracy of results when requested to separate layered samples. EMSL Analytical inc liability is limited to the cost of sample analysis. The test results contained within this report meet the requirements of NELAC unless otherwise noted. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by EMSL Analytical, Inc. San Diego, CA

Initial report from 05/10/2012 09:14:29

APPENDIX B LEAD XRF FIELD DATA AND RESULTS

XRF Lead-Based Paint Sampling Log

Client: City Of Santa Monica

Santa Monica Convention Center Site:

1855 Main Street Address: Santa Monica, CA 90401

Client Project #:

BEC Project #: 12034087.10

Inspector/Sampler: H. Gonzalez

Date Sampled: 4/13/2012



| ıtity | î u | | | | | | | | | | | |
|------------------|-------------|-------------|-------------|-------------|----------|----------|------------------|-----------------|------------------|-------------------|-------------------------------|-------------------------------|
| Results/Quantity | mg/kg (ppm) | 1.3 | 0.9 | 1.1 | 00:00 | 0.01 | 0.00 | 00:00 | 00:00 | 00:00 | 0.01 | 0.01 |
| - 1 | Color | RED | RED | RED | Gray | Gray | Blue | Blue | Blue | Tan | White | Blue |
| | Substrate | F 20 | 1 | 3. | Metal | Concrete | Concrete | Concrete | Plaster | Plaster | 4" Ceramic Tile | 4" Ceramic Tile |
| | Source | ļ | 1 | T, | Door | Wall | Wall | Wall | Wall | Stair Case/N-East | Wall | Wall |
| | Room | * | ı | 1. | South | South | Main Floor/South | Main Floor/West | Main Floor/South | Main Floor/North | Main Floor/North Cafeteria | Main Floor/North Cafeteria |
| | Building | CALIBRATION | CALIBRATION | CALIBRATION | Exterior | Exterior | Interior | Interior | Interior | Interior | Interior | Interior |
| | Side | ₹. | 9 | | U | U | v | ٥ | æ | ∢ | ∢ | ∢ |
| | XLNo | 2165 | 2166 | 2167 | 2168 | 2169 | 2170 | 2171 | 2172 | 2173 | 2174 | 2175 |

Fax (714) 247-0025 (714) 247-0024

2670 North Main Street, Suite 320

Santa Ana, CA 92705

Santa Monica Convention Center

1855 Main Street

Santa Monica, CA 90401

XRF Lead-Based Paint Sampling Log

| Side Building | Building | | Room | Source | Substrate | Color | Results/Quantity mg/kg (ppm) |
|---------------|----------|----|-------------------------------|------------|-----------------|-----------|---------------------------------|
| A Interior | Interior | 1 | Main Floor/North Cafeteria | Wall | Concrete | White | 0.01 |
| A Interior | Interior | | Men R/R North- West | Wall | 2" Ceramic Tile | White | 0.04 |
| A Interior | Interior | | Men R/R North- West | Wall | 2" Ceramic Tile | Green | 0.06 |
| A | Interior | | Men R/R North- West | Wall | 2" Ceramic Tile | Blue | 00:00 |
| Interior | Interior | | Men R/R North- West | Floor | 2" Ceramic Tile | Gray | 00.0 |
| A Interior | Interior | | Men R/R North- West | Sink | Porcelain | White | 0.01 |
| C Interior | | | Men R/R North- West | Toilet | Porcelain | White | 0.03 |
| A Interior | | | Men R/R North- West | Urinal | Porcelain | White | 5.3 |
| B Interior | Interior | | Men R/R North- West | Partition | Metal | Blue | 0.00 |
| A Interior | Interior | | Men R/R North- West | Door | Wood | White | 0.00 |
| A Interior | Interior | | Men R/R North- West | Door Frame | Metal | White | 0.05 |
| A Interior | | | Stage Entrance B | Door | Wood | Dark Gray | 0.00 |
| | | ١. | | | | | |

(714) 247-0024 Fax (714) 247-0025

Santa Monica Convention Center

1855 Main Street

Santa Monica, CA 90401

XRF Lead-Based Paint Sampling Log

| | | | | | | | Results/Ouantity |
|------|------|----------|----------------------------|------------|-----------|-----------|------------------|
| XLNo | Side | Building | Room | Source | Substrate | Color | mg/kg (ppm) |
| 2188 | A | Interior | Stage Entrance B | Door Frame | Metai | Dark Gray | 00:00 |
| 2189 | മ | Interior | Women R/R North | sink | Porcelain | White | 00:00 |
| 2190 | ٥ | Interior | Women R/R North | Toilet | Porcelain | White | 0.03 |
| 2191 | S | Interior | Storage/Entrance C Hali | Door | Metal | Black | 0.02 |
| 2192 | C | Interior | Storage/Entrance C Hali | Wall | Plaster | Gray | 0.02 |
| 2193 | D | Interior | Storage/Entrance C Hall | Door | Wood | Gray | 0.03 |
| 2194 | D | Interior | Storage/Entrance C Hall | Door Frame | Metal | White | 0.5 |
| 2195 | C | Interior | Storage Room | Wall | Plaster | Blue | 0.00 |
| 2196 | C | Interior | Storage Room | Wali | Wood | Blue | 0.15 |
| 2197 | Ą | Interior | Entrance D | Door | Wood | Tan | 00:0 |
| 2198 | А | Interior | Entrance D | Door Frame | Metal | Tan | 0.11 |
| 2199 | ٨ | Interior | North East/Men R/R | Urinal | Porcelain | White | 5.2 |
| | | | | | | | |

(714) 247-0024 Fax (714) 247-0025

Santa Monica Convention Center

1855 Main Street

Santa Monica, CA 90401

XRF Lead-Based Paint Sampling Log

| Source Substrate Color Mag/kg (ppm) Sink Porcelain White 0.09 Toilet Wood Red 0.00 Fire hose Cabinet Wood Red 0.00 Hand Rail Metal Green 0.00 Chair Base Metal Gray 0.16 Light Support Metal Gray 0.04 North Wall Metal Green 0.00 Yorth Wall Plaster Green 0.00 Door Wood Gray 0.00 Door Frame Metal Gray 0.00 | |
|---|------------------------------|
| Porcelain White Porcelain White Wood Red Metal Green Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Metal Gray Motal Gray Motal Gray | Room |
| Porcelain White Wood Red Metal Green Metal Gray Metal Gray Metal Gray Plaster Cight Blue Wood Gray Metal Gray Metal Gray | North East/Men R/R |
| Wood Red Metal Green Metal Gray Metal Gray Plaster Green Plaster Light Blue Wood Gray Metal Gray Metal Gray | North East/Men R/R |
| Metal Green Metal Gray Metal Gray Metal Gray Plaster Green Wood Gray Wood Gray | Entrance F Fire |
| Metal Gray Metal Gray Metal Gray Plaster Green Wood Gray Wood Gray | Entrance F |
| Metal Gray Metal Gray Plaster Green Wood Gray Whetal Gray | Sitting Area Cl |
| Metal Gray Metal Blue Plaster Green Wood Gray Metal Gray | Sitting Area E |
| Metal Blue Plaster Green Wood Gray Metal Gray | Sitting Area Ligh |
| Plaster Green Plaster Light Blue Wood Gray | Sitting Area No |
| Plaster Light Blue Wood Gray Metal Gray | Sitting Area Ea |
| Wood Gray Metal Gray | Convention Room North Wall |
| Metal Gray | Convention Room |
| | Convention Room Do |

(714) 247-0024 Fax (714) 247-0025

Santa Monica Convention Center

1855 Main Street

Santa Monica, CA 90401

XRF Lead-Based Paint Sampling Log

| | | | | | | | 7 | | ı | | | |
|---------------------------------|------------------|--------------------|----------------|-----------------|-----------------|-----------------|----------|------------|----------|----------|------------------------|------------|
| Results/Quantity mg/kg (ppm) | 00:00 | 0.05 | 0.00 | 8.8/1200SF | 0.00 | 0.00 | 0.14 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 |
| Color | Gray/White | Gray | Gray | White | Red | Red | Gray | Gray | White | White | White | White |
| Substrate | 12" ceramic Tile | 4"x8" Ceramic Tile | Metal | 4" Ceramic Tile | 6" Ceramic Tile | 6" Ceramic Tile | Wood | Metal | Plaster | Metal | Metal | Metal |
| Source | Floor | Base Board | Electric panel | Wall | Floor | Base Board | Door | Door Frame | Ceiling | Register | Door/South Entrance | Door Frame |
| Room | Convention Room | Convention Room | North Hallway | Kitchen | Kitchen | Kitchen | Kitchen | Kitchen | Kitchen | Kitchen | Kitchen | Kitchen |
| Building | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior |
| Side | 2401 | ۵ | A | ∢ | 3 | J | 4 | A | T. | ž | A | A |
| XLNo | 2212 | 2213 | 2214 | 2215 | 2216 | 2217 | 2218 | 2219 | 2220 | 2221 | 2222 | 2223 |

Fax (714) 247-0025 (714) 247-0024

Santa Monica Convention Center

1855 Main Street

Santa Monica, CA 90401

XRF Lead-Based Paint Sampling Log

| | TOLOGO (DOLL) | 122 | | | | | |
|------|---------------|----------|------------------------|------------------------------|----------------|--------|------------------------------|
| XLNo | Side | Building | Room | Source | Substrate | Color | Results/Quantity mg/kg (ppm) |
| 2224 | A | Interior | West/Custodian Room | Air Handler | Metal | Gray | 0.04 |
| 2225 | A | Interior | West/Custodian Room | Air Condition Duct | Metal | Gray | 0.07 |
| 2226 | C | Interior | West/Custodian Room | 6" Pipe | Metal | Gray | 0:30 |
| 2227 | С | Interior | West/Custodian Room | 2" Pipe | Metal | Gray | 0.30 |
| 2228 | C | Interior | West/Custodian Room | Wall | 12" Wall Tiles | White | 00:00 |
| 2229 | A | Interior | Main Office Hall | Door | Wood | Gray | 0.00 |
| 2230 | А | Interior | Main Office Hall | Door Frame | Metal | Gray | 0.00 |
| 2231 | D | Interior | West Exit | Double Door | Metal | Gray | 0.13 |
| 2232 | O | Interior | West Exit | Door Frame | Metal | Gray | 00:00 |
| 2233 | 8 | Interior | West Exit | Fire Extinguisher Housing | Wood | Red | 0.11 |
| 2234 | ⋖ | Interior | Office | Wall | Plaster | Yellow | 0.00 |
| | | | | | | | |

Fax (714) 247-0025 (714) 247-0024

XRF Lead-Based Paint Sampling Log

Client; City Of Santa Monica

Site: Civic Center Auditorium

Address: 1855 Main Street

Santa Monica, CA 90401

Client Project #:

BEC Project #: 12034087.10

Inspector/Sampler: Hector Gonzalez

Date Sampled: 4/13/2012



| ity | | | | | | | | | | | | | | |
|------------------|-------------|-------------|---------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|---------------|--------------------|
| Results/Quantity | mg/kg (ppm) | 00:00 | 90:0 | 6.8/200SF | 00:00 | 0.01 | 4.3 | 0.04 | 0.00 | 0.01 | 0.26 | 0.01 | 0.08 | 0.01 |
| Color | 000 | Yellow | Red | Green | White | Tan | White | Tan |
| Substrate | Substi ate | Plaster | Metal | 4" Ceramic Tile | Metal | Porcelain | Porcelain | Porcelain | Plaster | Wood | Metal | 8" Ceramic Tile | Metal | Plaster |
| Cource | aninoc | Wall | Fire Alarm Station Box | Wall | Partition | Sink | Urinal | Toilet | Wall | Door | Door Frame | Floor | 2'x3' Door | Wall |
| Boom | MOOIII | Main Office | Main Office | Main Office/Men R/R | Bathroom Hall | Front Desk Area |
| Building | Silining | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior |
| Side | 2010 | 8 | В | A | ř. | J | Ç | U | A | A | A | 10 | 8 | O |
| XINO | VEIGO | 2235 | 2236 | 2237 | 2238 | 2239 | 2240 | 2241 | 2242 | 2243 | 2244 | 2245 | 2246 | 2247 |

(714) 247-0024 Fax (714) 247-0025

Civic Center Auditorium

XRF Lead-Based Paint Sampling Log

1855 Main Street

Santa Monica, CA 90401

| Total Control of the | | | | | | | |
|---|---------|-----------------------|--------|----------------------------|-----------------|------------|------------------|
| Side Building Room | | Roc | ٤ | Source | Substrate | Color | Results/Quantity |
| D Interior Front Desk Area | | Front De Area | şsk | Walf | Concrete | Tan | 0.00 |
| A Interior Women R/R | | Women R | /к | Wali | 4" Ceramic Tile | Peach | 4.8/200 SF |
| A Interior Women R/R | | Women R/ | æ | Partition | Metal | Peach | 0.12 |
| C Interior Women R/R | | Women R, | ۳ | Feminine Napkin Storage | Metal | White | 0.00 |
| A Interior Women R, | Women R | Women R, | /R | Sink | Porcelain | White | 0.02 |
| A Interior Women R/ | Women R | Women R/ | /R | Toilet | Porcelain | White | 0.04 |
| C Interior Women R/ | Women R | Women R/ | /R | Wall | Plaster | White | 00:00 |
| C Interior Front Desk | | Front Desk | | Door | Wood | Tan | 0.02 |
| C Interior Front Desk | | Front Desk | | Door Frame | Metal | Tan | 0.17 |
| B Interior Office Hallway | | Office Hallw | ay | Fire control Panel | Metal | Red | 0.00 |
| Interior Office Hallway | | Office Hallw | ау | Ceiling | Plaster | Tan | 0.00 |
| B Interior Office/Copy Machine | | Office/Cop Machine | , | Wall | Plaster | Tan | 00:00 |
| A Interior Dressing Room 1 | | Dressing Roo | я 1 | Shower Wall | 4" Ceramic Tile | White | 6.4/60SF |
| A Interior Dressing Room 1 | | Dressing Roor | ม 7 | Wall | Plaster | Líght Blue | 0.00 |
| | | | | | | | |

(714) 247-0024 Fax (714) 247-0025

Civic Center Auditorium

1855 Main Street

Santa Monica, CA 90401

XRF Lead-Based Paint Sampling Log

| tity | | | | | | | | | | | | | | |
|---------------------------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|------------|--------------------------|---------------|-----------------|-----------------|---------------|---------------|---------------|
| Results/Quantity mg/kg (ppm) | 0.06 | 0.01 | 00:00 | 0:30 | 0.18 | 0.11 | 0.5 | 0.03 | 0.00 | 1.1/160SF | 7.3/60SF | 0.00 | 0.00 | 0.01 |
| Color | White | White | Blue | Blue | White | Beige | Orange | Tan | Orange | Red | White | Orange | Orange | Tan |
| Substrate | Porcelain | Porcelain | Mood | Metal | 8" Ceramic Tile | 8" Ceramic Tile | Metal | Metal | Wood | 8" Ceramic Tile | 4" Ceramic Tile | Wood | Metal | Plaster |
| Source | Toilet | sink | Door | Door frame | Floor | floor | Door Frame | Stair Case | Sheif | Floor | Shower Wall | Door | Door Frame | Wall |
| Room | Dressing Room 1 | Hallway | Green Room | Dressing Room Hallway | Dressing Room | Dressing Room | Dressing Room | Dressing Room | Dressing Room | Dressing Room |
| Building | Interior | Interior | {nterior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior |
| Side | В | ٧ | A | A | Ŷ. | ì | C | В | ∢ | • | 4 | v | v | В |
| XLNo | 2262 | 2263 | 2264 | 2265 | 2266 | 2267 | 2268 | 2269 | 2270 | 2271 | 2272 | 2273 | 2274 | 2275 |

(714) 247-0024 Fax (714) 247-0025

Civic Center Auditorium

Santa Monica, CA 90401 1855 Main Street

XRF Lead-Based Paint Sampling Log

Results/Quantity mg/kg (ppm) 6.4/4 Urinals 5.9/212SF 6.4/340SF 5.0/260SF 6.0/220SF 5.9/60SF 0.02 0.25 0.00 0.14 0.01 0.00 2.5 White/Green White/Black Peach White White Green White White Color Black Black Black Tan Tan Tan 4'x8' Ceramic tile 8" Ceramic Tile 4" Ceramic Tile 8" Ceramic tile Substrate Porcelain Porcelain Porcelain Porcelain Wood Shower Wall **Built in Desk** Baseboard Source Urinal Toilet Floor Floor Sink Wall Wall Wall Wall Door Second Floor East Second Floor East Second Floor East Second Floor East 2nd. Floor South 2nd. Floor South **Dressing Room Dressing Room Dressing Room Dressing Room Dressing Room** Men Dressing Men Dressing 2nd. Floor South Janitor Room Dressing RM Dressing RM **Dressing Room Dressing Room** Room Building Interior Side 8 ⋖ K Ç B ⋖ XLNo 2276 2279 2288 2278 2280 2282 2283 2285 2286 2289 2277 2281 2284 2287

Fax (714) 247-0025 (714) 247-0024

XRF Lead-Based Paint Sampling Log

Client: City Of Santa Monica

Site: Civic Center Auditorium

Address: 1855 Main Street

Santa Monica, CA 90401

Client Project #:

BEC Project #: 12034087.10

Inspector/Sampler: Hector Gonzalez

Date Sampled: 4/13/2012



| _ | | | | | | | r | | | | | | r' | |
|------------------|-------------|--|--|-----------|------------|---------------------|---------------------|---------------------|--------------------------|-----------------------|---------------------------|---------------------------|-----------------------|-------------|
| Results/Quantity | mg/kg (ppm) | 0.01 | 0.01 | 00'0 | 00:00 | 5.0/260SF | 0.07 | 0:30 | 2.6 | 5.0/260SF | 0.01 | 0.01 | 10.1/180SF | 6.0 |
| 200 | | Gray | Gray | White | White | Green | Tan | Tan | White | Peach | Yellow | Yellow | Gray | RED |
| Cubetrato | Substrate | Metal | Metal | Concrete | Concrete | 4' Ceramic Tile | Wood | Metal | Porcelain | 4" Ceramic Tile | Concrete | Concrete | Metal | Ě |
| Source | 201000 | Air handler No. 3 | Air Handler No. 4 | Wall | Wall | Wall | Door | Door Frame | Sink | Wall | Wall | Wall | Double Door | t |
| Room | | 3 rd . Floor mechanical Room | 3 rd . Floor mechanical Room | East side | North Side | Basement Men R/R | Basement Men R/R | Basement Men R/R | Basement Janitor Room | Basement Women R/R | Basement Electric Room | Basement Electric Room | Orchestra Pit Door | £ |
| Building | £ | Interior | Interior | Exterior | Exterior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | Interior | CALIBRATION |
| Side | | | , | В | Ü | А | A | ۷ | 80 | ٨ | A | æ | Α | • |
| XLNo | | 2305 | 2306 | 2307 | 2308 | 2309 | 2310 | 2311 | 2312 | 2313 | 2314 | 2315 | 2316 | 2317 |

| Civic Cen | Civic Center Auditorium | | F Lead-Ba | sed Paint | XRF Lead-Based Paint Sampling Log | b | |
|------------------|-------------------------|-------------|-----------|-----------|-----------------------------------|------|------------------|
| 1855 Main Street | in Street | | | | 0 | 0 | |
| Santa Mo | Santa Monica, CA 90401 | 1901 | | | | | |
| XLNo | Side | Ruilding | Boom | Course | Cohertmoto | 300 | Results/Quantity |
| | | 0 | | Source | Substrate | 5000 | mg/kg (ppm) |
| 2318 | Ŷ | CALIBRATION | Ē | ī | I | RED | 1.4 |
| 2319 | 7 | CALIBRATION | 1 | E | ŀ | RED | 0.7 |

APPENDIX C

ASBESTOS AND LEAD INSPECTOR'S CERTIFICATES














APPENDIX D

















PRE-APPLICATION MEETING REQUEST LOS ANGELES REGIONAL OFFICE

This form must be completed to request a pre-application meeting with Division of the State Architect (DSA) Los Angeles.

- Pre-application meetings may be in-person, or virtual using Microsoft Teams or a combination thereof. Meeting
 invites will be issued by DSA to the District/Owner representative and Architect/Structural Engineer and may be
 forwarded as appropriate.
- The District/Owner representative is required to attend. The Structural Engineer is required to attend any meeting with structural questions. Meetings may be terminated and rescheduled if these individuals are not in attendance.
- Meetings are typically scheduled for one hour unless the size and complexity of the project requires additional time, up to two hours maximum. Meeting discussions will be limited to the scope of questions listed on this form and information provided at the time of the meeting. Questions should be focused and specific as possible.
- If necessary to re-schedule or cancel a meeting, please provide as much advance notice to the DSA Project Services supervisor as possible.
- Applicant is required to submit a draft of meeting notes within one week for DSA review and final concurrence.
 Include within the notes all relevant plans discussed at the meeting. Final meeting notes are to be included with the plan review submittal.

INSTRUCTIONS

- 1. Download this form in Adobe Acrobat.
- 2. Complete Fields 1-13.
- 3. Attach pdfs of site plan, floor plan and/or other relevant supporting documents for DSA staff preview and in preparation for the meeting using Adobe Acrobat attachment tools. Meetings may not be scheduled prior to receipt of supporting documents.
- 4. Submit the request by clicking on the "Submit Via Email" text button on the last page of this form. Form will automatically open an email addressed to the Project Services Supervisor. Follow-up directly with the supervisor if you have not received an acknowledgement or response within 2 business days.

| CONTACT INFORMATION |
|---------------------------------|
| 1. Project Name: |
| 2. District/Owner: |
| a. District Contact: |
| b. District Work Phone: |
| c. District Email: |
| 3. Architectural Firm: |
| a. Architect Contact: |
| b. Architect Work Phone: |
| c. Architect Work Email: |
| 4. Structural Engineering Firm: |
| a. Engineer Contact: |
| b. Engineer Work Phone: |
| c. Engineer Work Email: |

PRE-APPLICATION MEETING REQUEST

| ME | ETING INFORMATION | | | | | | |
|----|------------------------------------|--|--|--|--|--|--|
| 5. | Number of Attendees Expected: | | | | | | |
| 6. | Meeting Dates and Times (List 3 a | alternate dates and times available in the space provided.) | | | | | |
| | a. Date: | Hours Available: | | | | | |
| | b. Date: Hours Available: | | | | | | |
| | c. Date: Hours Available: | | | | | | |
| 7. | ☐ Check this box if you prefer a f | ace-to-face meeting in DSA regional office instead of a virtual meeting. | | | | | |
| | | | | | | | |

| PRO | JECT INFORMATION |
|-----|------------------------------|
| 8. | School Name: |
| 9. | Street Address: |
| 10. | Estimated Construction Cost: |
| 11. | Approximate Submittal Date: |
| 12. | Project Description: |
| | |
| | |
| | |
| | |
| | |
| | |

NOTE: A Pre-application meeting IS NOT intended for preliminary plan review.


The intent is for DSA staff to provide answers and clarifications to specific questions regarding the project, DSA procedures, processes and/or code interpretations.


ITEMS FOR DISCUSSION

- 13. List specific questions for the following four categories in the space proved below. (Supplemental form DSA 211 may be attached if additional space is required.)
 - a. Structural

| PKE. | -Ar | PLICATION MEETING REQUEST |
|------|-----|---------------------------|
| | b. | Fire and Life Safety |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | C. | Accessibility |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | d. | DSA Processing |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

SUBMIT VIA EMAIL







DSA Pre-Intake Meeting Minutes

Project SMMUSD Santa Monica Civic Auditorium

NAC Project No. 161-23020 Meeting Date April 20, 2023

In Attendance (CA) Carlos Araujo, DSA

(YC) Yuan Chen (Charles), DSA (DH) Douglas Humphrey, DSA

(FK) Ferris Karim, DSA

(AB) Alan Braatvedt, SMMUSD (virtual) (BC) Barbara Chiavelli, SMMUSD (virtual) (SM) Steve Massetti, SMMUSD (virtual)

(LO) Leticia Ochoa, NAC Architecture (virtual)

(MP) Michael Pinto, NAC Architecture (EW) Esmeralda Ward, NAC Architecture

Discussion Items

(Text in italics indicates the items originally listed on the DSA 93 form submitted to schedule this meeting.)

Overview

CA requests meeting minutes from NAC Architecture for this meeting within one business week.

NAC provides an overview of the project:

The Santa Monica Civic Auditorium is a 1958 cast-in-place concrete building designed by Welton Becket that is currently owned by the City of Santa Monica. NAC Architecture is working through a feasibility study for the SMMUSD to determine the feasibility of utilizing the Civic Auditorium as an athletics/performance building for use primarily by Santa Monica High School students and staff. The feasibility study will provide the district with the information needed to make decisions on how/if they will move forward in negotiations with the City of Santa Monica.

In 2001 the Civic Auditorium was designated as a City Landmark by the Landmarks Commission of the City of Santa Monica. The building has been unused since 2013 due to structural and accessibility deficiencies. A full seismic retrofit would be required to bring the building up to current code/Field Act compliance, as well as significant improvements to provide code-compliant accessible path of travel restroom facilities, etc. The building has a 'tilting floor' in the main auditorium space that has two positions – completely flat which puts the auditorium floor flush with the stage level, and tilted which puts the edge of the auditorium floor adjacent to the stage at 3' below the stage level at the center of the stage and 3'-10" below the stage level at the edges of the stage.



DSA Pre-Intake Meeting Minutes 01

DSA 93 Item C1

Tilting Floor - The existing floor in the main space is a tilting floor that can alternate between a flat floor and a sloped floor. The floor has a slope of approximately 6.7% at its' fully sloped position. (Note: Since the time the DSA 93 form was submitted additional information in original drawings was found by the team to indicate that the floor slopes 5.68% at its' fully sloped position, not 6.7% as previously thought.) There are 6 vomitoria that provide access to the main space from the lobby, each of which contains a tilting ramp with an approximate slope of 5.3% at their fully sloped positions. (Note: Since the time the DSA 93 form was submitted additional information in original drawings was found by the team to indicate that the vomitorium ramps slope up to 4.3% at its' fully sloped position, not 5.3% as previously thought.)

- c1.1 Regarding the main space floor review the positions of seating that could be made accessible at the back of the main space floor to satisfy the requirement for a variety of seating options. Further options for accessible seating could be provided at the top level of fixed seating at the Concourse level.
- c1.2 Regarding the vomitoria spaces confirm that removable guards/handrails could serve 1 or 2 of these tilting ramps when in their fully tilted positions to provide an accessible path to accessible seating. (existing ramp lengths are less than 30'-0").

Discussion:

NAC's overall inquiry is to discuss the tilting floor and possible ways to preserve its functionality and historic status while still achieving an accessible solution.

At its tilted position the floor is approximately 5.68%. As this exceeds 5% the requirements of a ramp would be triggered (level landings, handrails, max. runs, etc.). These provisions will deem the floor unusable. NAC proposes a solution of limiting the floor's tilt to less than 5%. This would permit the floor to be considered a sloped walk, while still preserving a reasonable stage height. If accessible seating locations on this floor were required, they would need to be on level platforms (2% in all directions). CA sees this solution as a possibility. The process of level platforms being installed and uninstalled may deem this solution unfeasible, however. The group discusses whether accessible seating could be provided in the fixed seats only. CA notes that he would view the seating in the front and back sections as two separate requirements given that one is fixed and one is not. Since the back portion of the room provides fixed seats there is more of an obligation to provide a fully accessible solution there. This would require vertical dispersion of accessible seats, but CA anticipates a non-equal dispersion between the top and bottom could be acceptable (ex: 70% of required seats at the bottom of the fixed seats and 30% at the top). The team will look at potential solutions utilizing this approach.

The option of claiming a 'technical infeasibility' is discussed as a way to potentially alleviate some requirements. CA clarifies though that he would interpret a 'technical infeasibility' as something that cannot be amended without tearing the item/building down.

CA advises the team to look into the code exception that permits fixed seats to be used in lieu of handrails.



SMMUSD Santa Monica Civic Auditorium

DSA Pre-Intake Meeting Minutes 01

In summary, the option of keeping the tilting floor in operation is not off the table. More meetings with DSA-LA will be required to study proposed solutions.

DSA 93 Item C2

c2. Elevator - Review requirements for adding an elevator(s) to the building.

CBC 2022 11B-206.2.3.2 11B-206.2.3.1 notes that the addition of an accessible means of vertical access (such as an elevator) is triggered whenever a new stair or escalator is constructed. This project would not involve the construction of a new stair or escalator.

CBC 2022 11B-206.2.3.2 Distance to Elevators - "In existing buildings that exceed 10,000 square feet on any floor and in which elevators are required by Section 11B-206.2.3, whenever a newly constructed means of vertical access is provided via stairs or an escalator, an accessible means of vertical access via ramp, elevator or lift shall be provided within 200 feet of travel of each new stair or escalator."

Discussion:

NAC requests clarification on the requirements for a new elevator in the lobby in this project since the code language (CBC 2022) on this topic could be interpreted in some varying ways. 11B-206.2.3 requires at least one accessible route to connect each story and mezzanine in multistory buildings. 11B-206.2.3.1 requires the addition of an accessible means of vertical access (such as an elevator) to an existing building whenever a new stair or escalator is constructed, but this project would not require a new stair or escalator to be constructed in the lobby. 11B-20.6.2.3.2 requires a max. of 200' from a newly constructed stairs or escalator to a newly constructed elevator or ramp.

NAC requests clarification on whether the addition of an elevator (accessible means of vertical access) is required for this project at the lobby side of the building. The team believes the intent of the code is to require an elevator, however the language in 11B-206.2.3 could be interpreted to mean that an elevator is only required if a new stair or escalator were to be added. CA/DH respond that while the code language is confusing the intent of the code is to require an elevator in the lobby side of the building and DSA-LA would expect to see that.

Additional Items:

1. Historical Provisions in the code:

CA recommends the team look into the provisions in the code made for historical features. SM notes that the building's landmark status is only a local designation, not a state or federal designation. CA references the team to 11B-202.5 in DSA's 2019 California Access Compliance Advisory Reference Manual which clarifies that the CA "Office of Historic Preservation delegates authority to cities and counties as "certified local governments" to apply National Register criteria for creating local lists of historic buildings and properties" therefore it is considered a 'qualified historic building' as it relates to compliance with the CA Building Standards Code (Title 24).

2. Portable Steps:

The building contains 'portable steps' that provide access to the fixed seating portion when the floor is in its' tilted position. A means to provide a compliant egress path at this condition needs to be studied and coordinated with DSA-LA FLS. CA points out that the code differentiates between stairs and 'tiered steps' in fixed seating areas.



DSA Pre-Intake Meeting Minutes 01

3. Claims:

CA inquires whether any accessibility claims were filed against the City of Santa Monica on this building, as that might help identify accessibility issues to address. SM responds that the SMMUSD isn't aware of any such claims.

4. Restrooms:

FK inquires about the scope of work needed to provide accessible restrooms. NAC responds that a full renovation of existing restrooms is anticipated to make them accessible.

5. Assistive Listening Systems:

FK inquires about assistive listening systems and anticipates that these requirements would be triggered by the project. NAC anticipates this also.

If there are any corrections to these minutes, please notify the Architect within [7] days of receipt.

Prepared by Esmeralda Ward

cc: attendees

 $\label{lambda} $$ \operatorname{lal}-23020\0_{\rm egulatory}\d_dsa\230420_pre-app-mtg\230420_dsa_pre-intake_meetingminutes.docx $$ \operatorname{lal}-23020\0_{\rm egulatory}\d_dsa\230420_pre-app-mtg\230420_dsa_pre-intake_meetingminutes.docx $$ \operatorname{lal}-23020\0_{\rm egulatory}\d_dsa\230420_dsa_pre-intake_meetingminutes.docx $$ \operatorname{lal}-23020\0_{\rm egulatory}\d_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\230420_dsa\$

