

**MATERIAL INVENTORY
ASBESTOS SAMPLES**

CLIENT: Santa Monica Malibu Unified School District
PROJECT NO: SMSD-19-8865
PROJECT NAME: SMASH/John Muir Bldg 600

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Drywall mud	612-1	None Detected	600 northeast	Rooms 600, 602, 605, 610, 612, 615, restrooms, Computer Lab, main entry (walls only)	4,000 SF	No	Yes
Drywall mud	612-2	None Detected	610 southeast				
Drywall mud	612-3	None Detected	Main entry, south west				
Drywall mud	612-4	None Detected	615 northwest				
Drywall mud	612-5	None Detected	610 southwest	Note: Damage at base of the walls in Room 600, 602, Computer Lab, 605, main entry, water damage crew removed baseboard damaging the drywall with mud behind it			
Drywall	612-6	None Detected	600 south center				
Drywall	612-7	None Detected	605 north center				
Composite drywall mud	612-8	None Detected	600 northeast				
6" blue cove base with glue	612-9	None Detected	610 southwest				
6" blue cove base with glue	612-10	None Detected	Computer Lab, east center				
6" blue cove base with glue	612-11	None Detected	615 southwest				
4" pink cove base with glue	612-12	None Detected	Janitor's closet north center	Janitor's closet	10 LF	No	No
4" pink cove base with glue	612-13	None Detected	Janitor's closet southwest				
4" pink cove base with glue	612-14	None Detected	Janitor's closet southeast				
Yellow adhesive for blue carpet	612-15	None Detected	600 center	Rooms 600, 602, 605, 610, 612, 615, Computer Lab	5,000 LF	No	No
Yellow adhesive for blue carpet	612-16	None Detected	605 center				
Yellow adhesive for blue carpet	612-17	None Detected	615 center				

**MATERIAL INVENTORY
ASBESTOS SAMPLES**

CLIENT: Santa Monica Malibu Unified School District
PROJECT NO: SMSD-19-8865
PROJECT NAME: SMASH/John Muir Bldg 600

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
12"x12" blue speckled floor tile with yellow glue	612-18	None Detected	Main entry, northwest	Rooms 600, 605, main entry, 615	900 SF	No	No
12"x12" blue speckled floor tile with yellow glue	612-19	None Detected	600 north center				
12"x12" blue speckled floor tile with yellow glue	612-20	None Detected	605 north east				
12"x12" pink floor tile with yellow glue	612-21	None Detected	Main entry northwest	Rooms 600, 605, main entry, 615 (under 12" blue floor tile)	900 SF	No	No
12"x12" pink floor tile with yellow glue	612-22	None Detected	600 north center				
12"x12" pink floor tile with yellow glue	612-23	None Detected	605 north east				

Note: Only floors, baseboards and walls were to be tested. No ceramic. Client directed bulk sampling per SMMUSD rep Elizabeth Villalobos.

**MATERIAL INVENTORY
LEAD PAINT CHIP SAMPLES**

CLIENT: Santa Monica Malibu Unified School District
PROJECT NO: SMSD-19-8865
PROJECT NAME: SMASH/John Muir Bldg 600

Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Approx. Damage Qty.
Wall	PC -1	Drywall	Pink	Room 600 north center	Building 600 throughout	<46	No	
Door	PC -2	Wood	Orange	Room 605 north east		<47	No	
Door case	PC -3	Metal	Orange	Room 605 north east		<46	No	

Note: Client directed sampling only walls and doors are to be tested. No ceramic was tested per SMMUSD rep Elizabeth Villalobos.